



- NOTE:**
- TOPOGRAPHIC SURVEY BY WSP CANADA INC., DATED NOV. 13, 2013. ELEVATIONS ARE RELATIVE TO GEODETIC SURVEY OF CANADA (GSC).
 - SOUNDING SURVEY TO CHART DATUM (I.G.L.D. 1985) - 176.000m.
 - SOUNDING DATA BASED ON DRAWING MA-01, TITLED 20130906 SOUNDING SURVEY OCTOBER 2013.
 - IGLD AND GSC DATA ARE REFERENCED TO DIFFERENT BASE ELEVATIONS.
 - WATER LEVEL NOV. 13, 2013 - 176.0m.
 - THE CONTRACT DOCUMENTS HAVE BEEN PREPARED, IN PART, BY REFERENCE TO DRAWINGS PROVIDED BY OTHERS. THESE REFERRED TO DRAWINGS ARE INCLUDED AS AN APPENDIX IN THESE CONTRACT DOCUMENTS. THE DESIGNER AND THE PORT CANNOT ASSURE THE ACCURACY OF THIS INFORMATION. USE OF THIS INFORMATION BY THE CONTRACTOR IS THE CONTRACTOR'S SOLE RESPONSIBILITY. INDEPENDENT VERIFICATION OF THE ACCURACY OF SUCH INFORMATION SHOULD BE EMPLOYED BEFORE APPLYING THE INFORMATION FOR ANY PURPOSE.
 - THE CONTRACTOR SHALL REVIEW THE PROJECT GEOTECHNICAL INVESTIGATION REPORT IN DETAIL AND FOLLOW THE RECOMMENDATIONS PROVIDED THERE IN.
 - DIMENSIONS FOR REMOVAL OF MATERIALS SHOWN IN SECTIONS A, B, AND C, ARE APPROXIMATE. CONTRACTOR SHALL INCLUDE FOR ENCOUNTERED REMOVALS OF ALL MATERIALS.
 - EXISTING MOORING BOLLARDS TO BE REMOVED AND STORED. OBTAIN DIRECTION FROM OWNER.
 - EXISTING ELECTRICAL PEDESTALS TO BE DISCONNECTED AND REMOVED. CONFIRM WITH OWNER IF TO DISPOSE OR STORE.
 - EXISTING GAS PUMPS TO BE REMOVED BY OTHERS. CONCRETE ISLAND TO BE REMOVED BY CONTRACTOR.
 - REMOVE AND DISPOSE EXISTING TIMBER FENDERING.
 - SAW CUT AT LIMITS OF DEMOLITION.
 - PUMP-OUT SHED AND RELATED EQUIPMENT TO BE RELOCATED BY OTHERS.
 - BENCHES, PLANTERS & ICE MACHINE TO BE RELOCATED BY OTHERS.
 - EXISTING NAVIGATIONAL AID TO BE REMOVED BUT NOT BEFORE DECEMBER 1st 2016. CONTRACTOR IS TO OBTAIN DIRECTION FROM THE DEPARTMENTAL REPRESENTATIVE AS TO WHETHER TO STORE OR SALVAGED.
 - NEW NAVIGATIONAL AID IS TO BE PROVIDED BY OTHER. CONTRACTOR IS TO INSTALL NEW NAVIGATIONAL AID TO THE SAME ALIGNMENT AS EXISTING NAVIGATIONAL AID. CONTRACTOR TO OBTAIN APPROVAL FOR ALIGNMENT BY DEPARTMENTAL REPRESENTATIVE PRIOR TO FIXING TO THE DECK.
 - NEW ELECTRICAL PEDESTALS TO BE PROVIDED BY OTHERS.
 - FLOATING DOCKS TO BE RELOCATED BY OTHERS.
 - FUEL DOCK MOORING PILE TO BE REMOVED AND STORED. LENGTH OF PILE IS NOT KNOWN. LOCATION TO BE VERIFIED BY CONTRACTOR ON SITE. CONTRACTOR TO RE-INSTALL AFTER COMPLETION OF WORK.
 - EXISTING ELECTRICAL SERVICING TO BE MAINTAINED DURING CONSTRUCTION.
 - EXISTING HANDRAILS TO BE REMOVED. CONTRACTOR TO CONFIRM EXTENT WITH THE OWNER.
 - INTERLOCKING BRICK TO BE REMOVED, SALVAGED AND PLACED ON SKIDS AT A LOCATION CONFIRMED WITH THE OWNER.

LEGEND

	TREE		REMOVE AND DISPOSE		LP LIGHT POST
	SOUNDING DEPTH (METRES BELOW CHART DATUM)		ELECTRICAL BOX		PSE PAVING STONE EDGE
	SPOT ELEVATION TO (GEODETIC SURVEY DATUM)		RING TIE		TB TIMBER FENDER
	LADDER		BOLLARD		WRW WOOD RETAINING WALL
			CLEAT		CRW CONCRETE WALKWAY JOINT
					MP MOORING PILE

EXISTING STRUCTURE PLAN - CONCRETE COPE WALL ON TIMBER CRIB
1:200

SMALL CRAFT HARBOURS CENTRAL AND ARCTIC REGION



No.	Description	Drawn By / Des. Par	Date
5	ISSUED FOR TENDER	JJ	12/08/20
4	DWG. NUMBERS ADDED	JJ	03/24/15
3	ISSUED FOR COMPLETION	JJ	12/17/14
2	ISSUED FOR FINAL REVIEW	JJ	10/22/14
1	ISSUED FOR 100% REVIEW	JJ	09/17/14

Revision / Révision
Do not scale drawings. Verify all dimensions and conditions on site and immediately notify the Departmental Representative of all discrepancies.

A	Detail No. / No. du détail
B	drawing no. - where detail required / dessin no. - où détail exigé
C	drawing no. - where detailed / dessin no. - où détaillé



Project title / Titre du projet

PORT ELGIN WEST PIER REHABILITATION

Drawing title / Titre du dessin

EXISTING PIER DEMOLITION PLAN

Drawn by / Dessiné par PETER REGALADO	Designed by / Conçu par MARC PICHETTE
Approved by / Approuvé par JOHN JUFFS	Drawing Date / Date du dessin MAY 8 2014
Project manager / Administrateur de projet JOHN JUFFS	
HCEW Number / Numéro de CHTI -	Drawing Number / Numéro du Dessin MA-02
Project Number / Numéro du projet 131-23620-00-100	Sheet / Feuille 4 of 12