
Solicitation EC016-161302/A –
Elevator System Replacement Correctional Services Canada (CSC) St. Johns

AMENDMENT # 004

THE FOLLOWING AMENDMENT TO THE TENDER DOCUMENTS IS EFFECTIVE IMMEDIATELY. THE
AMENDMENT SHALL FORM A PART OF THE CONTRACT DOCUMENTS.

Addendum No. 2

SPECIFICATIONS

1. Specification clarification

Section 14 12 60, article 1.2.3.15, Related work - included as elevator contractor's responsibility,

Replace the following paragraph,

.15 Provide a ductless split machine room cooling unit size to 8,000 BTUs/hr per elevator, including mounting an electrical connection. Locate exterior condenser to owner's approved location.

With the following,

.16 Provide a ductless split machine room cooling unit size to 8,000 BTUs/hr per elevator, including all required exterior and interior structural mounting and all electrical wiring connections to power and control the unit. Locate exterior condenser to owner's approved location.

2. Add the following item to the Specification

Section 14 12 60, article 1.2.3.15, Related work - included as elevator contractor's responsibility,

.17 For both the elevator and lift devices, supply and install a proper sized power surge protection to ensure that surge voltages cannot cause damage to the new elevator/lift installation devices, it's interconnected equipment and any associated end devices. Ensure that the surge protective devices shall:

1. Limit the surge voltage in terms of amplitude so that the dielectric strength of the device is not exceeded.
2. Discharge the surge currents associated with surge voltages.

By submission of its tender, the Tenderer confirms that it has read and understands the requirements expressed in all addenda and has included all costs of these requirements in its
Total Tender Amount.

All other terms & conditions remain unchanged.
