

Wharf Reconstruction
Lawn, NL
P/N: 718889

Page 1
2016-07-06

PART 1 - GENERAL

- | | | |
|-------------------------------------------|----|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <u>1.1 SECTION
INCLUDES</u> | .1 | Barriers. |
| | .2 | Traffic Controls. |
| <u>1.2 INSTALLATION
AND REMOVAL</u> | .1 | Provide temporary controls in order to
execute work expeditiously. |
| | .2 | Remove from site all such work after use. |
| <u>1.3 HOARDING</u> | .1 | Erect temporary site enclosure using new
1.2 m high snow fence wired to rolled steel
"T" bar fence posts spaced at 2.4 m centres.
Provide one lockable truck gate. Maintain
fence in good repair. |
| <u>1.4 GUARD RAILS
AND BARRICADES</u> | .1 | Provide secure, rigid guard rails and
barricades around open excavations. |
| | .2 | Provide barricades along wharf structure when
wheelguard is removed. |
| | .3 | Provide as required by governing authorities. |
| <u>1.5 ACCESS TO SITE</u> | .1 | Provide and maintain access to adjacent
harbour facilities. |
| <u>1.6 PUBLIC
TRAFFIC FLOW</u> | .1 | Provide and maintain competent signal flag
operators, traffic signals, barricades and
flares, lights, or lanterns as required to
perform work and protect the public. |
| <u>1.7 FIRE ROUTES</u> | .1 | Maintain access to property including
overhead clearances for use by emergency |

Wharf Reconstruction
Lawn, NL
P/N: 718889

Page 2
2016-07-06

response vehicles.

1.8 PROTECTION FOR
OFF-SITE AND PUBLIC
PROPERTY

- .1 Protect surrounding private and public property from damage during performance of work.
- .2 Be responsible for damage incurred.