

Wharf Reconstruction
Lawn, NL
P/N: 718889

Page 1
2016-07-06

PART 1 - GENERAL

1.1 DESCRIPTION

- .1 This section specifies requirements for demolishing and removing wholly or in part various items designated to be removed or partially removed.
- .2 Demolition and removal will consist of, but not necessarily be limited to, the following:
 - .1 Removal of the wharf and associated wharf components, as noted on the drawings.
 - .2 Extraction of select piles/sheet piling to accommodate the new work, as noted on the drawings.
 - .3 Temporary shoring measures (such as sheet piling) to protect the existing private infrastructure, as noted on the drawings.

1.2 GENERAL
REQUIREMENTS

- .1 A Notice to Shipping is to be issued prior to commencement and upon completion of work.
- .2 During construction, any vessels or barges utilized must be marked in accordance with the provisions of the Canada Shipping Act Collision Regulations.
- .3 Upon completion of the project, a written Notice to Mariners must be issued.

1.3 PROTECTION

- .1 Protect existing objects designated to remain. In event of damage, immediately replace or make repairs to approval of and at no additional cost to Canada.
- .2 Place a floating boom around entire demolition site to prevent loss of any materials.

Wharf Reconstruction
Lawn, NL
P/N: 718889

Page 2
2016-07-06

- .3 Remove all floating debris from water on a routine and timely basis.

PART 2 - PRODUCTS

NOT APPLICABLE

PART 3 - EXECUTION

3.1 EXECUTION

- .1 Inspect site and verify with Departmental Representative objects designated for removal.
- .2 Locate and protect utility lines. Preserve in operating condition active utilities traversing site.

3.2 REMOVAL

- .1 Remove in their entirety all materials and objects specified for removal.
- .2 Do not disturb adjacent work designated to remain in place.

3.3 DISPOSAL OF MATERIAL

- .1 All demolished materials, except materials designated to be reused, will become property of contractor and will be removed from site and disposed of to satisfaction of Departmental Representative and in accordance with environmental guidelines. It is the sole responsibility of the contractor to dispose of all demolished materials at an approved disposal site. Ensure that disposal site is approved and willing to accommodate any materials disposed of from work site.
- .2 Contractor shall obtain and pay for all

Wharf Reconstruction
Lawn, NL
P/N: 718889

Page 3
2016-07-06

necessary permits and disposal fees for use
of an approved waste disposal site.

3.4 RESTORATION

- .1 Upon completion of work, remove debris, trim
surfaces and leave work site in clean
condition.
- .2 Reinstate areas and existing works outside
areas of demolition to conditions that
existed prior to commencement of work.