

**Geotechnical Investigation,
Bunker Retaining Wall
Assessment, Cape Spear
National Historic Site, NL**



Prepared for:

Parks Canada
1869 Upper Water St.,
Suite AH201
Halifax, NS B3J 1S9

Prepared by:

Stantec Consulting Ltd.
141 Kelsey Drive
St. John's, NL A1B 0L2
Tel: (709) 576-1458
Fax: (709) 576-2126

Final Report

File No: 133347329

June 15, 2016

**GEOTECHNICAL INVESTIGATION, BUNKER RETAINING WALL ASSESSMENT, CAPE SPEAR
NATIONAL HISTORIC SITE, NL**

Table of Contents

1.0 INTRODUCTION 1

2.0 SITE AND GEOLOGY..... 1

3.0 FIELD PROCEDURES 1

4.0 LABORATORY TESTING 2

5.0 SUBSURFACE CONDITIONS..... 2

5.1 Organic Soils..... 2

5.2 Fill..... 3

5.3 Silty Sand with Gravel..... 3

5.4 Inferred Bedrock..... 3

5.5 Groundwater..... 3

6.0 DISCUSSION AND RECOMMENDATIONS 4

6.1 Site Preparation 4

6.2 Foundation Design 4

6.3 Retaining Walls..... 5

6.4 Structural Fill..... 5

7.0 QUALITY ASSURANCE/QUALITY CONTROL..... 6

8.0 CLOSURE..... 7

LIST OF ATTACHMENTS

- Statement of General Conditions
- Symbols and Terms Used on Borehole and Test Pit Records
- Test Pit Records
- Test Pit Photographs
- Figure 1 – Gradation Curves
- Figure No: 01: Test Pit Location Plan

LIST OF TABLES

Table 6.1 Recommended Structural Fill Compaction Requirements..... 6

GEOTECHNICAL INVESTIGATION, BUNKER RETAINING WALL ASSESSMENT, CAPE SPEAR NATIONAL HISTORIC SITE, NL

INTRODUCTION

June 15, 2016

1.0 INTRODUCTION

Acting on the request and authorization of Parks Canada (the Client), Stantec Consulting Ltd. (Stantec) has completed a geotechnical investigation in support of the assessment of existing retaining walls associated with historical bunkers located at the Cape Spear Lighthouse, National Historic Site, Newfoundland and Labrador.

The scope of work completed for this project was in general accordance with Stantec's proposal dated April 25, 2016, and included the following:

- A geotechnical field subsurface investigation consisting of three (3) mechanically excavated test pits;
- Geotechnical laboratory testing on one (1) representative soil sample; and
- A geotechnical report presenting the findings of the field investigation, including test pit records and laboratory results, as well as comments and recommendations on foundation and retaining wall design.

This report has been prepared specifically and solely for the proposed development described herein and contains all of the findings of this investigation.

2.0 SITE AND GEOLOGY

The proposed site is located at the Cape Spear National Historic Site, Newfoundland and Labrador near the existing historical bunkers as shown on the attached Figure No. 01: Test Pit Location Plan. At the proposed development area, the ground surface is generally uneven and slopes downwards towards the ocean (north-northeast direction of the existing bunkers). Both sides of the existing access road are partially developed and/or undeveloped with vegetated areas. At the time of field investigation, bedrock outcroppings are noted across the site.

Based on previous experience in the area and available geological literature, the natural subsurface conditions in the area are understood to consist of a veneer of till layer which contains sand with less than 20 percent silt and clay (diamicton matrices) extending to bedrock. Bedrock geology at the site is mapped as pebble conglomerate with red sandstone at top of the Skerries Bight member, Cuckold Formation, Signal Hill Group.

3.0 FIELD PROCEDURES

The field investigation was completed on May 24, 2016 and consisted of excavating three (3) test pits using a rubber-tired backhoe provided by Stantec. The approximate test pit locations

GEOTECHNICAL INVESTIGATION, BUNKER RETAINING WALL ASSESSMENT, CAPE SPEAR NATIONAL HISTORIC SITE, NL

LABORATORY TESTING

June 15, 2016

are shown on the attached Figure No: 01: Test Pit Location Plan. Test pit locations were selected and established by Stantec in the field by using a handheld GPS unit with ± 5 m accuracy. Final test pit locations were staked by Stantec for future survey by the owner's surveyor.

All test pits were excavated to refusal on probable/inferred bedrock at depths ranging from 1.0 m to 1.6 m below the ground surface. Upon completion, the test pits were backfilled with the excavated material and nominally compacted using the excavator bucket. Once Stantec has departed the site, it is the responsibility of the Owner to address any potential hazards due to settlement of backfilled materials.

The field work was conducted under the inspection of Stantec personnel who maintained detailed field records of the various soil strata and groundwater conditions encountered during the investigation. The soils were classified in general accordance with the procedures outlined in the attached explanatory key: Symbol and Terms Used on Borehole and Test Pit Records. Representative soil samples were obtained directly from the test pit walls or from the excavator bucket during the field investigation. All soil samples were stored in moisture proof containers and sent to our laboratory for storage and selected testing. Samples remaining after testing will be stored for a period of three (3) months at which time they will be discarded, unless instructions to the contrary are received.

4.0 LABORATORY TESTING

Laboratory testing consisting of soil gradations and moisture content determinations were performed on representative samples obtained from TP-12. The laboratory test results are presented in the attached Figure 1 – Gradation Curves. Note that the samples tested for soil gradation excluded over-size materials larger than 75 mm (3 inches).

5.0 SUBSURFACE CONDITIONS

Subsurface conditions observed in the test pits are summarized in the subsections below and described in detail on the attached Test Pit Records along with an accompanying explanatory key: Symbols and Terms used on Borehole and Test Pit Records. Representative photographs of the excavated test pits and spoil piles are also attached.

5.1 Organic Soils

Surficial layers of organic soils including sod and/or rootmat were encountered at TP-12 and TP-14. The combined thickness of the organic soils ranged from 0.1 m to 0.2 m. Grass, roots and rootlets were encountered within the organic layers.

GEOTECHNICAL INVESTIGATION, BUNKER RETAINING WALL ASSESSMENT, CAPE SPEAR NATIONAL HISTORIC SITE, NL

SUBSURFACE CONDITIONS

June 15, 2016

5.2 Fill

Fill materials was encountered at TP-13. A layer of gravel and sand was encountered at the ground surface. The thickness of the layer was 0.2 m. Based on our visual observations, the materials can be described as grey, gravel with sand and silt (GP-GM) with trace rootlets. In terms of relative density, based on direct inspection in the test pit and excavator performance, the fill layer can be generally classified as loose.

5.3 Silty Sand with Gravel

A layer of sand was encountered underlying the surficial organic soils at TP-12 and TP-14 at depths ranging from 0.1 m to 0.2 m below the existing ground surface. A sand layer was also encountered at TP-13 underlying the upper fill material at a depth of 0.2 m below the existing ground surface. The thickness of the sand layer ranged from 1.0 m to 1.5 m.

Based on visual field observations and laboratory testing, the materials encountered at sand layer are generally classified as a dark brown to reddish brown to black, silty sand with gravel (SM) to sand with silt and gravel (SP-SM) with trace to some rootlets, organics, occasional to some cobbles, and occasional boulders. Slight odor was observed from the organic layer encountered at 1.1 m depth in TP-14. Gradation analyses conducted on one (1) representative sample provided 39.0% gravel, 48.1% sand and 12.9% fines (silt/clay). The moisture content of the sample was 9.6%. The result of the gradation analysis is shown on the attached Figure 1 – Gradation Curves.

In terms of relative density, based on direct inspection in the test pits and excavator performance, the layer is generally classified as loose to compact.

5.4 Inferred Bedrock

Inferred/probable bedrock was encountered at all test pit locations at depths ranging from 1.0 m to 1.6 m below ground surface. Inferred/probable bedrock as noted herein has been inferred based on excavator refusal.

The inference of bedrock has limitations due to size of the excavation and the nature of visual assessments from surface. Refusal can also result from the presence of large boulders or dense cobble and boulder rich horizons within the till stratum. In order to confirm bedrock at the test pit locations, borehole drilling and a minimum of 3 m of bedrock core recovery is recommended.

5.5 Groundwater

At the time of the field investigation, groundwater seepage was not encountered at any test pit locations. It should be noted that test pits were not left open for a sufficient length of time for water levels to stabilize. Furthermore, groundwater levels may fluctuate seasonally and in

GEOTECHNICAL INVESTIGATION, BUNKER RETAINING WALL ASSESSMENT, CAPE SPEAR NATIONAL HISTORIC SITE, NL

DISCUSSION AND RECOMMENDATIONS

June 15, 2016

response to precipitation events. To determine the long-term groundwater conditions at the site, borehole drilling and installation of groundwater monitor wells or standpipes would be required.

6.0 DISCUSSION AND RECOMMENDATIONS

At the time of issuing this report, it is understood that it is proposed to use box culvert type structures to partially/fully replace the existing historical bunkers as shown on the attached Figure No: 01. The comments and recommendations presented in this report are for general preliminary planning and design purposes only and should be reviewed by geotechnical personnel once the design details are known.

6.1 Site Preparation

In preparation for site development, all organic soils, and loose native soils should be excavated from the proposed foundation footprint. Excavated areas should be proof rolled and, if required, built to grade with an approved structural fill as described below. Any softened areas evident upon proof rolling must be removed and replaced with suitably compacted structural fill. Due to the composition of the site soils, guidance from geotechnical personnel during site earthworks will be necessary.

The site is underlain by silty sands with variable fines contents (silts / clays) on the order of 13%. Typically, where the fines content of a soil is in excess of 12%, the soil will tend to soften and become unsuitable and difficult to work when it becomes wetter than its optimum moisture content and is disturbed. In addition, silty soils that have been successfully compacted and approved, may require removal if they subsequently become wet and softened from water infiltration, precipitation or freezing.

Shallow bedrock and/or pinnacles of bedrock may be encountered during site earthworks.

Excavations may encounter ground water seepage and/or surface water runoffs during site preparation earthworks that will be important to control. All water seepage should be controlled using appropriate measures, such as drainage ditching and/or conventional pump and sump arrangements

6.2 Foundation Design

Shallow foundations will be suitable for this development. Foundations on proof-rolled native silty sands or properly placed and compacted structural fill may be designed for a maximum net allowable bearing pressure of 150 kPa. The associated total and differential settlements for these pressures are anticipated to be less than 25 mm and 19 mm.

GEOTECHNICAL INVESTIGATION, BUNKER RETAINING WALL ASSESSMENT, CAPE SPEAR NATIONAL HISTORIC SITE, NL

DISCUSSION AND RECOMMENDATIONS

June 15, 2016

Shallow foundations may be constructed on suitably prepared bedrock, if encountered, using an allowable bearing pressure of 500 kPa. The settlement of foundations on bedrock would be negligible.

Foundations should not be placed on frozen ground, and temporary frost protection during freezing conditions should be provided after construction of footings. Exterior footings and footings in unheated areas should have a minimum soil cover of 1,200 mm or equivalent for frost protection.

6.3 Retaining Walls

The following design parameters may be used for imported compacted granular structural fill.

Total Unit Weight, γ (kN/m ³)	21 kN/m ³
Effective Angle of Internal Friction, ϕ'	34 degrees
Earth Pressure Coefficient at Rest, k_0 (assuming level ground)	0.44
Active Earth Pressure Coefficient, k_a (assuming level ground)	0.28
Passive Earth Pressure Coefficient, k_p (assuming level ground)	3.54

Following ultimate sliding friction factor required for the sliding design of retaining wall is recommended:

Ultimate sliding friction factor between mass concrete and sand, $\tan(\delta)$ 0.4

Drainage control within the backfill materials is recommended to minimize the hydrostatic pressure exerted on the wall structure. Drainage can be achieved using lateral drain pipes. The drain pipes should consist of perforated pipe (weeping tile) and should be surrounded with properly graded fill material leading to a positive outlet.

6.4 Structural Fill

Structural fill should consist of a well-graded, free-draining granular material such as pit run sand and gravel or processed, well-graded rockfill. The maximum particle size should generally not exceed 200 mm.

Site excavated fill materials may be suitable for re-use as structural fill provided the moisture content is maintained within 1 to 2 percent below its optimum value and are free of deleterious materials (i.e. organics). If consideration is given to reusing the in-situ soils, the above noted concerns regarding handling and placement of these materials under wet and freezing conditions must be considered.

GEOTECHNICAL INVESTIGATION, BUNKER RETAINING WALL ASSESSMENT, CAPE SPEAR NATIONAL HISTORIC SITE, NL

QUALITY ASSURANCE/QUALITY CONTROL
June 15, 2016

Structural fill should be placed in horizontal lifts and compacted to the specifications outlined below in Table 6.1. In addition to the compaction requirements presented in Table 6.1, visual approval of all structural fill during placement is recommended. The lift thickness used during fill placement should be compatible with the compaction equipment and material type to ensure the required density throughout. Due to the particle size distribution of coarser grained soils (e.g., rockfill), verification of the field density by visual inspection during proof rolling by geotechnical personnel will be required. As a general guide, engineered fill should be placed in 300 to 400 mm lifts and compacted with a 10 tonne vibratory roller.

Table 6.1 Recommended Structural Fill Compaction Requirements

Structural Fill Application	Minimum Compaction Requirements Percent of Standard Proctor (ASTM D698) Maximum Dry Density, %
Foundation Areas	100
General Backfill	95

7.0 QUALITY ASSURANCE/QUALITY CONTROL

It is recommended that a program of quality assurance, quality control and inspection be carried out by geotechnical personnel during earthworks and construction. Such a program should include verification of excavation bases and approval before placement of additional fill or footing concrete; founding level inspection and approval; compaction testing during fill placement; subgrade proof-rolling, and field and laboratory testing during placement of granular fill materials.

GEOTECHNICAL INVESTIGATION, BUNKER RETAINING WALL ASSESSMENT, CAPE SPEAR NATIONAL HISTORIC SITE, NL

CLOSURE
June 15, 2016


8.0 CLOSURE

Use of this report is subject to the Statement of General Conditions, attached. It is the responsibility of Parks Canada who is identified as "the Client" within the Statement of General Conditions, and its agents to review the conditions and to notify Stantec should any of these not be satisfied. The Statement of General Conditions addresses the following: use of the report; basis of the report; standard of care; interpretation of site conditions; varying or unexpected site conditions; and planning, design, or construction.

Development or design plans and specifications should be reviewed by Stantec to confirm that this report addresses the project specifics and that the contents of this report have been properly interpreted. Site work relating to the recommendations included in this report should be carried out in the presence of a qualified geotechnical engineer; Stantec cannot be responsible for site work carried out without being present.

We trust this report meets your present requirements. Should any additional information be required, please do not hesitate to contact our office at your convenience.


Sincerely,
STANTEC CONSULTING LTD



Sterling Parsons, M. Eng., P.Eng.
Senior Associate, Senior Geotechnical Engineer
sterling.parsons@stantec.com



Rajib Dey, PhD
Geotechnical Engineer
rajib.dey@stantec.com





ATTACHMENTS

Statement of General Conditions

Symbols and Terms Used on Borehole and Test Pit Records

Test Pit Records

Test Pit Photographs

Figure 1 – Gradation Curves

Figure No: 01: Test Pit Location Plan

STATEMENT OF GENERAL CONDITIONS

USE OF THIS REPORT: This report has been prepared for the sole benefit of the Client or its agent and may not be used by any third party without the express written consent of Stantec Consulting Ltd. and the Client. Any use which a third party makes of this report is the responsibility of such third party.

BASIS OF THE REPORT: The information, opinions, and/or recommendations made in this report are in accordance with Stantec Consulting Ltd.'s present understanding of the site specific project as described by the Client. The applicability of these is restricted to the site conditions encountered at the time of the investigation or study. If the proposed site specific project differs or is modified from what is described in this report or if the site conditions are altered, this report is no longer valid unless Stantec Consulting Ltd. is requested by the Client to review and revise the report to reflect the differing or modified project specifics and/or the altered site conditions.

STANDARD OF CARE: Preparation of this report, and all associated work, was carried out in accordance with the normally accepted standard of care in the state or province of execution for the specific professional service provided to the Client. No other warranty is made.

INTERPRETATION OF SITE CONDITIONS: Soil, rock, or other material descriptions, and statements regarding their condition, made in this report are based on site conditions encountered by Stantec Consulting Ltd. at the time of the work and at the specific testing and/or sampling locations. Classifications and statements of condition have been made in accordance with normally accepted practices which are judgmental in nature; no specific description should be considered exact, but rather reflective of the anticipated material behavior. Extrapolation of in situ conditions can only be made to some limited extent beyond the sampling or test points. The extent depends on variability of the soil, rock and groundwater conditions as influenced by geological processes, construction activity, and site use.

VARYING OR UNEXPECTED CONDITIONS: Should any site or subsurface conditions be encountered that are different from those described in this report or encountered at the test locations, Stantec Consulting Ltd. must be notified immediately to assess if the varying or unexpected conditions are substantial and if reassessments of the report conclusions or recommendations are required. Stantec Consulting Ltd. will not be responsible to any party for damages incurred as a result of failing to notify Stantec Consulting Ltd. that differing site or subsurface conditions are present upon becoming aware of such conditions.

PLANNING, DESIGN, OR CONSTRUCTION: Development or design plans and specifications should be reviewed by Stantec Consulting Ltd., sufficiently ahead of initiating the next project stage (property acquisition, tender, construction, etc.), to confirm that this report completely addresses the elaborated project specifics and that the contents of this report have been properly interpreted. Specialty quality assurance services (field observations and testing) during construction are a necessary part of the evaluation of sub-subsurface conditions and site preparation works. Site work relating to the recommendations included in this report should only be carried out in the presence of a qualified geotechnical engineer; Stantec Consulting Ltd. cannot be responsible for site work carried out without being present.

SYMBOLS AND TERMS USED ON BOREHOLE AND TEST PIT RECORDS

SOIL DESCRIPTION

Terminology describing common soil genesis:

<i>Rootmat</i>	- vegetation, roots and moss with organic matter and topsoil typically forming a mattress at the ground surface
<i>Topsoil</i>	- mixture of soil and humus capable of supporting vegetative growth
<i>Peat</i>	- mixture of visible and invisible fragments of decayed organic matter
<i>Till</i>	- unstratified glacial deposit which may range from clay to boulders
<i>Fill</i>	- material below the surface identified as placed by humans (excluding buried services)

Terminology describing soil structure:

<i>Desiccated</i>	- having visible signs of weathering by oxidization of clay minerals, shrinkage cracks, etc.
<i>Fissured</i>	- having cracks, and hence a blocky structure
<i>Varved</i>	- composed of regular alternating layers of silt and clay
<i>Stratified</i>	- composed of alternating successions of different soil types, e.g. silt and sand
<i>Layer</i>	- > 75 mm in thickness
<i>Seam</i>	- 2 mm to 75 mm in thickness
<i>Parting</i>	- < 2 mm in thickness

Terminology describing soil types:

The classification of soil types are made on the basis of grain size and plasticity in accordance with the Unified Soil Classification System (USCS) (ASTM D 2487 or D 2488) which excludes particles larger than 75 mm. For particles larger than 75 mm, and for defining percent clay fraction in hydrometer results, definitions proposed by Canadian Foundation Engineering Manual, 4th Edition are used. The USCS provides a group symbol (e.g. SM) and group name (e.g. silty sand) for identification.

Terminology describing cobbles, boulders, and non-matrix materials (organic matter or debris):

Terminology describing materials outside the USCS, (e.g. particles larger than 75 mm, visible organic matter, and construction debris) is based upon the proportion of these materials present:

<i>Trace, or occasional</i>	Less than 10%
<i>Some</i>	10-20%
<i>Frequent</i>	> 20%

Terminology describing compactness of cohesionless soils:

The standard terminology to describe cohesionless soils includes compactness (formerly "relative density"), as determined by the Standard Penetration Test (SPT) N-Value - also known as N-Index. The SPT N-Value is described further on page 3. A relationship between compactness condition and N-Value is shown in the following table.

Compactness Condition	SPT N-Value
<i>Very Loose</i>	<4
<i>Loose</i>	4-10
<i>Compact</i>	10-30
<i>Dense</i>	30-50
<i>Very Dense</i>	>50

Terminology describing consistency of cohesive soils:

The standard terminology to describe cohesive soils includes the consistency, which is based on undrained shear strength as measured by *in situ* vane tests, penetrometer tests, or unconfined compression tests. Consistency may be crudely estimated from SPT N-Value based on the correlation shown in the following table (Terzaghi and Peck, 1967). The correlation to SPT N-Value is used with caution as it is only very approximate.

Consistency	Undrained Shear Strength		Approximate SPT N-Value
	kips/sq.ft.	kPa	
<i>Very Soft</i>	<0.25	<12.5	<2
<i>Soft</i>	0.25 - 0.5	12.5 - 25	2-4
<i>Firm</i>	0.5 - 1.0	25 - 50	4-8
<i>Stiff</i>	1.0 - 2.0	50 - 100	8-15
<i>Very Stiff</i>	2.0 - 4.0	100 - 200	15-30
<i>Hard</i>	>4.0	>200	>30

ROCK DESCRIPTION

Except where specified below, terminology for describing rock is as defined by the International Society for Rock Mechanics (ISRM) 2007 publication "The Complete ISRM Suggested Methods for Rock Characterization, Testing and Monitoring: 1974-2006"

Terminology describing rock quality:

RQD	Rock Mass Quality
0-25	Very Poor Quality
25-50	Poor Quality
50-75	Fair Quality
75-90	Good Quality
90-100	Excellent Quality

Alternate (Colloquial) Rock Mass Quality	
Very Severely Fractured	Crushed
Severely Fractured	Shattered or Very Blocky
Fractured	Blocky
Moderately Jointed	Sound
Intact	Very Sound

RQD (Rock Quality Designation) denotes the percentage of intact and sound rock retrieved from a borehole of any orientation. All pieces of intact and sound rock core equal to or greater than 100 mm (4 in.) long are summed and divided by the total length of the core run. RQD is determined in accordance with ASTM D6032.

SCR (Solid Core Recovery) denotes the percentage of solid core (cylindrical) retrieved from a borehole of any orientation. All pieces of solid (cylindrical) core are summed and divided by the total length of the core run (It excludes all portions of core pieces that are not fully cylindrical as well as crushed or rubble zones).

Fracture Index (FI) is defined as the number of naturally occurring fractures within a given length of core. The Fracture Index is reported as a simple count of natural occurring fractures.

Terminology describing rock with respect to discontinuity and bedding spacing:

Spacing (mm)	Discontinuities	Bedding
>6000	Extremely Wide	-
2000-6000	Very Wide	Very Thick
600-2000	Wide	Thick
200-600	Moderate	Medium
60-200	Close	Thin
20-60	Very Close	Very Thin
<20	Extremely Close	Laminated
<6	-	Thinly Laminated

Terminology describing rock strength:


Strength Classification	Grade	Unconfined Compressive Strength (MPa)
Extremely Weak	R0	<1
Very Weak	R1	1 – 5
Weak	R2	5 – 25
Medium Strong	R3	25 – 50
Strong	R4	50 – 100
Very Strong	R5	100 – 250
Extremely Strong	R6	>250

Terminology describing rock weathering:

Term	Symbol	Description
Fresh	W1	No visible signs of rock weathering. Slight discoloration along major discontinuities
Slightly	W2	Discoloration indicates weathering of rock on discontinuity surfaces. All the rock material may be discolored.
Moderately	W3	Less than half the rock is decomposed and/or disintegrated into soil.
Highly	W4	More than half the rock is decomposed and/or disintegrated into soil.
Completely	W5	All the rock material is decomposed and/or disintegrated into soil. The original mass structure is still largely intact.
Residual Soil	W6	All the rock converted to soil. Structure and fabric destroyed.

STRATA PLOT


Strata plots symbolize the soil or bedrock description. They are combinations of the following basic symbols. The dimensions within the strata symbols are not indicative of the particle size, layer thickness, etc.



SAMPLE TYPE

SS	Split spoon sample (obtained by performing the Standard Penetration Test)
ST	Shelby tube or thin wall tube
DP	Direct-Push sample (small diameter tube sampler hydraulically advanced)
PS	Piston sample
BS	Bulk sample
HQ, NQ, BQ, etc.	Rock core samples obtained with the use of standard size diamond coring bits.

WATER LEVEL MEASUREMENT



measured in standpipe, piezometer, or well



inferred

RECOVERY

For soil samples, the recovery is recorded as the length of the soil sample recovered. For rock core, recovery is defined as the total cumulative length of all core recovered in the core barrel divided by the length drilled and is recorded as a percentage on a per run basis.

N-VALUE

Numbers in this column are the field results of the Standard Penetration Test: the number of blows of a 140 pound (63.5 kg) hammer falling 30 inches (760 mm), required to drive a 2 inch (50.8 mm) O.D. split spoon sampler one foot (300 mm) into the soil. In accordance with ASTM D1586, the N-Value equals the sum of the number of blows (N) required to drive the sampler over the interval of 6 to 18 in. (150 to 450 mm). However, when a 24 in. (610 mm) sampler is used, the number of blows (N) required to drive the sampler over the interval of 12 to 24 in. (300 to 610 mm) may be reported if this value is lower. For split spoon samples where insufficient penetration was achieved and N-Values cannot be presented, the number of blows are reported over sampler penetration in millimetres (e.g. 50/75). Some design methods make use of N-values corrected for various factors such as overburden pressure, energy ratio, borehole diameter, etc. No corrections have been applied to the N-values presented on the log.

DYNAMIC CONE PENETRATION TEST (DCPT)

Dynamic cone penetration tests are performed using a standard 60 degree apex cone connected to 'A' size drill rods with the same standard fall height and weight as the Standard Penetration Test. The DCPT value is the number of blows of the hammer required to drive the cone one foot (300 mm) into the soil. The DCPT is used as a probe to assess soil variability.

OTHER TESTS

S	Sieve analysis
H	Hydrometer analysis
k	Laboratory permeability
y	Unit weight
G _s	Specific gravity of soil particles
CD	Consolidated drained triaxial
CU	Consolidated undrained triaxial with pore pressure measurements
UU	Unconsolidated undrained triaxial
DS	Direct Shear
C	Consolidation
Q _u	Unconfined compression
I _p	Point Load Index (I _p on Borehole Record equals I _p (50) in which the index is corrected to a reference diameter of 50 mm)

	Single packer permeability test; test interval from depth shown to bottom of borehole
	Double packer permeability test; test interval as indicated
	Falling head permeability test using casing
	Falling head permeability test using well point or piezometer



TEST PIT RECORD


CLIENT Parks Canada
 PROJECT Geotechnical Investigation - Cape Spear Bunker Retaining Wall Assessment
 LOCATION Cape Spear National Historic Site, NL
 DATES (mm-dd-yy): DUG 5-24-16 WATER LEVEL N/A

TEST PIT No. TP-12
 PROJECT No. 133347329
 DATUM N/A

DEPTH (m)	ELEVATION (m)	DESCRIPTION	STRATA PLOT	WATER LEVEL	SAMPLES			UNDRAINED SHEAR STRENGTH - kPa ★					
					TYPE	NUMBER	OTHER TESTS	20	40	60	80		
0		SOD/ROOTMAT											
		Loose to compact, brown to black, silty SAND with gravel (SM); some cobbles, occasional boulders											
					BS	1							
1		End of Test Pit No water seepage observed. Backhoe refusal on inferred bedrock.											
2													

TEST PIT RECORD

CLIENT Parks Canada
 PROJECT Geotechnical Investigation - Cape Spear Bunker Retaining Wall Assessment
 LOCATION Cape Spear National Historic Site, NL
 DATES (mm-dd-yy): DUG 5-24-16 WATER LEVEL N/A TEST PIT No. TP-13
 PROJECT No. 133347329
 DATUM N/A

DEPTH (m)	ELEVATION (m)	DESCRIPTION	STRATA PLOT	WATER LEVEL	SAMPLES			UNDRAINED SHEAR STRENGTH - kPa ★		WATER CONTENT & ATTERBERG LIMITS	
					TYPE	NUMBER	OTHER TESTS	20	40	60	80
0		Loose, grey, GRAVEL with sand and silt (GP-GM): FILL - trace rootlets Loose to compact, brown to reddish brown, silty SAND with gravel (SM); some cobbles - brown weathering seam observed throughout the layer - trace rootlets at top of layer									
		End of Test Pit No water seepage observed. Backhoe refusal on inferred bedrock.									



TEST PIT RECORD

CLIENT Parks Canada
 PROJECT Geotechnical Investigation - Cape Spear Bunker Retaining Wall Assessment
 LOCATION Cape Spear National Historic Site, NL
 DATES (mm-dd-yy): DUG 5-24-16 WATER LEVEL N/A TEST PIT No. TP-14
 PROJECT No. 133347329
 DATUM N/A

DEPTH (m)	ELEVATION (m)	DESCRIPTION	STRATA PLOT	WATER LEVEL	SAMPLES			UNDRAINED SHEAR STRENGTH - kPa ★					
					TYPE	NUMBER	OTHER TESTS	20	40	60	80		
0		SOD/ROOTMAT											
		Loose, black to brown, silty SAND with gravel (SM) to SAND with silt and gravel (SP-SM); occasional to some cobbles - with some rootlets, organics - 0.13 m thick black weathered organic layer encountered at 1.14 m depth - slight odour observed from organic material											
					BS	1							
		End of test pit No water seepage observed Backhoe refusal on inferred bedrock											

GEOTECHNICAL INVESTIGATION, CAPE SPEAR BUNKER RETAINING WALL ASSESSMENT, CAPE SPEAR NATIONAL HISTORIC SITE, NL



Test Pit TP-12



Test Pit TP-12 Spoil Pile

GEOTECHNICAL INVESTIGATION, CAPE SPEAR BUNKER RETAINING WALL ASSESSMENT, CAPE SPEAR NATIONAL HISTORIC SITE, NL



Test Pit TP-13



Test Pit TP-13 Spoil pile


**GEOTECHNICAL INVESTIGATION, CAPE SPEAR BUNKER RETAINING WALL ASSESSMENT, CAPE SPEAR
NATIONAL HISTORIC SITE, NL**



Test Pit TP-14



Test Pit TP-14 Spoil Pile



COBBLE	GRAVEL		SAND			SILT and CLAY
	coarse	fine	coarse	medium	fine	

Sample	Depth (m)	Description	W%	W _L	W _p	I _p
● TP-12 BS01	0.84	Silty SAND with gravel (SM)	9.6			

Sample	Depth (m)	D100	D60	D30	D10	%Gravel	%Sand	%Silt	%Clay
● TP-12 BS01	0.84	56.00	4.63	0.358		39.0	48.1	12.9	

REMARKS:

	Client: Parks Canada	FIGURE 1 GRADATION CURVES
	Project: Geotechnical Investigation - Cape Spear Bunker Retaining Wall Assessment	
	Project No.: 133347329	
	Location: Cape Spear National Historic Site, NL	

V:\01333\ACTIVE\133347244 - CAPE SPEAR\DESIGN\DRAWING\CIVIL\C3D\MODEL_FILES\Testpits_Drawing.dwg
2016/06/13 9:32 AM By: Benson, Amanda



ORIGINAL SHEET - ANSI B



141 Kelsey Drive
St. John's NL
www.stantec.com

Legend

■ - TEST PIT LOCATION

Notes

Client/Project
PARKS CANADA
GEOTECHNICAL INVESTIGATION - CAPE SPEAR BUNKER
RETAINING WALL ASSESSMENT
Figure No.
01
Title
TEST PIT LOCATION PLAN

16.06.13
133447244