



RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
Public Works and Government Services Canada
ATB Place North Tower
10025 Jasper Ave./10025 ave. Jasper
5th floor/5e étage
Edmonton
Alberta
T5J 1S6
Bid Fax: (780) 497-3510

SOLICITATION AMENDMENT MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Public Works and Government Services Canada
ATB Place North Tower
10025 Jasper Ave./10025 ave Jasper
5th floor/5e étage
Edmonton
Alberta
T5J 1S6

Title - Sujet New Driver Training Track	
Solicitation No. - N° de l'invitation EV385-170880/A	Amendment No. - N° modif. 004
Client Reference No. - N° de référence du client RCMP EV385-170880	Date 2016-09-02
GETS Reference No. - N° de référence de SEAG PW-\$PWU-023-10834	
File No. - N° de dossier PWU-6-39130 (023)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2016-09-07	Time Zone Fuseau horaire Mountain Daylight Saving Time MDT
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Taylor (RPC), Ian	Buyer Id - Id de l'acheteur pwu023
Telephone No. - N° de téléphone (780) 566-9487 ()	FAX No. - N° de FAX (780) 497-3510
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction:	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Part 1 To the Specifications

**1.1 To the Table between Summary of Work Section 01 11 00 and Work Restrictions
Section 01 14 00**

- .1 Updated table with the granular material for the driving surfaces.

Part 2 On the Drawings

2.1 New Sheet Detail 04

- .1 Asphalt area detail showing the structure.
- .2 Coconut/Straw matting installation detail.
- .3 Geomembrane installation detail.

4X4 Course		ADDENDUM 4			
Item	Description	Quant.	Units	Unit Price	Amount
1	Sitework				
	Clearing existing vegetation and disposal	33,800	m2		
	Stripping Topsoil	10,200	m3		
	Bulk Excavation (within the construction boundary)	3,878	m3		
	Extra Over for rock Removal	1	Allow	\$9,000	\$9,000
	Minor Dewatering	1	Allow	\$10,000	\$10,000
	Sub-Grade Preparation	4,280	m2		
	Backfill with Owner supplied material located on site.	63,000	m3		
	Geotextiles Straw matting (allowance)	5,000	m2		
	Geotextiles Coconut matting (allowance)	16,500	m2		
	Geotextiles LLDPE Liner (allowance)	1,000	m2		
	Site Rough Grading	51,610	m2		
	Final Grading & Compaction to main roadway	46,960	m2		
	Final Grading & compaction to sediment pond (assumed liner not requi	2,575	m2		
	Asphalt vehicle staging area	340	m2		
	Replace existing topsoil & hydro seed	33,550	m2		
	Tree, shrubs and ground cover planting (allowance)	32,800	m2		
	Road gravels	1,200	M3		
	Traffic signage (allowance)	1	Allow	\$9,000	\$9,000
2	Course Elements				
	Concrete "Mud" Pad	35	m2		
	concrete 200mm thick	7	m3		
	rebar	300	kg		
	formwork	4	m2		
	screed/cure/finish	35	m2		
	extra for grooves	18	m2		
	isolation/control joints	35	lm		
	gravel base, 200mm thick	7	m3		
	traffic topping	35	m2		
	Angled Berms, 45m2 ea, measured flat, 6 No. average depth 900mm	243	m3		
	Pea Gravel Pit	185	m2		
	pea gravel, loose compaction 5-10mm, 500mm thick	93	m3		
	concrete 200mm thick	37	m3		
	rebar	1,555	kg		
	formwork	9	m2		
	screed/cure/finish	185	m2		
	isolation/control joints	35	m2		
	gravel base, 200mm thick	37	m3		
	concrete lock block, 750 x 750 x 1500mm	44	no.		
	Static Winch Hill	4	no.		
	Tree Slalom	38	no.		
	Delineator bollard, 60 mm dia. X 1200mm, c/w reactive spring	38	no.		
	driveable base, 56mmx457mm	38	no.		

Item	Description	Quant.	Units	Unit Price	Amount
2	Course Elements (Continued)				
	Creek Crossing 4 No.	88	m2		
	river rock, 50-300mm	39	m3		
	compacted clay base	49	m3		
	Parallel Telephone Poles, 375mm dia x 4550mm wood pole	9	no.		
	Parallel Offset Railroad Ties, 150 x 2600mm	12	no.		
	Water Ford				
	large river rock	54	m3		
	concrete, 200mm thick	36	m3		
	rebar	1,500	kg		
	formwork	8	m2		
	screed/cure/finish	180	m2		
	isolation/control joints	180	m2		
	gravel base, 200mm thick	36	m3		
	concrete curb, 300mm	13	m		
	concrete lock block, 750 x 750 x 1500mm	30	no.		
	Staggered Railroad Ties, 150 x 2600mm	18	no.		
	Texas Gate	2			
	texas gate	32	m2		
	concrete pile, 150 x 450 mm	12	no.		
	Multiple Berms, 24m2 each, measured flat, 9 no. average depth 500mm	108	m3		
	Rail Crossing				
	segment rail track, 20m	4	no.		
	rail ties, 150 x 250mm	19	no.		
	compacted gravel base	27	m3		
	Ditch Crossing	1	sum		

Item	Description	Quant.	Units	Unit Price	Amount
3	Water Line				
	PVC 150	300	m		
	PVC 50	100	m		
	Valve 250	2	each		
	Valve 150	2	each		
	Valve 50	1	each		
	Hose Bib	1	each		
	Hydrant 150	1	each		
	Tee 250 x 150	1	each		
	Tee 150 x 50	1	each		
	Tie to existing	2	each		
	Testing and disinfection	400	m		

4	Sub-total	
	Escalation Allowance	Excluded
	Construction Allowance	Excluded
5	Total Construction Estimate Including Contingencies	
	GST	Excluded