
DIVISION 02

Part 1 General

1.1 REFERENCES

- .1 N/A.

1.2 MEASUREMENT PROCEDURES

- .1 This work is incidental and will not be measured for payment.

Part 2 Products

2.1 EQUIPMENT

- .1 Leave machinery running only while in use, except where extreme temperatures prohibit shutting machinery down.

Part 3 Execution

3.1 PREPARATION

- .1 Inspect site with Departmental Representative and verify extent and location of items designated for removal, disposal, alternative disposal, recycling, salvage and items to remain.
- .2 Locate and protect utilities. Preserve active utilities traversing site in operating condition.

3.2 REMOVAL OF HAZARDOUS WASTES

- .1 Remove contaminated or dangerous materials defined by authorities having jurisdiction, relating to environmental protection, from site and dispose of in safe manner to minimize danger at site or during disposal.

3.3 REMOVAL OPERATIONS

- .1 Remove items as indicated.
- .2 Do not disturb items designated to remain in place.
- .3 Removal of pavements, curbs and gutters:
 - .1 Square up adjacent surfaces to remain in place by saw cutting or other method approved by Departmental Representative.
 - .2 Protect adjacent joints and load transfer devices.
 - .3 Protect underlying and adjacent granular materials.
- .4 Stockpile topsoil for final grading and landscaping:
 - .1 Provide erosion control and seeding if not immediately used.
- .5 Disposal of Material:

-
- .1 Materials not designated for salvage or reuse on site shall become the property of the Contractor and be disposed of offsite in a manner and at a location acceptable to the Departmental Representative.
 - .6 Backfill:
 - .1 Backfill in areas as indicated and in accordance with Section 31 23 33.01 - Excavating, Trenching and Backfilling.
 - 3.4 STOCKPILING
 - .1 Label stockpiles, indicating material type and quantity.
 - .2 Designate appropriate security resources/measures to prevent vandalism, damage and theft.
 - .3 Locate stockpiled materials convenient for use in new construction to eliminate double handling wherever possible.
 - .4 Stockpile materials designated for alternate disposal in location which facilitates removal from site and examination by potential end markets, and which does not impede disassembly, processing, or hauling procedures.
 - .5 In all cases, onsite material stockpile locations and stockpiling procedures shall require prior approval from the Departmental Representative.
 - 3.5 RESTORATION
 - .1 Restore areas and existing works outside areas of demolition to match condition of adjacent, undisturbed areas.
 - .2 Use soil treatments and procedures which are not harmful to health, are not injurious to plants, and do not endanger wildlife, adjacent water courses or ground water.
 - 3.6 CLEANING
 - .1 Progress Cleaning: clean in accordance with Section 01 74 11 – Cleaning.
 - .1 Leave Work area clean at end of each day.
 - .2 Remove debris, trim surfaces and leave work site clean, upon completion of Work
 - .3 Use cleaning solutions and procedures which are not harmful to health, are not injurious to plants, and do not endanger wildlife, adjacent water courses or ground water.
 - .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 – Cleaning.
 - 3.7 PROTECTION
 - .1 Repair damage to adjacent materials or property caused by selective site demolition.

END OF SECTION