

PART 1 - GENERAL

- 1.1 SECTION INCLUDES .1 Barriers.  
.2 Traffic Controls.
- 1.2 INSTALLATION AND REMOVAL .1 Provide temporary controls in order to execute work expeditiously.  
.2 Remove from site all such work after use.
- 1.3 HOARDING .1 Erect temporary site enclosure using new 1.2 m high snow fence wired to rolled steel "T" bar fence posts spaced at 2.4 m centres. Provide one lockable truck gate. Maintain fence in good repair.
- 1.4 GUARD RAILS AND BARRICARDS .1 Provide secure, rigid guard rails and barricades around open excavations.  
.2 Provide barricades along wharf structure when wheelguard is removed.  
.3 Provide as required by governing authorities.
- 1.5 ACCESS TO SITE .1 Provide and maintain access to adjacent facilities.
- 1.6 PUBLIC TRAFFIC FLOW .1 Provide and maintain competent signal flag operators, traffic signals, barricades and flares, lights, or lanterns as required to perform work and protect the public.
- 1.7 FIRE ROUTES .1 Maintain access to property including overhead clearances for use by emergency response vehicles.

- |  |    |  |
|--|----|--|
| <u>1.8 PROTECTION FOR<br/>OFF-SITE AND PUBLIC<br/>PROPERTY</u> | .1 | Protect surrounding private and public property from damage during performance of work.  |
|  | .2 | Be responsible for damage incurred.  |
| <u>1.9 MEASUREMENT FOR<br/>PAYMENT</u>                         | .1 | No separate measurements for payment shall be made for items under this section. Include costs for Temporary Barriers & Enclosures in the Lump Sum portion of the work on the Bid and Acceptance Form. |

PART 2 - PRODUCTS

2.1 NOT USED

PART 3 - EXECUTION

3.1 NOT USED