

## **PART 1 - GENERAL**

### **1.1 DESCRIPTION**

- .1 This section specifies requirements for demolishing and removing wholly or in part various items designated to be removed or partially removed.
- .2 Demolition and removal will consist of, but not necessarily be limited to, the following:
  - .1 Complete removal and disposal of the existing marginal wharf and underlying timbers, as shown on the drawings.
  - .2 Complete removal and disposal of the stone barricades, as shown on the drawings.
  - .3 Complete removal and disposal of the floating dock crib, as shown on the drawings.
  - .4 Disconnect, remove and temporarily store gangway, crib connection plate, floating docks, chain and concrete anchors during construction activities, as directed by the Departmental Representative. Reinstall gangway, crib connection plate, floating docks, chain and concrete anchors, as shown on the drawings.
  - .5 Saw cut, remove and dispose of asphalt to limits shown on the drawings. Excavate, scarify and compact existing sub-grade, as required, to facilitate placement of new granulars, asphalt and concrete slab-on-grade to new grades indicated on the drawings.
- .3 Treated timber is present in the existing wharf structure, limiting disposal to an approved waste disposal site.

### **1.2 PROTECTION**

- .1 Protect existing objects designated to remain. In event of damage, immediately replace or make repairs to approval of and at no additional cost to Canada.
- .2 Place a floating boom around entire demolition site to prevent loss of any materials. Remove all floating debris from water on a routing and timely basis.

## **PART 2 - PRODUCTS**

N/A

### **PART 3 - EXECUTION**

#### **3.1 EXECUTION**

- .1 Inspect site and verify with the Departmental Representative objects designated for removal.
- .2 Locate and protect utility lines. Preserve in operating condition active utilities traversing site.

#### **3.2 REMOVAL**

- .1 Remove in their entirety all materials and objects specified for removal.
- .2 Do not disturb adjacent work designated to remain in place.

#### **3.3 DISPOSAL OF MATERIAL**

- .1 All demolished materials, except materials designated to be salvaged for the Departmental Representative or reused on the project, will be property of Contractor and will be removed from site and disposed to satisfaction of Departmental Representative.
- .2 Contractor to dispose of all demolished materials at an approved waste disposal site, including all treated timbers. Ensure that disposal site is approved and willing to accommodate any materials, including treated timbers disposed of from work site.
- .3 Contractor shall obtain and pay for all necessary permits and disposal fees for use of an approved waste disposal site.
- .4 Excavated material and dredging from below water to be transported using watertight dump trucks to an approved waste disposal site.

#### **3.4 RESTORATION**

- .1 Upon completion of work, remove debris, trim surfaces and leave work site in clean condition.
- .2 Reinstate areas and existing works outside areas of demolition to conditions that existed prior to commencement of work.