



**Public Works and  
Government Services Canada**

Requisition No. EZ899-171432

Buy & Sell I.D. No. \_\_\_\_\_

**SPECIFICATIONS**

for

Kingsgate Port of Entry  
Staff Parking Paving and PIL Improvement  
Kingsgate, B.C.

Project No. R.082785.001  
August 2016

**APPROVED BY:**

*Active for*  


Regional Manager, AES

Aug. 30/2016

Date



Construction Safety Coordinator

2016-08-30

Date

**TENDER:**



Project Manager

2016-08-30

Date

Section 00 01 10-Index of Plans and Specifications.....1 Page

Division 01 - GENERAL REQUIREMENTS

Section 01 11 55-General Instructions.....8 Pages  
Section 01 33 00-Submittal Procedures.....3 Pages  
Section 01 35 00.06-Special Procedures for Traffic Control.....3 Pages  
Section 01 35 33-Health and Safety Requirements.....10 Pages  
Section 01 35 43-Environmental Procedures.....3 Pages  
Section 01 45 00-Quality Control.....3 Pages  
Section 01 74 11-Cleaning.....1 Page  
Section 01 78 00-Closeout Submittals.....3 Pages

Division 03 - CONCRETE

Section 03 20 00-Concrete Reinforcing.....5 Pages  
Section 03 30 00-Cast-in-Place Concrete.....4 Pages

Division 31 - EARTHWORK

Section 31 05 16-Aggregate Materials.....5 Pages  
Section 31 23 10-Excavating, Trenching and Backfilling.....9 Pages

Division 32 - EXTERIOR IMPROVEMENTS

Section 32 11 23-Aggregate Base Course.....3 Pages  
Section 32 12 14-Asphalt Prime Coats.....3 Pages  
Section 32 12 15-Asphalt Tack Coats.....2 Pages  
Section 32 12 16-Asphalt Paving.....14 Pages  
Section 32 17 23-Pavement Markings.....3 Pages

Division 33 - UTILITIES

Section 33 05 13 - Manholes & Catchbasin Structures.....6 Pages  
Section 33 41 00 - Storm Utility Drainage Piping.....11 Pages

LIST OF DRAWINGS (Bound Separately)

Sheet No.	Description
01	Site Improvements
02	Details
03	Concrete Slab Details



1. CODES .1 Perform work to CURRENT Codes, Construction Standards and Bylaws, including Amendments up to the TENDER closing date
2. DESCRIPTION OF WORK .1 Work under this Contract comprises general construction for paving of the existing gravel staff parking area and replacement of the existing asphalt with reinforced concrete at the PIL at the Kingsgate Port of Entry in Southeastern British Columbia.
- .2 Work to be performed under this Contract includes, but is not limited to, the following items covered further in the Contract documents:
- .1 Submit Traffic Management Plan to Departmental Representative for review prior to mobilizing to site.
- .2 Remove existing asphalt and concrete in two phases
- .3 Prepare, re-grade, and test the base gravels.
- .4 Install reinforced concrete as indicated including testing
- .5 Install sidewalks and letdowns as indicated including tests
- .6 Complete asphalt paving of staff parking and complete tests
- .7 Complete site restorations to match existing conditions.
- .8 Provide the Department Representative will all test reports and final documentation.
3. CONTRACT DOCUMENTS .1 The Contract documents, drawings and specifications are intended to complement each other, and to provide for and include everything necessary for the completion of the work.
- .2 Drawings are, in general, diagrammatic and are intended to indicate the scope and general arrangement of the work.
4. OTHER CONTRACTS .1 Cooperate with other Contractors in carrying out their respective works and carry out instructions from Departmental Representative.
- .2 Coordinate work with that of other Contractors (if applicable). If any part of work under this Contract depends for its proper execution or result upon work of another Contractor, report promptly to

Departmental Representative, in writing, any defects which may interfere with proper execution of this Work.

5. DIVISION OF SPECIFICATIONS

- .1 The specifications are subdivided in accordance with the current 6-digit National Master Specifications System.
- .2 A division may consist of the work of more than 1 subcontractor. Responsibility for determining which subcontractor provides the labour, material, equipment and services required to complete the work rests solely with the Contractor.
- .3 In the event of discrepancies or conflicts when interpreting the drawings and specifications, the specifications govern.

6. TIME OF COMPLETION

- .1 Total completion of the site work shall be no later than 6 weeks from contract award date.

7. HOURS OF WORK

- .1 No hours of work restrictions have been applied to this contract.

8. WORK SCHEDULE

- .1 Carry on work as follows:
  - .1 Within 10 working days after Contract award, provide a schedule showing anticipated progress stages and final completion of the work within the time period required by the Contract documents. Indicate the following:
    - .1 Submission of shop drawings, product data, MSDS sheets and samples.
    - .2 Commencement and completion of work of each section of the specifications or trade for each phase as outlined.
    - .3 Final completion date within the time period required by the Contract documents.
  - .2 Do not change approved Schedule without notifying Departmental Representative.
  - .3 Interim reviews of work progress based on work schedule will be conducted as decided by Departmental Representative and schedule updated by Contractor in conjunction with and to approval of Departmental Representative.

9. COST BREAKDOWN

- .1 Before submitting the first progress claim, submit a breakdown of the Contract lump sum prices in detail as directed by the Departmental Representative and aggregating Contract price.

10. CODES, BYLAWS, STANDARDS

- .1 Perform work in accordance with the National

Building Code of Canada, and other indicated Codes, Construction Standards and/or any other Code or Bylaw of local application.

- .2 Comply with applicable local bylaws, rules and regulations enforced at the location concerned.
- .3 Meet or exceed requirements of Contract documents, specified standards, codes and referenced documents.
- .4 In any case of conflict or discrepancy, the most stringent requirements shall apply.

11. DOCUMENTS REQUIRED

- .1 Maintain 1 copy each of the following at the job site:
  - .1 Contract drawings.
  - .2 Contract specifications.
  - .3 Addenda to Contract documents.
  - .4 Copy of approved work schedule.
  - .5 Reviewed/approved shop drawings.
  - .6 Change orders.
  - .7 Other modifications to Contract.
  - .8 Field test reports.
  - .9 Reviewed/approved samples.
  - .10 Manufacturers' installation and application instructions.
  - .11 One set of record drawings and specifications for "as-built" purposes.
  - .12 National Building Code of Canada.
  - .13 Current construction standards of workmanship listed in technical Sections.

12. REGULATORY REQUIREMENTS

- .1 Obtain and pay for - Building Permit, Certificates, Licenses and other permits required by regulatory municipal, provincial or federal authorities to complete the work.
- .2 Provide inspection authorities with plans and information required for issue of acceptance certificates.
- .3 Furnish inspection certificates in evidence that the work installed conforms with the requirements of the authority having jurisdiction.

13. CONTRACTOR'S USE OF SITE

- .1 Site located on Canada Border Services Agency (CBSA) property at the Kingsgate Port of Entry.
- .2 Use of site:
  - .1 Assume responsibilities for work areas for performance of this work.
  - .2 Be responsible for coordination of all work activities on site, including the work of other contractors engaged by the Departmental

- Representative.
- .3 Perform work in accordance with Contract documents. Ensure work is carried out in accordance with indicated phasing.
  - .4 Do not unreasonably encumber site with material or equipment
  - .5 Accept liability for damage, safety of equipment and overloading of existing equipment.
  - .6 Provide portable toilet for use by crew during construction.

- .3 The border crossing will remain open during entire construction period and the contractor is expected work with CBSA to minimize any disruptions.
- .4 Co-operate with Department Representative in scheduling operations to minimize conflict with CBSA or public.
- .6 Execute work with least possible interference or disturbance to the operations and normal use of premises. Arrange with Departmental Representative to facilitate execution of work.
- .7 Repair or replace portions of existing work which have been altered during construction operations to match existing or adjoining work, as directed by Departmental Representative.
- .8 At completion of operations condition of existing work: equal to or better than that which existed before new work started.
- .9 Attend progress, safety and site security orientation meetings.

14. EXAMINATION

- .1 Examine site and be familiar and conversant with existing conditions likely to affect work.
- .2 Provide photographs of existing conditions, objects and structures prior to the start of the project.

15. EXISTING SERVICES

- .1 Notify, Departmental Representative and utility companies of intended interruption of services and obtain required permission.
- .2 Where Work involves breaking into or connecting to existing services, give the Departmental Representative 48 hours notice for necessary interruption throughout course of work. Minimize duration of interruptions. Carry out work at times as directed by governing authorities with minimum disturbance to pedestrian, vehicular traffic and tenant operations.

- .3 Provide alternative routes for personnel and pedestrian and vehicular traffic as applicable.
- .4 Establish location and extent of service lines in area of work before starting Work. Notify Departmental Representative of findings.
- .5 Submit schedule to and obtain approval from Departmental Representative for any shut-down or closure of active service or facility including power and communications services. Adhere to approved schedule and provide notice to affected parties.
- .6 Provide temporary services when directed by Departmental Representative to maintain critical buildings and tenant systems.
- .7 Provide adequate bridging over trenches which traveled areas to permit normal traffic.
- .8 Where unknown services are encountered, immediately advise Departmental Representative and confirm findings in writing.
- .9 Protect, relocate or maintain existing active services. When inactive services are encountered, cap off in manner approved by authorities having jurisdiction.
- .10 Record locations of maintained, re-routed and abandoned service lines.

16. LOCATION OF EQUIPMENT  
AND FIXTURES

- .1 Location of equipment, fixtures and outlets indicated or specified are to be considered as approximate.
- .2 Locate equipment, fixtures and distribution systems to provide minimum interference and maximum usable space, and in accordance with manufacturer's recommendations for safety, access and maintenance.
- .3 Inform Departmental Representative of impending installation and obtain his approval for actual location.
- .4 Submit field drawings or shop drawings to indicate the relative position of various services and equipment when required by the Departmental Representative and/or as specified.

17. SETTING OUT OF WORK

- .1 Assume full responsibility for and execute complete layout of work to locations, lines and elevations indicated.

- .2 Provide devices needed to lay out and construct work.
- .3 Supply such devices as templates required to facilitate Departmental Representative's inspection of work.

18. QUALITY OF WORK

- .1 Ensure that quality workmanship is performed through use of skilled tradesmen, under supervision of qualified journeyman.
- .2 In cases of dispute, decisions as to standard or quality of work rest solely with the Departmental Representative, whose decision is final.

19. WORKS COORDINATION

- .1 Coordinate work of subtrades:
  - .1 Designate one person to be responsible for review of contract documents and shop drawings and managing coordination of Work.
  - .2 Convene meetings between subcontractors whose work interfaces and ensure awareness of areas and extent of interface required.
- .2 Provide each subcontractor with complete plans and specifications for Contract, to assist them in planning and carrying out their respective work.
- .3 Develop coordination drawings when required, illustrating potential interference between work of various trades and distribute to affected parties.
  - .1 Pay particularly close attention to overhead work above ceilings and within or near to building structural elements.
  - .2 Identify on coordination drawings, building elements, services lines, rough-in points and indicate location services entrance to site.
  - .3 Facilitate meeting and review coordination drawings. Ensure subcontractors agree and sign off on drawings.
  - .4 Publish minutes of each meeting.
  - .5 Plan and coordinate work in such a way to minimize quantity of service line offsets.
  - .6 Submit copy of coordination drawings and meeting minutes to Departmental Representative for information purposes.
- .4 Submit shop drawings and order of prefabricated equipment or rebuilt components only after coordination meeting for such items has taken place.
- .5 Work cooperation:
  - .1 Ensure cooperation between trades in order to facilitate general progress of Work and avoid situations of spatial interference.
  - .2 Ensure that each trade provides all other trades reasonable opportunity for completion of Work and in such a way as to prevent unnecessary delays, cutting, patching and



removal or replacement of completed work.  
.3 Ensure disputes between subcontractors are resolved.

.6 The Departmental Representative is not responsible for, or accountable for extra costs incurred as a result of Contractor's failure to coordinate Work.

.7 Maintain efficient and continuous supervision.

20. APPROVAL OF SHOP  
DRAWINGS, PRODUCT DATA AND  
SAMPLES

.1 In accordance with Section 013300, submit the requested shop drawings, product data, MSDS sheets and samples indicated in each of the technical Sections.

.2 Allow sufficient time for the following:

- .1 Review of product data.
- .2 Approval of shop drawings.
- .3 Review of re-submission.

21. PROJECT MEETINGS

.1 Departmental Representative will arrange project meetings and assume responsibility for setting times and recording and distributing minutes.

22. TESTING AND INSPECTIONS

.1 See Section 01 45 00 - QUALITY CONTROL

.2 The contractor shall engage and pay for the services of an approved independent testing agency of test laboratory to complete all testing at indicated in Section 01 45 00.

.3 Employment of inspection / testing agencies does not relax responsibility to perform Work in accordance with Contract Documents.

.4 If defects are revealed during inspection and/or testing, appointed agency will request additional inspection and/or testing to ascertain full degree of defect. Correct defect and irregularities as advised by Departmental Representative at no cost to Departmental Representative. Pay costs for re-testing and re-inspection.

23. AS-BUILT DOCUMENTS

.1 The Departmental Representative will provide 2 sets of drawings, 2 sets of specifications, and 2 copies of the original AutoCAD files for "as-built" purposes.

.2 As work progresses, maintain accurate records to show all deviations from the Contract documents. Note on as-built specifications, drawings and shop drawings as changes occur.

.3 Closeout submittals in accordance with Section 01 78 00.

24. CLEANING .1 Daily conduct cleaning and disposal operations. Comply with local ordinances and anti-pollution laws.
- .2 Ensure cleanup of the work areas each day after completion of work.
25. ENVIRONMENTAL PROTECTION .1 Prepare an Erosion and Sediment Control Plan and provide monitoring and maintenance as per Section 01 35 43 - ENVIRONMENTAL PROCEDURES
- .2 Do not dispose of waste or volatile materials into water courses, storm or sanitary sewers.
- .3 Ensure proper disposal procedures in accordance with all applicable territorial regulations.
26. ADDITIONAL DRAWINGS .1 The Departmental Representative may furnish additional drawings for clarification. These additional drawings have the same meaning and intent as if they were included with plans referred to in the Contract documents.
- .2 Upon request, Departmental Representative may furnish up to a maximum of 10 sets of Contract documents for use by the Contractor at no additional cost. Should more than 10 sets of documents be required the Departmental Representative will provide them at additional cost.
27. SYSTEM OF MEASUREMENT .1 The metric system of measurement (SI) will be employed on this Contract.
28. SUBMISSION OF TENDER .1 Submission of a tender is deemed to be confirmation of the fact that the Tenderer has analyzed the Contract documents and is fully conversant with all conditions.

-----END OF SECTION-----

PART 1 - GENERAL

1.1 ADMINISTRATIVE

- .1 Submit to the Departmental Representative submittals listed for review. Submit promptly and in orderly sequence to not cause delay in Work. Failure to submit in ample time is not considered sufficient reason for extension of Contract Time and no claim for extension by reason of such default will be allowed.
- .2 Do not proceed with Work affected by submittal until review is complete.
- .3 Present shop drawings, product data, samples and mock-ups in SI Metric units.
- .4 Where items or information is not produced in SI Metric units converted values are acceptable.
- .5 Review submittals prior to submission to Departmental Representative. This review represents that necessary requirements have been determined and verified, or will be, and that each submittal has been checked and coordinated with requirements of Work and Contract Documents. Submittals not stamped, signed, dated and identified as to specific project will be returned without being examined and considered rejected.
- .6 Notify the Departmental Representative, in writing at time of submission, identifying deviations from requirements of Contract Documents stating reasons for deviations.
- .7 Verify field measurements and affected adjacent Work are coordinated.
- .8 Contractor's responsibility for errors and omissions in submission is not relieved by Departmental Representative's review of submittals.
- .9 Contractor's responsibility for deviations in submission from requirements of Contract Documents is not relieved by Departmental Representative review.
- .10 Keep one reviewed copy of each submission on site.

1.2 SHOP DRAWINGS AND  
PRODUCT DATA

- .1 The term "shop drawings" means drawings, diagrams, illustrations, schedules, performance charts, brochures and other data which are to be provided by Contractor to illustrate details of a portion of Work.

- .2 Indicate materials, methods of construction and attachment or anchorage, erection diagrams, connections, explanatory notes and other information necessary for completion of Work. Where articles or equipment attach or connect to other articles or equipment, indicate that such items have been coordinated, regardless of Section under which adjacent items will be supplied and installed. Indicate cross references to design drawings and specifications.
- .3 Allow 5 working days for Departmental Representative's review of each submission.
- .4 Adjustments made on shop drawings by Departmental Representative are not intended to change Contract Price. If adjustments affect value of Work, state such in writing to Departmental Representative prior to proceeding with Work.
- .5 Make changes in shop drawings as Departmental Representative may require, consistent with Contract Documents. When resubmitting, notify Departmental Representative in writing of revisions other than those requested.
- .6 Accompany submissions with transmittal letter, in duplicate, containing:
  - .1 Date.
  - .2 Project title and number.
  - .3 Contractor's name and address.
  - .4 Identification and quantity of each shop drawing, product data and sample.
  - .5 Other pertinent data.
- .7 Submissions include:
  - .1 Date and revision dates.
  - .2 Project title and number.
  - .3 Name and address of:
    - .1 Subcontractor.
    - .2 Supplier.
    - .3 Manufacturer.
  - .4 Contractor's stamp, signed by Contractor's authorized representative certifying approval of submissions, verification of field measurements and compliance with Contract Documents.
  - .5 Details of appropriate portions of Work as applicable:
    - .1 Fabrication.
    - .2 Layout, showing dimensions, including identified field dimensions, and clearances.
    - .3 Setting or erection details.
    - .4 Capacities.
    - .5 Performance characteristics.
    - .6 Standards.

- .7 Operating weight.
  - .8 Wiring diagrams.
  - .9 Single line and schematic diagrams.
  - .10 Relationship to adjacent work.
- .8 After Departmental Representative's review, distribute copies.
- .9 Submit one PDF of shop drawings for each requirement requested in specification sections and as Departmental Representative may reasonably request.
- .10 Delete information not applicable to project.
- .11 Supplement standard information to provide details applicable to project.
- .12 If upon review by Departmental Representative, no errors or omissions are discovered or if only minor corrections are made, transparency will be returned and fabrication and installation of Work may proceed. If shop drawings are rejected, noted copy will be returned and resubmission of corrected shop drawings, through same procedure indicated above, must be performed before fabrication and installation of Work may proceed.
- .13 The review of shop drawings by Public Works and Government Services Canada (PWGSC) is for sole purpose of ascertaining conformance with general concept.
- .1 This review shall not mean that PWGSC approves detail design inherent in shop drawings, responsibility for which shall remain with Contractor submitting same, and such review shall not relieve Contractor of responsibility for errors or omissions in shop drawings or of responsibility for meeting requirements of construction and Contract Documents.
  - .2 Without restricting generality of foregoing, Contractor is responsible for dimensions to be confirmed and correlated at job site, for information that pertains solely to fabrication processes or to techniques of construction and installation and for co-ordination of Work of sub-trades.
- 1.3 CERTIFICATES AND TRANSCRIPTS
- .1 Immediately after award of Contract, submit Workers' Compensation Board status.
- 1.4 APPROVALS
- .1 Approval of shop drawings: refer to Section 01 11 55, clause 20.0.

PART 1 - GENERAL

1.1 RELATED SECTIONS

- .1 Section 32 11 23-Aggregate Base Courses.
- .2 Section 32 11 16.01-Granular Sub-Base.

1.2 REFERENCES

- .1 Manual of Uniform Traffic Control Devices for Streets and Highways for Canada, Transportation Association of Canada.
- .2 Traffic Control Manual for Work on Roadways, BC Ministry of Transportation

1.3 PROTECTION OF PUBLIC TRAFFIC

- .1 Comply with requirements of Acts, Regulations and By-Laws in force for regulation of traffic or use of roadways upon or over which it is necessary to carry out Work or haul materials or equipment.
- .2 Comply with most recent editions of the Traffic Control Manual for Work on Roadways published by the BC Ministry of Transportation and the Manual of Uniform Traffic Control Devices for Streets and Highways for Canada published by the Transportation Association of Canada.
- .3 During progress of the Work, make adequate provision to accommodate normal traffic along roads and highways immediately adjacent to or crossing the works so as to cause minimum inconvenience to the general public.
- .4 When working on travelled way:
  - .1 Place equipment in position to present minimum of interference and hazard to travelling public.
  - .2 Keep equipment units as close together as working conditions permit and preferably on same side of travelled way.
  - .3 Do not leave equipment on travelled way overnight.
- .5 Do not close any lanes of road without prior approval of Departmental Representative. Before re-routing traffic erect suitable signs and devices in accordance with instructions reference manuals.
- .6 Keep travelled way graded, free of pot holes and of sufficient width for required number of lanes of traffic.
  - .1 Provide minimum 7 m wide temporary roadway for traffic in two-way sections through Work and on detours.

.2 Provide minimum 5 m wide temporary roadway for traffic in one-way sections through Work and on detours.

.7 As directed by Departmental Representative, provide graveled detours or temporary roads to facilitate passage of traffic around restricted construction area:

.1 Place and compact granular sub-base in accordance with Section 32 11 16.01 - Granular Sub-base.

.2 Place and compact granular base in accordance with Section 32 11 23 - Aggregate Base Courses.

.8 Provide and maintain road access and egress to property fronting along Work under Contract and in other areas as indicated, unless other means of road access exist that meet approval of Departmental Representative.

1.4 INFORMATIONAL AND  
WARNING DEVICES

.1 Provide and maintain signs, flashing warning lights and other devices required to indicate construction activities or other temporary and unusual conditions resulting from Project Work which requires road user response.

.2 Supply and erect signs, delineators, barricades and miscellaneous warning devices as specified reference manuals.

.3 Place signs and other devices in locations recommended in the reference manuals.

.4 Meet with Departmental Representative prior to commencement of Work to prepare list of signs and other devices required for project. If situation on site changes, revise list to approval of Departmental Representative.

.5 Continually maintain traffic control devices in use by:

.1 Checking signs daily for legibility, damage, suitability and location. Clean, repair or replace to ensure clarity and reflectance.

.2 Removing or covering signs which do not apply to conditions existing from day to day.

1.5 CONTROL OF PUBLIC  
TRAFFIC

.1 Provide competent flag persons, trained in accordance with, and properly equipped as specified in the reference manuals in following situations:

.1 When public traffic is required to pass working vehicles or equipment that block all or part of travelled roadway.

.2 When it is necessary to institute one-way traffic system through construction area or

- other blockage where traffic volumes are heavy, approach speeds are high and traffic signal system is not in use.
- .3 When workmen or equipment are employed on travelled way over brow of hills, around sharp curves or at other locations where oncoming traffic would not otherwise have adequate warning.
  - .4 Where temporary protection is required while other traffic control devices are being erected or taken down.
  - .5 For emergency protection when other traffic control devices are not readily available.
  - .6 In situations where complete protection for workers, working equipment and public traffic is not provided by other traffic control devices.
  - .7 At each end of restricted sections where pilot cars are required.
  - .8 Delays to public traffic due to contractor's operators: maximum 15 minutes.

- .2 Where roadway, carrying two-way traffic, is restricted to one lane, for 24 hours each day, provide portable traffic signal system. Adjust, as necessary, and regularly maintain system during period of restriction. Signal system to meet requirements of the reference manuals.

1.6 OPERATIONAL REQUIREMENTS

- .1 Maintain existing conditions for traffic throughout period of contract except that, when required for construction under contract and when measures have been taken as specified and approved by Departmental Representative to protect and control public traffic.
- .2 Maintain existing conditions for traffic crossing right-of-way.

-----END OF SECTION-----



1. REFERENCES

- .1 Government of Canada.
  - .1 Canada Labour Code - Part II
  - .2 Canada Occupational Health and Safety Regulations.
- .2 National Building Code of Canada (NBC):
  - .1 Part 8, Safety Measures at Construction and Demolition Sites.
- .3 The Canadian Electric Code (as amended)
- .4 Canadian Standards Association (CSA) as amended:
  - .1 CSA Z797-2009 Code of Practice for Access Scaffold
  - .2 CSA S269.1-1975 (R2003) Falsework for Construction Purposes
  - .3 CSA S350-M1980 (R2003) Code of Practice for Safety in Demolition of Structures
  - .4 CSA Z1006-10 Management of Work in Confined Spaces.
  - .5 CSA Z462- Workplace Electrical Safety Standard
- .5 National Fire Code of Canada 2010 (as amended)
  - .1 Part 5 - Hazardous Processes and Operations and Division B as applicable and required.
- .6 American National Standards Institute (ANSI):
  - .1 ANSI A10.3, Operations - Safety Requirements for Powder-Actuated Fastening Systems.
- .7 Province of British Columbia:
  - .1 Workers Compensation Act Part 3- Occupational Health and Safety.
  - .2 Occupational Health and Safety Regulations
  - .3 B.C. Ministry of Transportation and Infrastructure Traffic Control Manual for Work on Roadways (as amended)

2. RELATED SECTIONS

- .1 Refer to the following current sections as required:
  - .1 Submittals procedures:  
Section 01 33 00
  - .2 Special Procedures for Traffic Control:  
Section 01 35 00.06

3. WORKERS' COMPENSATION  
BOARD COVERAGE

- .1 Comply fully with the Workers' Compensation Act, regulations and orders made pursuant thereto, and any amendments up to the completion of the work.
- .2 Maintain Workers' Compensation Board coverage during the term of the Contract, until and including the date that the Certificate of Final Completion is issued.

4. COMPLIANCE WITH  
REGULATIONS

- .1 PSPC may terminate the Contract without liability to PSPC where the Contractor, in the opinion of PWGSC, refuses to comply with a requirement of the Workers' Compensation Act or the Occupational Health and Safety Regulations.
- .2 It is the Contractor's responsibility to ensure that all workers are qualified, competent and certified to perform the work as required by the Workers' Compensation Act or the Occupational Health and Safety Regulations.

5. SUBMITTALS

- .1 Submit to Departmental Representative submittals listed for review. [in accordance with Section 013300]
- .2 Work effected by submittal shall not proceed until review is complete.
- .3 Submit the following:
  - .1 Site Specific Health and Safety Plan.
  - .2 Copies of reports or directions issued by Federal and Provincial health and safety inspectors.
  - .3 Copies of incident and accident reports.
  - .4 Complete set of current Material Safety Data Sheets (MSDS), and all other documentation required by Workplace Hazardous Materials Information System (WHMIS) requirements.
  - .5 Emergency Procedures.
- .4 The Departmental Representative will review the Contractor's Site Specific Health and Safety Plan and emergency procedures, and provide comments to the Contractor within 5 days after receipt of the plan. Revise the plan as appropriate and resubmit to Departmental Representative.
- .5 Medical surveillance: where prescribed by legislation, regulation or safety program, submit certification of medical surveillance for site personnel prior to commencement of work, and submit additional certifications for any new site personnel to Departmental Representative.
- .6 Submission of the Site Specific Health and Safety Plan, and any revised version, to the Departmental Representative is for information and reference purposes only. It shall not:
  - .1 Be construed to imply approval by the Departmental Representative.
  - .2 Be interpreted as a warranty of being complete, accurate and legislatively compliant.

- .3 Relieve the Contractor of his legal obligations for the provision of health and safety on the project.

6. RESPONSIBILITY

- .1 Assume responsibility as the Prime Contractor for work under this contract.
- .2 Be responsible for health and safety of persons on site, safety of property on site and for protection of persons adjacent to site and environment to extent that they may be affected by conduct of Work.
- .3 Comply with and enforce compliance by employees with safety requirements of Contract documents, applicable Federal, Provincial, Territorial and local statutes, regulations, and ordinances, and with Site Specific Health and Safety Plan

7. HEALTH AND SAFETY  
COORDINATOR

- .1 The Health and Safety Coordinator:
  - .1 Be responsible for completing all health and safety training and ensuring that personnel that do not successfully complete the required training are not permitted to enter the site to perform work.
  - .2 Be responsible for implementing, revising, daily enforcing, and monitoring the Site Specific Health and Safety Plan.
  - .3 Be on site during execution of work.

8. GENERAL CONDITIONS

- .1 Provide safety barricades and lights around work site as required to provide a safe working environment for workers and protection for pedestrian and vehicular traffic.
- .2 Ensure that non-authorized persons are not allowed to circulate in designated construction areas of the work site.
  - .1 Provide appropriate means by use of barricades, fences, warning signs, traffic control personnel, and temporary lighting as required.
  - .2 Secure site at night time [or provide security guard] as deemed necessary to protect site against entry.

9. PROJECT/SITE CONDITIONS

- .1 Work at site will involve contact with:
  - .1 Multi-employer work site.
  - .2 Federal employees and general public.
  - .3 Energized electrical services.
  - .4 Working from heights
  - .5 Working in the open exposed to unpredictable weather.

- .6 High volumes of vehicular and pedestrian traffic
- 10. UTILITY CLEARANCES
  - .1 The Contractor is solely responsible for all utility detection and clearances prior to starting the work
  - .2 The Contractor will not rely solely upon the Reference Drawings or other information provided for utility locations.
- 11. REGULATORY REQUIREMENTS
  - .1 Comply with specified codes, acts, bylaws, standards and regulations to ensure safe operations at site.
  - .2 In event of conflict between any provision of the above authorities, the most stringent provision will apply. Should a dispute arise in determining the most stringent requirement, the Departmental Representative will advise on the course of action to be followed.
- 11. WORK PERMITS
  - .1 Obtain specialty permit[s] related to project before start of work.
- 12. FILING OF NOTICE
  - .1 The General Contractor is to complete and submit a Notice of Project as required by Provincial authorities.
  - .2 Provide copies of all notices to the Departmental Representative.
- 13. HEALTH AND SAFETY PLAN
  - .1 Conduct a site-specific hazard assessment based on review of Contract documents, required work, and project site. Identify any known and potential health risks and safety hazards.
  - .2 Prepare and comply with a site-specific project Health and Safety Plan based on hazard assessment, including, but not limited to, the following:
    - .1 Primary requirements:
      - .1 Contractor's safety policy.
      - .2 Identification of applicable compliance obligations.
      - .3 Definition of responsibilities for project safety/organization chart for project.
      - .4 General safety rules for project.
      - .5 Job-specific safe work procedures.
      - .6 Inspection policy and procedures.
      - .7 Incident reporting and investigation policy and Procedures.
      - .8 Occupational Health and Safety Committee/Representative procedures.

- .9 Occupational Health and Safety meetings.
- .10 Occupational Health and Safety communications and record keeping procedures.
- .2 Summary of health risks and safety hazards resulting from analysis of hazard assessment, with respect to site tasks and operations which must be performed as part of the work.
- .3 List hazardous materials to be brought on site as required by work.
- .4 Indicate Engineering and administrative control measures to be implemented at the site for managing identified risks and hazards.
- .5 Identify personal protective equipment (PPE) to be used by workers.
- .6 Identify personnel and alternates responsible for site safety and health.
- .7 Identify personnel training requirements and training plan, including site orientation for new workers.
- .3 Develop the plan in collaboration with all subcontractors. Ensure that work/activities of subcontractors are included in the hazard assessment and are reflected in the plan.
- .4 Revise and update Health and Safety Plan as required, and re-submit to the Departmental Representative.
- .5 Departmental Representative's review: the review of Site Specific Health and Safety Plan by Public Service and Procurement Canada (PSPC) shall not relieve the Contractor of responsibility for errors or omissions in final Site Specific Health and Safety Plan or of responsibility for meeting all requirements of construction and Contract documents.

14. EMERGENCY PROCEDURES

- .1 List standard operating procedures and measures to be taken in emergency situations. Include an evacuation plan and emergency contacts (i.e. names/telephone numbers) of:
  - .1 Designated personnel from own company.
  - .2 Regulatory agencies applicable to work and as per legislated regulations.
  - .3 Local emergency resources.
  - .4 Departmental Representative [site staff].
- .2 Include the following provisions in the emergency procedures:

- .1 Notify workers and the first-aid attendant, of the nature and location of the emergency.
  - .2 Evacuate all workers safely.
  - .3 Check and confirm the safe evacuation of all workers.
  - .4 Notify the fire department or other emergency responders.
  - .5 Notify adjacent workplaces or residences which may be affected if the risk extends beyond the workplace.
  - .6 Notify Departmental Representative [site staff].
- .3 Provide written rescue/evacuation procedures as required for, but not limited to:
- .1 Work at high angles.
  - .2 Work in confined spaces or where there is a risk of entrapment.
  - .3 Work with hazardous substances.
  - .4 Underground work.
  - .5 Work on, over, under and adjacent to water.
  - .6 Workplaces where there are persons who require physical assistance to be moved.
- .4 Design and mark emergency exit routes to provide quick and unimpeded exit.

15. HAZARDOUS PRODUCTS

- .1 Comply with requirements of Workplace Hazardous Materials Information System (WHMIS) regarding use, handling, storage and disposal of hazardous materials, and regarding labelling and provision of Material Safety Data Sheets (MSDS) acceptable to the Departmental Representative and in accordance with the Canada Labour Code.
- .2 Where use of hazardous and toxic products cannot be avoided:
- .1 Advise Departmental Representative beforehand of the product(s) intended for use. Submit applicable MSDS and WHMIS documents as per [Section 013300].
  - .2 In conjunction with Departmental Representative, schedule to carry out work during "off hours" when tenants have left the building.
  - .3 Provide adequate means of ventilation in accordance with Section 01 51 00.
  - .4 The contractor shall ensure that the product is applied as per manufacturers recommendations.
  - .5 The contractor shall ensure that only pre-approved products are brought onto the work site in an adequate quantity to complete the work.

16. ASBESTOS HAZARD
- .1 Carry out any activities involving asbestos in accordance with applicable Provincial Regulations.
  - .2 Removal and handling of asbestos will be performed as indicated.
17. PCB REMOVALS
- .1 Mercury-containing fluorescent tubes and ballasts which contain polychlorinated biphenyls (PCBs) are classified as hazardous waste.
  - .2 Remove, handle, transport and dispose of as indicated.
18. REMOVAL OF LEAD-CONTAINING PAINTS
- .1 All paints containing TCLP lead concentrations above 5 ppm are classified as hazardous.
  - .2 Carry out demolition activities involving lead-containing paints in accordance with applicable Provincial Regulations.
19. ELECTRICAL SAFETY REQUIREMENTS
- 1 Comply with authorities and ensure that, when installing new facilities or modifying existing facilities, all electrical personnel are completely familiar with existing and new electrical circuits and equipment and their operation.
    - .1 Before undertaking any work, coordinate required energizing and de-energizing of new and existing circuits with Departmental Representative.
    - .2 Maintain electrical safety procedures and take necessary precautions to ensure safety of all personnel working under this Contract, as well as safety of other personnel on site.
20. ELECTRICAL LOCKOUT
- 1 Develop, implement and enforce use of established procedures to provide electrical lockout and to ensure the health and safety of workers for every event where work must be done on any electrical circuit or facility.
  - .2 Prepare the lockout procedures in writing, listing step-by-step processes to be followed by workers, including how to prepare and issue the request/authorization form. Have procedures available for review upon request by the Departmental Representative.
  - .3 Keep the documents and lockout tags at the site and list in a log book for the full duration of the Contract. Upon request, make such data available for viewing by Departmental

- Representative or by any authorized safety representative.
21. OVERLOADING .1 Ensure no part of work is subjected to a load which will endanger its safety or will cause permanent deformation.
22. FALSEWORK .1 Design and construct falsework in accordance with CSA S269.1-1975 (R2003).
23. SCAFFOLDING .1 Design, construct and maintain scaffolding in a rigid, secure and safe manner, in accordance with CSA Z797-2009 and B.C. Occupational Health and Safety Regulations.
24. CONFINED SPACES .1 Carry out work in confined spaces in compliance with Provincial Regulations
25. POWDER-ACTUATED DEVICES .1 Use powder-actuated devices in accordance with ANSI A10.3 only after receipt of written permission from the Departmental Representative.
26. FIRE SAFETY AND HOT WORK .1 Obtain Departmental Representative's authorization before any welding, cutting or any other hot work operations can be carried out on site.
- .2 Hot work includes cutting/melting with use of torch, flame heating roofing kettles, or other open flame devices and grinding with equipment which produces sparks.
27. FIRE SAFETY REQUIREMENTS .1 Store oily/paint-soaked rags, waste products, empty containers and materials subject to spontaneous combustion in ULC approved, sealed containers and remove from site on a daily basis.
- .2 Handle, store, use and dispose of flammable and combustible materials in accordance with the National Fire Code of Canada.
- .3 Portable gas and diesel fuel tanks are not permitted on most federal work sites. Approval from the DR is required prior to any gas or diesel tank being brought onto the work site
28. FIRE PROTECTION AND ALARM SYSTEM .1 Fire protection and alarm systems shall not be:
- .1 Obstructed.
- .2 Shut off.
- .3 Left inactive at the end of a working day or shift.
- .2 Do not use fire hydrants, standpipes and hose systems for purposes other than firefighting.
- .3 Be responsible/liable for costs incurred from the fire department, the building owner and the tenants, resulting from false alarms.



29. UNFORESEEN HAZARDS .1 Should any unforeseen or peculiar safety-related factor, hazard or condition become evident during performance of the work, immediately stop work and advise the Departmental Representative verbally and in writing.
30. POSTED DOCUMENTS .1 Post legible versions of the following documents on site:
- .1 Site Specific Health and Safety Plan.
  - .2 Sequence of work.
  - .3 Emergency procedures.
  - .4 Site drawing showing project layout, locations of the first-aid station, evacuation route and marshalling station, and the emergency transportation provisions.
  - .5 Notice of Project.
  - .6 Floor plans or site plans.
  - .7 Notice as to where a copy of the Workers' Compensation Act and Regulations are available on the work site for review by employees and workers.
  - .8 Workplace Hazardous Materials Information System (WHMIS) documents.
  - .9 Material Safety Data Sheets (MSDS).
  - .10 List of names of Joint Health and Safety Committee members, or Health and Safety Representative, as applicable.
- .2 Post all Material Safety Data Sheets (MSDS) on site, in a common area, visible to all workers and in locations accessible to tenants when work of this Contract includes construction activities adjacent to occupied areas.
- .3 Postings should be protected from the weather, and visible from the street or the exterior of the principal construction site shelter provided for workers and equipment, or as approved by the Departmental Representative.
31. MEETINGS .1 Attend health and safety pre-construction meeting and all subsequent meetings called by the Departmental Representative.
32. CORRECTION OF NON-COMPLIANCE .1 Immediately address health and safety non-compliance issues identified by the Departmental Representative.
- .2 Provide Departmental Representative with written report of action taken to correct non-compliance with health and safety issues identified.

- .3 The Departmental Representative may issue a "stop work order" if non-compliance of health and safety regulations is not corrected immediately or within posted time. The General Contractor/subcontractors will be responsible for any costs arising from such a "stop work order".

-----END OF SECTION-----

PART 1 - GENERAL

1.1 DEFINITIONS

- .1 Environmental Pollution and Damage: presence of chemical, physical, biological elements or agents which adversely affect human health and welfare; unfavourably alter ecological balances of importance to human life; affect other species of importance to humankind; or degrade environment aesthetically, culturally and/or historically.
- .2 Environmental Protection: prevention/control of pollution and habitat or environment disruption during construction. Control of environmental pollution and damage requires consideration of land, water, and air; biological and cultural resources; and includes management of visual aesthetics; noise; solid, chemical, gaseous, and liquid waste; radiant energy and radioactive material as well as other pollutants.

1.2 FIRES

- .1 Fires and burning of rubbish on site not permitted.

1.2 DISPOSAL OF WASTES

- .1 Do not bury rubbish and waste materials on site unless approved by Departmental Representative.
- .2 Do not dispose of waste or volatile materials, such as mineral spirits, oil or paint thinner into waterways, storm or sanitary sewers.
- .3 Safely dispose of wet concrete and pipe grout off-site in accordance with Municipal, Provincial and Federal authorities' requirements.

1.3 EROSION AND SEDIMENT  
CONTROL / DRAINAGE

- .1 Provide temporary erosion and sedimentation control measures to prevent soil erosion and discharge of soil-bearing water runoff or airborne dust that complies with the most stringent requirements of the authorities having jurisdiction.
- .2 The contractor shall inspect, repair, and maintain erosion and sedimentation control measures during construction until permanent vegetation has been established.
- .3 All work shall be undertaken and completed in such a manner as to prevent the release of sediment, silt, or sediment laden water, concrete or concrete leachate or any other deleterious substance into any ditch or water course.
- .4 Do not pump water containing suspended materials into waterways, sewer or drainage systems.
- .5 The contractor shall keep all portions of the work

drained during construction until completion. Where necessary, catch water ditch shall be constructed along the tops of excavations or fill slopes to prevent water flowing into or over the excavated or filled area. The contractor will be responsible for the repair for the damage, directly resulting for their operations and for the removal or dirt or debris from existing system, which may be caused by or which may result from water backing up or overflowing through, from, or along any part of the work or adjacent properties. The contractor shall bear all costs associated with these repairs until works are complete and accepted by the Department Representative.

- .6 The contractor shall modify and/or provide additional silt control measures as necessary to accommodate construction activities and satisfy the requirements or the governing agencies.
- .7 The contractor shall maintain all silt control facilities on an as-needed basis
- .8 Control disposal or runoff of water containing suspended materials or other harmful substances in accordance with local authority requirements.
- .9 Remove erosion and sedimentation controls and restore and stabilize areas disturbed during removal.

1.4 SITE CLEARING AND PLANT PROTECTION

- .1 Protect trees and plants on site and adjacent properties where indicated.
- .2 Wrap in burlap, trees and shrubs adjacent to construction work, storage areas and trucking lanes, and encase with protective wood framework from grade level to height of 2 m.
- .3 Protect roots of designated trees to dripline during excavation and site grading to prevent disturbance or damage. Avoid unnecessary traffic, dumping and storage of materials over root zones.
- .4 Minimize stripping of topsoil and vegetation.
- .5 Restrict tree removal to those indicated or designated by Departmental Representative.

1.5 POLLUTION CONTROL

- .1 Maintain temporary erosion and pollution control features installed under this contract.
- .2 Control emissions from equipment and plant to local authorities' emission requirements.

- .3 Cover or wet down dry materials and rubbish to prevent blowing dust and debris. Provide dust control for temporary roads.

1.6 NOTIFICATION

- .1 Departmental Representative will notify Contractor in writing of observed noncompliance with Federal, Provincial or Municipal environmental laws or regulations, permits, and other elements of Contractor's Environmental Protection plan.
- .2 Contractor: after receipt of such notice, inform Departmental Representative of proposed corrective action and take such action for approval by Departmental Representative.
- .3 Departmental Representative will issue stop order of work until satisfactory corrective action has been taken.
- .4 No time extensions granted or equitable adjustments allowed to Contractor for such suspensions.

-----END OF SECTION-----

PART 1 - GENERAL

1.1 INSPECTION

- .1 The Contractor shall as part of the work perform, or cause to be performed, all tests, inspections and approvals of the work as required by the Contract Documents, and if a test, inspection or approval requires a representative sample of materials or workmanship the Contractor shall at the Contractor's own cost supply the labour and materials necessary to provide the sample.
- .2 If any portion of the work is designated for special tests, inspections or approvals (either as a requirement in the Contract Documents, or by the Department Representative's instructions, or by the laws or regulations applicable at the place of the work), then:
  - .1 if the Department Representative is to perform or arrange for the test, inspection or approval the Contractor shall give the Department Representative timely notice requesting such test, inspection or approval; and
  - .2 if other authorities are to perform the test, inspection or approval the Contractor shall arrange for such test, inspection or approval and shall give the Department Representative timely notice of the date and time for such test, inspection or approval.
- .3 Department Representative will order part of Work to be examined if Work is suspected to be not in accordance with Contract Documents. If, upon examination such work is found not in accordance with Contract Documents, correct such Work and pay cost of examination and correction. If such Work is found in accordance with Contract Documents, Department Representative shall pay cost of examination and replacement.
- .4 If the Contractor disagrees with Department Representative's determination of the Work not meeting the Specifications based on the results of inspection or testing required in the Contract Documents or ordered by the Department Representative, the Contractor may elect to carry out such further inspection or testing which the Department Representative agrees is acceptable for the purpose of determining whether the work complies with the requirements of the Contract Documents. If such further inspection or testing determines that the Work is not in accordance with the requirements of the Contract Documents, then the Contractor shall correct such Work and pay the

costs of the inspection and testing including all costs of the correction and further testing. If such further inspection or testing determines that the Work is in accordance with the requirements of the Contract Documents, then the Department shall pay all costs of the inspection and testing.

- .5 If Contractor covers or permits to be covered Work that has been designated for special tests, inspections or approvals before such is made, uncover such Work, have inspections or tests satisfactorily completed and make good such Work at the Contractor's own expense, and Contractor shall comply with such direction.
- .6 The Contractor shall promptly provide the Department Representative with 4 copies of all certificates, inspection and testing reports required by the Contract Documents or ordered by the Department Representative.
- .7 The Contractor shall not undertake any Work outside the working hours, as specified in the Contract Documents, which under the Contract Documents requires tests, inspection, or approval by the Department Representative unless the Contractor obtains the Department Representative's prior approval. The Contractor shall reimburse the Department for any additional costs incurred to provide tests, inspections or approvals outside such specified working hours.
- .8 Independent Inspection / Testing Agencies will be engaged by the Contractor for purpose of inspecting and/or testing portions of the Work. Cost of such services will be borne by the Contractor.
- .9 Submit for approval by Departmental Representative proposed Independent Inspection / Testing Agencies.
- .10 Employment of inspection / testing agencies does not relax responsibility to perform Work in accordance with Contract Documents.
- .11 If defects are revealed during inspection and/or testing, appointed agency will request additional inspection and/or testing to ascertain full degree of defect. Correct defect and irregularities as advised by Departmental Representative at no cost to Departmental Representative. Pay costs for re-testing and re-inspection.

1.2. ACCESS TO WORK

- .1 Allow Department Representative access to Work. If part of Work is in preparation at locations other than Place of Work, allow access to such Work whenever it is in progress.

1.3 TESTING FREQUENCY

- .1 The following outlines the minimum testing frequency for various components of the Work:
  - .1 Road Subbase and Granular Base Densities:
    - .1 One per 500m<sup>2</sup>.
  - .2 Sieve Analyses and Proctors:
    - .1 One prior to commencing work.
    - .2 One every 200 tonne.
  - .3 Asphalt Marshall Test:
    - .1 One per asphalt type.
    - .2 Minimum one per day.
  - .4 Asphalt Cores:
    - .1 One per 700m<sup>2</sup>.
    - .2 For asphalt pavement areas less than 3500m<sup>2</sup>, pavement is deemed to have met specifications if results from all cores average the design thickness  $\pm$  5mm with no individual core greater than 10mm less than the design thickness.
    - .3 Core holes shall be reinstated to the satisfaction of the Department Representative.

1.4 REPORTS

- .1 Submit 4 copies of inspection and test reports to Departmental Representative. The inspection and certification report are to be submitted in PDF format during the construction stage with hard copies included in the Close Out documentation.

1.5 TESTS AND MIX DESIGNS

- .1 Furnish test results and mix designs as requested.
- .2 Cost of tests and mix designs beyond those called for in Contract Documents or beyond those required by law of Place of Work will be appraised by Departmental Representative and may be authorized as recoverable.

-----END OF SECTION-----



PART 1 - GENERAL

1.1 REFERENCES

- .1 Public Works Government Services Canada (PWGSC) Standard Acquisition Clauses and Conditions (SACC)- ID: R0202D, Title: General Conditions "C", In Effect as Of: May 14, 2004.

1.2 PROJECT  
CLEANLINESS

- .1 Maintain Work in tidy condition, free from accumulation of waste products and debris, other than that caused by Departmental Representative or other Contractors.
- .2 Remove waste materials from site at daily regularly scheduled times. Do not burn waste materials on site, unless approved by Departmental Representative.
- .3 Clear snow and ice from site to provide a safe working areas.
- .4 Make arrangements with and obtain permits from authorities having jurisdiction for disposal of waste and debris.
- .5 Provide on-site containers for collection of waste materials and debris. Dispose of waste materials and debris off site.
- .6 Store volatile waste in covered metal containers, and remove from premises at end of each working day.

1.3 FINAL CLEANING

- .1 When Work is Substantially Performed remove surplus products, tools, construction machinery and equipment not required for performance of remaining Work.
- .2 Remove waste products and debris other than that caused by others, and leave Work clean and suitable for occupancy.
- .3 Prior to final review remove surplus products, tools, construction machinery and equipment.
- .4 Make arrangements with and obtain permits from authorities having jurisdiction for disposal of waste and debris.
- .5 Broom clean and wash exterior walks, steps and surfaces; rake clean other surfaces of grounds. Remove dirt and other disfiguration from exterior surfaces. Sweep and wash clean paved areas.

-----END OF SECTION-----

PART 1 - GENERAL

1.1 RELATED SECTIONS

- .1 Section 01 33 00-Submittal Procedures.
- .2 Section 01 45 00-Quality Control

1.2 SUBMITTALS

- .1 Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Copy will be returned after final inspection with Departmental Representative comments.
- .3 Revise content of documents as required prior to final submittal.
- .4 Furnish evidence, for type, source and quality of products provided.
- .5 Defective products will be rejected, regardless of previous inspections. Replace products at own expense.
- .6 Pay costs of transportation.
- .7 Submit to Department Representative, 4 final copies of all test reports completed for this project including compaction tests, granular material gradations, pipeline pressure tests, watermain certifications, a minimum 2 weeks prior to Substantial Performance of the Work.

1.3 FORMAT

- .1 Organize data as instructional manual.
- .2 Binders: vinyl, hard covered, 3 'D' ring, loose leaf 216 x 279mm with spine and face pockets.
- .3 When multiple binders are used correlate data into related consistent groupings. Identify contents of each binder on spine.
- .4 Cover: identify each binder with type or printed title 'Project Record Documents'; list title of project and identify subject matter of contents.
- .5 Arrange content by process flow, under Section numbers and sequence of Table of Contents.
- .6 Provide tabbed fly leaf for each separate product and system, with typed description of product and major component parts of equipment.
- .7 Text: manufacturer's printed data, or typewritten data.
- .8 Drawings: provide with reinforced punched binder

tab. Bind in with text; fold larger drawings to size of text pages.

1.4 CONTENTS - EACH  
VOLUME

- .1 Table of Contents: provide title of project;
  - .1 Date of submission; names.
  - .2 Addresses, and telephone numbers of Consultant and Contractor with name of responsible parties.
  - .3 Schedule of products and systems, indexed to content of volume.
- .2 For each product or system:
  - .1 List names, addresses and telephone numbers of subcontractors and suppliers, including local source of supplies and replacement parts.
- .3 Product Data: mark each sheet to identify specific products and component parts, and data applicable to installation; delete inapplicable information.
- .4 Drawings: supplement product data to illustrate relations of component parts of equipment and systems, to show control and flow diagrams.
- .5 Typewritten Text: as required to supplement product data. Provide logical sequence of instructions for each procedure, incorporating manufacturer's instructions specified in Section 01 45 00 - Quality Control.

1.5 AS-BUILTS

- .1 Maintain, in addition to requirements in General Conditions, one record copy of:
  - .1 Contract Drawings.
  - .2 Specifications.
  - .3 Addenda.
  - .4 Change Orders and other modifications to Contract.
  - .5 Reviewed shop drawings, product data, and samples.
  - .6 Field test records.
  - .7 Inspection certificates.
  - .8 Manufacturer's certificates.
- .2 Store record documents in field office apart from documents used for construction. Provide files, racks, and secure storage.
- .3 Label record documents and file in accordance with Section number listings in List of Contents of this Project Manual. Label each document "PROJECT RECORD" in neat, large, printed letters.
- .4 Maintain record documents in clean, dry and legible condition. Do not use record documents for

construction purposes.

- .5 Keep record documents and samples available for inspection by Departmental Representative.

1.6 RECORDING ACTUAL SITE  
CONDITIONS

- .1 Record information on set of blue line, opaque drawings, and in copy of Project Manual, provided by Departmental Representative.
- .2 Provide felt tip marking pens, maintaining separate colours for each major system, for recording information.
- .3 Record information concurrently with construction progress. Do not conceal Work until required information is recorded.
- .4 Contract Drawings and shop drawings: mark each item to record actual construction, including:
  - .1 Measured depths of elements of foundation in relation to finish first floor datum.
  - .2 Measured horizontal and vertical locations of underground utilities and appurtenances, referenced to permanent surface improvements.
  - .3 Measured locations of internal utilities and appurtenances, referenced to visible and accessible features of construction.
  - .4 Field changes of dimension and detail.
  - .5 Changes made by change orders.
  - .6 Details not on original Contract Drawings.
  - .7 References to related shop drawings and modifications.
- .5 Specifications: mark each item to record actual construction, including:
  - .1 Manufacturer, trade name, and catalogue number of each product actually installed, particularly optional items and substitute items.
  - .2 Changes made by Addenda and change orders.
- .6 Other Documents: maintain manufacturer's certifications, inspection certifications, field test records, required by individual specifications sections to provide certification that all works have been completed as specified and that works are ready for tie-in.

-----END OF SECTION-----

PART 1 - GENERAL

1.1 RELATED SECTIONS

- .1 Section 01 33 00-Submittal Procedures.
- .2 Section 03 30 00-Cast-In-Place Concrete.
- .3 Section 31 23 10-Excavating, Trenching and Backfilling.
- .4 Section 33 05 13-Manholes and Catch Basin Structures.
- .5 Section 33 41 00-Storm Utility Drainage Piping.

1.2 REFERENCES

- .1 American Concrete Institute (ACI)
  - .1 SP-66, ACI Detailing Manual 2004.
    - .1 ACI 315, Details and Detailing of Concrete Reinforcement.
    - .2 ACI 315R, Manual of Engineering and Placing Drawings for Reinforced Concrete Structures.
- .2 American Society for Testing and Materials International (ASTM)
  - .1 ASTM A 143/A 143M, Standard Practice for Safeguarding Against Embrittlement of Hot-Dip Galvanized Structural Steel Products and Procedure for Detecting Embrittlement.
  - .2 ASTM A 185/A 185M, Standard Specification for Steel Welded Wire Reinforcement, Plain, for Concrete.
  - .3 ASTM A 497/A 497M, Standard Specification for Steel Welded Wire Reinforcement, Deformed, for Concrete.
  - .4 ASTM A 775/A 775M, Standard Specification for Epoxy-Coated Reinforcing Steel Bars.
  - .5 ASTM A 325-06, Standard Specification for structural bolts, steel, heat treated 120/105 ksi minimum tensile strength.
- .3 Canadian Standards Association (CSA International)
  - .1 CSA-A23.1/A23.2, Concrete Materials and Methods of Concrete Construction/Methods of Test and Standard Practices for Concrete.
  - .2 CSA-A23.3, Design of Concrete Structures.
  - .3 CAN/CSA- G30.18-M92 (R2002), Billet Steel Bars for Concrete Reinforcement, Grade 400W.
  - .4 CAN/CSA- G30.114-M1983 (R1998), Welded Deformed Steel Wire Fabric for Concrete Reinforcement.
  - .5 CAN/CSA- S16-01 (R2005), Limit State Design of Steel Structures.
  - .6 CAN/CSA- W186-M1990 (R2002), Welding of Reinforcing Bars in Reinforced Concrete Construction.
  - .7 CSA- W59-03, Welded Steel Construction (Metal

- Arc Welding).
- .8 CSA-G40.20-04/CSA-G40.21-04, General Requirements for Rolled or Welded Structural Quality Steel/Structural Quality Steel.
- .9 CAN/CSA-G164, Hot Dip Galvanizing of Irregularly Shaped Articles, A National Standard of Canada.

- .4 Reinforcing Steel Institute of Canada (RSIC)
  - .1 RSIC, Reinforcing Steel Manual of Standard Practice.

- .5 National Building Code of Canada 2005.

### 1.3 SUBMITTALS

- .1 Submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Prepare reinforcement drawings in accordance with ACI 315.
- .3 Submit shop drawings including placing of reinforcement and indicate:
  - .1 Bar bending details.
  - .2 Lists.
  - .3 Quantities of reinforcement.
  - .4 Sizes, spacings, locations of reinforcement and mechanical splices if approved by Departmental Representative, with identifying code marks to permit correct placement without reference to structural drawings.
- .4 Detail lap lengths and bar development lengths to CSA-A23.3.
- .5 When Chromate solution is used as replacement for galvanizing non-prestressed reinforcement, provide product description for review by Departmental Representative prior to its use.
- .6 Quality Assurance: in accordance with Section 01 45 00 - Quality Control and as described in PART 2 - SOURCE QUALITY CONTROL.
  - .1 Mill Test Report: upon request, provide Departmental Representative with certified copy of mill test report of reinforcing steel.
  - .2 Upon request submit in writing to Departmental Representative proposed source of reinforcement material to be supplied.

### 1.4 DELIVERY, STORAGE AND HANDLING

- .1 Waste Management and Disposal:
  - .1 Place materials defined as hazardous or toxic in designated containers.

## PART 2 - PRODUCTS

### 2.1 MATERIALS

- .1 Substitute different size bars only if permitted in

writing by Departmental Representative.

- .2 Reinforcing steel: billet steel, grade as specified on contract drawings deformed bars to CAN/CSA-G30.18 grade 400W, unless indicated otherwise.
- .3 Reinforcing steel: weldable low alloy steel deformed bars to CSA-G30.16.
- .4 Cold-drawn annealed steel wire ties: to CSA G30.3.
- .5 Deformed steel wire for concrete reinforcement: to CSA G30.14.
- .6 Welded deformed steel wire fabric: to CSA G30.15.
  - .1 Provide in flat sheets only.
- .7 Epoxy Coating of non-prestressed reinforcement: to ASTM A 775/A 775M.
- .8 Galvanizing of non-prestressed reinforcement: to CAN/CSA-G164, minimum zinc coating 610 g/m<sup>2</sup>.
  - .1 Protect galvanized reinforcing steel with chromate treatment to prevent reaction with Portland cement paste.
  - .2 If chromate treatment is carried out immediately after galvanizing, soak steel in aqueous solution containing minimum 0.2% by weight sodium dichromate or 0.2% chromic acid.
    - .1 Temperature of solution equal to or greater than 32 degrees and galvanized steels immersed for minimum 20 seconds.
  - .3 If galvanized steels are at ambient temperature, add sulphuric acid as bonding agent at concentration of 0.5% to 1%.
    - .1 In this case, no restriction applies to temperature of solution.
  - .4 Chromate solution sold for this purpose may replace solution described above, provided it is of equivalent effectiveness.
    - .1 Provide product description as described in PART 1 - SUBMITTALS
- .9 Chairs, bolsters, bar supports, spacers: to CSA-A23.1.
- .10 Mechanical splices: subject to approval of Departmental Representative.
- .11 Plain round bars: to CSA-G40.20/G40.21.

## 2.2 FABRICATION

- .1 Fabricate reinforcing steel in accordance with CSA-A23.1 and ACI 315.
  - .1 ACI 315R unless indicated otherwise.
- .2 Obtain Departmental Representative's approval for locations of reinforcement splices other than those

shown on placing drawings.

- .3 Upon approval of Departmental Representative, weld reinforcement in accordance with CSA W186.
- .4 Ship bundles of bar reinforcement, clearly identified in accordance with bar bending details and lists.

#### 2.3 SOURCE QUALITY CONTROL

- .1 Upon request, provide Departmental Representative with certified copy of mill test report of reinforcing steel, showing physical and chemical analysis.
- .2 Upon request inform Departmental Representative of proposed source of material to be supplied.

#### 2.4 STRUCTURAL STEEL WORK

- .1 Unless noted otherwise on drawings:
  - .1 All structural steel shall conform to CAN/CSA-G40.20/G40.21-92 grade 300W.
  - .2 Welding shall be carried out in accordance with CSA W59-1989.
  - .3 All steel plates, threaded rods, washers and nuts shall be galvanized in accordance with CAN/CSA G164-M92.

### PART 3 - EXECUTION

#### 3.1 PREPARATION

- .1 Galvanizing to include chromate treatment.
  - .1 Duration of treatment to be 1 hour per 25 mm of bar diameter.
- .2 Conduct bending tests to verify galvanized bar fragility in accordance with ASTM A 143/A 143M.

#### 3.2 FIELD BENDING

- .1 Do not field bend or field weld reinforcement except where indicated or authorized by Departmental Representative.
- .2 When field bending is authorized, bend without heat, applying slow and steady pressure.
- .3 Replace bars, which develop cracks or splits.

#### 3.3 PLACING REINFORCEMENT

- .1 Place reinforcing steel as indicated on placing drawings and in accordance with CSA-A23.1/A23.2.
- .2 Use plain round bars as slip dowels in concrete.
  - .1 Paint portion of dowel intended to move within hardened concrete with one coat of asphalt paint.
  - .2 When paint is dry, apply thick even film of mineral lubricating grease.
- .3 Prior to placing concrete, obtain Departmental



Representative's approval of reinforcing material and placement.

- .4 Minimum concrete cover to reinforcing steel, unless shown otherwise in the drawings:
  - .1 faces cast and permanently exposed against earth = 75mm
  - .2 inside faces of walls = 50mm
  - .3 slabs and other formed walls = 40mm
- .5 Ensure cover to reinforcement is maintained during concrete pour.
- .6 Protect coated portions of bars with covering during transportation and handling.
- .7 Development length as follows:

	Uncoated Vertical Bars	Uncoated Horizontal Bars
10M	300mm	350mm
15M	400mm	500mm
20M	550mm	700mm

- .8 Lap splices shall be staggered with minimum lap length as follows:

	Uncoated	Uncoated Top Bars
10M	350mm	450mm
15M	500mm	650mm
20M	700mm	900mm

- .9 Splices shall be staggered so that no more than 50% of the reinforcing is spliced at any one location, unless shown otherwise on the drawings.
- .10 All exposed edges of concrete to be chamfered 19mm.

3.4 FIELD TOUCH-UP

- .1 Touch up damaged and cut ends of epoxy coated or galvanized reinforcing steel with compatible finish to provide continuous coating.

-----END OF SECTION-----

PART 1 - GENERAL

1.1 RELATED SECTIONS

- .1 Section 31 23 10-Excavating, Trenching and Backfilling.

1.2 REFERENCES

- .1 American Society for Testing and Materials International (ASTM)
  - .1 ASTM C 260, Standard Specification for Air-Entraining Admixtures for Concrete.
  - .2 ASTM C 309, Standard Specification for Liquid Membrane-Forming Compounds for Curing Concrete.
  - .3 ASTM C 494/C 494M, Standard Specification for Chemical Admixtures for Concrete.
  - .4 ASTM D 1751, Standard Specification for Preformed Expansion Joint Filler for Concrete Paving and Structural Construction (Nonextruding and Resilient Bituminous Types).
  - .5 ASTM D 1752, Standard Specification for Preformed Sponge Rubber Cork and Recycled PVC Expansion Joint Fillers for Concrete Paving and Structural Construction.
- .2 Canadian Standards Association (CSA International)
  - .1 CAN/CSA-A23.1-04, Concrete Materials and Methods of Concrete Construction.
  - .2 CAN/CSA-A23.2-04, Methods of Test and Standard Practice for Concrete.
  - .3 CAN/CSA-A23.3-04, Design of Concrete Structures.
  - .4 CSA A283, Qualification Code for Concrete Testing Laboratories.
  - .5 CAN3 - A5-M1983, Portland Cements.
  - .6 CAN/CSA-A3000, Cementitious Materials Compendium (Consists of A3001, A3002, A3003, A3004 and A3005).
    - .1 CSA-A3001, Cementitious Materials for Use in Concrete.
- .3 National Building Code of Canada 2010.

1.3 CERTIFICATION

- .1 Minimum 2 weeks prior to starting concrete work submit to Department Representative manufacturer's test data and certification by qualified independent inspection and testing laboratory that following materials will meet specified requirements:
  - .1 Portland cement.
  - .2 Blended hydraulic cement.
  - .3 Supplementary cementing materials.
  - .4 Grout.
  - .5 Admixtures.
  - .6 Aggregates.
  - .7 Water
  - .8 Waterstops.
  - .9 Waterstop joints.
  - .10 Joint filler
- .2 Provide certification from Materials Representative

that plant, equipment, and materials to be used in concrete comply with requirements of CAN/CSA-A23.1

- .3 Provide certification from Materials Representative that mix proportions selected will produce concrete of specified quality, durability and yield and that strength will comply with CAN/CSA-A23.1.

1.4 CONSTRUCTION QUALITY CONTROL

- .1 Quality Assurance: in accordance with Section 01 45 00 - Quality Control.
- .2 Health and Safety Requirements: do construction occupational health and safety in accordance with Section 01 35 33 - Health and Safety Requirements.
- .3 Submit proposed quality control procedures for DEPARTMENT Representative's approval. Submit in accordance to 01 33 00 - Submittal Procedures.

PART 2 - PRODUCTS

2.1 MATERIALS

- .1 Portland Cement: to CAN/CSA-5.
- .2 Supplementary Cementing Materials: to CSA-A23.5.
- .3 Water: to CSA-A23.1.
- .4 Aggregates: to CAN/CSA-A23.1.
- .5 Air entraining admixture: to CAN/CSA-A266.1.
- .6 Chemical admixtures: to CAN/CSA-A266.2. Department Representative to approve acceleration or set retarding admixtures during cold and hot weather placing.
- .7 Grout:
  - .1 Provide grout certification prior to use.
  - .2 To be as specified in Contract Documents. Alternative to be approved by Department Representative.
  - .3 Use in accordance with manufacturer's recommendations.
- .8 Curing Compound:
  - .1 To be spray applied, liquid type conforming to ASTM C309 containing a fugitive dye.
  - .2 To be applied in accordance with manufacturer's recommendations.
  - .3 Other curing methods such as sheet material and burlap mats, subject to DEPARTMENT Representative's approval.

- .9 Premoulded Joint Fillers (expansion joint):  
Bituminous impregnated fibre board: to ASTM D1751.

## 2.2 CONCRETE MIXES

- .1 Proportion concrete in accordance with CAN/CSA-A23.1, Table 11. Group and to specific design criteria specified on Contract Drawings.
- .2 Concrete shall have a minimum compressive strength of 35MPa at 28 days
- .3 Concrete mix to have 6% +- 1% air content, 60mm +- 20mm slump and 0.45 maximum water to cement ratio by mass.
- .4 Concrete to have exposure class C-XL.

## 2.3 FORMS

- .1 Forms to CAN/CSA-A23.1.11.
- .2 Free from surface defects for all concrete faces exposed to view.
- .3 Form ties to be metal and of type such that no metal left within 25mm of concrete surface when forms removed.

## 2.4 FORM RELEASE AGENT

- .1 Non-staining material type form release agent: chemically active release agents containing compounds that react with free lime to provide water soluble soap.

## PART 3 - EXECUTION

### 3.1 GENERAL

- .1 Do cast-in-place concrete work, including surface tolerances, finishing and field quality control, in accordance with CAN/CSA-A23.1 except where specifically stated otherwise.

### 3.2 FORMWORK

- .1 Formwork to conform to shape, lines and dimensions shown on Contract Drawings.
- .2 Formwork to be substantial, sufficiently tight to prevent leakage of mortar and braced and tied to maintain position and shape.
- .3 Formwork to be unlined unless specified otherwise.

### 3.3 CONSTRUCTION

- .1 Obtain DEPARTMENT Representative's approval before placing concrete. Providing minimum 24h notice prior to placing of concrete.
- .2 Pumping of concrete is permitted only after Department Representative's approval of equipment and mix.
- .3 Ensure reinforcement and inserts are not disturbed during concrete placement.

- .4 Prior to placing of concrete obtain Department Representative's approval of proposed method for protection of concrete during placing and curing.
- .5 Ensure placement and compaction procedures to CAN/CSA-A23.1 and to approval of Department Representative.
- .6 Protect exposed surfaces from weather and vandalism during initial set period.
- .7 Strip forms ensuring no damage to concrete.
- .8 Ensure curing procedures consistent with weather and temperature conditions.
- .9 Maintain accurate records of poured concrete items to indicate date, location of pour, quality, air temperature and test samples taken.
- .10 Don not place load upon new concrete until authorized by Department Representative.

3.4 JOINT FILLERS

- .1 Furnish filler for each joint in single piece for depth and width required for joint, unless authorized otherwise by Department Representative. When more than one piece is required for a joint, fasten abutting ends and hold securely to shape by stapling or other positive fastening.
- .2 Locate and form all joints as shown on Contract Drawings or as otherwise require. Install joint filler where applicable.
- .3 Use 13mm thick joint filler to separate slabs-on-grade from vertical surfaces and extend joint filler from bottom of slab to finished slab surface unless indicated at bottom.

-----END OF SECTION-----

PART 1 - GENERAL

1.1 RELATED SECTIONS

1. Section 01 33 00-Submittal Procedures.
2. Section 32 11 23-Aggregate Base Courses.

1.2 REFERENCES

1. ASTM; AWWA; CAN - As specified in the contract document

1.3 SOURCE QUALITY CONTROL

1. Submit samples in accordance with Section 01 33 00 - Submittal Procedures.
2. Inform Department Representative of proposed source and provide samples or access for sampling at least 2 weeks prior to commencing production.
3. If, in opinion of Department Representative, materials from proposed source do not meet, or cannot reasonably be processed to meet, specified requirements, locate an alternative source or demonstrate that material from source in question can be processed to meet specified requirements.
4. Should a change of material source be proposed during work, advise Department Representative 2 weeks in advance of proposed change to allow sampling and testing.
5. Acceptance of material does not preclude future rejection if it is subsequently found to lack uniformity, or if it fails to conform to requirements specified.
6. Pay cost of sampling and testing of aggregates which fail to meet specified requirements.

1.4 WASTE MANAGEMENT AND DISPOSAL

1. Divert unused granular materials from landfill to local facility as approved by Department Representative.

PART 2 - PRODUCTS

2.1 MATERIALS

1. Gravel to be composed of inert, durable material, reasonably uniform in quality and free from soft or disintegrated particles. In absence of satisfactory performance records over a five year period for particular source of material, soundness to be tested according to ASTM test procedure C-88 or latest revised issue. Maximum weight average losses for course and fine aggregates to be 30% when magnesium sulphate is used after five cycles.

2. All crushed gravel when tested according to ASTM C-136 and ASTM C-117, or latest revised issue, to have a generally uniform gradation and conform to following gradation limits and 60% of the material passing each sieve must have one or more fractured faces. Determination of the amount of fractured material shall be in accordance with the Ministry of Transportation and Highways' Specification I-11, Fracture Count for Coarse Aggregate, Method "A", which determines fractured faces by count. The Plasticity Index for crushed gravel to not exceed 6.0.

2.2 NATIVE MATERIAL

1. To be any workable soil free of organic or foreign matter; any material obtained within limits of Contract may be approved by the Department Representative. Native material content or compact to specified density.

2.3 PIT RUN GRAVEL

- .1 To be well graded granular material, substantially free from clay lumps, organic matter and other extraneous material, screened to remove all stones in excess of maximum diameter specified in material description (300 mm Pit Run Gravel, 200 mm Pit Run Gravel, 100 mm Pit Run Gravel). Material to compact to specified density and conform to following gradations:

<b>Sieve Designation</b>	<b>Percent Passing</b>
(300mm dia)	(100)
(200mm dia)	(100)
(100mm dia)	(100)
75mm	100
50mm	70-100
25mm	50-100
4.75mm	22-100
2.36mm	10-85
0.075mm	2-8

Recycled concrete free from contaminated and other extraneous material, conforming to the specified gradations may be used as pit run gravel.

2.4 PIT RUN SAND

1. To be well graded pit run sand, free from organic materials and conform to following gradations:

<b>Sieve Designation</b>	<b>Percent Passing</b>
12.5mm	100
4.75mm	35-100
2.36mm	20-70
1.18mm	13-50

0.600mm	8-35
0.300mm	5-25
0.150mm	2-15
0.075mm	0-6

2.5 RIVER SAND

1. River sand, to be used only where shown on Contract Drawings or otherwise specified and approved by Department Representative, to be free of organic material, salt and foreign objects and conform to following gradations:

Sieve Designation	Percent Passing
19mm	100
4.75mm	80-100
0.600mm	20-80
0.150mm	0-20
0.075mm	0-8

2.6 DRAIN ROCK

- .1 To consist of clean round stone or crushed rock conforming to the following gradations:

Sieve Designation	Percent Passing	
	Course	Fine
25.0mm	100	
19.0mm	0-100	
9.5mm	0-5	100
4.75mm	0	50-100
2.36mm		5-15
1.18mm		15-38
0.600mm		0-8
0.300mm		0-5
0.150mm		0-2
0.075mm		0

- .2 Drain rock to be used only where specified on Contract Drawings. Use of drain rock other than as specified requires approval of DEPARTMENT Representative after examination of soils against which drain rock will be placed.

2.7 GRANULAR PIPE BEDDING AND SURROUND MATERIAL

- Crushed or graded gravels to conform to following gradations:

Sieve Designation	Percent Passing	
	Type 1*	Type 2*
25.0mm	100	100
19.0mm	90-100	90-100
12.5mm	65-85	70-100
9.5mm	50-75	
4.75mm	25-50	40-70



2.36mm	10-35	25-52
1.18mm	6-26	15-38
0.600mm	3-17	6-27
0.300mm		3-20
0.075mm	0-5	0-8

Type 1\* standard gradation  
 Type 2\* to be used only in dry trench conditions  
 and with Departmental Representative's  
 prior approval

Recycled concrete free from contaminated and other extraneous material, conforming to the Type 1 gradations, may be used as pipe bedding and surround material.

- .2 Other permissible materials: only where shown on Contract Drawings or directed by Departmental Representative shall drain rock, pit run sand or approved native material be used for bedding and pipe surround.

2.8 SELECT GRANULAR SUB-BASE1.

To be well graded granular material, substantially free from lumps and organic matter, screened if required to conform to following gradations:

Sieve Designation	Percent Passing
75mm	100
25mm	50-85
0.150mm	0-15
0.075mm	0-8

2.9 CRUSHED GRANULAR SUB-BASE

- .1 To be 75mm crushed gravel conforming to following gradations:

Sieve Designation	Percent Passing
80mm	
75mm	100
38mm	60-100
25.0mm	-
19.0mm	35-80
12.5mm	-
9.5mm	26-60
4.75mm	20-40
2.36mm	15-30
1.18mm	10-20
0.60um	5-15
0.30um	3-10
0.18um	-
0.15um	-
0.075um	0-5

2.10 GRANULAR BASE

- .1 To be 19mm crushed gravel conforming to following gradations:

<b>Sieve Designation</b>	<b>Percent Passing</b>
19.0mm	100
12.5mm	75-100
9.5mm	60-90
4.75mm	40-70
2.36mm	27-55
1.18mm	16-42
0.600mm	8-30
0.300mm	5-20
0.075mm	2-8

2.11 RECYCLED AGGREGATE MATERIAL

- .1 Aggregates containing recycled material may be utilized if approved by the DEPARTMENT Representative. In addition to meeting all other conditions of this specification, recycled material should not reduce the quality of construction achievable with quarried materials. Recycled material should consist only of crushed Portland cement concrete; other construction and demolition materials such as asphaltic pavements, bricks, plaster, etc. are not acceptable.

PART 3 - EXECUTION

3.1 HANDLING

- .1 Handle and transport aggregates to avoid segregation, contamination and degradation.
- .2 Do not use intermixed or contaminated materials. Remove and dispose rejected materials within 48 h of rejection.

-----END OF SECTION-----

PART 1 - GENERAL

1.1 RELATED SECTIONS

1. Section 01 35 43-Environmental Procedures.
2. Section 31 05 16-Aggregate Materials.
3. Section 33 05 13-Manholes and Catch Basin Structures
4. Section 33 41 00-Storm Utility Drainage Piping

1.2 REFERENCES

- .1 American Society for Testing and Materials International (ASTM)
  - .1 ASTM C 117, Standard Test Method for Material Finer than 0.075 mm Sieve in Mineral Aggregates by Washing.
  - .2 ASTM C 136, Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates.
  - .3 ASTM D 422-63, Standard Test Method for Particle-Size Analysis of Soils.
  - .4 ASTM D 698, Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Standard Effort (600 kN-m/m<sup>3</sup>).
  - .5 ASTM D 1557, Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Modified Effort (2,700 kN-m/m<sup>3</sup>).
  - .6 ASTM D 4318, Standard Test Methods for Liquid Limit, Plastic Limit, and Plasticity Index of Soils.
- .2 Canadian General Standards Board (CGSB)
  - .1 CAN/CGSB-8.1, Sieves, Testing, Woven Wire, Inch Series.
  - .2 CAN/CGSB-8.2, Sieves, Testing, Woven Wire, Metric.
- .3 Canadian Green Building Council (CaGBC)
  - .1 LEED Canada-NC Version 1.0, LEED (Leadership in Energy and Environmental Design): Green Building Rating System For New Construction and Major Renovations.
- .4 Canadian Standards Association (CSA International)
  - .1 CAN/CSA-A3000, Cementitious Materials Compendium (Consists of A3001, A3002, A3003, A3004 and A3005).
    - .1 CSA-A3001, Cementitious Materials for Use in Concrete.
    - .2 CSA-A23.1/A23.2, Concrete Materials and Methods of Concrete Construction/Methods of Test and Standard Practices for Concrete.
- .5 U.S. Environmental Protection Agency (EPA)/Office of Water
  - .1 EPA 832R92005, Storm Water Management for Construction Activities: Developing Pollution

Prevention Plans and Best Management Practices.

1.3 DEFINITIONS

1. Common Excavation: excavation of materials of whatever nature, which are not included under definitions of rock excavation including dense tills, hardpan, partially cemented materials, clay or frozen materials which can be ripped and excavated with heavy construction equipment.
2. Over-excavation: excavation below design elevation of bottom of specified bedding, and including backfilling of resultant excavation with specified material, as authorized by Department Representative.
3. Removals: removal and disposal at an approved location off-site of surface concrete structures and walks, curbs, gutters, manholes, catchbasins, pipes, culvers, enwalls, and any other structure on surface or underground specifically designated on Contract Drawings for removal. Removals to include backfilling of resultant excavation with specified material.
4. Native Topsoil: to Section 32 91 19-Topsoil Placement and Grading.

1.4 SAFETY REQUIREMENTS

1. Comply with Section 01 35 33-Health and Safety Requirements.
2. Design and install trench shoring in accordance with the regulations of the Workers Compensation Act of British Columbia.

1.5 BLASTING

1. Not Permitted.

1.6 DISPOSAL

1. Dispose of all surplus spoil from excavations on-site and/or off-site as shown on Contract Drawings or as specified in Contract Documents. Suitability of excavated material for use as native bedding or trench backfill will be governed by Part 2 of this Section.  
Dumping of spoil on private property will be permitted only upon written approval from property owner and provided all necessary permits and approvals have been obtained.

1.7 LIMITATIONS OF OPEN TRENCH

1. Excavate trenches only as far in advance of pipe laying operation as safety, traffic, and weather conditions permit and, in no case, to exceed 30m. Before stopping work on last day of work before each weekend or holiday, completely backfill every trench. If circumstances do not permit complete backfilling of all trenches, adequately protect all open trenches or excavations with approved fencing or barricades and, where required, with flashing lights.

PART 2 - PRODUCTS

2.1 USE OF SPECIFIED MATERIALS

1. Back filling for over-excavated trench or structure excavations to be one of the following:
  - .1 Granular pipe bedding and surround material.
  - .2 Pit run sand.
  - .3 Drain rock (only where approved by Department Representative)
  - .4 Concrete.
  - .5 Controlled density fill.
2. Pipe bedding and surround: see applicable Sections:
  1. Section 33 41 00-Storm Utility Drainage Piping
3. Trench and excavation backfill to be one of the following:
  - .1 Approved native material.
  - .2 Pit run gravel.
  - .3 Pit run sand.
  - .4 Controlled density fill.
4. Surface treatment to be:
  - .1 Restoration to match existing conditions
  - .2 Subgrade, subbase and base for works described in other Sections
  - .3 Topsoil, grass, sod or requirements for landscaping works described in other Sections.

2.2 MATERIALS

1. Refer to Section 31 05 16 - Aggregates Materials for specifications for approved granular materials and approved native materials.
2. Other granular materials: granular materials approved for roadwork (subbase, base,) also acceptable for trench backfill subject to approval of Department Representative.
3. Concrete: to Section 03300, to be minimum 20 MPa.

PART 3 - EXECUTION

3.1 SITE PREPARATION

1. Remove all brush, weeds, grasses and accumulated debris to an approved offsite location.
2. Cut pavements or sidewalk neatly along limits of proposed excavation as shown on Contract Drawings in order that surface may break evenly and cleanly. Cut beyond limits shown only if authorized by Department Representative.
3. Where trench passes through lawn, neatly cut and remove

sod before trench excavation. Save sod for replacement upon backfilling trench.

4. Strip topsoil after area has been cleared and stockpile in locations as directed by Department Representative. Stockpile height not to exceed 2m. Avoid mixing topsoil with subsoil. Dispose of unused topsoil as specified. Do not handle topsoil while wet or frozen condition or in any manner in which soil structure is adversely affected.

### 3.2 STOCKPILING

1. Stockpile fill materials in areas designated by Department Representative. Stockpile granular materials in manner to prevent segregation.

### 3.3 EXCAVATION

1. Connecting to existing mains:
  - .1 Prior to or at commencement for construction, check existing main for line and elevation at point of connection. If found different from Contract Drawings report such difference to Department Representative immediately.
  - .2 Connections to existing waterworks, sanitary and storm sewer systems to be made by the Contractor unless shown otherwise on Contract Drawings. Notify Department Representative minimum 48 hours in advance of schedule connection. Make connection in presence of Department Representative.
  - .3 To prevent damage to existing utilities, excavation last 300 mm over utility by hand.
2. Surface Drainage:
  - .1 Provide suitable temporary ditches or other approved means of handling drainage prior to excavation and during construction to protect construction area and adjacent lands. Provide siltation controls to protect natural watercourses or existing drainage facilities.
  - .2 Comply with Section 01 35 43-Environmental Procedures.
3. Excavation to grade: excavation trenches to allow pipe to be laid to alignment and grades required with allowance for specified pipe bedding.
4. Excavation below grade: when bottom of excavated trench at subgrade is unstable and in opinion of Department Representative, cannot adequately support pipe, install pipe as shown on Contract Drawings or over-excavate trench to suitable subgrade or as directed by Department Representative. Backfill over excavated with specified materials and compact to minimum 95% Modified Proctor density in compliance with ASTM D1557. Use drain rock backfill only if authorized by Department Representative.

5. Trench width: excavation trench to section and dimension shown on Contract Drawings. If width exceeds maximum allowable, Contractor may be required to demonstrate that specified pipe is still adequate or provide pipe with approved higher class bedding. All additional requirements as a result of excessive trench width to be to Contractor's cost.
6. Hand excavation: excavate by hand if necessary to preserve or minimize damage to existing trees, shrubs, building and all similar existing features or facilities.
7. Trench bottom conditions: remove disturbed or softened material from trench bottom before placing bedding material. Maintain trench free from water and soft materials during placement of pipe bedding, pipe installation and trench backfill to ensure proper compaction of granular materials.
8. Trench drainage:
  - .1 During pipe laying, jointing, bedding and backfilling, keep trench free of water by pumping or other appropriate means. Provide pumps and dewatering equipment and take precautions to prevent any damage to adjoining buildings, structures, roads or land from prolonged or excessive pumping by installing shoring, sheeting or other supportive measures. Discharge water from excavations in such manner as not to cause nuisance, injury, loss or damage. Contractor to be responsible for any claims or actions arising from such discharge of water.
  - .2 Keep bell holes free from water during jointing. Diverting trench water through newly laid system not allowed, unless authorized by Department Representative.
9. Disposal of surplus soil: Dispose of surplus excavation soil off-site. Side-casting not allowed in restricted areas where, in opinion of Department Representative, side-casting would create interference with flow of traffic. In such case, temporarily store materials or dispose to an approved site. Provisions of Provincial Contaminated Sites Legislation must be met prior to disposal of soil offsite.
10. Where native backfill is approved for re-use, and side-casting not allowed, transport approved material to other locations where material is required or temporarily store at approved site. Protect stored material from contamination, segregation and weather.
11. Rock excavation: Section 31 23 17-Rock Removal.

12. Maintain roads used for transporting materials and equipment in clean condition. Clean, flush and/or sweep on daily basis and more frequently if directed by Department Representative.

#### 3.4 PIPE INSTALLATION

1. Related work: Pipe installation, including bedding, pipe laying, and granular surround to be in accordance with following sections:
  1. Section 33 05 13-Manholes and Catch Basin Structures
  2. Section 33 41 00-Storm Utility Drainage Piping
2. Concrete encasements or protection: where specified or required by Department Representative provide concrete encasements of pipe or slab protection as shown on Contract Drawings. Do not place backfill material until concrete has taken its initial set and in no case less than 1 hour.
3. Anchor blocks: where specified or required by Department Representative provide anchor blocks as shown on Contract Drawings. Ensure all concrete anchor blocks at least 150 mm into undisturbed ground on bottom side of each trench.

#### 3.5 BACKFILL AND COMPACTION

1. General: Place backfill carefully in trench to prevent damage to installed pipe.
2. Shoring: during backfill and compaction of trench, remove shoring in such a manner as to allow proper compaction and to prevent trench walls from collapsing. Remove all bracing and/or shoring from trench.
3. Backfill Materials:
  - .1 Boulevards and easements: for trenches in boulevards, easements or other areas not subjected to vehicle loading, and outside of ditch lines, backfill with approved native materials except as shown otherwise on Contract Drawings.
  - .2 Roads, driveways and shoulders: for trenches in paved or graveled roads, driveways, shoulders or other areas subjected to vehicle loading, backfill with imported granular material or approved native material as specified on Contract Drawings. Road shoulder is that portion of right-of-way between travelled, and road ditch. Where no ditch exists, ensure shoulder width minimum of 1.5 m.
  - .3 Ditches: backfill with imported granular material or approved native material as specified on Contract Drawings.
  - .4 Department Representative may permit native materials for all above uses subject to suitability



of native material for said use. Native material approved for re-use to be handled, stockpiled and compacted using construction method appropriate for given moisture content and weather conditions.

4. Compaction: place backfill and compact to following Modified Proctor densities in compliance with ASTM D1557. (All following references to density imply compliance with ASTM D1557).
  - .1 Boulevards and easements to minimum 90%.
  - .2 Roads, driveways, shoulders, re-shaped ditches and sidewalks to minimum 95%.
  - .3 Use caution in pipe zone to ensure no damage to pipe.

### 3.6 SURFACE RESTORATION

1. General:
  - .1 Restore all disturbed surfaces to condition at least equal to which existed prior to construction.
  - .2 Make good any damage to adjacent lands or improvements.
  - .3 Resolve all reasonable claims arising from Contractor's actions and obtain written releases from land owners following final restoration.
2. Boulevards and easements:
  - .1 Restore surface to minimum 100 mm depth.
  - .2 Restore unimproved surfaces with material equal to that removed at surface.
  - .3 Restore gardens with approved topsoil or bark mulch to match existing conditions.
  - .4 Restore lawns with approved topsoil and seed or sod to match existing lawn.
  - .5 Restore gravel surfaces with matching granular materials.
  - .6 Complete final restorations immediately upon completion of trench backfilling.
3. Graveled roads and driveways:
  - .1 Restore surface with minimum 75 mm to 100 mm thick lift of 19 mm granular road base material.
  - .2 Compact to minimum 95% Modified Proctor density.
  - .3 Complete final restoration immediately upon completion of trench backfilling.
4. Ditches:
  - .1 Re-shape ditches to specified lines, grades and sections as specified to ensure stability of ditch slopes and bottom.
  - .2 Compact to minimum 95% Modified Proctor Density.
  - .3 Complete final restoration immediately upon completion of trench backfilling.

5. Base preparation for paved surfaces:
  - .1 Paved surfaces to include all paved roads, driveways, sidewalks and parking areas.
  - .2 If native material used for backfill provide specified depth of subbase as shown on Contract Drawings.
  
6. Temporary pavement patching:
  - .1 Patch roads same day excavation made.
  - .2 Patch all other roads within 24 hours of closing trench.
  - .3 Patching material to be hot-mix asphalt on all roads unless specified otherwise, cold-mix may be used only where directed by Department Representative.
  - .4 Place temporary pavements to 50 mm minimum thickness.
  - .5 Maintain temporary patch to ensure safe and smooth conditions.
  
7. Permanent pavement restoration:
  - .1 Install permanent pavement within 30 days of placement of temporary patch or sooner where directed by Department Representative.
  - .2 Remove broken or cracked pavement as well as any paves areas showing settlement and dispose off-site.
  - .3 Remove underlying granular road base material as required to permit placement of specified thickness of permanent pavement. Ensure remaining base meets specified thickness. Material and placement of road base to Section 32 11 23-Aggregate Base Courses
  - .4 Compact base to minimum 95% Modified Proctor density.
  - .5 Restore pavement as detailed on Contract Drawings. If thickness of existing pavement permits, grind 40 mm depth along edge of pavement. Dry if necessary and paint clean, dry edge with asphalt emulsion (tack coat).
  - .6 Place and compact hot-mix pavement material to minimum thickness as shown on Contract Drawings.
  - .7 Material and placement of hot-mix pavement to Section 32 12 16-Asphalt Paving.
  - .8 Restore surface to smooth condition and match with grade of adjacent pavement.
  - .9 Where shown on Contract Drawings place hot-mix overlay over restored trench section and adjacent pavement to Section 32 12 16-Asphalt Paving.
  - .10 Maintain restored pavements in complete repair during Maintenance Period. Effect repairs within 14 days from receipt of written notice from Department Representative or immediately

if so directed by Department Representative if dangerous situation exists.

8. Landscape Restoration:
  1. Restoration of planted areas to consist of restoration to original condition by replacement to original depth of approved topsoil (minimum 100mm), seeding or sodding of grassed areas and replacement of any killed or removed plants or shrubs by ones equal quality, type and maturity to originals.
  2. Plant replacement trees and shrubs at a suitable time of year in accordance with good horticulture practice, to provide maximum assurance of plant survival. If tree or shrub has died, or shows signs of dying, as a result of environmental disturbance, cutting of roots, or other causes directly attributed to Contractors work, close to but not actually within excavation areas, replace with new tree or shrub of a similar variety, age and size, up to limits of maximum available size.
9. Restoration acceptance: no restoration work to be considered satisfactory until acceptance by Department Representative.

-----END OF SECTION-----

PART 1 - GENERAL

1.1 RELATED SECTIONS

1. Section 01 35 14-Special Procedures for Traffic Control.
2. Section 31 05 16-Aggregate Materials.
3. Section 32 11 19-Granular Sub-Base.

1.2 REFERENCES

- .1 American Society for Testing and Materials (ASTM)
  - .1 ASTM C 117, Standard Test Methods for Material Finer Than 0.075 mm Sieve in Mineral Aggregates by Washing.
  - .2 ASTM C 131, Standard Test Method for Resistance to Degradation of Small-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine.
  - .3 ASTM C 136, Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates.
  - .4 ASTM D 698, Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Standard Effort (600kN-m/m<sup>3</sup>).
  - .5 ASTM D 1557-[00], Test Method for Laboratory Compaction Characteristics of Soil Using Modified Effort (2,700kN-m/m<sup>3</sup>).
  - .6 ASTM D 1883, Standard Test Method for CBR (California Bearing Ratio) of Laboratory Compacted Soils.
  - .7 ASTM D 4318, Standard Test Methods for Liquid Limit, Plastic Limit and Plasticity Index of Soils.
- .2 Canadian General Standards Board (CGSB)
  - .1 CAN/CGSB-8.1, Sieves, Testing, Woven Wire, Inch Series.
  - .2 CAN/CGSB-8.2, Sieves, Testing, Woven Wire, Metric.

1.3 WASTE MANAGEMENT AND DISPOSAL

- .1 Divert unused granular material from landfill to local facility as approved by Department Representative.

PART 2 - PRODUCTS

2.1 MATERIALS

- .1 Material for road base to be:
  - .1 19 mm crushed gravel.
  - .2 Refer to Section 31 05 16-Aggregate Materials for material specifications.

PART 3 - EXECUTION

3.1 INSPECTION OF UNDERLYING SUBGRADE SURFACE

- .1 Ensure underlying subbase surface true to cross-section and grade and compacted to 95% Modified Proctor density in compliance with ASTM D1557. Do not

place granular subbase until subgrade is inspected and approved by Department Representative.

### 3.2 PLACING

1. Place material only on clean unfrozen surface, properly shaped and compacted and free from snow or ice.
2. Begin spreading sub-base material on crown line or high side of one-way slope.
3. Place granular sub-base materials using methods which do not lead to segregation or degradation.
4. Place material to full width in uniform layers not exceeding 150mm compacted thickness. Department Representative may authorize thicker lifts (layers) if specified compaction can be achieved.
5. Shape each layer to smooth contour and compact to specified density before succeeding layer is placed.
6. Remove and replace portion of layer in which material has become segregated during spreading.

### 3.3 COMPACTION

- .1 Compaction equipment to be capable of obtaining required material densities.
- .2 Compact to density of not less than 95% Modified Proctor Density.
- .3 Shape and roll alternately to obtain smooth, even and uniformly compacted sub-base.
- .4 Apply water as necessary during compaction to obtain specified density. If material is excessively moist, aerate by scarifying with suitable equipment until moisture content is suitable for compaction.
- .5 In areas not accessible to rolling equipment, compact to specified density with mechanical tampers approved by Department Representative.

### 3.4 SITE TOLERANCES

1. Ensure finished base within plus or minus 10 mm of specified grade and cross-section but not uniformly high or low.
2. Ensure finished surface has no irregularities exceeding 10 mm when checked with a 3 m straight edge placed in any direction.
3. Correct surface irregularities by loosening and adding or removing material until surface is within specified tolerance.

### 3.5 PROOF ROLLING

1. For proof rolling use fully loaded single or dual axle dump truck.
2. Department Representative may authorize use of other

acceptable proof rolling equipment.

3. Proof roll top of base upon completion of fine grading and compaction.
  4. Make sufficient passes with proof roller to subject every point on surface to three separate passes of loaded tire.
  5. Where proof rolling reveals area of unsuitable subgrade:
    1. Remove base, subbase and subgrade material to depth and extent as directed by Department Representative.
    2. Backfill excavated subgrade with approved embankment material and compact in accordance with Section 31 24 13-Roadway Embankments.
    3. Replace subbase material and compact in accordance with this Section 32 11 19-Granular Sub-Base.
    4. Replace base material and compact in accordance with this Section.
  6. Where proof rolling reveals areas of unsuitable base or subbase, remove unsuitable materials to depth and extent directed by Department Representative and replace with new materials in accordance with Section 32 11 19-Granular Sub-Base at no extra cost.
- 3.6 MAINTENANCE .1 Maintain finished sub-base in condition conforming to this section until succeeding base is constructed, or until granular sub-base is accepted by Department Representative.

-----END OF SECTION-----

PART 1 - GENERAL

- 1.1 SECTION INCLUDES
- .1 Materials and application of asphalt prime to granular base surface prior to asphalt paving.
- 1.2 RELATED SECTIONS
- .1 Section 01 33 00-Submittal Procedures.
  - .2 Section 01 35 14-Special Procedures for Traffic Control.
  - .3 Section 32 11 23-Aggregate Base Courses
  - .4 Section 32 12 16-Asphalt Paving.
- 1.3 REFERENCES
- .1 American Society for Testing and Materials International, (ASTM)
    - .1 ASTM D 140, Standard Practice for Sampling Bituminous Materials.
  - .2 Canadian General Standards Board (CGSB)
    - .1 CAN/CGSB-16.1, Cutback Asphalts for Road Purposes.
    - .2 CAN/CGSB-16.2, Emulsified Asphalts, Anionic Type, for Road Purposes.
- 1.4 QUALITY ASSURANCE
- .1 Upon request from Department Representative, submit manufacturer's test data and certification that asphalt prime material meets requirements of this Section.
  - .2 Provide access on tanker for Department Representative to sample asphalt material to be incorporated into work, in accordance with ASTM D140.
- 1.5 DELIVERY, STORAGE AND HANDLING
- .1 Deliver, store and handle materials to ASTM D 140.
- 1.6 WASTE MANAGEMENT AND DISPOSAL
- .1 Divert unused asphalt materials from landfill to local facility approved by Department Representative.
  - .2 Divert unused aggregate materials from landfill to local facility approved by Department Representative.
- PART 2 - PRODUCTS
- 2.1 MATERIAL
- .1 Asphalt material: to CAN/CGSB-16.1 grade: RM-20, RM-70 or CAN/CGSB-16.2 grade: SS-1h.

- .2 Sand blotter: clean granular material passing 4.75mm sieve and free from organic matter or other deleterious materials.

## 2.2 EQUIPMENT

- .1 Pressure distributor to be :
  - .1 Designed, equipped, maintained and operated so that asphalt material can be:
    - .1 Maintained at even temperature.
    - .2 Applied uniformly on variable widths of surface up to 5 m.
    - .3 Applied at controlled rates from 0.2 to 5.4 L/m<sup>2</sup> with uniform pressure, and allowable variation from any specified rate not exceeding 0.1 L/m<sup>2</sup>.
    - .4 Distributed in uniform spray without atomization at temperature required.
  - .2 Equipped with meter registering metres of travel per minute, visibly located to enable truck driver to maintain constant speed required for application at specified rate.
  - .3 Equipped with pump having flow meter graduated in units of 5 L or less per minute passing through nozzles and readily visible to operator. Pump power unit to be independent of truck power unit.
  - .4 Equipped with easily read, accurate and sensitive device which registers temperature of liquid in reservoir.
  - .5 Equipped with accurate volume measuring device or calibrated tank.
  - .6 Equipped with nozzles of same make and dimensions, adjustable for fan width and orientation.
  - .7 Equipped with nozzle spray bar, with operational height adjustment.
  - .8 Cleaned if previously used with incompatible asphalt material.
- .2 Hand Sprayer: For small and/or inaccessible areas, a pressurized hand-held spray wand may be used.

## PART 3 - EXECUTION

### 3.1 APPLICATION

- .1 Obtain Department Representative's approval of granular base surface before applying asphalt prime.
- .2 Cutback asphalt:
  - .1 Heat asphalt prime to between 60 and 70 degrees C for pumping and spraying.
  - .2 Apply asphalt prime to granular base at rate as directed by Department Representative, but not to exceed 2 L/m<sup>2</sup>.
  - .3 Apply on dry surface unless otherwise directed by Department Representative.
- .3 Emulsified asphalt:
  - .1 Dilute asphalt emulsion with clean water at 1:1



ratio for application.

.2 Mix thoroughly by pumping or other method approved by Department Representative.

.3 Apply diluted asphalt emulsion at rate directed by Department Representative, but do not exceed 5 L/m<sup>2</sup>.

.4 Apply diluted asphalt emulsion on damp surface unless otherwise directed by Department Representative.

.4 Do not apply prime when air temperature is less than 5 degrees C or when rain is forecast within 2 hours.

.5 Paint contact surfaces of curbs, gutters, headers, manholes and like structures with thin, uniform coat of asphalt prime material.

.6 Where traffic is to be maintained, treat no more than one-half width of surface in one application.

.7 Prevent overlap at junction of applications.

.8 Do not prime surfaces that will be visible when paving is complete.

.9 Apply additional material to areas not sufficiently covered as directed by Department Representative.

.10 Keep traffic off primed areas until asphalt prime has cured.

.11 Permit prime to cure before placing asphalt paving.

3.2 USE OF SAND  
BLOTTER

.1 If asphalt prime fails to penetrate within 24 hours, spread sand blotter material in amounts required to absorb excess material.

.2 Sweep and remove excess blotter material.

-----END OF SECTION-----

PART 1 - GENERAL

1.1 RELATED  
SECTIONS

- .1 Section 01 33 00-Submittal Procedures.
- .2 Section 01 35 14-Special Procedures for Traffic Control.
- .3 Section 32 12 16-Asphalt Paving.

1.2 REFERENCES

- .1 American Society for Testing and Materials International, (ASTM)
  - .1 ASTM D 140, Standard Practice for Sampling Bituminous Materials.
- .2 Canadian General Standards Board (CGSB)
  - .1 CAN/CGSB-16.2, Emulsified Asphalts, Anionic Type, for Road Purposes.

1.3 QUALITY  
ASSURANCE

- .1 Upon request by Department Representative, submit manufacturer's test data and certification that asphalt tack coat material meets requirements of this section.
- .2 Provide access on tanker for Department Representative to sample asphalt material to be incorporated into work, in accordance with ASTM D140.

1.4 DELIVERY,  
STORAGE AND  
HANDLING

- .1 Deliver, store and handle materials in accordance with ASTM D 140.

1.5 WASTE  
MANAGEMENT AND  
DISPOSAL

- .1 Divert unused asphalt from landfill to facility capable of recycling materials.

PART 2 - PRODUCTS

2.1 MATERIALS

- .1 Emulsified asphalt: to CAN/CGSB-16.2, grade: SS-1.

PART 3 - EXECUTION

3.1 EQUIPMENT

- 1. Refer to Section 32 12 14-Asphalt Prime Coats.

3.2 APPLICATION

- .1 Obtain Department Representative's approval of surface before applying asphalt tack coat.
- .2 Apply asphalt tack coat only on clean and dry surface.
- .3 Dilute asphalt emulsion with water at 1:1 ratio for application.

- .1 Mix thoroughly by pumping or other method approved by Department Representative.
- .4 Apply asphalt tack coat evenly to pavement surface at rate as directed by Department Representative, but not to exceed 0.7 L/m<sup>2</sup> when diluted with water at 1:1 ratio.
- .5 Paint contact surfaces of curbs, gutters, headers, manholes and like structures with thin, uniform coat of asphalt tack coat material.
- .6 Do not apply asphalt tack coat when air temperature is less than 5 degrees C or when rain is forecast within 2 hours of application.
- .7 Apply asphalt tack coat only on unfrozen surface.
- .8 Asphalt tack oil, is toxic to aquatic life. Provide extra caution near catchbasins and storm drain inlets as all storm sewers in the worksite drain to an environmentally sensitive watercourse.
- .9 Evenly distribute localized excessive deposits of tack coat by brooming as directed by Department Representative.
- .10 Where traffic is to be maintained, treat no more than one half of width of surface in one application.
- .11 Keep traffic off tacked areas until asphalt tack coat has set.
- .12 Re-tack contaminated or disturbed areas as directed by Department Representative.
- .13 Permit asphalt tack coat to set before placing asphalt pavement.

-----END OF SECTION-----

PART 1 - GENERAL

- 1.1 SECTION INCLUDES
- .1 Materials and installation for asphalt concrete paving for roads and airport runways.
- 1.2 RELATED SECTIONS
1. Section 01 33 00-Submittal Procedures.
2. Section 01 35 14-Special Procedures for Traffic Control.
3. Section 31 05 16-Aggregate Materials.
4. Section 32 12 14-Asphalt Prime Coats
5. Section 32 12 15-Asphalt Tack Coats.
- 1.3 REFERENCES
- .1 American Association of State Highway and Transportation Officials (AASHTO)
- .1 AASHTO M320, Standard Specification for Performance Graded Asphalt Binder.
- .2 AASHTO R29, Standard Specification for Grading or Verifying the Performance Graded of an Asphalt Binder.
- .3 AASHTO T245, Resistance to Plastic flow of Bituminous Mixtures Using Marshall Apparatus.
- .2 Asphalt Institute (AI)
- .1 AI MS2 Sixth Edition, Mix Design Methods for Asphalt Concrete and Other Hot-Mix Types.
- .3 American Society for Testing and Materials International, (ASTM)
- .1 ASTM C 88, Standard Test Method for Soundness of Aggregates by Use of Sodium Sulphate or Magnesium Sulphate.
- .2 ASTM C 117, Standard Test Method for Material Finer Than 0.075mm (No.200) Sieve in Mineral Aggregates by Washing.
- .3 ASTM C 123, Standard Test Method for Lightweight Particles in Aggregate.
- .4 ASTM C 127, Standard Test Method for Specific Gravity and Absorption of Coarse Aggregate.
- .5 ASTM C 128, Standard Test Method for Density, Relative Density (Specific Gravity), and Absorption of Fine Aggregate.
- .6 ASTM C 131, Standard Test Method for Resistance to Degradation of Small-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine.
- .7 ASTM C 136, Standard Method for Sieve Analysis of Fine and Coarse Aggregates.
- .8 ASTM C 207, Standard Specification for Hydrated Lime for Masonry Purposes.

- .9 ASTM D 995, Standard Specification for Mixing Plants for Hot-Mixed, Hot-Laid Bituminous Paving Mixtures.
  - .10 ASTM D 2419, Standard Test Method for Sand Equivalent Value of Soils and Fine Aggregate.
  - .11 ASTM D 3203, Standard Test Method for Percent Air Voids in Compacted Dense and Open Bituminous Paving Mixtures.
  - .12 ASTM D 4791, Standard Test Method for Flat Particles, Elongated Particles, or Flat and Elongated Particles in Coarse Aggregate.
- .4 Canadian General Standards Board (CGSB)
    - .1 CAN/CGSB-8.1, Sieves Testing, Woven Wire, Inch Series.
    - .2 CAN/CGSB-8.2, Sieves Testing, Woven Wire, Metric.
    - .3 CAN/CGSB-16.3, Asphalt Cements for Road Purposes.

#### 1.4 PRODUCT DATA

- .1 Submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Submit manufacturer's test data and certification that asphalt cement meets requirements of this Section.
- .3 Submit asphalt concrete mix design and trial mix test results to Department Representative for review at least 4 weeks prior to beginning Work.

#### 1.5 WASTE MANAGEMENT AND DISPOSAL

- .1 Separate waste materials for reuse and recycling.
- .2 Remove from site and dispose of all packaging materials at appropriate recycling facilities.
- .3 Divert unused aggregate materials from landfill to facility for reuse as approved by Department Representative.
- .4 Divert unused asphalt from landfill to facility capable of recycling materials.

### PART 2 - PRODUCTS

#### 2.1 MATERIALS

- .1 Asphalt cement: to CAN/CGSB-16.3-M90, grade: 80-100.
- .2 Reclaimed asphalt pavement:
  - .1 Crushed and screened so that 100% of RAP material passes 37.5 mm screen before mixing.
- .3 Aggregates: in accordance with Section 31 05 16 - Aggregate Materials: General following requirements:
  - .1 Crushed stone or gravel consisting of hard, durable angular particles, free from clay lumps,

cementation, organic material, frozen material and other deleterious materials.

.2 Gradations: within limits specified when tested to ASTM C 136 and ASTM C 117.

.3 Table

Sieve Designation	% Passing	
	Lower Course #1	Upper Course #1
25 mm	100	--
19 mm	--	--
12.5 mm	70-85	100
9.5 mm	--	--
4.75 mm	40-65	55-75
2.36 mm	32-53	38-58
1.18 mm	26-44	28-47
0.600 mm	18-36	20-36
0.300 mm	10-26	10-26
0.150 mm	4-17	4-17
0.075 mm	3-8	3-8

.4 Coarse aggregate: aggregate retained on 4.75mm sieve and fine aggregate is aggregate passing 4.75mm sieve when tested to ASTM C 136.

.5 When dryer drum plant or plant without hot screening is used, process fine aggregate through 4.75mm sieve and stockpile separately from coarse aggregate.

.6 Do not use aggregates having known polishing characteristics in mixes for surface courses.

.7 Sand equivalent: ASTM D 2419 Min: 40.

.8 Magnesium Sulphate soundness: to ASTM C 88 Max% loss by mass after five cycles:

.1 Coarse aggregate: 15%.

.2 Fine aggregate: 18%.

.9 Los Angeles abrasion: Grading B, to ASTM C 131 Max % loss by mass:

.1 Coarse aggregate, upper course: 25%

.2 Coarse aggregate, lower course: 35%.

.10 Absorption: to ASTM C 127 Max % by mass:

.1 Coarse aggregate, upper course: 1.75%.

.2 Coarse aggregate, lower course: 2.00%.

.11 Loss by washing: to ASTM C 117 Max % passing 0.075 mm sieve:

.1 Coarse aggregate, upper course: 1.5

.2 Coarse aggregate, lower course: 2.0

.12 Flat and elongated particles: to ASTM D 4791, (with length to thickness ratio greater than 3): Max% by mass:

.1 Coarse aggregate, upper course: 10%.

.2 Coarse aggregate, lower course: 10%.

.13 Crushed fragments: at least 60% of particles by mass within each of following sieve designation ranges, to have at least 2 freshly fractured face. Material

to be tested according to ASTM C 136 and ASTM C117.  
Determination of amount of fractured material will be in accordance with Ministry of Transportation and Highways' Specification I-11, Fracture Count for Coarse Aggregate, Method "B", which determines fractured faces by mass.

<u>Passing</u>		<u>Retained on</u>
25 mm	to	12.5mm
12.5 mm	to	4.75mm

.14 Regardless of compliance with specified physical requirements, fine aggregates may be accepted or rejected on basis of past field performance.

- .4 Mineral filler:
  - .1 Finely ground particles of limestone, hydrated lime, Portland cement or other approved non-plastic mineral matter, thoroughly dry and free from lumps.
  - .2 Add mineral filler when necessary to meet job mix aggregate gradation or as directed to improve mix properties.
  - .3 Mineral filler to be dry and free flowing when added to aggregate.

## 2.2 EQUIPMENT

- .1 Pavers: mechanical grade controlled self-powered pavers capable of spreading mix within specified tolerances, true to line, grade and crown indicated.
- .2 Rollers: sufficient number of type and weight to obtain specified density of compacted mix.
- .3 Vibratory rollers:
  - .1 Minimum drum diameter: 1200mm.
  - .2 Maximum amplitude of vibration (machine setting): 0.5mm for lifts less than 40 mm thick.
- .4 Haul trucks: sufficient number and of adequate size, speed and condition to ensure orderly and continuous operation and as follows:
  - .1 Boxes with tight metal bottoms.
  - .2 Covers of sufficient size and weight to completely cover and protect asphalt mix when truck fully loaded.
  - .3 In cool weather or for long hauls, insulate entire contact area of each truck box.
  - .4 Use only trucks which can be weighed in single operation on scales supplied.
- .5 Hand tools:
  - .1 Lutes or rakes with covered teeth for spreading and finishing operations.
  - .2 Tamping irons having mass not less than 12 kg and bearing area not exceeding 310 cm<sup>2</sup> for compacting material along curbs, gutters and other structures

inaccessible to roller. Mechanical compaction equipment, when approved by Department Representative may be used instead of tamping irons.

.3 Straight edges, 3.0m in length, to test finished surface.

2.3 MIX DESIGN

.1 Mix design provided by the Contractor (to be developed by testing laboratory) for approval by Department Representative.

.2 Mix to contain maximum 20% by mass of RAP. Department Representative may approve higher proportion of RAP if Contractor demonstrates ability to produce mix meeting requirements of specification.

.3 Design of mix: by Marshall method to requirements below.

.1 Compaction blows on each face of test specimens: 75.

.2 Mix physical requirements:

Property	Roads	
Marshall Stability at 60°C	kN min	5.5 upper course
		6.4 lower course
Flow Value	mm	2-4
Air Voids in Mixture	%	3-5 upper course
		3-6 lower course
Voids in Mineral Aggregate	% min	15 upper course 2
		14 upper course 1
		14 lower course 2
		13 lower course 1
Index of Retained Stability	% minimum	75

.3 Measure physical requirements as follows:

.1 Marshall load and flow value: to ASTM D1559.

.2 Air voids: to ASTM D3203.

.3 Index of Retained Stability: measure in accordance with Marshall Immersion Test (ASTM D1559).

.4 Do not change job-mix without prior approval of Department Representative. When change in material source proposed, new job-mix formula to be reviewed by Department Representative.



PART 3 - EXECUTION

3.1 PLANT AND  
MIXING REQUIREMENTS

- .1 Batch and continuous mixing plants:
  - .1 To ASTM D 995.
  - .2 Feed aggregates from individual stockpiles through separate bins to cold elevator feeders. Do not load frozen materials into bins.
  - .3 Feed cold aggregates to plant in proportions to ensure continuous operations.
  - .4 Calibrate bin gate openings and conveyor speeds to ensure mix proportions are achieved.
  - .5 Before mixing, dry aggregates to moisture content not greater than 0.5% by mass or to lesser moisture content if required to meet mix design requirements.
  - .6 Immediately after drying, screen aggregates into hot storage bins in sizes to permit recombining into gradation meeting job-mix requirements.
  - .7 Store hot screened aggregates in manner to minimize segregation and temperature loss.
  - .8 Heat asphalt cement and aggregate to mixing temperature directed by Department Representative. Do not heat asphalt cement above 160 degrees C.
  - .9 Maintain temperature of materials within 5 degrees C of specified mix temperature during mixing.
  - .10 Mixing time:
    - .1 In batch plants, both dry and wet mixing times as directed by Department Representative. Continue wet mixing as long as necessary to obtain thoroughly blended mix but not less than 30s or more than 75s.
    - .2 In continuous mixing plants, mixing time as directed by Department Representative but not less than 45s.
    - .3 Do not alter mixing time unless directed by Department Representative.
- .11 Where RAP is to be incorporated into mix:
  - .1 Feed from separate cold feed bin specially designed to minimize consolidation of material. Provide 37.5mm scalping screen on cold feed to remove oversized pieces of RAP.
  - .2 Ensure positive and accurate control of RAP cold feed by use of hydraulic motor or electric clutch and equip with anti rollback device to prevent material from sliding backward on feed belt.
  - .3 Combine RAP and new aggregates in proportions as directed by Department Representative. Dry mix thoroughly, until uniform temperature within plus or minus 5 degrees C of mix temperature, as directed by Department Representative Consultant is achieved prior to adding new asphalt cement. Do not add new asphalt cement where temperature of dried mix material is above 160 degrees C.

- .2 Dryer drum mixing plant:
  - .1 To ASTM D 995.
  - .2 Load aggregates from individual stockpiles to separate cold feed bins. Do not load frozen materials into bins.
  - .3 Feed aggregates to burner end of dryer drum by means of multi-bin cold feed unit and blend to meet job-mix requirements by adjustments of variable speed feed belts and gates on each bin.
  - .4 Where RAP is to be incorporated into mix, dryer drum mixer is to be designed to prevent direct contact of RAP with burner flame or with exhaust gases hotter than 180 degrees C.
  - .5 Feed RAP from separate cold feed bin designed to minimize reconsolidation of material.
  - .6 Meter total flow of aggregate and RAP by an electronic weigh belt system with indicator that can be monitored by plant operator and which is interlocked with asphalt pump so that proportions of aggregate RAP and asphalt entering mixer remain constant.
  - .7 Provide for easy calibration of weighing systems for aggregates and RAP without having material enter mixer.
  - .8 Calibrate bin gate openings and conveyor speeds to ensure mix proportions are achieved. Calibrate weigh bridge on charging conveyor by weighing amount of aggregate passing over weigh bridge in set amount of time. Difference between this value and amount shown by plant computer system to differ by not more than plus or minus 2%.
  - .9 Make provision for conveniently sampling full flow of materials from cold feed.
  - .10 Provide screens or other suitable devices to reject oversize particles or lumps of aggregate and RAP from cold feed prior to entering drum.
  - .11 Provide system interlock stop on feed components if either asphalt or aggregate from bin stops flowing.
  - .12 Accomplish heating and mixing of asphalt mix in approved parallel flow dryer-mixer in which aggregate enters drum at burner end and travels parallel to flame and exhaust gas stream. Control heating to prevent fracture of aggregate or excessive oxidation of asphalt. Equip system with automatic burner controls and provide for continuous temperature sensing of asphalt mixture at discharge, with printing recorder that can be monitored by plant operator. Submit printed record of mix temperatures at end of each week, if required.
  - .13 Mixing period and temperature to produce uniform mixture in which particles are thoroughly coated, and moisture content of material as it leaves mixer to be less than 0.5%.
- .3 Temporary storage of hot mix:
  - .1 Provide mix storage of sufficient capacity to permit continuous operation and designed to prevent

segregation.

.2 Do not store asphalt mix in storage bins in excess of 12 hour.

.4 Mixing tolerances:

.1 Permissible variation in aggregate gradation from job mix (percent of total mass).

4.75 mm sieve and larger	5.5
2.36 mm sieve	4.5
0.600 mm sieve	3.5
0.150 mm sieve	2.5
0.075 mm sieve	1.5

.2 Permissible variation of asphalt cement from job mix: 0.3%.

.3 Permissible variation of mix temperature at discharge from plant: 5 degrees C.

3.2 EQUIPMENT

.1 Pavers: mechanical grade controlled self-powered pavers capable of spreading mix within specified tolerances, true to line, grade and crown indicated.

.2 Rollers: sufficient number of type and weight to obtain specified density of compacted mix.

.3 Vibratory rollers:

.1 Minimum drum diameter: 1200mm.

.2 Maximum amplitude of vibration (machine setting): 0.5mm for lifts less than 40 mm thick.

.4 Haul trucks: sufficient number and of adequate size, speed and condition to ensure orderly and continuous operation and as follows:

.1 Boxes with tight metal bottoms.

.2 Covers of sufficient size and weight to completely cover and protect asphalt mix when truck fully loaded.

.3 In cool weather or for long hauls, insulate entire contact area of each truck box.

.4 Use only trucks which can be weighed in single operation on scales supplied.

.5 Hand tools:

.1 Lutes or rakes with covered teeth for spreading and finishing operations.

.2 Tamping irons having mass not less than 12 kg and bearing area not exceeding 310 cm<sup>2</sup> for compacting material along curbs, gutters and other structures inaccessible to roller. Mechanical compaction equipment, when approved by Department Representative may be used instead of tamping irons.

.3 Straight edges, 3.0m in length, to test finished

surface.

3.3 PREPARATION

- .1 Reshape granular road bed, if required.
- .2 When paving over existing asphalt surface, clean pavement surface. When leveling course is not require, patch and correct depressions and other irregularities to approval of Department Representative before beginning paving operations.
- .3 Adjust existing castings to new elevations and protect from asphaltic mix.
- .4 When matching new pavement with existing pavement make vertical cut between existing pavement and new pavement as shown on Contract Drawings.
- .5 Apply prime coat and/or tack coat in accordance with Section 32 12 14-Asphalt Prime Coats and/or Section 32 12 15-Asphalt Tack Coats prior to paving.
- .6 Prior to laying mix, clean surfaces of loose and foreign material.

3.4 TRANSPORTATION  
OF MIX

- .1 Transport mix to job site in vehicles cleaned of foreign material.
- .2 Paint or spray truck beds with limewater, soap or detergent solution, or non petroleum based commercial product, at least daily or as required. Elevate truck bed and thoroughly drain. No excess solution to remain in truck bed.
- .3 Schedule delivery of material for placing in daylight, unless Department Representative approves artificial light.
- .4 Deliver material to paver at uniform rate and in an amount within capacity of paving and compacting equipment.
- .5 Deliver loads continuously in covered vehicles and immediately spread and compact. Deliver and place mixes at temperature within range as directed by Department Representative, but not less than 125 degrees C.

3.5 PLACING

- .1 Obtain Department Representative's approval of base and existing surface and tack coat and prime coat prior to placing asphalt.
- .2 Place asphalt concrete to thicknesses, grades and lines as shown on Contract Drawings.
- .3 Placing conditions:
  - .1 Place asphalt mixtures only when air temperature

is above 5 degrees C. Place overlay pavement only when air temperature is above 10 degrees C.

.2 When temperature of surface on which material is to be placed falls below 10 degrees C, provide extra rollers as necessary to obtain required compaction before cooling.

.3 Do not place hot-mix asphalt when pools of standing water exist on surface to be paved, during rain, or when surface is damp.

.4 Place asphalt concrete in compacted lifts of thickness as shown on Contract Drawings:

.1 Levelling courses to thicknesses required but not exceeding 100mm.

.2 Lower course in layers of 100mm each.

.3 Surface course in layers of maximum 60mm each.

.5 Where possible do tapering and levelling where required in lower lifts. Overlap joints by not less than 300 mm.

.6 Spread and strike off mixture with self propelled mechanical finisher.

.1 Construct longitudinal joints and edges true to line markings. Position and operate paver to follow established line closely.

.2 When using pavers in echelon, have first paver follow marks or lines, and second paver follow edge of material placed by first paver. Work pavers as close together as possible and in no case permit them to be more than 30 m apart.

.3 Maintain constant head of mix in auger chamber of paver during placing.

.4 If segregation occurs, immediately suspend spreading operation until cause is determined and corrected.

.5 Correct irregularities in alignment left by paver by trimming directly behind machine.

.6 Correct irregularities in surface of pavement course directly behind paver. Remove by shovel or lute excess material forming high spots. Fill and smooth indented areas with hot mix. Do not broadcast material over such areas.

.7 Do not throw surplus material on freshly screeded surfaces.

.7 When hand spreading is used:

.1 Use approved wood or steel forms, rigidly supported to assure correct grade and cross section. Use measuring blocks and intermediate strips to aid in obtaining required cross-section.

.2 Distribute material uniformly. Do not broadcast material.

.3 During spreading operation, thoroughly loosen and uniformly distribute material by lutes or covered rakes. Reject material that has formed into lumps and

does not break down readily.

.4 After placing and before rolling, check surface with templates and straightedges and correct irregularities.

.5 Provide heating equipment to keep hand tools free from asphalt. Control temperature to avoid burning material. Do not use tools at higher temperature than temperature of mix being placed.

### 3.6 COMPACTING

.1 Roll asphalt continuously to density not less than 97% of 75 blow Marshall density to ASTM D1559 with no individual test less than 95%.

.2 General:

.1 Provide at least two rollers and as many additional rollers as necessary to achieve specified pavement density. When more than two rollers are required, one roller must be pneumatic tired type.

.2 Start rolling operations as soon as placed mix can bear weight of roller without excess displacement of material or cracking of surface.

.3 Operate roller slowly initially to avoid displacement of material. For subsequent rolling do not exceed 5 km/h for static steel-wheeled and 8 km/h for pneumatic tired rollers.

.4 For lifts 50 mm thick and greater, adjust speed and vibration frequency of vibratory rollers to produce minimum of 20 impacts per metre of travel. For lifts less than 50 mm thick, impact spacing not to exceed compacted lift thickness.

.5 Overlap successive passes of roller by minimum of 200mm and vary pass lengths.

.6 Keep wheels of roller slightly moistened with water to prevent pick-up of material but do not over-water.

.7 Do not stop vibratory rollers on pavement that is being compacted with vibratory mechanism operating.

.8 Do not permit heavy equipment or rollers to stand on finished surface before it has been compacted and has thoroughly cooled.

.9 After traverse and longitudinal joints and outside edge have been compacted, start rolling longitudinally at low side and progress to high side. Ensure that all points across width of pavement receive essentially equal numbers of passes of compactors.

.10 When paving in echelon, leave unrolled 50 to 75 mm of edge which second paver is following and roll when joint between lanes is rolled.

.11 Where rolling causes displacement of material, loosen affected areas at once with lutes or shovels and restore to original grade of loose material before re-rolling.

.3 Breakdown rolling:

.1 Commence breakdown rolling immediately following rolling of transverse and longitudinal joint

and edges.

.2 Operate rollers as close to paver as necessary to obtain adequate density without causing undue displacement.

.3 Operate breakdown roller with drive roll or wheel nearest finishing machine. Exceptions may be made when working on steep slopes or super-elevated sections.

.4 Use only experienced roller operators for this work.

.4 Second rolling:

.1 Use pneumatic-tired, steel wheel or vibratory rollers and follow breakdown rolling as closely as possible and while paving mix temperature allows maximum density from this operation.

.2 Rolling to be continuous after initial rolling until mix placed has been thoroughly compacted.

.5 Finished rolling:

.1 Accomplish finish rolling with steel wheel rollers while material is still warm enough for removal of roller marks.

.2 Conduct rolling operations in close sequence.

### 3.7 JOINTS

.1 General:

.1 Remove surplus material from surface of previously laid strip. Do not deposit on surface of freshly laid strip.

.2 Construct joints between asphalt concrete pavement and Portland cement concrete pavement as indicated.

.3 Paint contact surfaces of existing structures such as manholes, curbs or gutters with bituminous material prior to placing adjacent pavement.

.2 Transverse joints:

.1 Offset transverse joint in succeeding lifts by at least 600mm.

.2 Cut back to full depth vertical face and tack face with thin coat of hot asphalt prior to continuing paving.

.3 Compact transverse joints to provide smooth riding surface. Use methods to prevent rounding of compacted surface at joints.

.3 Longitudinal joints:

.1 Offset longitudinal joints in succeeding lifts by at least 150mm.

.2 Cold joint is defined as joint where asphalt mix is placed, compacted and left to cool below 100 degrees C prior to paving of adjacent lane.

.1 For airfield runway paving, avoid cold joint construction in mid 30 m of runway.

- .2 If cold joint can not be avoided, tack face with thin coat of hot asphalt prior to continuing paving.
  - .3 Overlap previously laid strip with spreader by 100mm.
  - .4 Before rolling, carefully remove and discard coarse aggregate in material overlapping joint with lute or rake.
  - .5 Roll longitudinal joints directly behind paving operation.
  - .6 When rolling with static roller over onto previously placed lane in order that 100 to 150 mm of drum width rides on newly laid lane, then operate roller to pinch and press fines gradually across joint. Continue rolling until thoroughly compacted neat joint is obtained.
  - .7 When rolling with vibratory roller, have most of drum width ride on newly placed lane with remaining 100 to 150 mm extending onto previously placed and compacted lane.
- 
- .4 Construct feather joints so that thinner portion of joint contains fine graded material obtained by changed mix design or by raking out coarse aggregate in mix. Place and compact joint so that joint is smooth and without visible breaks in grade. Location of feather joints as indicated.
  - .5 Construct butt joints as indicated.
  - .6 Wherever practical, locate joints under future traffic markings (paint lines.)
- 
- 3.8 PAVEMENT PATCHING
- .1 Ensure temporary and permanent pavement patching done by handwork conforms to all standards specified for machine place asphaltic concrete.
  - .2 Subbase and base preparation as specified in Section 32 11 19 and 32 11 23, respectively, unless shown otherwise on Contract Drawings.
- 
- 3.9 SIDEWALKS, DRIVEWAYS AND CURBS
- .1 Hot-mix asphalt concrete sidewalks, driveways and curbs as shown on Contract Drawings.
  - .2 Machine place where practical.
  - .3 Ensure placement by handwork conforms to all standards specified for machine placed asphaltic concrete.
  - .4 Other than requirements relating specifically to Portland cement concrete, ensure hot-mix asphalt concrete sidewalks and curbs comply with all requirements of Section 32 16 15-Concrete Walks, Curbs and Gutters.



- .5 Ensure hot-mix asphalt concrete driveways comply with all requirements of Section 32 12 16-Asphalt Paving.

3.8 FINISH  
TOLERANCES

- .1 Finished asphalt surface to be within 6mm of design elevation but not uniformly high or low.
- .2 Finished asphalt surface not to have irregularities exceeding 6mm when checked with 3 m straight edge placed in any direction.
- .3 Water ponding not permitted.
- .4 Against concrete gutter, finished asphalt surface to be higher than the gutter by not more than 6mm.

3.9 DEFECTIVE WORK

- .1 Correct irregularities which develop before completion of rolling by loosening surface mix and removing or adding material as required. If irregularities or defects remain after final compaction, remove surface course promptly and lay new material to form true and even surface and compact immediately to specified density.
- .2 Repair areas showing checking, rippling, or segregation.
- .3 Adjust roller operation and screed settings on paver to prevent further defects such as rippling and checking of pavement.

3.10 CLEAN-UP

- .1 Remove lids or covers from all castings and clean any prime, tack coat or hot-mix asphaltic concrete from frames, lids and covers of all castings.

-----END OF SECTION-----

PART 1 - GENERAL

- 1.1 RELATED WORK .1 Section 01 33 00-Submittal Procedures.
- 1.2 REFERENCES .1 CAN/CGSB-1.5-M91, Low Flash Petroleum Spirits Thinner.  
.2 CGSB 1-GP-12c-68, Standard Paint Colours.  
.3 CGSB 1-GP-71-83, Method, of Testing Paints and Pigments.  
.4 CGSB 1-GP-74M-79, Paint, Traffic, Alkyd.

PART 2 - PRODUCTS

- 2.1 MATERIALS .1 Paint:  
.1 To CGSB 1-GP-74M, alkyd traffic paint.  
.2 To CGSB 1-GP-149M, alkyd reflectorized traffic paint.  
.3 Colour: to CGSB 1-GP-12C, yellow 505-308, black 512-301, white 513-301.
- .2 Thinner: to CGSB-1-GP-5M.
- .3 Glass beads:  
.1 Overlay type: to CGSB 1-GP-74M.
- .4 Temporary pavement marking tape:  
.1 Self adhesive temporary pavement marking tape designed to provide reflective delineation.  
.2 To consist of high quality optical glass spheres embedded into weather and traffic-resistant binder on conformable metallic backing precoated with pressure sensitive adhesive.  
.3 Colour as specified.  
.4 To be readily removable by methods not requiring sandblasting, solvents or grinding.
- .5 Thermoplastic material:  
.1 Material composition shall be at the discretion of the manufacturer subject to the approval of the Department Representative. Each formulation shall be identified by a code number.  
.2 No retained water when tested by ASTM D-570.  
.3 Specific gravity of the supplied product shall be within 3% of that specified for the selected formulation.  
.4 Material shall not deteriorate upon contact with deicing chemicals, gasoline, diesel fuel or grease dropped by traffic.  
.5 Material shall not break down, deteriorate, scorch or discolour, if held within the application temperature range specified by the manufacturer for a period of four hours and it must be able to be reheated

from room temperature to the application temperature four (4) times without showing any of these detrimental effects.

.6 When applied at the temperature recommended by the manufacturer and at a film thickness of 2 to 4mm, the material shall set solid and show no tracking under traffic after elapsed times as follows:

.1 Two (2) minutes at an air temperature of 10°C, relative humidity less than 75%, and road surface temperature from 10°C to 20°C.

.2 Five (5) minutes at an air temperature of 32°C, relative humidity less than 75%, and road surface temperature from 32°C to 50°C

.3 The drying time under conditions intermediate between the two air temperatures shall be interpolated using a straight line model.

.7 The quantity, type, and gradation of the component reflecting glass spheres premixed in the thermoplastic material shall be at the discretion of the manufacturer, but shall provide retroreflection levels specified below.

.8 The colour of the marking to be brilliant white or yellow as specified. The brightness value shall exceed 70% for white and 45% for yellow obtained with a Gardner Multi-purpose Reflectometer when measuring 0° - 45° daylight luminous directional reflectance with the green filter.

.9 The material shall have a softening point not less than 103°C when tested in accordance with ASTM D36 (ASSHTOM-249-79).

### PART 3 - EXECUTION

#### 3.1 EQUIPMENT REQUIREMENTS

- .1 Paint applicator to be an approved pressure type mobile distributor capable of applying paint in single, double and dashed lines. Applicator to be capable of applying marking components uniformly, at rates specified, and to dimensions as indicated, and to have positive shut-off.
- .2 Distributor to be capable of applying reflective glass beads as an overlay on freshly applied paint.

#### 3.2 CONDITION OF SURFACES

- .1 Pavement surface to be dry, free from ponded water, frost, ice, dust, oil, grease and other foreign materials.

#### 3.3 APPLICATION

- .1 Temporary Markings:
  - .1 Application and removal to manufacturer's instructions.
  - .2 Temporary traffic lines and stop bars shall be placed immediately following laying of the asphalt pavement.
  - .3 The traffic line shall be a 100mm x 300mm strip of prefabricated reflective yellow tape having an

adhesive backing and shall be place at 10 metre intervals along the centre of pavement.

.4 The stop bar shall be 2 - 100mm continuous strips of prefabricated reflective white tape having an adhesive backing and placed across the travel lanes at traffic control intersections.

.5 Remove the tape when instructed.

.2 Painted Markings:

.1 Layout pavement markings.

.2 Unless approved otherwise by DCC Representative, apply paint only when air temperature is above 10°C and no rain is forecast.

.3 Apply traffic paint evenly at rate of 3m<sup>2</sup>/L.

.4 Do not thin paint unless approved by DCC Representative.

.5 Symbols and letters to conform to dimensions shown on Contract Drawings.

.6 Ensure paint lines of uniform colour and density with sharp edges.

.7 Thoroughly clean distributor tank before refilling with paint of different colour.

.8 Apply glass beads at rate specified.

.9 Apply other marking materials specified in Contract Documents.

.10 Ensure all pavement markings in accordance with latest edition of TAC Manual of Uniform Traffic Control Devices.

.3 Thermoplastic Markings:

.1 Pavement shall be clean and dry and free of sand, grave, loose dust and foreign mater.

.2 Temperature of surface to be marked shall not be less than 50°C.

.3 Thermoplastic material shall be heated in the melter to a temperature of 382°C

.4 Thermoplastic material thickness shall be:

.1 Lane line 2.286mm

.2 Stop bars and crosswalks 3.157mm

.5 Testing of material thickness to be determined by placing metal plate of known thickness in the area to be painted. Once applied the sample is removed and the material plus metal plate is measured.

.6 Immediately following application glass spheres shall be dropped onto the molten surface. Spheres to be applied at a rate of 300 grams per square meter of line area.

3.4 TOLERANCE

.1 Paint markings to be within plus or minus 10mm of dimensions indicated.

3.5 PROTECTION OF COMPLETED WORK

.1 Protect pavement markings until dry.

-----END OF SECTION-----

PART 1 - GENERAL

1.1 RELATED  
SECTIONS

- .1 Section 01 33 00-Submittal Procedures.
- .2 Section 31 23 10-Excavating, Trenching and Backfilling.
- .3 Section 33 41 00-Storm Utility Drainage Piping.

1.2 REFERENCES

- .1 American Society for Testing and Materials International (ASTM)
  - .1 ASTM A 48/A 48M, Standard Specification for Gray Iron Castings.
  - .2 ASTM C 117, Standard Test Method for Materials Finer than 75- $\mu$ m Sieve in Mineral Aggregates by Washing.
  - .3 ASTM C 136, Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates.
  - .4 ASTM C 139, Standard Specification for Concrete Masonry Units for Construction of Catch Basins and Manholes.
  - .5 ASTM C 478M, Standard Specification for Precast Reinforced Concrete Manhole Sections [Metric].
  - .6 ASTM D 698, Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Standard Effort (600 kN-m/m<sup>3</sup>).
- .2 Canadian General Standards Board (CGSB)
  - .1 CAN/CGSB-8.1, Sieves, Testing, Woven Wire, Inch Series.
  - .2 CAN/CGSB-8.2, Sieves, Testing, Woven Wire, Metric.
- .3 Canadian Standards Association (CSA International)
  - .1 CAN/CSA-A23.1/A23.2-[04], Concrete Materials and Methods of Concrete Construction/Methods of Test and Standard Practices for Concrete.
  - .2 CAN/CSA-A3000, Cementitious Materials Compendium (Consists of A3001, A3002, A3003, A3004 and A3005).
    - .1 CSA-A3001, Cementitious Materials for Use in Concrete.
    - .2 CSA-A3002, Masonry and Mortar Cement.
  - .3 CAN/CSA-A165 Series, CSA Standards on Concrete Masonry Units (Consists of A165.1, A165.2 and A165.3).
  - .4 CAN/CSA-G30.18, Billet Steel Bars for Concrete Reinforcement.
  - .5 CAN/CSA-G164, Hot Dip Galvanizing of Irregularly Shaped Articles.
- .4 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
  - .1 Material Safety Data Sheets (MSDS).

1.3 SUBMITTALS

- .1 Provide submittals in accordance with

Section 01 33 00 - Submittal Procedures.

- 1.4 DELIVERY,  
STORAGE AND  
HANDLING
- .1 Packing, shipping, handling and unloading:
    - .1 Deliver, store and handle materials in accordance with manufacturer's written instructions.

PART 2 - PRODUCTS

- 2.1 MATERIALS
- .1 Concrete:
    - .1 to Section 03 30 00-Cast-In-Place Concrete.
    - .2 concrete to be minimum 20 MPa or as specified otherwise on Contract Drawings.
  - .2 Concrete reinforcement: to Section 03 20 00-Concrete Reinforcing.
  - .3 Precast manhole sections: to ASTM C 478M, complete with ladder rungs.
  - .4 Precast "Tee" Sections: precast "Tee" sections constructed as an integral component of mainline pipe will be acceptable where shown on Contract Drawings as an approved alternative.
  - .5 Manhole lids: to be precast reinforced concrete designed to withstand H20 loading.
  - .6 Cast iron frame and cover: as shown on Contract Drawings.
    - .1 Frame and cover must conform to ASTM A48 and be designed to withstand H20 loading.
    - .2 Frame and cover must bear manufacturer identification on castings.
  - .7 Ladder runs to be:
    - 1. As shown on Contract Drawings.
    - 2. To conform to ASTM C-497, C-478 load test
    - 3. 20 mm cold rolled steel, hot dipped after bending to CSA G164, welded to reinforcing bars and cast with manhole sections or epoxy grouted into manhole walls.
    - 4. 20 mm aluminum alloy #6351-T6 (CSA-S157 and NBC 1977), complete with polyethylene anchor insulating sleeves and installed in 25 mm or 26 mm precast or drilled holes in manhole sections.
    - 5. Polypropylene encased steel ladder rungs: polypropylene ASTM-D-4101 steel core to be ½ inch dia grade 60 per ASTM A615M.
    - 6. Distance from top of manhole cover to top rung to be maximum 500 mm where no handhold provided. Maximum distance may be extended to 660 mm where handhold provided.
    - 7. In compliance with all requirements of Workers'

Compensation Board.

- .8 Safety platform: to be installed as shown on Contract Drawings in all manholes in excess of 6 m deep.
- .9 Precast catch basin sections: to ASTM C478M.
- .10 Catchbasin leads to be minimum 200 mm diameter and of PVC DR35.
- .11 Catchbasin lids: to be precast reinforced concrete designed to withstand H20 loading.
- .12 Cast iron catchbasin frame and grate: as shown on Contract Drawings.
  - 1. Frame and grate must conform to ASTM A48 and be designed to withstand H20 loading.
  - 2. Frame and grate must bear manufacturers identification on casting.
- .13 Joints: made watertight using rubber rings to ASTM C443 or cement mortar.
- .14 Mortar:
  - .1 Aggregate: to CSA A82.56.
  - .2 Masonry Cement: to CAN/CSA-A8.
- .15 Adjusting rings: to ASTM C 478.
- .16 Concrete Brick: to CAN3-A165 Series.
- .17 Drop manhole pipe: to be as shown on Contract Drawings.
- .18 Lawn drains to be: as shown on Contract Drawings.
- .19 Concrete bags to be: Jute, burlap or synthetic bag of suitable size and texture filled to 2/3 capacity with mixture of 1 part Portland cement to 2 parts sand, thoroughly mixed, and weighing approximately 27 kg.
- .20 Concrete blocks: to be H type concrete construction blocks conforming to latest ASTM Specifications.
- .21 Prebenched manhole bases:
  - 1. Where precast manhole sections are incorporated into precast base by bonding to concrete benching, use precast reinforced concrete manhole sections to ASTM C478 complete with ladder rungs above benching.
  - 2. Where base benching is cast monolithically with manhole walls, reinforce wall and joint sections as specified in ASTM C478.
  - 3. Precast concrete base section minimum thickness to be 120 mm, measured from underside of base to lowest point in concrete channeling.

PART 3 - EXECUTION

- 3.1 EXCAVATION AND BACKFILL .1 Excavating and backfilling in accordance with Section 31 23 10-Excavating, Trenching and Backfilling.
- 3.2 CONCRETE WORK .1 Place concrete reinforcement in accordance with Section 03 20 00-Concrete Reinforcing.
- .2 Do concrete work in accordance with Section 03 30 00-Cast-In-Place Concrete.
- 3.3 MANHOLE INSTALLATION .1 Install manholes as shown on Contract Drawings, concurrently with pipe laying.
- .2 Ensure excavation free of water prior to placing concrete.
- .3 Place minimum 100mm of 25mm bedding gravel compacted to minimum 95% Modified Proctor density in compliance with ASTM D1557.
- .4 Construct base to ensure first precast riser section is set plumb.
- .5 Set all inlet and outlet pipes to specified alignments and elevations.
- .6 Connect concrete pipe into manhole using spigot or bell precast into manhole wall or, alternatively, grout pipe into pre-formed rough core in manhole wall using fast-setting grout.
- .7 Connect PVC pipe into manhole using "manhole adapter ring" or approved equal.
- .8 Ensure placement of concrete does not disturb connecting pipes.
- .9 Set remaining precast riser sections plumb with joints consisting of cement mortar or gaskets to ASTM C443.
- .10 Where possible, for channeling using half-sections of pipe or suitable fittings. Bench to direct flow parallel to main flow of sewer. From top of benching as high as crown of sewer pipe. Finish concrete to smooth surface using steel trowel.
- .12 Brace capped inlets or stubs to withstand testing head.
- .13 Set frames by firmly embedding in mortar on minimum of 1, maximum of 3 courses of bricks or precast concrete riser rings, or cast-in-place form system with due regard to maximum distance to first step.



- .14 "Butter" inside and outside faces of bricks with mortar to ensure neat even finish. Grout inside, outside and between courses of bricks or grade rings with mortar to ensure neat even finish. Pre-wet all joints before placing mortar.
- .15 Plug lifting holes in pipe.
- .16 Install drop structures where required to Contract Drawings.
- .17 Paint manhole covers if specified on Contract Drawings.
- .18 Ensure frames conform to design contour of pavement or existing surface.
- .19 Pre-fabricated Corrugated Steel Pipe Manholes to be installed as shown on the Contract Drawings and to manufacturers specifications.
- 3.4 CLEANOUT INSTALLATION .1 Install cleanouts as shown on Contract Drawings, to standards and installation procedures described in 3.3.
- 3.5 CATCHBASIN INSTALLATION .1 Install catchbasins as Shown on Contract Drawings, to general standards and installation procedures described in 3.3.
  - .2 Place minimum of 100 mm bedding gravel under base, compact to 95% Modified Proctor density.
  - .3 Install catchbasin leads in accordance with Section 33 41 00-Storm Utility Drainage Piping.
- 3.6 LAWN DRAIN INSTALLATION .1 Install lawn drains as shown on Contract Drawings.
- 3.7 ENDWALL INSTALLATION .1 Install reinforced concrete endwalls as shown on Contract Drawings or as shown otherwise on Contract Drawings and in accordance with Section 03 20 00-Concrete Reinforcing and Section 03 30 00-Cast-In-Place Concrete.
  - .2 Precast concrete endwalls may be installed where shown on Contract Drawings as an approved alternative.
- 3.8 GRILLAGE TRASH SCREENS .1 Where specified, install grillage trash screens as shown on Contract Drawings.
- 3.9 ADJUSTING TOPS OF EXISTING UNITS .1 Remove existing gratings, frames and store for re-use at locations specified.
  - .2 Precut units:
    - .1 Raise or lower precast units by adding or removing

precast sections as required.  
.2 When amount of raise is less than 300 mm use standard manhole bricks, precast riser rings or Cast-in place form system.

- .3 Cast-in-Place units:
- .1 Raise cast-in-place units by roughening existing top to ensure proper bond and extend to required elevation with cast-in-place concrete.
  - .2 Lower cast-in-place units with straightwall by removing concrete to elevation indicated for rebuilding.
  - .3 Install additional manhole ladder rungs in adjusted portion of units as required.
  - .4 Re-use existing gratings, frames.
- .4 Re-set gratings and frames to required elevation on not more than 3 courses of brick. Make brick joints and join brick to frame with cement mortar, parge and trowel smooth.
- .5 Ensure adjustments conform to requirements regarding distance to first step.

3.10 REMOVE EXISTING UNITS .1 Remove existing structures where shown on Contract Drawings. Backfill in accordance with Section 31 23 10-Excavating, Trenching and Backfilling.

3.11 LEAKAGE TEST .1 Perform leakage testing of sanitary manholes in accordance with Section 33 31 13-Public Sanitary Utility Sewerage Piping.

-----END OF SECTION-----

PART 1 - GENERAL

- 1.1 SECTION INCLUDES .1 Materials and installation for storm sewer.
- 1.2 RELATED SECTIONS .1 Section 01 33 00-Submittal Procedures.  
.2 Section 03 30 00-Cast-in-Place Concrete.  
.3 Section 31 05 16-Aggregate Materials.  
.4 Section 31 23 10-Excavating, Trenching and Backfilling.  
.5 Section 33 05 13-Manholes and Catch Basin Structures.
- 1.3 REFERENCES .1 American Society for Testing and Materials International, (ASTM)  
.1 ASTM C 14M, Standard Specification for Concrete Sewer, Storm Drain and Culvert Pipe (Metric).  
.2 ASTM C 76M, Standard Specification for Reinforced Concrete Culvert, Storm Drain and Sewer Pipe (Metric).  
.3 ASTM C 117, Standard Test Method for Material Finer Than 0.075 mm Sieve in Mineral Aggregates by Washing.  
.4 ASTM C 136, Standard Method for Sieve Analysis of Fine and Coarse Aggregates.  
.5 ASTM C 443M, Standard Specification for Joints for Concrete Pipe and Manholes, Using Rubber Gaskets (Metric).  
.6 ASTM C 506M, Standard Specification for Reinforced Concrete Arch Culvert, Storm Drain and Sewer Pipe.  
.7 ASTM C 507M, Standard Specification for Reinforced Concrete Elliptical Culvert, Storm Drain and Sewer Pipe (Metric).  
.8 ASTM D 698, Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Standard Effort (600 kN-m/m<sup>3</sup>).  
.9 ASTM D 1056, Standard Specification for Flexible Cellular Materials-Sponge or Expanded Rubber.  
.10 ASTM D 2680, Standard Specification for Acrylonitrile-Butadiene-Styrene (ABS) and Poly (Vinyl Chloride) (PVC) Composite Sewer Piping.  
.11 ASTM D 3034, Standard Specification for Type PSM Poly (Vinyl Chloride) (PVC) Sewer Pipe and Fittings.  
.12 ASTM F 405, Standard Specification for Corrugated Polyethylene (PE) Tubing and Fittings.  
.13 ASTM F 667, Standard Specification for Large Diameter Corrugated Polyethylene Tubing and Fittings.

.14 ASTM F 794, Standard Specification for Poly(Vinyl Chloride) (PVC) Profile Gravity Sewer Pipe and Fittings Based on Controlled Inside Diameter.

- .2 Canadian General Standards Board (CGSB)
  - .1 CAN/CGSB-8.1, Sieves, Testing, Woven Wire, Inch Series.
  - .2 CAN/CGSB-8.2, Sieves, Testing, Woven Wire, Metric.
  - .3 CAN/CGSB-34.9, Asbestos-Cement Sewer Pipe.
- .3 Canadian Standards Association (CSA International)
  - .1 CAN/CSA-A3000, Cementitious Materials Compendium (Consists of A5-98, A8-98, A23.5-98, A362-98, A363-98, A456.1-98, A456.2-98, A456.3-98).
    - .1 CAN/CSA-A5, Portland Cement.
    - .2 CAN/CSA-A257 Series-[M92(R1998)], Standards for Concrete Pipe.
    - .3 CSA B1800-[02], Plastic Non-pressure Pipe Compendium - B1800 Series (Consists of B181.1, B181.2, B181.3, B181.5, B182.1, B182.2, B182.4, B182.6, B182.7, B182.8 and B182.11).
      - .1 CSA B182.2, PVC Sewer Pipe and Fittings (PSM Type).
      - .2 CSA B182.4, Profile PVC Sewer Pipe and Fittings.
      - .3 CSA B182.11, Recommended Practice for the Installation of Thermoplastic Drain, Storm, and Sewer Pipe and Fittings.
  - .4 CSA-G401, Corrugated Steel Pipe Products.

#### 1.4 MATERIAL CERTIFICATION

- .1 Submit shop drawings in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Products having CSA certification to be used where readily available. Certification by Standards Council of Canada approved independent third body that products conform to CSA standards in acceptable in lieu of CSA certification.
- .3 At least 2 weeks prior to commencing work, submit manufacturer's recent test data and certification that materials to be incorporated into works are representative and meet requirements of this Section. Include manufacturer's drawings where pertinent.

#### 1.5 SCHEDULING OF WORK

- .1 Schedule Work to minimize interruptions to existing services. Maintain existing flow during construction.
- .2 Submit schedule of expected interruptions to Department Representative for approval and adhere to interruption schedule as approved by Department Representative.

1.6 WASTE  
MANAGEMENT AND  
DISPOSAL

- .1 Remove from site and dispose of packaging materials at appropriate recycling facilities.
- .2 Divert unused concrete materials from landfill to local facility as approved by Department Representative.
- .3 Divert unused aggregate materials from landfill to facility for reuse as approved by Department Representative.
- .4 Handle and dispose of hazardous materials in accordance with the Regional and Municipal regulations.
- .5 Dispose of unused asbestos cement pipe in accordance with regulations governing the disposal of hazardous materials.
- .6 Fold up metal banding, flatten and place in designated area for recycling.

PART 2 - PRODUCTS

2.3 PLASTIC PIPE,  
MAINLINE SMOOTH  
PROFILE AND  
PERFORATED DRAIN TILE

- .1 Polyvinyl chloride pipe up to 675mm in diameter, DR35. Pipe to have minimum pipe stiffness (F/Y) of 320 kPa at 5.0% deflection, ASTM D2412. Pipe to be manufactured to specification for pipe size ranges as follows:
  - .1 100mm dia. - 375mm dia. to ASTM D3034
  - .2 450mm dia. - 1200mm dia. to ASTM F679.
- .2 Pipes to be certified by Canadian Standards Association to standards for pipe size ranges below.
  - .1 100mm dia. - 1200mm dia. to CSA B182.2
- .3 Joint: Pipe to include integral bell and spigot ends with stiffened wall section and formed groove for a rubber gasket; joints to conform to ASTM D3212, gaskets to ASTM F477.
- .4 Normal pipe length joint to joint to be 4.0 m.
- .5 Maximum installed deflection not to exceed 7.5% of the base inside diameter.

2.4 SERVICE  
CONNECTIONS

- .1 Storm sewer service connections to be 100mm minimum diameter; maximum diameter as specified on Contract Drawings.
- .2 Storm sewer service connections 100mm and 150mm diameter to be PVC type DR28 sewer pipe.

- .3 100mm and 150mm DR28 PVC storm service connection pipe to have a minimum pipe stiffness of 625kPa. Pipe to be manufactured to ASTM D3034 and certified by Canadian Standards Association to CSA B182.2
- .4 Storm sewer service connections greater than 150mm diameter to be of size and material specified on Contract Drawings and to conform to applicable specifications for mainline pipe.
- .5 Manufactured connections to non-reinforced or reinforced concrete mainline pipe to be made using sanded PVC pipe male end stub with integral bell by either:
  - .1 Stub grouted into neatly chipped hole in pipe wall by concrete pipe manufacturer. Grout to be Portland cement based grout.
  - .2 Stub epoxy resin cemented into neatly cored hole in pipe wall by concrete pipe manufacturer.
- .6 Stub and bell orientation to be 45° to centerline of mainline 2pipe (wyes) for concrete pipe less than 1050mm diameter. Orientation may be 90° to centerline of mainline pipe (tees) for concrete pipe 1050mm diameter or larger. No section of service stubs to protrude past inside of concrete pipe wall.
- .7 Manufactured wye connections to PVC mainline pipe to be made with extrusion moulded PVC or fabricated PVC fittings manufactured to ASTM D3034 and CSA B182.2
- .8 Field installed tees and wyes:
  - .1 In-situ installation of tees and wyes into concrete or PVC mainline pipe shall be made with approved PVC swaddle installed to the manufacturers specifications into a neatly cored hole in the pipe wall.
  - .2 Connections to ribbed PVC pipe to be made with a preformed tee and wye fitting when connection is up to two sizes smaller than mainline pipe. For these pipes, in-situ installation of tees or wyes involving cutting across pipe ribs not permitted. For connections more than two sizes smaller than mainline pipe, an insertable tee for ribbed PVC pipe is permitted. When an insertable is used, hole cut into mainline pipe to cut as few ribs as possible.
- .9 PVC service connection pipe and fitting joints: push-on type comprised of integral bell with single elastomeric gasket to ASTM D3212 and ASTM F477. Normal pipe laying length joint to joint to be 4.0m.
- .10 Pipe and fitting joints for service connection pipe materials other than PVC type PSM sewer pipe to be as specified for applicable mainline pipe.

2.6 PIPE BEDDING AND SURROUND MATERIAL .1 Granular material in accordance with Section 31 05 16 - Aggregate Materials  
.2 Concrete mixes and materials for bedding, cradles, encasement, supports: in accordance with Section 03 30 00 - Cast-in-Place Concrete.

2.7 BACKFILL MATERIAL .1 As shown on Contract Drawings.  
.2 In accordance with Section 31 05 16-Aggregate Materials.

PART 3 - EXECUTION

3.1 PREPARATION .1 Clean pipes and fittings of debris and water before installation, and remove defective materials from site to approval of Department Representative.

3.2 TRENCHING .1 Do trenching Work in accordance with Section 31 23 10 - Excavating, Trenching and Backfilling.  
.2 Do not allow contents of sewer or sewer connection to flow into trench.  
.3 Trench alignment and depth as shown on Contract Drawings.

3.3 CONCRETE BEDDING AND ENCASEMENT .1 Do concrete Work in accordance with Section 03 30 00 - Cast-in-Place Concrete. Place concrete to details as indicated.  
.2 Position pipe on concrete blocks to facilitate placing of concrete.  
.1 When necessary, rigidly anchor or weight pipe to prevent flotation when concrete is placed.  
.3 Do not backfill over concrete within 24 h after placing

3.4 GRANULAR BEDDING .1 Fill over-excavation below design elevation of bottom of specified bedding with granular bedding placed and compacted. Drain rock may be used for backfill of over-excavation only with Department Representative's approval.  
.2 Place granular bedding material across full width of trench bottom in uniform layers not exceeding 150mm compacted thickness to depth as shown on Contract Drawings.  
.3 Shape bed true to grade and to provide continuous,

uniform bearing surface for pipe. Do not use blocks when bedding pipes.

- .4 Shape transverse depressions as required to suit joints.
- .5 Compact each layer full width of bed to at least 95% Modified Proctor Density in compliance with ASTM D1557. (All following references to density imply in compliance with ASTM D1557).

### 3.5 INSTALLATION

- .1 Handle pipe in accordance with manufacturer's recommendations.
  - .1 Do not use chains or cables passed through rigid pipe bore so that weight of pipe bears upon pipe ends.
- .2 Lay and join pipes to manufactureer's instructions and specifications except as noted otherwise herein. Concrete pipe as specified herein, PVC pipe to CSA B182.11.
- .3 Horizontal tolerances:  $\pm 50$  mm from specified alignment  
Vertical tolerances:  $\pm 10$  mm from specified grade.  
Reverse grade is not acceptable.
- .4 Lay pipes on prepared bed, true to line and grade. Ensure barrel of each pipe is in contact with shaped bed throughout its full length.
- .5 Commence laying at outlet and proceed in upstream direction with socket ends of pipe facing upgrade.
- .6 Pipes on curved alignments:
  - .1 Concrete pipe and ribbed profile PVC plastic pipe. Do not exceed permissible joint defection recommend by pipe manufacturer.
  - .2 Smooth PVC pipe: for 100 mm to 300 mm sizes conform to required curvature by bending pipe barrel. In no case shall radius of curvature to be less than 300 times outside diameter of pipe barrel. Joint defection not permitted for smooth profile PVC pipe.
- .7 Keep jointing materials and installed pipe free of dirt, water and other foreign materials. Do not allow water to flow through pipes during construction except as may be permitted by Department Representative.
- .8 Whenever Work is suspended, install removable watertight bulkhead at open end of last pipe laid to prevent entry of foreign materials.
- .9 Cut pipes as required, as recommended by pipe manufacturer, without damaging pipe and leave smooth



end at right angles to axis of pipe.

- .10 Joints:
  - .1 Install gaskets as recommended by manufacturer.
  - .2 Support pipes with hand slings or crane as required to minimize lateral pressure on gasket and maintain concentricity until gasket is properly positioned.
  - .3 Align pipes before joining.
  - .4 Maintain pipe joints free from mud, silt, gravel and other foreign material.
  - .5 Avoid displacing gasket or contaminating with dirt or other foreign material. Remove disturbed or dirty gaskets; clean, lubricate and replace before joining is attempted.
  - .6 Complete each joint before laying next length of pipe.
  - .7 Minimize joint deflection after joint has been made to avoid joint damage.
  - .8 Apply sufficient pressure in making joints to ensure that joint is complete as outlined in manufacturer's recommendations.
- .11 Ensure completed joints are restrained by compacting bedding material alongside and over installed pipes or as specified otherwise.
- .12 When any stoppage of Work occurs, restrain pipes as directed by Department Representative, to prevent "creep" during down time.
- .13 Plug lifting holes with approved prefabricated plugs, to pipe suppliers recommendations for sealing methods.
- .14 Make watertight connections to manholes.
  - .1 Use shrinkage compensating grout when suitable gaskets are not available.
  - .2 Core neat circular holes in walls of existing manholes. Do not hammer or ship except as approved by Department Representative.

### 3.6 PIPE SURROUND

- .1 Upon completion of pipe laying, and after Department Representative has inspected work in place, surround and cover pipes as shown on Contract Drawings.
- .2 Hand place surround material in uniform layers not exceeding 150mm compacted thickness simultaneously on each side of pipe. Do not dump material within 1 m of pipe.
- .3 Compact each layer from pipe invert to underside of backfill to minimum 95% Modified Proctor Density.

3.7 CONNECTIONS  
TO EXISTING  
MAINLINE PIPES

- .1 Use prefabricated saddles or approved field connection materials and techniques to connect service pipes to existing mainline sewer pipe.
- .2 Where feasible, make connections to existing non-reinforced or reinforced concrete mainline pipe by coring or sawing circular holes in existing pipe walls. Where not feasible, make as follows:
  - .1 Break in to pipe by drilling small diameter holes, spaced at approximately 50 mm along pipe axis, using a drill or chipping gun. Use hammer to strike concrete adjacent to centre holes to create small core, and similarly expand core to suit outside dimensions of stub.
  - .2 Core dimensions to allow maximum 20 mm clearance around stub at any point.
  - .3 Trim stub to conform closely to shape of pipe interior when installed.
  - .4 Insert stub into core, ensuring that no portion of stub protrudes beyond interior of pipe.
  - .5 Prepare non-shrink, fast-setting cementitious grout to "dry pack" consistency. Pack grout tightly into void between stub and pipe.
  - .6 Hand finish interior and exterior grout surfaces to smooth surface.
  - .7 Allow sufficient time for strength development of grout prior to installation of connecting pipe or trench backfill.
- .3 For new connections to existing PVC mainline sewers, drill hole in mainline to exact dimension of new connection. Use saddle or insertable tee for connections more than two sizes smaller than mainline. Insertable tees may be used for all types of gravity mains provided insertable tee designed for applicable pipe thickness is used.
- .4 For new connections to existing ribbed PVC pipe mainline sewers use performed tee or wye fitting when connection is up to two sizes smaller than mainline pipe. For these pipes, in-situ installation of tees or wyes involving cutting across pipe ribs not permitted. For connections more than two sizes smaller than mainline pipe, an insertable tee for ribbed PVC pipe is permitted. When an insertable tee is used, hole cut into mainline pipe to cut as few ribs as possible.

3.8 BACKFILL

- .1 Place backfill in accordance with Section 31 23 10 - Excavating, Trenching and Backfilling.
- .2 Backfill requirements, including type of material and compaction requirements, as shown on Contract Drawings.

- .3 Under paving and walks, compact backfill to at least 95% Modified Proctor Density.

3.9 SERVICE CONNECTIONS

- .1 Install service connections to 3.5 and as shown on Contract Drawings.
- .2 Install inspection chamber at specified location set plumb and to specified elevation. If inspection chamber located in driveway, lane or paved surface install cover or lid as shown on Contract Drawings.
- .3 Place location marker at ends of plugged or capped unconnected sewer lines.
  - .1 Each marker: 40 x 90 mm stake extending from pipe end at pipe level to 0.6 m above grade.
  - .2 Paint exposed portion of stake green with designation STM SWR LINE in black.
- .4 Sawcut adjacent curb on alignment of service connection and paint green.

3.10 CLEANING AND FULSHING

- .1 Before flushing and testing, ensure sewer system is completely finished and make arrangements with Department Representative for scheduling of testing.
- .2 Water may be supplied from Department fire hydrants upon application for a Hydrant Use Permit.
- .3 Obtain Department approval prior to discharging flushing water to sewers or drainage ditches.
- .4 Comply Section 01 35 43-Environmental Procedures in regard to discharge of flushing water.
- .5 Provide Department Representative with all required approvals prior to discharging flushing water.
- .6 Remove foreign material from pipe and related appurtenances by flushing with water. Main to be flushed at water velocities as high as can be obtained from available water sources. Continue flushing at least until flow from most distant point has reached discharge point and until water discharged is clean and clear.

3.11 VIDEO INSPECTION

- .1 The Contractor shall video inspect completed storm sewers under 900 mm in diameter following completion of installation. The video inspection report shall be in the form specified by the Department Representative. Copies of the video tapes and written report shall be forwarded to the Department

Representative when available.

- .2 Should video inspection indicate apparent deficiencies, Department Representative may direct Contractor to perform additional testing as follows.
- .3 Additional testing may include passing rubber ball, mandrel or test plug having a minimum dimension of 95% of diameter of sewer pipe completely through pipes and appurtenances. A light test may be performed in lieu of ball test at discretion of Department Representative.

### 3.12 INSTALLATION STANDARD

- .1 Repair all deficiencies and visible leaks.
- .2 Repair procedures and materials subject to approval of Department Representative.
- .3 Department Representative reserves right to require Contractor to replace defective installations at Contractor's sole cost.
- .4 Test Procedures, including video inspection, to be repeated and repairs made until satisfactory results are obtained.
- .5 Acceptable Ponding:
  - .1 Connections: 10mm maximum ponding over 3m length of pipeline.
  - .2 Mainline PVC sewers:
    - .1 300mm diameter or less: 20mm maximum ponding over 3m length of pipe
    - .2 Greater than 300mm diameter: 30mm ponding over 3m length of pipeline.
  - .3 Mainline Concrete sewers:
    - .1 300mm diameter: 20mm maximum ponding over a 5m length of pipeline
    - .2 Greater than 300mm diameter: 30mm maximum ponding over a 5m length of pipeline.

### 3.13 CONNECTIONS TO EXISTING MAINS

- .1 Make connections to existing storm sewer systems unless shown otherwise on Contract Drawings. Notify Department Representative minimum 48 h in advance of scheduled connection.
- .2 Make connection in presence of Department Representative. To prevent damage to existing utilities, excavate last 300 mm over utility by hand.

### 3.15 PERFORATED DRAIN PIPE

- .1 Where shown on Contract Drawings or where directed by Department Representative install perforated drain pipe adjacent to sidewalk or curb and gutter.

- .2 Drain pipe to be 100 mm minimum.
- .3 Connect to catchbasins.
- .4 Install other perforated drain pipes as shown on Contract Drawings.
- .5 Install sweep bend and cap at ground grade at upstream end of run.
- .6 Install with perforations downward.

-----END OF SECTION-----