

PART 1 - GENERAL

- |                                    |    |   |
|------------------------------------|----|---|
| 1.1 <u>Work Included</u>           | .1 | This section specifies the requirements for the removal and disposal of materials including, but is not limited to:<br>.1 Steel plating, bollards, cleats, anchors, top of SSP, miscellaneous steel sections.<br>.2 Pressure treated timber wheelguards, miscellaneous timber and creosote timber fender.<br>.3 Reinforced concrete slabs and foundations.<br>.4 Asphalt pavement, gravels and backfill materials (above Chart Datum).<br>.5 Marine deposits (below chart datum).<br>.6 Water service lines.<br>.7 Electrical equipment, conduit, wiring, cabling and hydrographic station. |
| 1.2 <u>Existing Conditions</u>     | .1 | Items to be relocated or removed are to be based on their condition on date that Tender is accepted.  |
|                                    | .2 | A site visit for bidders has been scheduled as noted in the tender solicitation documents.  |
|                                    | .3 | Native fill material may contain creosote treated timber debris. The existing timber fender on the East Wall to be removed is treated with creosote.  |
| 1.3 <u>Regulatory Requirements</u> | .1 | Perform work in compliance with applicable Federal, Provincial and Municipal Regulations.   |
|                                    | .2 | Carry out Work in accordance with the Prince Edward Island Occupational Health and Safety Act and Section 01 35 29 - Health and Safety.   |

PART 2 - PRODUCTS

- |                     |    |                 |
|---------------------|----|-----------------|
| 2.1 <u>Not Used</u> | .1 | Not applicable. |
|---------------------|----|-----------------|

PART 3 - EXECUTION

- |     |                                |    |  |
|-----|--------------------------------|----|--|
| 3.1 | <u>Preparation</u>             | .1 | Inspect site with Departmental Representative and verify extent and location of items designated for removal and items to remain.  |
| 3.2 | <u>Safety Code</u>             | .1 | Observe construction safety measures of Provincial Government, including but not limited to the Occupational Health and Safety Act, Workers' Compensation Board and Municipal authority provided that in any case of conflict or discrepancy the more stringent requirement applies.   |
|     |                                | .2 | Exercise pollution and environmental control of construction activities as specified and as required during the Work.  |
|     |                                | .3 | Submit to the Departmental Representative prior to commencement of Work, printed information detailing means and methods so the following will be carried out:<br>.1 To ensure that health and safety of persons at or near the Work.<br>.2 To ensure the measures and procedures of the regulatory agencies specified are carried out.<br>.3 To ensure every employee, self-employed person and employer performing Work under this Contract complies with the regulatory agencies specified. |
| 3.3 | <u>Saw Cutting</u>             | .1 | Cut concrete and asphalt at joints and along straight lines.   |
| 3.4 | SSP Wall<br><u>Top Removal</u> | .1 | Cut off SSP wall along straight lines to elevations shown on drawings.   |

- 3.5 Disposal
- .1 Dispose of all removed items off site in an environmentally acceptable location at no additional cost to the Contract.
  - .2 Management of creosote treated timber debris and impacted soils present in native fill will be required. Dispose of material off-site and in accordance with local disposal regulations.
- 3.6 Cleanup
- .1 Upon completion of work, remove debris, trim surfaces and leave work site clean.
- 3.7 Reinstatement
- .1 Protect items designated for reinstatement. Repair and replace any item damaged as a result of inadequate protection.
  - .2 Reinstate items in accordance with Section 32 98 00.