

PART 1 –

- 1.1 SUBMITTALS .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- 1.2 INSTALLATION AND REMOVAL .1 Provide construction facilities in order to execute work expeditiously.
.2 Remove from site all such work after use.
- 1.3 HOISTING .1 Provide, operate and maintain hoists/cranes required for moving of workers, materials and equipment
.2 Hoists/cranes to be operated by qualified operator.
- 1.4 SITE STORAGE/LOADING .1 Confine work and operations of employees by Contract Documents. Do not unreasonably encumber premises with products.
.2 Do not load or permit to load any part of Work with weight or force that will endanger Work.
- 1.5 PARKING .1 Parking is not provided on site.
- 1.6 SECURITY .1 Contractor responsible for security and contents of site after working hours and during holidays.
- 1.7 EQUIPMENT, TOOL AND MATERIALS STORAGE .1 Provide and maintain, in clean and orderly condition, lockable weatherproof sheds for storage of tools, equipment and materials.
.2 Locate materials not required to be stored in weatherproof sheds on site in manner to cause least interference with work activities.
- 1.8 SANITARY FACILITIES .1 Provide sanitary facilities for work force in accordance with governing regulations and ordinances.
.2 Post notices and take precautions as required by local health authorities. Keep area and premises in sanitary condition.
- 1.9 PROTECTION AND MAINTENANCE OF TRAFFIC .1 Maintain and protect traffic on affected roads during construction.
.2 Provide measures for protection and diversion of traffic, including provision of watch-persons and flag-persons, erection of barricades, placing of lights around and in front of equipment and work, and erection and maintenance of adequate warning, danger, and direction signs
.3 Protect travelling public from damage to person and property.
.4 Contractor's traffic on roads selected for hauling material to and from site to interfere as little as possible with public traffic.
.5 Provide snow removal during period of Work.
- 1.10 CLEAN-UP .1 Remove construction debris, waste materials, packaging material from work site daily.

- .2 Clean dirt or mud tracked onto paved or surfaced roadways.
- .3 Store materials resulting from demolition activities that are salvageable.
- .4 Stack stored new or salvaged material not in construction facilities.

END OF SECTION