

PART 1 - GENERAL

- 1.1 INSTALLATION AND REMOVAL
- .1 Provide temporary controls in order to execute Work expeditiously.
 - .2 Remove from site all such work after use.
 - .3 Removal from building to occur only on weekends and evenings using access routes outlined on drawings.
 - .4 Dumpsters and debris chutes shall be removed during regular business hours.
- 1.2 HOARDING
- .1 Erect temporary interior enclosures using 38 x 89 mm construction grade lumber framing at 600 mm centres, and ½" gypsum board panels, taped and filled to create dust proof screen.
 - .2 Erect and maintain pedestrian walkways complete with signs and electrical lighting as required by law.
 - .3 Arrange for sidewalk closure permits when required for Argyle, Duke or Barrington as required.
 - .4 Provide alternative barrier free access during work if main entrance is restricted. Erect signs to alternative route.
- 1.3 GUARD RAILS AND BARRICADES
- .1 Provide secure, rigid guard rails and barricades around open stair wells, and open edges of floors and roofs.
 - .2 Provide as required by governing authorities.
- 1.4 FIRE ROUTES
- .1 Maintain access to property including overhead clearances for use by emergency response vehicles.
- 1.5 PROTECTION FOR OFF-SITE AND PUBLIC PROPERTY
- .1 Protect surrounding private and public property from damage during performance of Work.
 - .2 Be responsible for damage incurred.
 - .3 Work shall not restrict public access.
- 1.6 PROTECTION OF BUILDING FINISHES
- .1 Provide protection for finished and partially finished building finishes and equipment during performance of Work.
 - .2 Provide necessary screens, covers, and hoardings.
 - .3 Confirm with CLIENT Representative and Consultant locations and installation schedule 3 days prior to installation.
 - .4 Be responsible for damage incurred due to lack of or improper protection.
- 1.7 WASTE MANAGEMENT AND DISPOSAL
- .1 Separate waste materials for reuse and recycling in accordance with Section 01 74 21 - Waste Management And Disposal.