

1. ALL WORKS TO BE PERFORMED IN ACCORDANCE WITH CONTRACT DRAWINGS AND SPECIFICATIONS AND WITH PUBLIC WORKS AND GOVERNMENT SERVICES CANADA (PWSC) GUIDELINES AND REQUIREMENTS.
2. CONTRACTOR TO OBTAIN ALL NECESSARY PERMITS REQUIRED TO PERFORM WORKS, COMPLY WITH ALL PERMIT REQUIREMENTS AND CONDITIONS.
3. SITE SURVEY INFORMATION IS COMPILED FROM A VARIETY OF DIFFERENT SOURCES ON DIFFERENT DATES. THEREFORE ACCURACY AND CONSISTENCY IS NOT GUARANTEED. CONTRACTOR TO CONFIRM ALL SITE CONDITIONS PRIOR TO CONSTRUCTION AND IMMEDIATELY INFORM DEPARTMENTAL REPRESENTATIVE OF ANY DISCREPANCIES.
4. BASE PLANS ARE FROM BACKGROUND INFORMATION PROVIDED BY PWSC REALTY SERVICES FROM DRAWING S-4198.DWG. ORIGINAL SURVEY WAS CARRIED OUT IN MAY 1999 AND A SUPPLEMENTARY SURVEY WAS UNDERTAKEN IN DECEMBER 2005.
5. CONTRACTOR IS TO CONFIRM SUBGRADE INFILTRATION RATES AT 3 EQUALLY SPACED LOCATIONS ALONG THE LENGTH OF THE TRENCH AND AT EACH OF THE DRY WELL INSTALLATIONS. REPORT FINDINGS TO DEPARTMENT REPRESENTATIVE AND OBTAIN APPROVAL PRIOR TO INITIATING CONSTRUCTION.
6. A GEOTECHNICAL DRILLING REPORT WAS PREPARED BY HARBOURSIDE GEOTECHNICAL CONSULTS (JULY 7, 2016) AND IS AVAILABLE FROM PWSC FOR INFORMATION.
7. THE CONTRACTOR IS RESPONSIBLE FOR ALL CONSTRUCTION LAYOUT ACTIVITIES. ALL ELEVATIONS ARE METRIC AND GEODETIC.
8. CONTRACTOR IS RESPONSIBLE FOR THE PROTECTION OF WETLANDS AND THE OCEAN FROM DAMAGE DUE TO SILTATION RUNOFF FROM THE CONSTRUCTION SITE. ACCEPTABLE CONSTRUCTION PROCEDURE MAY BE OBTAINED FROM "EROSION AND SEDIMENTATION CONTROL HANDBOOK FOR CONSTRUCTION SITES", CURRENT EDITION BY THE NOVA SCOTIA DEPARTMENT OF ENVIRONMENT. THE CONTRACTOR SHALL MAKE NECESSARY REPAIRS TO SEDIMENTATION AND EROSION CONTROL DEVICES AS DIRECTED BY DEPARTMENTAL REPRESENTATIVE.

