NRC-CNRC

Addendum/Addenda

No./N° 4

Project Description / Description de projet			
M-38 Flexible Research Facil	ity		
Solicitation No./ N° de sollicitation	Project No./N° de projet		W.O. No./N° d'ordre de travail
16-22072	5044-M38		
Departmental Representative / représentant ministériel	Date		
Allan Smith	2016 Sep 20		
Notice:		Nota:	
This addendum shall form part of the tender conditions shall apply and be read in conjun plans and specifications.		toutes les conditions énd	ntégrale des dossiers d'appel d'offres; oncées doivent être lues et appliquées plans et les devis originaux.

DRAWINGS

Structural drawings S01 through S06:


The entire set of are revised and re-issued with this addendum.

Civil drawings C02 through C06:

These civil drawings are revised and reissued with this addendum, as CIMA civile addendum no. CIV-01 2016-8-20.

Electrical drawing E01:

Revise note 2 to read "PROVIDE NEW PRE-CAST MANHOLE, REFER TO E02 NOTES"





NRC-CNRC

Mechanical drawing M04:

Refer to "NOTES"

Change:

1. PROVIDE A NEW ENERGY RECOVERY VENTILATOR. STANDARD OF ACCEPTANCE: MANUFACTURER: RENEW AIRE, MODEL: HE2XRT, MOTOR: 240V/1Ø, 2x1.5 H.P, C/W 1.12x0.96x0.36 METER FACTORY MANUFACTURER CURB, EXACT LOCATION TO BE COORDINATED ON SITE.

To:

1. PROVIDE A NEW ENERGY RECOVERY VENTILATOR (38HRU01)

STANDARD OF ACCEPTANCE: MANUFACTURER: RENEW AIRE,

MODEL: HE2XRTV

MOTOR: 240V/1Ø, 2x1.5 H.P,

SUMMER/WINTER TOTAL EFFICIENCT: 60%/70% at 1000 SCFM (at AHRI 1060 STANDRAD CONDITIONS)

NOMINAL SHIPPING WEIGH: 335 KG TEFC PREMIUM EFFICIENCY MOTORS

AIR FLoW: 1300 SCFM @ 0.5 IN W.G EXTERNAL STATIC

CONTRACTOR SHALL PROVIDE A NEW SECTION OF FRESH AIR AND EXHAUST INSULATED DUCTWORK (250x600mm) FROM UNIT TO 1000mm INTO BUILDING.

UNIT TO BE C/W:

- -FACTORY MANUFACTURER CURB (1.12x0.96x0.36 METER), EXACT LOCATION TO BE COORDINATED ON SITE WITH NRC.
- -DOUBLE WALL CONSTRUCTION
- -ONBOARD VFD'S FOR BOTH AIR STREAMS
- -MOTORIZED OUTSIDE AIR AND EXHAUST DAMPERS
- -DUCTWORK TO BE
- -EXTERIOR PAINT COLOR: WHITE
- -TWO SPARE SETS OF MERV-8 FILTERS
- -AHRI CERTIFIED
- -MANUFACTURER RECOMMENDED WIND LOAD RETROFIT INSTALLATION

ALTERNATE MANUFACTURER: ALDES CANADA

ALTERNATES

Mechanical equipment acceptable alternates:

1. Exhaust Fan: Alternate manufacturer: Cook Fan

2. Ceiling Fan: Alternate manufacturer: Banvil 2000

Note: Final acceptance of all alternates will be based on official shop drawing submittals during construction. It is the contractor's responsibility to allow for all direct and indirect modification to the project as a result of alternate selections.





NRC-CNRC

REFERENCE INFORMATION

KWC Architecural addendum no.1:

Addendum no. 1 issued by KWC Architects is attached to this addendum.

Contractor Environmental Protection Plan:

An environmental protection plan which shall be implemented by the contractor is attached to this addendum.

Building M36 drawings:

Three original construction drawings showing the general size and shape of the M36 North East entrance, where steam piping shall be modified under this contract, are attached to this addendum.

Contractor's site access and parking map:

A Google Earth map showing the contractor's site access route in red and parking areas in yelow is attached to this addendum.

Bidder's questions and answers:

Tender Period Questions no. 1, a document to to address requests for information or clarifications received from the bidders, is attached to this addendum.


Attendees list:


The list of attendees at the 2 mandatory site visits is attached to this addendum.


End of Addendum No.1























GENERAL NOTES:

- EXCAVATE, AS REQUIRED, TO ELEVATIONS SHOWN ON MECHANICAL
- BACKFILL MINIMUM 75 mm ABOVE ROOF SLABS WITH SAND AND COMPACT TO 95% PROCTOR DRY DENSITY.
- THE REMAINDER OF THE BACKFILL SHALL BE 20 mm GRADED CRUSHED STONE COMPACTED TO 95% PROCTOR DRY DENSITY.
- AT ROADWAY, REINSTATE ASPHALT PAVEMENT.
- IN OTHER AREAS, PLACE MINIMUM OF 100 mm TOP SOIL AND GRASS

CONCRETE WORK:

- CONCRETE SHALL HAVE A 28-DAY COMPRESSIVE STRENGTH OF 35 MPa, WITH 6% ENTRAINED AIR.
- REINFORCING STEEL SHALL CONFORM TO CSA G30.18-09, GRADE 400.
- CONCRETE COVER TO REINFORCING STEEL SHALL BE AS FOLLOWS: - CONCRETE SLABS = 75 mm - PRECAST CONCRETE SLABS = 50 mm
- THE CONTRACTOR SHALL SUBMIT BAR LISTS AND PLACING DRAWINGS FOR THE REINFORCING STEEL.
- THE CONTRACTOR SHALL TAKE THREE CONCRETE COMPRESSION TEST CYLINDERS FOR EACH CONCRETE POUR. ONE SHALL BE TESTED AT 7 DAYS AND TWO AT 28 DAYS.
- THE CONCRETE FLOOR SLABS SHALL RECEIVE A WOOD FLOAT FINISH.
- THE PRECAST CONCRETE SLAB SUPPLIER SHALL SUBMIT SHOP DRAWINGS FOR CONCRETE ROOF SLABS.
- ALL CONCRETE WORK SHALL CONFORM TO CSA A23.1-04 AND
- NOTIFY THE ENGINEER BEFORE EACH CONCRETE POUR.
- THE MEMBRANE SHALL BE SOPREMA COLPHENE TORCH 'N STICK, OR EQUIVALENT, AND SHALL BE APPLIED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.
- THE CONTRACTOR SHALL SUBMIT TECHNICAL LITERATURE FOR THE PROPOSED MEMBRANE.

National Research
Council Canada

Conseil national de recherches Canada Administrative Services Division des services and Property Management administratifs et gestion

de l'immobilier

NRC - CNRC


Leibe Engineering Associates Consulting Engineers / Ingenieurs-Conseils

22 Antares Drive, Suite 201


Ottawa, Ontario, K2E 7Z6

tel: (613) 723-7765 fax: (613) 723-0095





- · Verify all dimensions and site conditions and be responsible for same.
- Vérifier toutes les dimensions et l'état des liéux et en assumer la responsabilité.



A Detail no. No. du détail B Location drawing no. sur dessin no. C Drawing no dessin no.


BUILDING M-38 FLEXIBLE RESEARCH FACILITY MONTREAL ROAD CAMPUS

STRUCTURAL: STEAM PIPE TRENCH PLAN AND **DETAILS**

	R.L.	•	JUNE, 2016
drawn	M.P.	dessiné	AS SHOWN échelle
checked	R.L.	vérifié	sheet feuille S07 of/de S07
approved		approuvé	W.O.no. D.T.no.

5049-S07

ASPM A1 (841 x 594)



- 1.2 The boreholes and test pits shown on the plan are for information purposes only. Their location on the plan is approximate.
- 1.3 Site preparation includes clearing, grubbing, stripping of topsoil, demolition, removal of unsuitable materials, cut, fill and rough grading of all areas to receive finished surfaces, including the preparation of the building pad and the temporary ditch.
- 1.4 The location of underground municipal services and public utilities are approximative. The Contractor must determine the exact location, size, material and elevation of all existing utilities (on-site and off-site) prior to any excavation work. Damage to any existing services and/or existing utilities during construction, whether or not shown on the drawings must be repaired by the contractor at his own expense.
- 1.5 Contractor shall refer to the boreholes and test pits records to obtain information about observed stratigraphy on site. (See available geotechnical report)
- 1.6 All material shall conform to the OPS specifications, be compacted as per the requirements and be approved by the consultant prior to delivery to the site.
- 1.7 Compaction shall conform to the following requirements:

1.0 GENERAL - GRADING

- Exposed subgrade: 95% Standard Proctor (SPMDD) - Granular foundations: 100% Standard Proctor (SPMDD)
- Asphalt: 97% Marshall Density
- Subgrade fill (pavement areas OPSS Select Subgrade Material): 95% Standard Proctor (SPMDD)
- 1.8 If groundwater is encountered during construction, dewatering of excavations could be required. It is assumed that groundwater may be controlled by sump and pumping methods. The contractor shall obtain a 'permit to take water' (PTTW) if site conditions require taking more than a total of 50 000 I/day.
- 1.9 Maintain benchmarks and landmark references as is, otherwise these references will be repositioned by a certified land surveyor at the Contractor's expense
- 1.10 The Contractor is responsible for obtaining all permits required to complete all works and bear cost of same, including road cut permit and associated costs. (If required)
- 1.11 Temporary excavation in the overburden should be sloped at 1 horizontal and 1 vertical from the base of the excavation and as per the requirements of the occupational health and safety act (OHSA) and local regulations.
- 1.12 During the construction period the Contractor is responsible for installing and maintaining temporary traffic signage, including traffic signs, traffic markings and temporary traffic lights, and flagmen, as required by the NRC, City, the MTO, and other governing authorities.
- 1.13 The Contractor must control surface runoff from precipitation during construction.
- 1.14 Unless they are to be modified within the contract documents scope of work, all altered existing infrastructures must be reinstated to its original condition.
- 2.0 DEMOLITION
- 2.1 The Contractor must visit the premises in order to be aware of all the elements to be removed and demolished. No claim due to a bad evaluation of work to be carried out will be accepted.
- 2.2 The Contractor must perform all demolition required to complete the proposed work as specified is the drawings.
- 2.3 The Contractor must conform to all laws, codes, ordinances, and regulations adopted by federal, provincial or municipal government councils and government agencies, applying to work which it carried out.
- 2.4 The Contractor must protect and maintain in service the existing works which must remain in place. If they are damaged, the Contractor must immediately make the replacements and necessary repairs to the satisfaction of the Owner's representative and without additional expenses to the Owner.
- 2.5 The Contractor is the only person in charge of safety on the building site. The Contractor is responsible for providing adequate protection of the workers, other personnel and the general public, protection of materials, as well as maintaining in good condition the completed works and works to be completed. The Contractor must provide at any time:
- (a) A sufficient number of fences, barriers, posters, guards and others to ensure safety;
- 2.6 The Contractor must discard demolition materials in the authorized licensed landfills and in conformity with the applicable laws and regulations. The Contractor must be able to provide, upon request, copies of the disposal tickets to the Owner's representative.
- 2.7 The Contractor must ensure all reinstatement for the demolition required in ALL Electrical conduits and Steam pipes installation. For Road or Parkings, reinstatement shall be as per the Heavy Duty pavement structure detail (202). For the walkways, it shall be as per the Asphalt sidewalk (108) detail. For any landscaping, sodding must be used as per specifications.
- 3.0 EXCAVATION AND BACKFILL BUILDING FOOTPRINT, PARKING AREAS AND ACCESS ROADS
- 3.1 All surface vegetation, rootmat, organics, underlying topsoil, debris, fill, soft drainage ditch sediments, test pit backfill and other deleterious material shall be removed from beneath the proposed building footprint. All loose or disturbed materials shall be removed and replaced with compacted fill. (See geotechnical report for further information)
- 3.2 Beneath the proposed parking, access roads and landscaped areas, all surface vegetation, rootmat, organics, topsoil, debris, soft drainage ditch sediments, test pit backfill and other deleterious material shall be removed.
- 3.3 Earth removal shall be inspected by a geotechnical engineer to ensure that all unsuitable materials are removed prior to placement of fill, concrete and/or others, and to confirm the compaction degree and the conditions of the founding soils. All unsuitable materials shall be hauled off-site and disposed as per provincial and municipal regulations.
- 3.4 Subgrade shall be approved by experienced geotechnical personnel before proceeding with placement of fill.
- 3.5 All soft areas revealed under surface compaction shall be removed, to a minimum depth of 500mm, and replaced with compacted subgrade fill (OPSS granular B type I or II) as directed by the Geotechnical Consultant, Transition around sub-excavation, where backfill and native material are not of similar nature, shall be sloped at 3H:1V within 1.5 m of finished surface.

- 3.6 Structural fill, used for building pad preparation, shall consist of OPSS granular "A" or granular "B" type II material, approved by the Geotechnical Consultant prior to delivery to the site. (See geotechnical report for further information)
- 3.7 Subgrade fill, used for grading beneath the parking areas, access roads and sidewalks, shall consist of OPSS granular "B" type I or II, approved by the Geotechnical Consultant prior to delivery to the site. Subgrade fill used below rigid surfaces, such as concrete sidewalks and concrete slabs, must not contain more than 25% silt.
- 3.8 All structural and subgrade fill shall be placed in lifts no thicker than 300 mm and compacted using suitable methods.
- 3.9 In general landscaping areas where settlement of the ground surface is of minor concern, non-specified existing fill, along with site excavated soil may be used. In landscaped areas the fill must be spread in thin lifts and compacted by the tracks of spreading equipment to minimize voids. When used to build up subgrade level in areas to be paved, the fill should be compacted in thin lifts to a minimum density of 95% SPMDD.
- 3.10 Non-specified fills and site-excavated soils are not suitable for use as backfill against foundation walls.
- 3.11 All heavy equipment shall not operate directly on the subgrade. A minimum of 500 mm of fill shall be used to allow traffic over subgrade. Subgrade surfaces will be prone to disturbance by weather and traffic, therefore preparation of the subgrade shall be scheduled such that the granular materials are placed as quickly as possible.
- 3.12 Provisions shall be made for erosion and sediment control measures prior to stripping the site of vegetation and other deleterious materials. Measures such as phase stripping, vegetation buffer zones, silt fences, sediment control fences, straw bales, sediment traps/basins and rock checks shall be constructed and maintained in order to control sediment, as required by the
- consultant / engineer 3.13 No contaminated materials have been detected on site. However, if contaminated material is found, all excavated material that needs to be disposed off-site shall be disposed of as per all "Ontario Ministry of the Environment" (MOE) regulations. If required, the contractor will be compensated seperatly for this work. Prior to the start of the work, the Contractor shall provide the name and location of the landfill(s) where the contaminated material will be disposed. The landfill owner shall provide, to the Owner / Consultant, the MOE documents confirming that he has the right to accept the contaminated material. Also, prior to start any work, the Owner / Consultant shall approve the disposal site(s). During work, the Contractor shall provide, to the Consultant, all check-in receipts issued by the landfill owner.

- 3.14 The Contractor is responsible to provide a confirmation that the imported material used as subgrade fill is free of any contaminants such as Petroleum Hydrocarbons (C10-C50), PAH (Polycyclic Aromatic Hydrocarbons), MAH (Monocyclic Aromatic Hydrocarbons) and metals like mercury, silver, arsenic, cadmium, cobalt, chromium, copper, tin, manganese, molybdenum, nickel, lead and zinc.
- 3.15 The Contractor is responsible for constructing all temporary access roads, as required to complete the work. The Contractor must also maintain all temporary access roads in good and tidy condition at all times to the satisfaction of the Owner and/or Consultant.
- 3.16 It is expected that some bedrock removal may be required. Consideration should be given to line-drilling in conjunction with hoe-ramming or controlled blasting. Bedrock removal by hoe-ramming may be sufficient in areas of weathered bedrock and where only small quantities of removal are required. Prior to any blasting a pre-blast or pre-consultation survey of the existing structures within proximity of the blasting must be carried out.
- 4.0 PAVEMENT STRUCTURE
- 4.1 Heavy duty pavement to be constructed as per details.
- 4.2 Transition between existing and proposed pavement shall be constructed as per details.
- 4.3 Asphalt concrete material shall conform to OPSS Form 1150. Minimum Performance Graded (PG) 58-34 asphalt cement must be used for this project.
- 4.4 Asphalt mix design shall be reviewed and approved by a geotechnical engineer prior to start
- 5.0 LANDSCAPING

either side of centreline).

- 5.1 Erosion Blanket shall be installed as specified 0.75m from centreline to top of ditch to stabilize embankments until vegetation is established. It shall be Nilex BioNet S150BN (or approved equivalent) installed as per manufacturer's recommendations. 150mm Topsoil (as per OPSS 802) and Seed shall be placed prior to placement of erosion blanket. Seed mix shall be: Bank Seed Mix 8215 by OPS Seeds (or approved equivalent), applied at rates recommended by the supplier with Oat nurse crop.
- 5.2 Sodding shall be installed as specified and provide any sodding reinstatement. Sodding shall be Number 1 Grade Turfgrass Nursery Sod, placed as per OPSS 803. Any disturbed areas beyond the limits shown on the drawings shall be reinstated with 150mm topsoil and sod at no additional cost. Sod shall be installed (as per OPSS 803) and staked in the ditch invert (0.75m

7.0 GENERAL - SERVICING

- 7.1 Unless otherwise indicated, all materials and construction methods to be in accordance 9.9 For roof drains, refer to architectural and mechanical drawings. with the latest edition of the standardized specifications from OPSS, the City of Ottawa standard specifications and drawings and all other governing authority requirements as they apply.
- 7.2 The location of underground municipal services and public utilities is approximate. Contractor must determine the exact location, size, material and elevation of all existing services and existing utilities prior to any excavation work. Damage to any existing services and/or existing utilities during construction, whether or not shown on this drawing, must be repaired by the Contractor at his own expense.
- 7.3 The Contractor shall be responsible for obtaining all permits required to complete all works and bear cost of same, including water permit and associated costs.
- 7.4 The Contractor shall be responsible for all excavation, backfill, reinstatement of all areas disturbed during construction to existing condition or better and all associated works to the satisfaction of the engineer and municipal authorities.
- Asphalt reinstatements must be in accordance with OPSS 310. - Landscaped areas must be reinstated with 100 mm of topsoil and sod.
- 7.5 Within landscaping areas, backfill for service trenches may consist of excavated material replaced and compacted in lifts.
- 7.6 A minimum of 150 mm of OPSS granular "A" must be used for pipe bedding for sewer and water pipes and must extend to the spring line of the pipe. Cover material from the spring line to at least 300 mm above the pipe obvert must also consist of granular "A" material. Bedding and cover material must be placed in maximum 300 mm lifts and compacted to a minimum of 95% SPMDD.
- 7.7 Re-use of organic free, moist (not wet) overburden material should generally be possible. Wet materials may not be suitable as proper compaction will not be possible without an extensive drying period. Stones greater than 300 mm in their longest dimension and other deleterious materials must be remove prior to the re-use of materials.
- 7.8 Well fractured bedrock is acceptable as backfill provided the rock fill is placed at least 300 mm above the top of the pipe and that all stones greater than 300 mm in their longest dimension are removed. Where fractured rock is used, a blinding layer (OPSS granular "A" crushed stone) or a geotextile may be required above the fractured rock to reduce the loss of fines in the voids of the blast rock.
- 7.9 It may happen that services will be placed in both bedrock and overburden materials. Where the bedrock slopes at more than 3H:1V a transition treatment is required. At these locations the bedrock must be excavated and extra bedding material must be placed to provide a 3H:1V (or flatter) transition from the bedrock subgrade towards the soil subgrade.
- 7.10 Trench backfill material within the frost zone (approx. 1.8 m below finished grade) must match the soils exposed at the trench walls to reduce potential frost heave. The backfill must be placed in maximum 300 mm loose lifts and compacted to a minimum of 95%
- 7.11 The Contractor shall be responsible for making or arranging all connections to the existing sewers as per requirements of the governing authorities. Prior to connection, the Contractor must provide for approval all test results performed on the internal services to the Consultant / Engineer and the governing authorities. Test results shall include T.V. inspection of sewers, infiltration/exfiltration tests for sewers and manholes, deformation tests of sewers, watermain hydrostatic leakage test, flushing and disinfecting operations and bacteriological water analysis.
- 7.12 This drawing to be read in conjunction with architectural, mechanical and electrical.
- 7.13 Connections to existing for storm and sanitary sewers must be performed as per detail included in the present plans.
- 8.0 WATERMAIN
- 8.1 Watermain pipe material shall be class 150 PVC DR 18, unless otherwise shown on
- 8.2 All watermain shall be installed with a minimum of 2400 mm cover from finished grade.
- 8.3 The Contractor shall construct watermain, water services, connections and appurtenances as per municipal specifications, and shall coordinate and pay all related costs including the cost of connection, inspection and disinfection by municipal personnel.
- 8.4 Watermain service connections shall be installed a minimum of 2400 mm from any catch basin, manhole or object that may contribute to freezing. Thermal insulation shall be installed where 2400 mm separation cannot be achieved (as per City of Ottawa details W22 and W23).
- 8.5 Thrust block and restraints shall be as per City of Ottawa.
- 8.6 A continuous 12 gauge copper tracer wire shall be installed over all watermains. Tracer wire shall be tied to all fire hydrants.
- 8.7 All watermains shall be hydrostatically and bacterialogically tested as per municipal and provincial regulations. It is the Contractor's responsibility to ensure that all their requirements are followed.
- 8.8 Contractor must coordinate the supply and installation of water meter and remote water meter with mechanical Contractor.
- 8.9 Valve and valve box to be as per City of Ottawa standards.
- 9.0 STORM SEWER
- 9.1 Storm sewers pipes must be PVC SDR-35, unless otherwise noted on the drawings.
- 9.2 PVC storm sewers to be installed as per OPSD 802.01. Bedding and cover material to be OPSS granular 'A' compacted to 95% Standard Proctor Density (SPMDD).
- 9.3 All storm sewers to be T.V. inspected by the Contractor as per the City of Ottawa and the Owner's standards. Report shall be provided to the Consultant in two (2) copies.
- 9.4 Storm manholes and manhole/catchbasins to be as per OPSD 701.01 and OPSD 701.013, sizes specified on drawing, and shall be equipped with OPSD 404.020 safety grates when exceeding 5.0 m to the lowest invert.
- 9.5 Storm sewer manhole excavations to be backfilled with granular 'B' compacted to 100% Standard Proctor Density (SPMDD). Joints between manhole sections shall be wrapped in a non-woven geotextile.
- 9.6 Storm manholes frame and cover to be as per OPSD 401.010, type 'A' closed cover.
- 9.7 All polyvinylchloride (PVC) storm pipes shall meet current MOE specifications / City of Ottawa standards.
- 9.8 The Contractor must implement best management practices to provide for protection of receiving storm sewer or drainage during construction activities (i.e. filter cloth on catch basins, straw bale check dams sediment controls around all disturbed areas). Dewatering shall be sumped into sediment traps. See erosion control plan.

- 10.0 SANITARY SEWER

SERVICES

- 10.1 Sanitary sewer pipes must be PVC SDR-35, unless otherwise indicated on the drawings. Installation must be as per OPSD 1005.02. Bedding and cover material must be OPSS granular 'A' compacted to 95% Standard Proctor Density (SPMDD).
- 10.2 All sanitary and combined sewers to be T.V. inspected by the Contractor as per the City of Ottawa and the Owner's standards. Report shall be provided to the Consultant in two (2) copies.
- 10.3 All polyvinylchloride (PVC) sanitary pipes shall meet current MOE specifications / City of Ottawa standards.
- 10.4 Sanitary manholes to be as per OPSD 701.01 and sizes specified on drawing.
- 10.5 Sanitary sewer manhole excavations to be backfilled with granular 'B' compacted to 100% Standard Proctor Density (SPMDD). Joints between manhole sections shall be wrapped in a non-woven geotextile.
- 10.6 Sanitary manholes frame and cover to be as per OPSD 401.01, Type 'A' closed cover.

and Property Management

administratifs et gestion

NAC · CNAC

GENERAL NOTES


- CONTRACTORS TO CHECK AND VERIFY ALL DIMENSIONS ON SITE PRIOR TO DEMOLITION OR CONSTRUCTION AND REPORT ANY ERRORS OR OMISSIONS TO DEPARTMENTAL REPRESENTATIVE.
- CONTRACTORS MUST VISIT THE SITE & FULLY FAMILIARIZE THEMSELVES WITH THE SCOPE OF THE WORK.
- PREVENT THE SPREAD OF DUST & DEBRIS BEYOND THE WORK AREA AND CLEAN ALL SURFACES AT COMPLETION.
- MAKE GOOD ALL SURFACES AFFECTED BY THIS WORK,
- COORDINATE ALL SHUTDOWNS WITH THE DEPARTMENTAL REPRESENTATIVE.
- PROVIDE ALL LABOUR AND MATERIAL REQUIRED TO FORM A COMPLETE, FUNCTIONAL SYSTEM AS DESCRIBED ON DRAWINGS.

110-240 Catherine Street Ottawa ON K2P 2G8 Téléphone : 613 860-2462

Télécopie: 613 860-1870

A000630C

KEY PLAN



SEPT 20, 2016 | ADDENDUM CIV-01 CTT AUG 29, 2016 TENDER CTT Date Revision Date Printed Date imprimée

AND/OR FROM THE CITY EACH RESPECTIVELY. ALL INFORMATION UNDER THE LEGEND 'EXISTING' IS FOR INFORMATION ONLY, COMPLETE OR EXACT LOCATION AND ELEVATION OF UNDERGROUND SERVICES ARE NOT GUARANTEED

THE UNDERGROUND FEATURES AND INFORMATION THAT APPEAR ON

THE DRAWINGS WERE OBTAINED FROM THE PUBLIC UTILITY COMPANIES

CERTAIN UNDERGROUND FEATURES ON PRIVATE PROPERTY ARE NOT SHOWN ON THE CURRENT DRAWING. ANYONE WHO PROCEEDS WITH EXCAVATION WORK SHALL VERIEV THE

EXACT LOCATION OF ALL UNDERGROUND FEATURES, BY EXPLORATORY

EXCAVATIONS, AND SHALL ASSUME FULL RESPONSIBILITY IF THERE IS

ANY DAMAGE THAT OCCURS DURING WORK THE CONTRACTOR WILL HAVE THE RESPONSIBILITY AND THE OBLIGATION TO VALIDATE, BY EXPLORATORY EXCAVATION, THE SIZE OF THE PUBLIC UTILITIES UNDERGROUND SERVICES AND TO WARN THE

ENGINEER OF ANY CONFLICT WITH THE PROJECTED WORK.

NOTE OF CAUTION

THE GEODETIC COORDINATES OF EVERY ITEM INCLUDED AS PART OF THIS DOCUMENT HAVE NO LEGAL VALUE. THE SITE LAYOUT MUST BE COMPLETED USING THE OFFICIAL BENCHMARKS OF AN ACCREDITED LAND SURVEYOR.

THE UNDERGROUND FEATURES AND INFORMATION THAT APPEAR ON THE DRAWINGS WERE OBTAINED FROM THE PUBLIC UTILITY COMPANIES AND/OR FROM THE CITY EACH RESPECTIVELY.

ALL INFORMATION UNDER THE LEGEND 'EXISTING' IS FOR INFORMATION ONLY. COMPLETE OR EXACT LOCATION AND ELEVATION OF UNDERGROUND SERVICES ARE NOT GUARANTEED.

CERTAIN UNDERGROUND FEATURES ON PRIVATE PROPERTY ARE NOT SHOWN ON THE CURRENT DRAWING. ANYONE WHO PROCEEDS WITH EXCAVATION WORK SHALL VERIFY THE EXACT LOCATION OF ALL UNDERGROUND FEATURES, BY

EXPLORATORY EXCAVATIONS, AND SHALL ASSUME FULL

RESPONSIBILITY IF THERE IS ANY DAMAGE THAT OCCURS DURING THE CONTRACTOR WILL HAVE THE RESPONSIBILITY AND THE

OBLIGATION TO VALIDATE, BY EXPLORATORY EXCAVATION, THE SIZE OF THE PUBLIC UTILITIES UNDERGROUND SERVICES AND TO WARN

Verify all dimensions and site conditions and be responsible

o Vérifier toutes les dimensions et l'etat des liéux et en

A Detail no.

No. du détail B Location drawing no. sur dessin no. C Drawing no.

BUILDING M-38, MONTREAL ROAD CAMPUS

OTTAWA, ONTARIO

1200 MONTREAL ROAD CAMPUS

SPECIFICATIONS AND NOTES

JULY 22, 2016 C. L.-LEBEL échelle dessiné scale R.YANTHA 1:200 C. L-LEBEL of/de 6 approuvé W.O.no. D.T.no. approved C. LYON

ASPM A1 (841x594)

An exact copy of all working documents including,

without limitations, the original of the present

document or plan is kept on file by Cima+. Any

or to accompanying documents without written

modification carried out to this document or plan

authorization by the engineer is prohibited.

Authorized modifications must be signed and

sealed by an engineer and this engineer will be

completely responsible for these modifications.


Cima+ is not and will not be responsible for the


consequences of these modifications or for modifications carried out without it's consent. PROJECTED WORK.

THE DEPARTEMENTAL REPRESENTATIVE OF ANY CONFLICT WITH THE

5049-C03

dessin no.






- CLASSE DE BÉTON: C-2; / CONCRETE CLASSE: C-2 WATER / BINDER MAX. RATIO : 0.45 - MINIMAL COMPRESSIVE STRENGTH AT 28 DAYS: 35MPa
- MAXIMUM NOMINAL Ø FOR AGGREGATE: 20mm AIR CONTENT: 5% À 8%; - SLUMP: 80mm ± 30mm POUR COFFRAGE FIXE 30mm ± 30mm POUR COFFRAGE GLISSANT;

- SEE DETAIL 109 FOR EXPANSION, CONTROL AND CONSTRUCTION JOINTS




SIDEWALK SLAB - TYPE






CONCRETE CURB DETAIL (TYPICAL)






ASPM A1 (841x594)

ASPHALT SIDEWALK






EXPANSION JOINTS OF CONCRETE WORK AT 6.0m C/C MAX. DIRECTION CHANGE AND AT CONTACT WITH CONCRETE STRUCTURES
 EDGES AND CONTROL JOINTS SHALL BE GROOVED, TOOLED AND BURNISHED WITH BRONZE EDGERS AND GROOVERS.


CONSTRUCTION AND EXPANSION JOINT




EXPANSION. CONTROL AND CONSTRUCTION JOINTS FOR CONCRETE WORK



A TRANSITION IS REQUIRED WHERE SUBGRADE FILL MATERIAL HAS DIFFERENT FROST SUCEPTIBILITY. TRANSITION SHALL REACH A MAXIMUM DEPTH OF 1.8 m BELOW PROJECTED PAVEMENT ELEVATION. THE CONTRACTOR MUST SUBMIT THE RETAINING WALL DESIGN AND SHOP DRAWINGS SEALED AND SIGNED BY AN PEO LICENSED ENGINEER PRIOR TO START CONSTRUCTION.





TYPICAL SECTION - TRANSITION BETWEEN **DIFFERING PAVEMENT STRUCTURES**

PAVEMENT SUPERPAVE 12.5 A/C SURFACE COURSE THICKNESS 40mm - SUPERPAVE 19.0 A/C BASE COURSE EXISTING GROUND THICKNESS 50mm -CRUSHED STONE OPSS GRANULAR 'A' THICKNESS 150mm

— SUBGRADE MINIMUM PERFORMANCE GRADED (PG) 58-34 ASPHALT

ACCEPTABLE FILL MATERIAL



TYPICAL SECTION - GRANULAR FOUNDATION AND ASPHALT PAVEMENT (HEAVY DUTY)

GENERAL NOTES CONTRACTORS TO CHECK AND VERIFY ALL DIMENSIONS ON SITE PRIOR TO DEMOLITION

and Property Management

OR CONSTRUCTION AND REPORT ANY ERRORS OR OMISSIONS TO DEPARTMENTAL REPRESENTATIVE. CONTRACTORS MUST VISIT THE SITE & FULLY

NRC - CNRC

administratifs et gestion

FAMILIARIZE THEMSELVES WITH THE SCOPE OF THE WORK. PREVENT THE SPREAD OF DUST & DEBRIS

BEYOND THE WORK AREA AND CLEAN ALL SURFACES AT COMPLETION. MAKE GOOD ALL SURFACES AFFECTED BY

THIS WORK,

COORDINATE ALL SHUTDOWNS WITH THE DEPARTMENTAL REPRESENTATIVE.


PROVIDE ALL LABOUR AND MATERIAL REQUIRED TO FORM A COMPLETE, FUNCTIONAL SYSTEM AS DESCRIBED ON DRAWINGS.

CIMA

110-240 Catherine Street Ottawa ON K2P 2G8

Téléphone : 613 860-2462 Télécopie : 613 860-1870 www.cima.ca

KEY PLAN



2	SEPT 20, 2016	ADDENDUM CIV-ØI	CTT
1	AUG 29, 2016	TENDER	CTT
No.	Date	Revision	By: Par:
Date	Printed	Date in	nprimé

o Verify all dimensions and site conditions and be responsible

o Vérifier toutes les dimensions et l'etat des liéux et en

A Detail no.

No. du détail B Location drawing no. sur dessin no. C Drawing no.

BUILDING M-38, MONTREAL ROAD CAMPUS

dessin

D.T.no.

dessin no.

1200 MONTREAL ROAD CAMPUS OTTAWA, ONTARIO

DETAILS

C. L.-LEBEL JULY 22, 2016 échelle R.YANTHA NTS C. L-LEBEL **5** of/de **6**

approuvé | W.O.no. approved C. LYON

5049-C05

Cima+ is not and will not be responsible for the consequences of these modifications or for modifications carried out without it's consent.

An exact copy of all working documents including, without limitations, the original of the present document or plan is kept on file by Cima+. Any modification carried


out to this document or plan or to accompanying documents without written


Authorized modifications must be signed and sealed by an engineer and this

engineer will be completely responsible for these modifications.

authorization by the engineer is prohibited.

- CRUSHED STONE OPSS GRANULAR 'B' TYPE II





designed	conçu	date			date
C. LLEBEL		JUL'	Y 22, 20	216	
drawn	dessiné	scale			échelle
R.YANTHA			NTS		
checked	vérifié	sheet			feuille
C. L-LEBEL		6	of/de	6	
approved	approuvé	W.O.no.			D.T.no.
C. LYON			_		

NRC Project No: 5044 PROJECT NAME: M-38 DATE: September 19-2016

The following changes in the tender documents are effective immediately. This addendum will form part of the contract documents.

SPECIFICATIONS;

- 1. Refer to 07 46 50 Preformed Siding
 - .1 Revise item 2.1.(.2) to read **915mm wide**, panel height as detailed.
- 2. Refer to 07 46 50 Preformed Siding
 - .1 Revise item 2.1.(.6.2) to read "Type 1 Kingspan "Microrib" exterior surface

DRAWINGS;

- 1. Reference drawing 5044-A00 Cover
 - .1 Revise all type W3 to read 13mm FIBER REINFORCED CEMENT BOARD PANEL TO 600mm BELOW GRADE

2. Reference drawing 5044-A05 & A05a – Building Elevations

Revise elevation to remove horizontal reveal. No horizontal reveal is required Refer to revised elevations 2/A05 and 1 A05a on attached ASK-01.


3. Reference drawing 5044-A05- Building Elevations


Revise elevations 1 and 2/A05. Remove all vertical reveals as indicated by elevation tag "MR". Horizontal reveal to remain as per elevation tag "MR".


4. Reference drawing 5044-2/A05 - Building Elevations

.4 Revise elevation TAG for center overhead door from FD to OD.

END OF KWC ADDENDUM no. 01











scale 1:50 date

drawing no.

ASK-01 19-SEPT-16 drawn CD

rev. 1629

5044 project NO project project M-38

M38-5044 Flexible Research Facility - Environmental Review


Appendix B: Contractor Environmental Protection Plan


Project Description:


This project involves the construction of a flexible, modular research building to be located across the road from building M-39 at the NRC Montreal Road Campus (1200 Montreal Road, Ottawa, ON). The new building number will be M-38.


Contractor Environmental Protection Plan:


- 1. To help mitigate impacts related to air emissions and noise, all equipment used during construction will be in good working order, free from leaks, and meet applicable standards and regulations regarding noise and air emissions (e.g., Occupational Health and Safety Act, provincial Drive Clean standards, etc.). Equipment idling should also be reduced or eliminated when possible.
- 2. Vegetation will not be removed unless necessary.
- 3. Disturbed areas will be re-vegetated as soon as possible and any native trees that are over 30cm diameter at breast height that are removed will be replaced at a ratio of 3:1. Replacement trees must be native to the area and should be at least be 5 cm diameter if a deciduous tree or 2 m tall if a coniferous tree. Replacement trees should be tended for a minimum of two years.
- 4. Native trees over 30cm diameter at breast height or other desirable trees (e.g. apple trees) that will not be removed must be protected during construction. This can be accomplished by installing snow fence or other markings around the critical root zone to ensure no disturbance in that area. The critical root zone extends outward from the trunk of each tree for a distance 12 times the tree's diameter at breast height.
- 5. There is a single Butternut tree located in the large patch of trees approximately 45 m northwest of M-48 (UTM coordinates: 18 T 451369N; 5033721E). This tree is affected by Butternut canker and is very sick (Leckie, 2015a; Leckie, 2015b). However, since this is a federally-listed endangered species, this tree will not be removed and will be protected during construction. No disturbance will take place within the critical root zone (3.3m) and disturbance should be minimized to the extent possible within 7.5 m of the tree.
- 6. The construction area will be visually searched immediately prior to construction and any wildlife species will be allowed to transit the site before excavation begins. If a Milksnake is encountered during construction, stop work and contact the Environmental Operations Office for advice.
- 7. The site is located within the C3 bird nesting zone in Canada and has a regional nesting period from the beginning of April to the end of August. Tree clearing should take place outside of this window. If this is not possible, contact the Environmental Operations Office who will conduct a bird nest survey. If an occupied nest is found, the nest will be left in place undisturbed along with the neighbouring vegetation until nesting is completed.
- 8. If excavation reveals a potential archaeological artifact or deposit stop work immediately and notify the NRC Project Manager who will contact Parks Canada for instructions on how to proceed.
- 9. Adequate spill containment materials will be readily available and employees and contractors working on the project will review NRC emergency procedures with the NRC Project Manager.
- 10. As a safety precaution, all underground services must be located prior to commencement of work.














REVISIONS

No. DATE CHANGE BY NATIONAL F

23/12/55 EXHAUST FAN ZAISED ELG.

PLANT ENC

NATIONAL RESEARCH COUNCIL

PLANT ENGINEERING SERVICES

OTTAWA

CANADA

DATE
MARCH 30, 1955

DESIGNED BY
DRAWN BY
CHECKED BY

MONTREAL ROAD LABORATORIES

MECHANICAL

SERVICE ROOM-PIPING & EQUIPMENT

A-550

发"= 1 FT."



NAC-CNAC

NAC-CNAC						
Mandatory Site Visit Attendance / Visite de chantier obligatoire	it Attendance / Visi	te de chantier	obligatoire			
Project Description / Description de projet	M-38 - Flexible Research Facility	cility			September 27th	Closing time 2:00 PM
Solicitation No./N° de solicitation	16-22072	Project No	Project No./No de projet	, ,	1st Showing September 13th	Showing Time
Departmental Representative / représentant Allan Smith	8	Signature	Alternate/Questions deadline September 16th	Addendum Deadline September 20th / 12:00	2nd Showing September 15th	9:00 AM
COMPANY/COMPAGNIE	NAME/NOM	SIGNATURE	PHONE/TELEPHONE	FAX/TELECOPIEUR	EMAIL/COURRIEL	
ToFCOL	JOHN O FACREIL	1 oF	4178425814	613 2243630	OFARRELL @ TOPEON. CA	·CA
RUITER	BRIAN COUGHLAN	Kit	6137250354	LB 725 3400	ruiter @ ruiter sonstruction.ea.	lion.ca.
Modern Niggara	Jason Ratuse	A M	613-511-7505	613-541-1528	jatuse Emoderaniagan com	com
TRAFIEX	Simon GORMAN	150	613 736 6987	613 736 1193	Sprinan e templey. Ca	
Methodald BastHens	LARRY SAURURE	The state of the s	2229-158 20	613.8315528	LORRY @ MBC. Ca.	'a
Butter East	Roseit McKIMMEY	B	613 857-1980		LACKINGS & BUTTON EAST. COM	. Com
Re Hely Construction	JOHN ACCOUPIN	2	613)831-2335	(613) 831-8779	incorthy@rehein.com	COM
0	LATIN CACO	Other	613-286-2326	613-749-9860	OWEND INSTANTONET CA	J. C. A.
8MI	JADE ANZURES	JANA Y	613-325-6016	613 235 2126	lade@ bmi-ind.com	com
S.C. Sulpher corst	FRANCIS Sulphen	John	613-384-5550	613-384-5589	estimating a 1c sulpher. com	R. COM
CEMME PROPERTIES	Anoper DeACU		514-829. 0073	3.	andrew. deacor & mountainviteu. Con	NV TEU. CON
Douga Devenos.	AUDY C.3305	A A	613-224-7268	6.3.224.0579	ESTIMATING & DOLYNICOM	25
GRACIECK CONST	Rhondas harbard.	RS halloyo.	613-591-9100x cs-413591-8109	-413-591-8109	Rhandace graebeckeen / public Egmebeckee	bie Ogmebeck.co
SESNY 11010115	MINE MATTINE	Misthe	817-413-4116		MINETIME OF SEIND COMMISSION	12,0011
(Torin Moore	Your Moore	613-267-4265		Toring and contractors. Oa	ctors. a
1 2	RAFIK OLIDITIOA	that I	613.834-0709	613-830.3338	RAFIK & GAULEC CONTRACTIME. COM	ZACTING. COM
FULCER CONST	JOEY KRUEGER	So His	613 820 6000		BID @ FULLER, CA	25
1		1				

NAC-CNAC

Mandatory Site Visit Attendance / Visite de chantier obligatoire

				Closing Date	Closing time
Project Description / Description de projet	cility		.54	September 27th	2:00 PM
		Project No /No de projet		1st Showing	Showing Time
Solicitation No./N° de solicitation			2	September 13th	
Departmental Representative / représentant	Signature	deadline	Addendum Deadline	2nd Showing Sentember 15th	9:00 AM
Allan Smith			Ceptellibel 20til 12:00		
	SIGNATURE	PHONE/TELEPHONE	FAX/TELECOPIEUR	EMAIL/COURRIEL	E
MIPAIN T/COINIF AGINIL	A STATE OF THE STA	613293 1885		Steven daguet Ostmetycom	Kechicom
10		(13-745-7871		Cesapa Cindeconstituction	CC NOW CO
CIMOS COMOS SERVED	Jan Sand	7	£8°	bseld micron.ca	8
aren Jose J	14 11	613-240-008		Kavery @ PCSGC.CA	77
Lant all Soll		613-32-580		Brimation (a) Roly on France	as on Price Pro
	THE THE PERSON OF THE PERSON O	\$12 C) 17CE		deed haven construction	4,602
an Dougles	2	000000			
Though Cansalan No Ale Beautist	1 CX	615,540,1654	a a	(1) 1 6 (1) C. F.	
4	J X Y	K13-932-2022		15+louis (2 rybourago, com	John Com
ACCONTACION	1 Kerry	SH11-186-819		christopher @ Jumes	mer. com
This poly that on the state of	7 8			READLEY O FREGON CA	
FRECON CONTROLL BRAD DORESTRIEDICZ		112 021 799		1.4 6 of the Wall ! e .	Jina . Ca
#X2+F2) WFU !: 00 PODDIE #1 EOD	The plan	1017-101-010			
M. J. M. J. S. J. M. J. S. J. M. J. S. J. J. M. J. S. J.		(013 884 6661		derek a marothica	
CMIT	я			<i>x</i>	
			22		

This document is issued to address requests for information or clarifications received from the bidders.

- 1. Q Upon review of the specifications this project has a construction duration of 24 weeks. Can this timeline be extended to 52 weeks? If one takes into account that the first 4 weeks are pretty well dedicated to the issuance of contracts, front end submittals and the shop drawing review process, one is only left with 5 months to deliver the building. Not to mention that this project is to be constructed in the upcoming winter months which will most definitely affect labour productivity most importantly the slab-on-grade construction, the second floor concrete deck, roofing and the exterior yard piping.
 - A NRC cannot extend the construction period to 52 weeks. Substantial completion of the building and buried services is required by March 31st. Paving and sodding may need to wait until spring 2017.
- 2. Q Will you be issuing a soils report as part of the tender documents?
 - A Soils reports were provided in Addendum No 1 and Addendum No. 3.
- 3. Q I found nothing in the documents regarding the Building Permit. Is the General Contractor responsible for this cost or will the Owner (NRC) be paying for this?
 - A According to article GC14 of the General Conditions, Section C of the specifications, the contractor shall carry the cost of a municipal building permit.
- 4. Q The geotechnical information does not cover the area of work which makes the pricing of rock removal impossible within the lump sum as the nearest geotech puts the rock at 1m depth but on site where we are to work bedrock appears on the surface, could a rate per m3 for rock removal be introduced?
 - A Two copies of a geotechnical report for an area close by were posted in error. The report that relates to the test pits shown on the civil drawings is attached to addendum no.

 3.
- 5. Q Structural FOUNDATION PLAN requires rock to be excavated to 1650 mm below floor slab. Architectural FOUNDATION PLAN states future slab area to be unexcavated Please define the extent of the floor area that is to have the rock excavated to 1650mm below slab. Also is it necessary for the rock to be removed from site or can it be used as shatter fill somewhere?
 - A The entire building footprint shall be excavated to 1650 mm below the finished ground floor slab. Excavated rock shall be removed from the site.
- 6. Q Please confirm that the USF of the typical wall strip footing is to be at 98.5 Geodetic level (100.6 1.65)
 - A The underside of the footings, except at pits and trenches, shall be at project elevation 98.350 according the structural drawing S01. This corresponds to geodetic elevation 98.95 m.
- 7. Q What is the purpose of the rip rap pad at the front of the building? Is there a drain to this?
 - A See the revised civil drawings attached to Addendum No. 4.
- 8. Q Does this building require perimeter drainage?
 - A perimeter foundation drain is specified on mechanical drawing M01and on the revised civil drawings attached to Addendum No. 4.

- 9. Q The Geotechnical Report in addendum 1 and 2 appears to be the wrong document please send the report that relates to the test pits on the drawing.
 - A Refer to the answer for question 4 above.
- 10. Q In this case the secondary containment system is designed much like that with a more common 'pad mount' transformer. That is to say, designed around the perimeter of the transfer vault. In rare instances the vault is designed to capture the escaping oil and we simply design a geomembrane liner inside the vault to protect the concrete. Before I design the system I wanted to confirm it will be the more traditional 'perimeter' design.
 - A You are required to provide perimeter design.
- 11. Q Please clarify the width of the insulated metal panels required. The specification notes 42" wide though the elevations show 36" wide. This is critical as there are specific joint locations that line up with the OH doors and windows and are drawn showing full width panels. As shown, if the panels are 42" we would have to cut half the panels to create the reveal joints which would create a lot of wasted material and the panels would not all be the same width. Please advise the intent of the design and the width of the panels.
 - A See KWC architectural Addendum No. 1 attached to NRC Addendum No. 4.
- 12. Q Is there a horizontal reveal joint between the panels at the low roof and the panels at the upper wall between grids C and D on 1/A05A?
 - A See KWC architectural Addendum No. 1 attached to NRC Addendum No 4.
- 13. Q Please confirm if space will be available across the street at Building M-37 for parking and materials laydown for this new project, or indicate if we are to provide our own on site area for parking etc.
 - A map showing contractor's parking is included in Addendum No. 4. The contractor shall use the off road space around the building site for materials laydown.
- 14. Q When tying into existing services (steam, electrical, plumbing), will shutdowns affect any of the existing buildings nearby?
 - A Steam service connections will require a shutdown affecting existing buildings. These shutdowns shall be coordinated with the Departmental representative well in advance.
- 15. Q Please confirm if any trees currently on site are to be saved?
 - A shown on the civil drawing CO4, an endangered butternut tree shall be protected during construction, and the large trees shown north of the building site shall be saved.
- 16. Q Would you please clarify and provide additional information on the steam trench noted on drawing S07:
 - a) Please provide specifications on the precast roof.
 - b) Please confirm if the walls are cast-in-place or precast. Typically precast trench covers are inclusive of the walls and ceiling.
 - c) Please provide dimensions (centres) of each precast section.
 - d) Please provide connections details from cast-in-place to precast member.
 - A Answers:
 - a) Precast concrete specifications are the same as for the cast-in-place concrete.
 - b) The trench walls are poured-in-place concrete.
 - c) Precast concrete roof sections typically are 1200 mm wide.

- d) The precast concrete roof slabs are supported on the cast-in place walls without a connection, similar to other locations on the NRC campus.
- 17. Q Please confirm if we are required to carry the costs of the building permit in our tender price.
 - A According to article GC14 of the General Conditions, Section C of the specifications, the contractor shall carry the cost of a municipal building permit.
- 18. Q According to the footing schedule noted on drawing S01 we are to provide an 'F3' type footing however, upon review of the structural drawings there appears to be no such type of footing. Is 'F3' required?
 - A The 'F3' footing is no longer required.
- 19. Q -According to the general notes of drawing S01 we are to refer to a geotechnical report prepared by Golder & Associates however, it appears that this document is missing from the specifications. Please provide the document.
 - A See the answer for question no. 2.
- 20. Q Dwg S01 First general note indicates rock is to be excavated to an elevation of 1650 mm below the finished floor elevation. Can you confirm if this is for the entire area of the building, or if it is for the location of the footings only? We understand deeper excavation is needed at the elevator pit, steam pit, and sump pit.
 - A See the answer for question no. 5.
- 21. Q Dwg S01 Should there be stepped footings between the F4 footing at grid C3, and the two adjoining F4 footings at grids C4 and B3?
 - A Stepped footings shall be provided in accordance with the General Notes on the revised structural drawing S01, which is attached to addendum no. 4.
- 22. Q 2/A05 middle overhead door is marked as FD or Future Door. Should this not be OD or overhead roll up door?
 - A See KWC architectural Addendum No. 1 attached to NRC Addendum No. 4.
- 23. Q W3 on A00 Does the rigid insulation go to 400 mm below grade as well as the fiber reinforced cement board panel, or does it go deeper. The sections do not show, and the spec says to refer to dwgs. Please clarify.
 - A See KWC architectural Addendum No. 1 attached to NRC Addendum No. 4.
- 24. Q Would you please provide the list of attendees at both mandatory site visits.
 - A The list is attached to addendum no 4.
- 25. Q According to notes 10 and 17 of drawing M01 we are to tie the weeping tile to sump pit 38SUP01 however upon review of the enlarged piping layout it appears that these two lines do not enter the pit. Please provide a revised piping layout drawing including details of these two lines entering the pit.
 - A The weeping tile lines shall piped into the storm water sump pit as directed on site.
- 26. Q Please issue a civil drawing indicating the location of the perforated subdrain as this item is typically provided by the civil contractor and not the mechanical contractor.
 - A This is addressed on the revised civil drawings attached to Addendum No. 4.
- 27. Q According to note 3.13 of drawing CO3 we are responsible to dispose of contaminated materials however, upon review of the geotechnical report there appears to be no presence of

contaminants. We assume that should contaminated soils be encountered that this item would be treated as additional to the original contract.

- A This is addressed on the revised civil drawings attached to Addendum No. 4.
- 28. Q Are we supposed to be providing the transformer, switchgear and cabling? It is not mentioned in the documents. Please clarify.
 - A None of these items are to be provided under this contract.
- 29. Q There is a note on the Structural drawings stating that "The Contractor shall excavate the rock to an elevation of 1650mm below the ground floor slab", however, the GeoTech report states that the footings can be constructed directly on the bedrock with the addition of insulation in order to meet the criteria of minimum frost protection. Which method are we to employ?
 - A The structural drawings govern.
- 30. Q Please confirm that the length of the retaining wall is 9 meters.
 - A As per drawing CO2 the retaining wall length is about 9 meters.
- 31. Q It would appear that wall height noted on the left hand side of the detail does not match the elevations provided on the grading drawing.
 - A This is addressed on the revised civil drawings attached to Addendum No. 4.
- 32. Q Please clarify the extent of the asphalt pathway removal (drawing C06).
 - A Removal to be as required to complete the work. It is indicated on plan CO4.
- 33. Q Please confirm if concrete curbing is required around the perimeter of the heavy duty asphalt paving.
 - A Curbing is not specified on the plans, therefore it is not planned.
- 34. Q Please provide a detail of the vertical reveal trim. It is recommended that the panel be continuous behind the joint to minimize air infiltration.
 - A See KWC architectural Addendum No. 1 attached to NRC Addendum No. 4.

End of tender Period Questions no. 1