

- 1.1 SITE ACCESS AND PARKING
- .1 Contractor's access to project site as well as parking facilities for equipment and workers will be by arrangement with the Harbour Authority. Site space is limited.
 - .2 The Contractor is advised that while parking facilities for his workers and subcontractors will be on property, such parking facilities may be remote from the actual site of the work. In any case, follow all instructions from the Harbour Authority in regards to parking facilities.
 - .3 Build and maintain any required temporary access roads or structures and provide snow removal and dust control during period of work.
 - .4 Maintain existing roads and parking areas at site, where used by Contractor, for duration of contract.
 - .1 Keep clean and free of mud and dirt by washing on a regular basis.
 - .2 Provide snow removal in areas located within construction site or enclosed by work.
 - .3 Make good and repair damage resulting from Contractor's use of existing roads, asphalted areas and lawns on site.
- 1.2 CONTRACTOR'S SITE OFFICE
- .1 Be responsible for and provide own site office including electricity, heat, lights and telephone. Locate site office as directed by Harbour Authority.
- 1.3 MATERIAL STORAGE
- .1 Material storage space on site is limited. Coordinate delivery to minimize storage period on site before being needed for incorporation into work. Material storage areas will be designated by the departmental representative.

- 1.4 SITE ENCLOSURES
- .1 Provide temporary fence to enclose work site.
 - .2 Erect plastic mesh fence constructed as follows:
 - .1 1200 mm height, constructed of high density polyethylene mesh fence fabric, orange in color.
 - .2 Supported by steel T-bar posts or other similar framing, of sufficient quantity, adequate spacing and set firmly in ground to secure fence against sags.
 - .3 Inspect fence regularly, repairing sags and damaged sections.
 - .4 Incorporate within fence one operable truck gate and one pedestrian gate.
 - .3 Make all gates lockable and provide keyed padlocks.
 - .4 Obtain Departmental Representative's approval beforehand of location and layout of all temporary fence enclosures.
 - .5 Provide illumination around the perimeter of the site enclosure to clearly mark its location at night.
 - .6 Provide warning signs affixed to all fenced areas, identifying those enclosed areas as "Construction Zones" with access restricted to only those persons so authorized by General Contractor.
 - .7 Ensure maximum safety and security to facility users during the course of work.

- 1.5 SANITARY FACILITIES AND WATER SUPPLY
- .1 Provide sanitary facilities and water supply for work force in accordance with governing regulations and ordinances.

- .2 Post notices and take such precautions as required by local health authorities. Keep area and premises in sanitary condition.

1.6 ENCLOSURE OF STRUCTURE

- .1 Design enclosures to withstand wind pressure and snow loading.

1.7 POWER

- .1 Power supply may be available and may be provided for construction use only. However, power costs used to run equipment in the winter months will be reimbursed to the Harbour Authority.
 - .1 Make arrangements for the use of such services through the Harbour Authority.
 - .2 The Harbour Authority will designate and approve each location of existing power source to which connections can be made to obtain temporary power service.
 - .3 Connect to existing power supply in accordance with Canadian Electrical Code.
- .2 Provide and maintain temporary lighting to conduct work. Ensure illumination level is not less than 162 lx in all locations.

1.8 CONSTRUCTION SIGN AND NOTICES

- .1 Contractor or subcontractor advertisement signboards are not permitted on site.
- .2 Safety and Instruction Signs and Notices:
 - .1 Signs and notices for safety and instruction shall be in both official languages or commonly understood graphic symbols conforming to CAN3-Z321-96(R2006).
- .3 Maintenance and Disposal of Site Signs:
 - .1 Maintain approved signs and notices in good condition for duration of project and dispose of offsite on completion of project or earlier if directed by Departmental

Structure #303	Temporary	01 50 00
Breakwater Extension	Facilities	Page 4
Skinners Pond, Prince Co., PE		
Project No. R.078386.001		August 2016

Representative.

1.9 REMOVAL OF TEMPORARY FACILITIES	.1	Remove temporary facilities from site when work is complete.
---	----	---