

This Addendum #04 is raised to modify solicitation EW699-170946/A as follows:

- A. Remove Work Scope - Remove Core Racks from demolition items and Partially Intact Cabin from Goodrock
- B. Add Work Scope – Move salvaged core racks at Kidney Pond

A) Remove Work Scope - Remove Core Racks from demolition items and Partially Intact Cabin from Goodrock

- 1) In the specifications Section 02 41 16 Clause 1.1.1.1:

DELETE TABLE AND REPLACE WITH:

Site	Structures Requiring Demolition	Drawing
Burnt Island	<u>Knutsen Camp Area:</u> Former Cabins (3) Dock	C-BUR-02
	<u>Shaft Area:</u> Drill Rig Headframe	C-BUR-03
	<u>Old Mill Area:</u> Mill Building and Pump House	C-BUR-06
Camlaren	<u>South Muir Island (Mine Area South and Mine Area North):</u> Dock Hoist Pad Mill Pad Wooden Culvert Outhouse Partially collapsed buildings (2) Potential Hollow Area	C-CAM-02, C-CAM-03
	<u>North Cabin Area:</u> Cabin Partially intact shack Stone Oven	C-CAM-04
Goodrock	<u>Camp Area</u>	C-GOO-02
	<u>Mill Area</u> Crusher Foundation (potentially will require demolition)	C-GOO-03
Kidney Pond	<u>1983 Camp:</u> Dock	C-KID-02
	<u>1939 Camp:</u> Cabin Wood Platform	C-KID-04
	<u>Portal Area:</u>	C-KID-06
	<u>Kidney Pond Area:</u>	C-KID-07
Treacy	<u>Mill Area:</u> Mill Remains	C-TRE-02
Try Me	<u>Main Camp:</u> Cabin and other wooden structures	C-TRY-02
West Bay	<u>South Area:</u> Dock Former Buildings (3)	C-WES-02

- 2) Remove References to Core Demolition:
DELETE: Note 9 on Drawing C-BUR-03
DELETE: Note 7 on Drawing C-KID-03
DELETE: "Core Shack, Drill Core, Cores Boxes" from Note 6 on Drawing C-KID-04

DELETE: Note 6 on Drawing C-KID-06 and reference Item C) 1) below

DELETE: Note 6 on Drawing C-KID-07:

DELETE: "Core Racks" from Note 7 on Drawing C-TRY-02:

DELETE: Note 6 on Drawing C-WES-02:

- 3) Remove References to Partially Intact Cabin from Goodrock:

DELETE: Note 7 on Drawing C-GOO-02

B) Add Work Scope – Move salvaged core racks at Kidney Pond

- 1) In the specifications Section 01 11 00:

ADD CLAUSE 1.3.1.13.4.5:

Move salvaged core (identified on Drawing C-KID-06 within KID_WR_01) to an area outside of the work area (to be determined onsite by the contractor). Contractor should expect a move of 150m. Cores will be salvaged in core boxes and placed on pallets to support movement.