



**RETURN BIDS TO:**  
**RETOURNER LES SOUMISSIONS À:**  
Bid Receiving Public Works and Government  
Services Canada/Réception des  
soumissions/Travaux publics et Services  
gouvernementaux Canada  
The Cambridge Building  
3 Queen Street/3, rue Queen  
Charlottetown  
Prince Edward Island  
C1A 4A2

**SOLICITATION AMENDMENT**  
**MODIFICATION DE L'INVITATION**

The referenced document is hereby revised; unless otherwise  
indicated, all other terms and conditions of the Solicitation  
remain the same.

Ce document est par la présente révisé; sauf indication contraire,  
les modalités de l'invitation demeurent les mêmes.

**Comments - Commentaires**

**Vendor/Firm Name and Address**  
**Raison sociale et adresse du**  
**fournisseur/de l'entrepreneur**

**Issuing Office - Bureau de distribution**  
Public Works and Government Services Canada  
The Cambridge Building  
3 Queen Street/3 rue, Queen  
PO Box 1268/CP 1268  
Charlottetown  
Prince Ed  
C1A 4A2

<b>Title - Sujet</b> Petroleum Tank Upgrade - Dalvay,PEI	
<b>Solicitation No. - N° de l'invitation</b> ED001-171477/A	<b>Amendment No. - N° modif.</b> 001
<b>Client Reference No. - N° de référence du client</b> R.080258.004	<b>Date</b> 2016-09-26
<b>GETS Reference No. - N° de référence de SEAG</b> PW-\$PWC-010-3964	
<b>File No. - N° de dossier</b> PWC-6-39099 (010)	<b>CCC No./N° CCC - FMS No./N° VME</b>
<b>Solicitation Closes - L'invitation prend fin</b> <b>at - à 02:00 PM</b> <b>on - le 2016-10-06</b>	
<b>F.O.B. - F.A.B.</b> <b>Plant-Usine:</b> <input type="checkbox"/> <b>Destination:</b> <input checked="" type="checkbox"/> <b>Other-Autre:</b> <input type="checkbox"/>	
<b>Address Enquiries to: - Adresser toutes questions à:</b> MacDonald, Anne (PWC) D.	<b>Buyer Id - Id de l'acheteur</b> pwc010
<b>Telephone No. - N° de téléphone</b> (902) 626-4949 ( )	<b>FAX No. - N° de FAX</b> (902) 566-7514
<b>Destination - of Goods, Services, and Construction:</b> <b>Destination - des biens, services et construction:</b>	

**Instructions: See Herein**

**Instructions: Voir aux présentes**

<b>Delivery Required - Livraison exigée</b>	<b>Delivery Offered - Livraison proposée</b>
<b>Vendor/Firm Name and Address</b> <b>Raison sociale et adresse du fournisseur/de l'entrepreneur</b>	
<b>Telephone No. - N° de téléphone</b> <b>Facsimile No. - N° de télécopieur</b>	
<b>Name and title of person authorized to sign on behalf of Vendor/Firm</b> <b>(type or print)</b> <b>Nom et titre de la personne autorisée à signer au nom du fournisseur/</b> <b>de l'entrepreneur (taper ou écrire en caractères d'imprimerie)</b>	
<b>Signature</b>	<b>Date</b>

**Addendum # 1  
September 26, 2016  
ED001-171477**

**THE FOLLOWING AMENDMENT TO THE TENDER DOCUMENTS IS EFFECTIVE IMMEDIATELY. THIS ADDENDA SHALL FORM PART OF THE CONTRACT DOCUMENTS.**

**1. Drawing:**

**1. Re-issuing a revised drawing**

**Delete** Drawing G101 – Proposed Site Plan

**Replace** with Drawing G101 – Proposed Site Plan – Revision 6

- a. The extents of the existing asphalt pavement in the area of the proposed new petroleum storage tank system have changed. The Contractor shall sawcut and remove existing asphalt for new concrete fuel-dispensing island, apron, tank pad and electrical trench. Contractor shall supply and install new asphalt patch pavement around new concrete fuel-dispensing island, apron, tank pad and electrical trench as illustrated on Drawing G101, Proposed Site Plan, Revision 6.

New asphalt shall consist of 60mm base mix a and 40mm seal mix b as per Prince Edward Island Department of Transportation, Infrastructure and Energy specifications.

Drawing G101 – Proposed Site Plan – Revision 6 – Attached.

**2. Specification**

Specification section 01 10 10

**Delete** clause 1.1.2 paragraph 5

"Contractor shall sawcut and remove existing asphalt for new concrete fuel-dispensing apron. Contractor shall supply and install new asphalt patch pavement around new apron. New asphalt shall consist of 60mm base mix A and 40mm seal Mix B as per Prince Edward Island Department of Transportation, Infrastructure and Energy specifications."

**Replace with**

"Contractor shall sawcut and remove existing asphalt for new concrete fuel-dispensing island, apron, tank pad and electrical trench. Contractor shall supply and install new asphalt patch pavement around new concrete fuel-dispensing island, apron, tank pad and electrical trench. New asphalt shall consist of 60mm base mix A and 40mm seal Mix B as per Prince Edward Island Department of Transportation, Infrastructure and Energy specifications."



revision	description	date
1	ISSUED FOR 99% REVIEW	03/17/2016
2	ISSUED FOR REVIEW	07/16/2016
3	REVISED TRAFFIC PROTECTION	09/02/2016
4	REVISED ASPHALT	02/02/2016
5	ISSUED FOR TENDER	05/29/2016
6	ISSUED FOR ADDENDUM #1	09/02/2016

**PETROLEUM STORAGE TANK SYSTEM UPGRADE PEI NATIONAL PARK DALVAY MAINTENANCE COMPOUND**

**PROPOSED SITE PLAN**

designer	E. FINNAMORE
date	MARCH 31, 2016
drawn	M. BEMSEY
date	MARCH 31, 2016
approved	S. CASHIN
date	MARCH 31, 2016
checked	M. BEMSEY
date	MARCH 31, 2016

Project number: R.080258.004  
 Project name: Administration de Parcs Canada  
 Project location: PEI National Park Dalvay Maintenance Compound  
 Drawing no.: G101  
 Rev. de dessin: 01

