

Revision/	Description/Description	Date/Date
0	ISSUED FOR TENDER	Sept. 12, 16

Client/client

Public Works and Government Services Canada

100 - 167 Lombard Avenue
Winnipeg, Manitoba

Project title/Titre du projet
Lower Fort Garry (LFG)
National Historic Site, Manitoba

HERITAGE BUILDING
RECAPITALIZATION

Approved by/Approuvé par
HCC

Designed by/Concept par
PL

Drawn by/Dessiné par
RD

PWGSC Project Manager/Administrateur de Projets TPSGC
CHRISTINA KOVACS

PWGSC, Architectural and Engineering Resources Manager/
Ressources Architectural et de Directeur d'ingénierie, TPSGC

Client/client
PARKS CANADA

Drawing title/Titre du dessin

BIG HOUSE

BASEMENT AND MAIN FLOOR

EXISTING/DEMOLITION POWER


AND LIFE SAFETY SYSTEMS PLAN

Project No./No. du projet
R.075212.001


Sheet/Feuille
E4

Revision no./La Révision
no.
0

OF 24



1 BIG HOUSE - BASEMENT EXISTING/DEMOLITION POWER AND LIFE SAFETY SYSTEMS PLAN
E4 1:100



2 BIG HOUSE - MAIN FLOOR EXISTING/DEMOLITION POWER AND LIFE SAFETY SYSTEMS PLAN
E4 1:100

GENERAL NOTES:

- ALL ITEMS SHOWN DASHED WITH AN "E" ARE EXISTING AND ARE TO REMAIN. ITEMS SHOWN DASHED WITH A "D" ARE TO BE DISCONNECTED AND REMOVED AND HAVE ALL ASSOCIATED WIRE AND CONDUIT REMOVED BACK TO ASSOCIATED PANEL. WHERE EXISTING CONDUIT CANNOT BE REMOVED WITHOUT DAMAGING SURFACES, RENDER CONDUIT PERMANENTLY UNUSABLE AND ABANDON.
- WIRE AND CONDUIT SERVING DEVICES REQUIRED TO REMAIN IN USE SHALL BE RE-ROUTED AND DIVERTED AS REQUIRED TO MAINTAIN OPERATION. EXTEND, RE-ROUTE, RE-WIRE AND RE-CONNECT AS REQUIRED. CONFIRM EXISTING ON SITE.
- REPORT ANY DISCREPANCIES BETWEEN THE CONTRACT DOCUMENTS AND SITE OBSERVATIONS TO DEPARTMENTAL REPRESENTATIVE.
- REMOVE ALL EXISTING ELECTRICAL DEVICES LOCATED ON WALLS OR PORTIONS OF THE BUILDING BEING DEMOLISHED OR MODIFIED. MAINTAIN INTEGRITY OF ALL EXISTING ELECTRICAL SYSTEMS IN AREAS NOT INCLUDED IN THIS PROJECT AND IN PARTS OF THE BUILDING WITHIN RENOVATION THAT ARE NOT SUBJECTED TO ANY DEMOLITION WORK.
- REFER TO SYMBOL SCHEDULE FOR ELECTRICAL SYMBOLS AND LETTER DESIGNATIONS.
- ALL EXISTING DEVICES ON WALLS, FLOORS OR CEILING NOT BEING AFFECTED BY RENOVATION ARE TO REMAIN.
- DISCONNECT AND REMOVE ALL EXISTING RECEPTACLES ALONG WITH ASSOCIATED DEVICE BOX WIRE AND CONDUIT BACK TO PANEL.
- ALL MAIN FLOOR ROOMS WITH THE EXCEPTION OF ROOM L11, 11 AND 12 CONTAIN EXISTING CEILING RADIANT HEATING WITHIN THE PLASTER. DISCONNECT ALL EXISTING AND REMOVE ALL ASSOCIATED CONDUIT, WIRING, BOXES ETC. BACK TO PANEL. CONFIRM EXISTING ON SITE.
- EXISTING WIRING TO RADIANT CEILING PANEL HEATERS TO REMAIN, EXTEND, RE-WIRE AND RECONNECT AS REQUIRED.
- PATCH ALL EXISTING SURFACES DAMAGED BY THE REMOVAL OF EQUIPMENT TO MATCH EXISTING CONDITION. REFER TO ARCHITECTURAL.