

APEGM
Certificate of Authorization
HDK Consulting Incorporated
No. 5539 Date: 04/30/2017

Revision/Revision	Description/Description	Date/Date
0	ISSUED FOR TENDER	Sept. 12, 16

Client/client
Public Works and Government Services Canada
100 - 167 Lombard Avenue
Winnipeg, Manitoba

Project title/Titre du projet
**Lower Fort Garry (LFG)
National Historic Site, Manitoba**

**HERITAGE BUILDING
RECAPITALIZATION**

Approved by/Approve par
HCC
Designed by/Concept par
PL

Drawn by/Dessine par
RD
PWGSC Project Manager/Administrateur de Projets TPSCG
CHRISTINA KOVACS

PWGSC, Architectural and Engineering Resources Manager/
Ressources Architectural et de Directeur d'ingénierie, TPSCG


Client/client
PARKS CANADA

Drawing title/Titre du dessin
**BIG HOUSE -
BASEMENT AND MAIN FLOOR
NEW POWER PLAN**

Project No./No. du projet R.075212.001	Sheet/Fauille E6 OF 24	Revision no./ La Révision no. 0
---	------------------------------	--

NOTES:

- ALL POWER WIRING TO BE CONCEALED BEHIND WALLS, BENEATH FLOORS AND ABOVE CEILING.
- EXACT LOCATIONS OF ALL RECEPTACLES TO BE CONFIRMED ON SITE WITH PARKS CANADA PRIOR TO ROUGH-IN. ALLOW FOR UP TO 3.0m RELOCATION OF ANY DEVICE AT NO ADDITIONAL COST. PROVIDED ROUGH-IN OF DEVICE HAS NOT BEEN COMPLETED.
- WIRE AND CONNECT NEW IN-FLOOR DOOR OPERATORS. PUSH BUTTONS TO BE WIRELESS TYPE.
- EXISTING WIRING PATHWAYS TO BE RE-USED FOR NEW WIRING, PATCH ALL PATHWAYS TO MATCH EXISTING. REFER TO ARCHITECTURAL.
- NEW WIRING FOR RECEPTACLES TO FOLLOW SAME PATH AS EXISTING. CONFIRM EXISTING ON SITE.
- ALL WIRING BENEATH BASEMENT FLOOR TO BE WITH LIQUID TIGHT FLEX.
- ALL NEW PENETRATIONS THRU EXISTING STONE WALL TO BE THRU MORTAR JOINTS. COORDINATE ALL WORK WITH PARKS CANADA.
- NO NEW PENETRATIONS THRU EXISTING STRUCTURE SHALL BE PERMITTED.



1 BIG HOUSE - BASEMENT NEW POWER PLAN
E6 1:100



2 BIG HOUSE - MAIN FLOOR NEW POWER PLAN
E6 1:100