

0	ISSUED FOR TENDER	Sept. 12, 16
---	-------------------	--------------

Revision/	Description/Description	Date/Date

Client/client
Public Works and Government Services Canada
100 - 167 Lombard Avenue
Winnipeg, Manitoba

Project title/Titre du projet
**Lower Fort Garry (LFG)
National Historic Site, Manitoba**

**HERITAGE BUILDING
RECAPITALIZATION**

Approved by/Approve par
HCC
Designed by/Concept par
PL


Drawn by/Dessine par
RD
PWSC Project Manager/Administrateur de Projets TPSC
CHRISTINA KOVACS

PWSC, Architectural and Engineering Resources Manager/
Ressources Architectural et de Directeur d'ingénierie, TPSC
Client/client
PARKS CANADA


Drawing title/Titre du dessin

**FURLOFT -
BASEMENT AND MAIN FLOOR
EXISTING/DEMOLITION
ELECTRICAL PLAN**

Project No./No. du projet R.075212.001	Sheet/Fauille E10 OF 24	Revision no./ La Révision no. 0
--	--------------------------------------	--



1 FURLOFT - BASEMENT EXISTING/DEMOLITION ELECTRICAL PLAN
E10 1:50



2 FURLOFT - MAIN FLOOR EXISTING/DEMOLITION ELECTRICAL PLAN
E10 1:50

GENERAL NOTES:

1. MAINTAIN THE INTEGRITY OF ALL EXISTING SYSTEMS REQUIRED TO REMAIN OPERATIONAL, IDENTIFY ALL CIRCUIT BREAKERS, WIRING, JUNCTION BOXES AND DEVICES PRIOR TO PROCEEDING WITH WORK. CONTACT DEPARTMENTAL REPRESENTATIVE IF UNSURE BEFORE SHUTDOWNS, DEMOLITION, OR RELOCATION OF ANY DEVICES.
2. ALL ITEMS SHOWN DASHED WITH AN 'E' ARE EXISTING AND ARE TO REMAIN. ITEMS SHOWN DASHED WITH A 'D' ARE TO BE DISCONNECTED AND REMOVED AND HAVE ALL ASSOCIATED WIRE AND CONDUIT REMOVED BACK TO PANEL. WHERE EXISTING CONDUIT CANNOT BE REMOVED WITHOUT DAMAGING SURFACES, RENDER CONDUIT PERMANENTLY UNUSABLE AND ABANDON.
3. WIRE AND CONDUIT SERVING DEVICES REQUIRED TO REMAIN IN USE SHALL BE RE-ROUTED AND DIVERTED AS REQUIRED TO MAINTAIN OPERATION. EXTEND, RE-ROUTE, RE-WIRE AND RE-CONNECT AS REQUIRED. CONFIRM EXISTING ON SITE.
4. REPORT ANY DISCREPANCIES BETWEEN THE CONTRACT DOCUMENTS AND SITE OBSERVATIONS TO DEPARTMENTAL REPRESENTATIVE.
5. REMOVE ALL EXISTING ELECTRICAL DEVICES LOCATED ON WALLS OR PORTIONS OF THE BUILDING BEING DEMOLISHED OR MODIFIED. MAINTAIN INTEGRITY OF ALL EXISTING ELECTRICAL SYSTEMS IN AREAS NOT INCLUDED IN THIS PROJECT AND IN PARTS OF THE BUILDING WITHIN RENOVATION THAT ARE NOT SUBJECTED TO ANY DEMOLITION WORK.
6. REFER TO SYMBOL SCHEDULE FOR ELECTRICAL SYMBOLS AND LETTER DESIGNATIONS.
7. ALL EXISTING DEVICES ON WALLS, FLOORS OR CEILING NOT BEING AFFECTED BY RENOVATION ARE TO REMAIN.
8. SYSTEMS AND DEVICES IN AREAS OF LIMITED SCOPE OF WORK AREAS TO REMAIN OPERATIONAL. PROVIDE ALL MODIFICATIONS TO ACCOMMODATE SCOPE OF WORK.
9. DISCONNECT AND REMOVE ALL EXISTING RECEPTACLES AND HEAT DETECTORS ALONG WITH ASSOCIATED DEVICE BOX, WIRE AND CONDUIT BACK TO SOURCE.
10. PATCH ALL EXISTING SURFACES DAMAGED BY THE REMOVAL OF EQUIPMENT TO MATCH EXISTING CONDITION.
11. ELECTRICAL CONTRACTOR TO DISCONNECT AND REMOVE ALL EXISTING DISTRIBUTION EQUIPMENT WITHIN THE BIG HOUSE ALONG WITH ASSOCIATED WIRE AND CONDUIT.