

APEGM
Certificate of Authorization
HDK Consulting Incorporated
No. 5539 Date: 04/30/2017

0	ISSUED FOR TENDER	Sept. 12, 16
Revision/	Description/Description	Date/Date

Client/client

Public Works and Government Services Canada
100 - 167 Lombard Avenue
Winnipeg, Manitoba

Project title/Titre du projet
**Lower Fort Garry (LFG)
National Historic Site, Manitoba**

**HERITAGE BUILDING
RECAPITALIZATION**

Approved by/Approve par
HCC

Designed by/Concept par
PL

Drawn by/Dessine par
RD

PWSC Project Manager/Administrateur de Projets TPSC
CHRISTINA KOVACS

PWSC, Architectural and Engineering Resources Manager/
Ressources Architectural et de Directeur d'ingénierie, TPSC

Client/client
PARKS CANADA



Drawing title/Titre du dessin

**MEN'S HOUSE -
MAIN FLOOR AND ATTIC SPACE
EXISTING/DEMOLITION
ELECTRICAL PLAN**

Project No./No. du projet
R.075212.001

Sheet/Fauille
E14
OF 24

Revision no./
La Révision
no.
0



1 MEN'S HOUSE - MAIN FLOOR EXISTING/DEMOLITION ELECTRICAL PLAN
E14 1:50

2 MEN'S HOUSE - ATTIC SPACE EXISTING/DEMOLITION ELECTRICAL PLAN
E14 1:50

GENERAL NOTES:

1. MAINTAIN THE INTEGRITY OF ALL EXISTING SYSTEMS REQUIRED TO REMAIN OPERATIONAL. IDENTIFY ALL CIRCUIT BREAKERS, WIRING, JUNCTION BOXES AND DEVICES PRIOR TO PROCEEDING WITH WORK. CONTACT DEPARTMENTAL REPRESENTATIVE IF UNSURE BEFORE SHUTDOWNS, DEMOLITION, OR RELOCATION OF ANY DEVICES.
2. ALL ITEMS SHOWN DASHED WITH AN 'E' ARE EXISTING AND ARE TO REMAIN. ITEMS SHOWN DASHED WITH A 'D' ARE TO BE DISCONNECTED AND REMOVED AND HAVE ALL ASSOCIATED WIRE AND CONDUIT REMOVED BACK TO PANEL. WHERE EXISTING CONDUIT CANNOT BE REMOVED WITHOUT DAMAGING SURFACES, RENDER CONDUIT PERMANENTLY UNUSABLE AND ABANDON.
3. WIRE AND CONDUIT SERVING DEVICES REQUIRED TO REMAIN IN USE SHALL BE RE-ROUTED AND DIVERTED AS REQUIRED TO MAINTAIN OPERATION. EXTEND, RE-ROUTE, RE-WIRE AND RE-CONNECT AS REQUIRED. CONFIRM EXISTING ON SITE.
4. REPORT ANY DISCREPANCIES BETWEEN THE CONTRACT DOCUMENTS AND SITE OBSERVATIONS TO DEPARTMENTAL REPRESENTATIVE.
5. REMOVE ALL EXISTING ELECTRICAL LOCATED ON WALLS OR PORTIONS OF THE BUILDING BEING DEMOLISHED OR MODIFIED. MAINTAIN INTEGRITY OF ALL EXISTING ELECTRICAL SYSTEMS IN AREAS NOT INCLUDED IN THIS PROJECT AND IN PARTS OF THE BUILDING WITHIN RENOVATION THAT ARE NOT SUBJECT TO ANY DEMOLITION WORK.
6. REFER TO SYMBOL SCHEDULE FOR ELECTRICAL SYMBOLS AND LETTER DESIGNATIONS.
7. ALL EXISTING DEVICES ON WALLS, FLOORS OR CEILING NOT BEING AFFECTED BY RENOVATION ARE TO REMAIN.
8. SYSTEMS AND DEVICES IN AREAS OF LIMITED SCOPE OF WORK AREAS TO REMAIN OPERATIONAL. PROVIDE ALL MODIFICATIONS TO ACCOMMODATE SCOPE OF WORK.
9. DISCONNECT AND REMOVE ALL EXISTING RECEPTACLES ALONG WITH ASSOCIATED DEVICE BOX, WIRE AND CONDUIT BACK TO SOURCE.
10. COORDINATE FINAL LOCATION OF ALL DEVICES ON SITE WITH PARKS CANADA PRIOR TO ROUGH-IN.
11. PATCH ALL EXISTING SURFACES DAMAGED BY THE REMOVAL OF EQUIPMENT TO MATCH EXISTING CONDITION.