

1.1 SITE ACCESS AND PARKING

- .1 The Departmental Representative will designate Contractor's access to project site, as well as parking facilities for equipment. Contractor's personnel will have to find alternative off-site parking throughout the entire construction period.
- .2 Vehicular traffic and staging areas will be restricted to present-day roadways and disturbed areas.
- .3 Maintain existing roads and parking areas at site, where used by Contractor, for duration of contract.
 - .1 Keep clean and free of mud and dirt by washing on a regular basis.
 - .2 Provide snow removal in areas located within construction site or enclosed by work.
 - .3 Make good and repair damage resulting from Contractor's use of existing roads, asphalted areas and lawns on site.

1.2 BUILDING ACCESS

- .1 Use only access doors, and circulation routes and elevators within building as designated by Departmental Representative to access interior work.

1.3 CONTRACTOR'S SITE OFFICE

- .1 Be responsible for and provide own site office, if required, including electricity, heat, lights and telephone. Locate site office as directed by Departmental Representative.

1.4 MATERIAL STORAGE

- .1 Area for site storage trailers will be made available to the left of the building (when facing the building from parking lot).

1.5 SITE ENCLOSURES

- .1 Provide temporary fence to enclose various construction areas of work site.
- .2 Erect wood fence to 2400 mm height, constructed as follows:
 - .1 Use 38 x 89 mm construction grade framing spaced at maximum 600 mm oc covered with 13 mm thick exterior grade fir plywood on public side and adequately braced.
 - .2 Apply plywood panels vertically with flush and butted joints.
 - .3 Provide one truck gate and at least one pedestrian door as directed by Departmental Representative.
 - .4 Paint public side of site enclosure in selected colours with one coat primer to CGSB 1-GP-55e and one coat exterior paint to CGSB 1-GP-59M.
 - .5 Maintain public side of enclosure in clean condition.
- .3 Make all gates lockable and provide keyed padlocks.
- .4 Obtain Departmental Representative's approval beforehand of location and layout of all temporary fence enclosures.

- .5 Provide battery powered lanterns around the perimeter of the site enclosure to clearly mark its location at night.
- .6 Provide warning signs affixed to all fenced areas, identifying those enclosed areas as "Construction Zones" with access restricted to only those persons so authorized by General Contractor.
- .7 Do not construe fencing as an acceptable replacement for pedestrian walkway and hoarding requirements specified below.

1.6 PEDESTRIAN WALKWAYS AND HOARDING

- .1 Ensure maximum safety and security to facility users during the course of work.
- .2 Be responsible for and provide temporary 2.4 metre high plywood construction hoarding when work is adjacent to exterior sidewalks and circulation routes used by facility employees and public.
- .3 Maintain access and egress to building entrances and fire exits designated by Departmental Representative to remain in use. Provide enclosed walkways when work is adjacent to such doors as follows:
 - .1 Erect wooden pedestrian walkway complete with roof and side covers.
 - .2 Install walkways as soon as work is in the vicinity of entrance and exit doors and poses a potential danger to facility users.
 - .3 Construct to approximate size of 2.0 metre wide x 2.1 metre high x length as required to fully clear danger zone.
 - .4 Provide signage and lighting.
 - .5 Submit details of walkway size, location, layout and construction to Departmental Representative beforehand and obtain approval.
- .4 Adequately frame and brace hoarding and walkways to resist wind, and other weather or site conditions.
- .5 Erect such protective devices during Facility's non-operational off hour periods.
- .6 Obtain Departmental Representative's concurrence prior to removal of hoarding and walkways.

1.7 INTERIOR HOARDING

- .1 Erect hoarding inside building to isolate construction areas and protect occupants for duration of work.
- .2 Construct hoarding as follows:
 - .1 Height: to underside of floor or roof above.
 - .2 Framing type: wood studs spaced at 600 oc
 - .3 Covering: 12 mm thick plywood sheathing, finished and painted as follows: to match adjacent.
 - .4 Sealed to abutting surfaces and insulated.
 - .5 Access Doors: 1 wood pedestrian door soundsealed, dust tight and lockable.

1.8 INTERIOR DUST CONTROL AND DUST BARRIERS

- .1 Control creation and spread of dust and dirt to building interior and in particular to areas within premises still under use by occupants.
- .2 Develop and implement a dust control plan, addressing effective measures to carry out work with least amount of dust being created and propagated.
 - .1 Carefully evaluate the type of work to be undertaken and the physical layout of each work area on site.
 - .2 Provide specifically tailored strategy for each work area.
 - .3 Pre-determine location and placement of dust barriers to confine resulting dust to immediate work area.
 - .4 Inform Departmental Representative of the proposed dust control measures to be followed at each work area and for each major dust generating activities. Obtain Departmental Representative's approval before proceeding with work.
- .3 Dust control plan to incorporate as a minimum the following dust protection and cleaning requirements:
 - .1 Erect dustproof partitions completely around work area to fully isolate construction from other parts of the building.
 - .2 Construct dust partitions as follows:
 - .1 Use 10 mm polyethylene installed and sealed tightly to abutting walls, ceilings and floor with continuous duct tape along all edges and seams. Support in position with 38 x 89 wood framing at 400 mm o.c. Locate seams only at framing members and overlap sheeting by minimum of 150 mm.
 - .3 Provide additional dust barriers, placed tightly to underside of the floor/roof deck above, in locations where existing walls are used as part of the dust barrier system but simply terminate at the finished ceiling level resulting in an open space above, or other similar condition, permitting dust to migrate beyond the construction areas.
 - .4 Make all dust barriers airtight, effectively blocking and stopping all dust migration.
 - .5 Inspect dust barriers at various intervals during each work shift. Immediately fix tears, unsealed edges and maintain barriers effectively sealed for the entire work duration.
 - .6 Shut down existing ventilation system feeding construction space, or disconnect and seal-off supply and return air ducts to stop dust from contaminating other areas.
 - .7 Immediately clean areas in use by occupants and public contaminated by work.
 - .8 Vacuum carpets, wash floors and walls. Remove accumulated dust from all surfaces. Clean and remove smears, scuffs and marks.
- .4 Meager attempts at controlling dust will not be tolerated. Failure to provide effective dust control during work and to perform satisfactory cleaning thereafter will result in Departmental Representative to proceed and obtain a separate cleaning service agency to perform cleaning to tenant's satisfaction with cost for such services being charged against this Contract in the form of financial holdbacks.

- .5 Obtain Departmental Representative's approval before erecting any dust partitions simply to underside of finish ceiling.
- .6 Construction of dust barriers, enclosures and placement of temporary protective devices to be performed during Facility non-operational off-hour periods.

1.9 SANITARY FACILITIES

- .1 Provide sanitary facilities for work force in accordance with governing regulations and ordinances.
- .2 Post notices and take such precautions as required by local health authorities. Keep area and premises in sanitary condition.
- .3 Sanitary facilities are available at the site and may be used by Contractor's work force. Make arrangements for the use of such facilities through the Departmental Representative.
- .4 When permanent water and drain connections are completed, provide temporary water closets and urinals complete with temporary enclosures, inside building. Permanent facilities may be used on approval of Departmental Representative.

1.10 ENCLOSURE OF STRUCTURE

- .1 Provide temporary weathertight enclosures and protection for exterior openings until permanently enclosed.
- .2 Provide weathertight and heated enclosures to conduct exterior work during winter and other inclement weather conditions. Erect to allow accessibility for installation of materials and working inside of enclosure.
- .3 Design enclosures to withstand wind pressure and snow loading.

1.11 POWER

- .1 Power supply is available and will be provided for construction usage at no cost.
 - .1 Make arrangements for the use of such services through the Departmental Representative.
 - .2 Departmental Representative will designate and approve each location of existing power source to which connections can be made to obtain temporary power service.
 - .3 Connect to existing power supply in accordance with CSA C22.1-15, Canadian Electrical Code.
- .2 Provide and pay all costs to supply and install temporary cabling, panelboards, switching devices and other equipment as required to connect into power source, provide adequate ground fault protection and extend power supply from existing source to work areas. Perform work and make all connections in accordance with the CSA C22.1-15 Canadian Electrical Code, in compliance with the federal and provincial Occupational Health and Safety Regulations as specified in section 01 35 30 and to lockout requirements specified in section 01 35 25.
- .3 Provide and maintain temporary lighting to conduct work. Ensure illumination level is not less than 162 lx in all locations.

- .4 Electrical power and lighting systems installed under this Contract can be used for construction requirements provided that guarantees are not affected thereby. Make good damage. Replace lamps which have been used over period of 3 months.

1.12 WATER SUPPLY

- .1 Water supply is available in existing building and will be provided for construction usage at no cost. Make arrangements for the use and transportation of such services to work area through the Departmental Representative.

1.13 SCAFFOLDING

- .1 Design, construct and maintain scaffolding in rigid, secure and safe manner in accordance with CSA Z797-09, Code of Practice for Access Scaffold.
- .2 Erect scaffolding independent of walls. Remove when no longer required.

1.14 HEATING AND VENTILATING

- .1 Supply, install and pay for costs of temporary heat and ventilation used during construction, including costs of installation, fuel, operation, maintenance and removal of equipment. Use of direct-fired heaters discharging waste products into work areas will not be permitted.
- .2 Provide temporary heat and ventilation in enclosed areas as required to:
 - .1 Facilitate progress of work.
 - .2 Protect work and products against dampness and cold.
 - .3 Prevent moisture condensation on surfaces.
 - .4 Provide ambient temperatures and humidity levels for storage, installation and curing of materials.
 - .5 Provide adequate ventilation to meet health regulations for safe working environment.
- .3 Maintain minimum temperature of 10 degrees C, or higher where specified, as soon as finishing work is commenced and maintain until acceptance of structure by Departmental Representative.
 - .1 Maintain ambient temperature and humidity levels as required for comfort of office personnel.
- .4 Ventilating:
 - .1 Prevent accumulations of dust, fumes, mists, vapours or gases in areas occupied during construction.
 - .2 Provide local exhaust ventilation to prevent harmful accumulation of hazardous substances into atmosphere of occupied areas.
 - .3 Dispose of exhaust materials in manner that will not result in harmful exposure to persons.
 - .4 Ventilate storage spaces containing hazardous or volatile materials.
 - .5 Ventilate temporary sanitary facilities.
 - .6 Continue operation of ventilation and exhaust system for time after cessation of work process to assure removal of harmful contaminants.
- .5 Maintain strict supervision of operation of temporary heating and ventilating equipment to:

- .1 Conform with applicable codes and standards.
- .2 Enforce safe practices.
- .3 Prevent abuse of services.
- .4 Prevent damage to finishes.
- .5 Vent direct-fired combustion units to outside.
- .6 Submit bid assuming existing or new equipment and systems will not be used for temporary heating and ventilating.
- .7 Upon acceptance of bid, Departmental Representative may permit use of permanent system providing agreement can be reached on:
 - .1 Conditions of use, special equipment, protection and maintenance.
 - .2 Saving on Contract price.
 - .3 Provisions relating to warranties on equipment.

1.15 CONSTRUCTION SIGN AND NOTICES

- .1 Upon request by Departmental Representative, erect a self supporting project sign in location indicated.
- .2 Departmental Representative will provide a vinyl sign facing for installation by Contractor on sign framework. Sign frame to be plywood face of approximately 1200 x 2400 mm in size complete with required wood framing at 400 mm o.c and support posts.
- .3 Install sign plumb and level in neat wood framework and securely anchor in ground by posts to withstand wind pressure of 160 km/h.
- .4 Contractor or subcontractor advertisement signboards are not permitted on site.
- .5 Safety and Instruction Signs and Notices:
 - .1 Signs and notices for safety and instruction shall be in both official languages or commonly understood graphic symbols conforming to CAN/CSA-Z321-96(R2006).
- .6 Maintenance and Disposal of Site Signs:
 - .1 Maintain approved signs and notices in good condition for duration of project and dispose of off site on completion of project or earlier if directed by Departmental Representative.

1.16 REMOVAL OF TEMPORARY FACILITIES

- .1 Remove temporary facilities from site when directed by Departmental Representative.

END OF SECTION