

---

**CANADA MORTGAGE AND HOUSING CORPORATION**

**ITT – Exterior Lighting Upgrade – Phase 2**

**AMENDMENT #4**

*This amendment forms part of the Contract Documents and is to be read, interpreted and coordinated with all other parts. The cost of all work contained herein shall be included in the Contract Sum. The following revisions supersede the information contained in the original drawings and specifications issued for tender for the above named project to the extent referenced and shall become part hereof.*

The following specifications are to be included in Part 4 – Project Specifications and Drawings

1. 1¼ Rigid Conduit to be changed to ¾ Rigid Conduit.
2. Do not tie into photocell circuits inside parkades
3. Install 1 more Spot Light type "GD" on exterior of Bldg. 36 southwest corner (dwg. E02 and E06). To line up with display cabinets (3). Tie these spot lights into a photocell.
4. All lintel lights to be pendant mount; model number to be determined
5. We do not require galvanized boxes, standard boxes are acceptable