

PART 1 - GENERAL

- | | | |
|--------------------------------|----|--|
| <u>1.1 Description of Work</u> | | This Section includes but is not limited to the following: |
| | .1 | All sitework, demolition and removals as required to complete the work. All items to be verified by a site visit prior to submission of a tender. All available plans of the existing structure are available for viewing at PWGSC office, 3 Queen Street, Charlottetown, P.E. |
| <u>1.2 Related Work</u> | .1 | Refer to other specification sections for related information. |
| | .2 | Refer to Section 01 33 00 for Submittal Procedures. |
| <u>1.3 Submissions</u> | .1 | Methodology:
.1 When requested, provide methodology for carrying out the work. |
| | .2 | Provide submissions in accordance with Section 01 33 00. |
| <u>1.4 Protection</u> | .1 | Prevent movement, settlement or damage of adjacent structures. Provided bracing and shoring as required. In event of damage, immediately replace such items or make repairs to approval of a Departmental Representative and at no additional cost. |
| | .2 | Prevent debris from entering harbour and creating navigational hazards. |
| | .3 | All damage to existing structures, roadways, pipelines, electrical systems not specified for removal to be repaired |

at the Contractor's cost to the satisfaction of the Departmental Representative.

- | | | |
|-----------------------------------|----|---|
| <u>1.5 Measurement of Payment</u> | .1 | Demolition and removals will be measured in accordance with Section 01 10 10 and shall include demolitions, selective demolitions, removals, transportation, disposal, environmental protective measures, and site cleanup. |
|-----------------------------------|----|---|

PART 2 - PRODUCTS Not applicable.

PART 3 - EXECUTION

- | | | |
|------------------------|----|--|
| <u>3.1 Preparation</u> | .1 | Inspect site and verify with a Departmental Representative items designated for removal and items to be preserved. |
| | .2 | Do not disturb adjacent structures designated to remain in place. |

- | | | |
|--------------------|----|---|
| <u>3.2 Removal</u> | .1 | Remove items indicated. |
| | .2 | Do not disturb adjacent structures designated to remain in place. |
| | .3 | At end of each day's work, leave work in safe condition so no part is in danger of toppling or failing. |
| | .4 | Excavate to extents and dimensions indicated on the drawings. |

- | | | |
|---------------------------------|----|---|
| <u>3.3 Disposal of Material</u> | .1 | Disposal of materials not designated for salvage or re-use in work, will be the |
|---------------------------------|----|---|

contractor's responsibility, and must be disposed of off-site.

- .2 The material to be disposed is to be transported and disposed of in an environmentally acceptable manner to the satisfaction of a Departmental Representative, and in accordance with any local, Municipal, Provincial and Federal restrictions and regulations.
- .3 All creosote materials to be disposed of at land fill located in Wellington, PE or approved equivalent.

3.4 Restoration

- .1 Upon completion of work, remove debris, trim surfaces and leave work site clean.
- .2 Reinstate areas and existing works outside areas of demolition to conditions that existed prior to commencement of work. Match condition of adjacent, undisturbed areas.