

---

TEMPORARY BARRIERS AND  
ENCLOSURES

Section 01 56 00

Wharf Reconstruction  
Seal Cove White Bay, NL

Page 1  
2016-06-15

---

PART 1 - GENERAL

- |   |    |  |
|---|----|--|
| <u>1.1 SECTION<br/>INCLUDES</u>           | .1 | Barriers.  |
|   | .2 | Traffic Controls.  |
| <u>1.2 INSTALLATION<br/>AND REMOVAL</u>   | .1 | Provide temporary controls in order to<br>execute work expeditiously.  |
|   | .2 | Remove from site all such work after use.  |
| <u>1.3 HOARDING</u>                       | .1 | Erect temporary site enclosure using new<br>1.2 m high snow fence wired to rolled steel<br>"T" bar fence posts spaced at 2.4 m centres.<br>Maintain fence in good repair.      |
| <u>1.4 GUARD RAILS<br/>AND BARRICADES</u> | .1 | Provide secure, rigid guard rails and<br>barricades around open excavations.   |
|   | .2 | Provide barricades along wharf structure when<br>wheelguard is removed.  |
|   | .3 | Provide as required by governing authorities.  |
| <u>1.5 ACCESS TO SITE</u>                 | .1 | Provide and maintain access to adjacent<br>harbour facilities.   |
| <u>1.6 PUBLIC<br/>TRAFFIC FLOW</u>        | .1 | Provide and maintain competent signal flag<br>operators, traffic signals, barricades and<br>flares, lights, or lanterns as required to<br>perform work and protect the public. |
| <u>1.7 FIRE ROUTES</u>                    | .1 | Maintain access to property including<br>overhead clearances for use by emergency  |

response vehicles.

1.8 PROTECTION FOR  
OFF-SITE AND PUBLIC  
PROPERTY

- .1 Protect surrounding private and public property from damage during performance of work.
- .2 Be responsible for damage incurred.