



Fisheries and Oceans  
Canada

Pêches et Océans  
Canada

Procurement Hub – Ottawa Office,  
Station 9W081, 9th Floor,  
200 Kent Street,  
Ottawa, Ontario K1A 0E6

October 12, 2016

**ADDENDUM NO. 2**

**Subject:** Invitation to Tender No. FP802-160208  
**Steveston Gulf Wharf 404 Reconstruction**

Dear Sir/Madam:

Further to the above-mentioned Request for Proposal, this Addendum (#2) is to advise potential bidders of the question(s) received during this tender call to date. Both the question(s) and the response(s) are indicated in the attached Annex A.

**All other terms and conditions remain unchanged.**

**Tenderers are to acknowledge this Addendum by signing in the space provided below and enclosing a copy of this document with their tender submission.**

Yours truly,

(Original signed by)

**Beverly Shawana**  
Senior Contracting Officer,  
Financial & Materials Management Operations

**RECEIPT ACKNOWLEDGED**

Name of Company

Signature \_\_\_\_\_

**Canada**

## Annex A

### **1.0 Response to Bidders' Inquiries:**

1.1 Please find below a response to bidder's inquiries received as of Oct 4, 2016.

Q1: What are treatment of existing decking, stringers, piles and caps?

A1: Bidders shall assume decking is salt treated, stringers and caps are creosote and piles are untreated.

Q2: What is the average length of pile being replaced?

A2: Bidders can assume an average length of 2m. The range is approx. between 1-4m.

Q3: Referring to Section 01 13 00, 17, please advise which permits will be the responsibility of Contractor to obtain and pay for?

A3: No permits are required.

Q4: Is access to the work only available through the decking that is being replaced?

A4: There is access under Wharf 404 on the north side of Building 7 and on the east and west sides of Building 8. Access can also be made through the deck, subject to Owner approval. However, the Contractor will be responsible for replacing decking that is damaged during removal, at the Contractor's expense.

Q5: Do you have drawings or a cross section of what the wharf looks like?

A5: Cross sectional drawings are not available. Bidders are recommended to visit the site.

Q6: I believe the work will take more than 7.5 days with a 3-man labour crew, is the foreman included in the hourly rate or separate?

A6: Refer to specification amendment 2.1 and 2.2. All crew, including the foreman, are included in the man-day rate.

Q7: If we need confined space entry, we may need an additional person (non-working) to watch CO levels etc.

A7: There will no requirement for enclosed space work in this contract. If it is deemed required during the execution of the contract, then the owner will request an additional proposal for that grade of work.

Q8: Can the inspection report be provided to bidders and how did inspectors gain access?

A8: No inspection reports will be provided with this tender. Refer to A4 for accessibility.

### **2.0 Specification Amendments:**

2.1 Refer to "Pricing Table – Schedule of Quantities and Prices", table item 1.5:

Delete: "180 hours"

Replace with: "180"

2.2 Refer to Pricing Table – Schedule of Quantities and Prices, item 1.5:

Delete: “Each”

Replace with: “Man-Days”

2.3 Refer to Specifications, Section 01 11 00, 3.5:

Delete: “Construction Tender Form: 13.0 Combined Price Schedule”

Replace with: “Price Table – Schedule of Quantities and Prices”