

Ottawa Walls Repairs 2016 (Ottawa, Ontario)
R.079197.020, Solicitation No: EQ754-171545/A

Tender Period Questions#2:

Addendum Information

1. Quality Control Section 03 30 00 3.12.1 states Concrete testing by departmental representative but section 01 45 01 1.3.2 states the contractor is responsible for all quality control. Please confirm who is doing what QC and QA ?
 - a. ***It is the duty of the Contractor to provide their own QC notwithstanding any subsequent testing requested within the contract documents as stated in the specifications Section 03-30-00 3.12.3.” Inspection or testing by Departmental Representative or third party service provider will not augment or replace Contractor quality control nor relieve Contractor of his contractual responsibility.” I.e. Third party testing should not negate completion of material supplier testing.***
2. If we are required to carry out QC can we do the QC by our own departmental forces rather than 3rd party?
 - a. ***No, a Third Party testing facility shall be used.***
3. Can you confirm if the reinforcing for the post bid item 11,12,13 is included in the reinforcing bid item or the reinforcing is included in those 3 items.
 - a. ***Reinforcement is to be Included in the individual price items for the three components.***
4. The bent drill and grout bars at the bottom of the wall show Type D1 dowels, in the specs Type D1 shows Headed bars. I believe this bars should be Type D2 Bend dowels only. All the Headed bars are specified on the drawings could you get this confirm please.
 - a. ***The lower “bent” dowel at the base of the refacing wall is supposed to show Type D2.***