

Cape Spear Lightstation
Remediation/Risk Management
Cape Spear, NL

2016-08-20

PART 1 - GENERAL

1.1 SECTION
INCLUDES

.1 Barriers.

1.2 INSTALLATION
AND REMOVAL

.1 Provide temporary controls in order to
execute work expeditiously.

.2 Remove from site all such work after use.

1.3 HOARDING

.1 Erect temporary site enclosure if required
by governing authorities, using new 1.2 m
high snow fence wired to rolled steel "T" bar
fence posts spaced at 2.4 m centres. Provide
one lockable truck gate. Maintain fence in
good repair.

1.4 GUARD RAILS
AND BARRICADES

.1 Provide secure, rigid guard rails and
barricades as required to protect against
falls.

.2 Provide as required by governing authorities.