

Cape Spear Lightstation  
Remediation/Risk Management  
Cape Spear, NL

2016-08-20

1.1 SECTION  
INCLUDES

- .1 Project Record Documents as follows:
  - .1 As-built drawings and specifications.
  - .2 Weigh bill slips for quantity of impacted soil removed for off-site disposal.
  - .3 Weigh bill slips for quantity of new gravel fill and topsoil delivered to site.

1.2 PROJECT RECORD  
DOCUMENTS

- .1 Departmental Representative will provide two white print sets of contract drawings and two copies of Specifications.
- .2 Maintain at site one set of the contract drawings and specifications to record actual "As-Built" site conditions.