

Ottawa Walls Repairs 2016 (Ottawa, Ontario)
R.079197.020, Solicitation No: EQ754-171545/A

Tender Period Questions #4:

Addendum Information

- 1) I have noted in section 35 20 22 article 1.7.8 “Ensure that dewatering system and cofferdam does not exceed the maximum six (6) meter construction limit within the Canal channel” but in sheet 105 of plan we have ten (10) meter of work area. What is the right width?
 - a. ***Specification is the governing document. 6m is the limit of the work Zone. If additional space is required, submittals have to be provided to departmental representative for review and approval.***

- 2) Also, in the same section article 2.1.7 “ Note that Fisheries & Oceans prefers gravel/rockfill dams with rubber membrane...”, we understand that we can use a rock cofferdam to do the work, is it accurate?
 - a. ***Full specification statement clarification is “Note that Fisheries & Oceans prefers gravel/rockfill dams with rubber membrane, caissons, interlocking concrete blocks, rubber dams, sand bags and bulkbags, bolted pre-engineered frame-type structures or other types of cofferdams which do not generate turbidity.” – Any method proposed to be used will still subject to Departmental Representative review and acceptance.***