

The following changes to the tender documents are effective immediately and will form part of the contract documents:

#### **1. RESPONSE TO CONTRACTOR INQUIRY**

1.1 The line diagram on Drawing E17 indicates the new direct buried feeder from the CSTE to the 800 amp main distribution is based on Table 2, but table 2 in the Electrical CodeBook is not for direct burial cables or conduits. This needs to be revised.

Response: Two runs of 4#600MCM multi conductor may also be utilized provided that the installation is per Diagram D10 detail 2. The use of multi conductor vs single conductor is per the contractor's preference. Both table D10A and Table 2 ampacities must be reviewed and the larger cable size to be used.

1.2 Panel BH-P6A is shown as 120/208 volt but it appears it should be 347/600 volt.

Response: See Addendum No. 2.

END OF ADDENDUM NO. 3