

Part 1 General

1.1 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Shop Drawings:
 - .1 Submit drawings stamped and signed by professional engineer registered or licensed in Province of Manitoba, Canada.
 - .2 Indicate on drawings:
 - .1 Mounting arrangements.
 - .2 Operating and maintenance clearances.
 - .3 Shop drawings and product data accompanied by:
 - .1 Detailed drawings of bases, supports, and anchor bolts.
 - .2 Acoustical sound power data, where applicable.
 - .3 Points of operation on performance curves.
 - .4 Manufacturer to certify current model production.
 - .5 Certification of compliance to applicable codes.
 - .4 In addition to transmittal letter referred to in Section 01 33 00 - Submittal Procedures: use MCAC "Shop Drawing Submittal Title Sheet". Identify section and paragraph number.
- .4 Sustainable Design Submittals:
 - .1 Construction Waste Management:
 - .1 Submit project Waste Management Plan highlighting recycling and salvage requirements.
 - .2 Building Energy and Water Consumption:
 - .1 Constant and variable motor loads.
 - .2 Cooling load.
 - .3 Air economizer and heat recovery cycle.
 - .4 Air distribution static pressures and ventilation air volumes.
 - .5 Building-related process energy systems and equipment.
 - .3 Recycled Content:
 - .1 Submit listing of recycled content products used, including details of required percentages or recycled content materials and products.

1.2 CLOSEOUT SUBMITTALS

- .1 Submit in accordance with Section 01 78 00 - Closeout Submittals.
- .2 Operation and Maintenance Data: submit operation and maintenance data for incorporation into manual.
 - .1 Operation and maintenance manual approved by, and final copies deposited with, Departmental Representative before final inspection.
 - .2 Operation data to include:
 - .1 Control schematics for systems including environmental controls.
 - .2 Description of systems and their controls.
 - .3 Description of operation of systems at various loads together with reset schedules and seasonal variances.
 - .4 Operation instruction for systems and component.
 - .5 Description of actions to be taken in event of equipment failure.
 - .6 Valves schedule and flow diagram.
 - .7 Colour coding chart.
 - .3 Maintenance data to include:
 - .1 Servicing, maintenance, operation and trouble-shooting instructions for each item of equipment.
 - .2 Data to include schedules of tasks, frequency, tools required and task time.
 - .4 Performance data to include:
 - .1 Equipment manufacturer's performance datasheets with point of operation as left after commissioning is complete.
 - .2 Equipment performance verification test results.
 - .3 Special performance data as specified.
 - .4 Testing, adjusting and balancing reports as specified in Section 23 05 93 - Testing, Adjusting and Balancing for HVAC.
 - .5 Approvals:
 - .1 Submit 2 copies of draft Operation and Maintenance Manual to Departmental Representative and Consultant for approval. Submission of individual data will not be accepted unless directed by Departmental Representative or Consultant.
 - .2 Make changes as required and re-submit as directed by Departmental Representative or Consultant.
 - .6 Additional data:
 - .1 Prepare and insert into operation and maintenance manual additional data when need for it becomes apparent during specified demonstrations and instructions.
 - .7 Site records:
 - .1 Departmental Representative and Consultant will provide 1 set of reproducible mechanical drawings. Provide sets of white prints as required for each phase of work. Mark changes as work progresses and

- as changes occur. Include changes to existing mechanical systems, control systems and low voltage control wiring.
- .2 Transfer information weekly to reproducibles, revising reproducibles to show work as actually installed.
- .3 Use different colour waterproof ink for each service.
- .4 Make available for reference purposes and inspection.
- .8 As-built drawings:
 - .1 Prior to start of Testing, Adjusting and Balancing for HVAC, finalize production of as-built drawings.
 - .2 Identify each drawing in lower right hand corner in letters at least 12 mm high as follows: - "AS BUILT DRAWINGS: THIS DRAWING HAS BEEN REVISED TO SHOW MECHANICAL SYSTEMS AS INSTALLED" (Signature of Contractor) (Date).
 - .3 Submit to Departmental Representative and Consultant for approval and make corrections as directed.
 - .4 Perform testing, adjusting and balancing for HVAC using as-built drawings.
 - .5 Submit completed reproducible as-built drawings with Operating and Maintenance Manuals.
- .9 Submit copies of as-built drawings for inclusion in final TAB report.

1.3 MAINTENANCE MATERIAL SUBMITTALS

- .1 Submit in accordance with Section 01 78 00 - Closeout Submittals.
- .2 Furnish spare parts as follows:
 - .1 One set of packing for each pump.
 - .2 One casing joint gasket for each size pump.
 - .3 One filter cartridge or set of filter media for each filter or filter bank in addition to final operating set.
- .3 Provide one set of special tools required to service equipment as recommended by manufacturers.
- .4 Furnish one commercial quality grease gun, grease and adapters to suit different types of grease and grease fittings.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials indoors in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect equipment from nicks, scratches, and blemishes.

- .3 Replace defective or damaged materials with new.
- .4 Develop Construction Waste Management Plan related to Work of this Section.
- .5 Packaging Waste Management: remove as specified in Construction Waste Management Plan Waste Reduction Workplan in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

Part 2 Products

2.1 MATERIALS

- .1 HVAC and R Equipment:
 - .1 Refrigerant: R-410A
 - .1 HCFC based refrigerant.
 - .2 HFC based refrigerant.

Part 3 Execution

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental Representative or Consultant.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied.

3.2 PAINTING REPAIRS AND RESTORATION

- .1 Do painting in accordance with Section 09 91 23 - Interior Painting.
- .2 Prime and touch up marred finished paintwork to match original.
- .3 Restore to new condition, finishes which have been damaged.

3.3 SYSTEM CLEANING

- .1 Clean interior and exterior of all systems including strainers. Vacuum interior of new ductwork and air handling units.

3.4 FIELD QUALITY CONTROL

- .1 Site Tests: conduct following tests in accordance with Section 01 45 00 - Quality Control and submit report as described in PART 1 - ACTION AND INFORMATIONAL SUBMITTALS.
- .2 Manufacturer's Field Services:

- .1 Obtain written report from manufacturer verifying compliance of Work, in handling, installing, applying, protecting and cleaning of product and submit Manufacturer's Field Reports as described in PART 1 - ACTION AND INFORMATIONAL SUBMITTALS.
- .2 Provide manufacturer's field services consisting of product use recommendations and periodic site visits for inspection of product installation in accordance with manufacturer's instructions.

3.5 DEMONSTRATION

- .1 Departmental Representative will use equipment and systems for test purposes prior to acceptance. Supply labour, material, and instruments required for testing.
- .2 Trial usage to apply to following equipment and systems:
 - .1 Air Handling, Fans, Unit Heaters.
- .3 Supply tools, equipment and personnel to demonstrate and instruct operating and maintenance personnel in operating, controlling, adjusting, trouble-shooting and servicing of all systems and equipment during regular work hours, prior to acceptance.
- .4 Use operation and maintenance manual, as-built drawings, and audio visual aids as part of instruction materials.
- .5 Instruction duration time requirements as specified in appropriate sections.
- .6 Departmental Representative DCC Representative Consultant will record these demonstrations on video tape for future reference.

3.6 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .3 Waste Management: separate waste materials in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

3.7 PROTECTION

- .1 Protect equipment and systems openings from dirt, dust, and other foreign materials with materials appropriate to system.

END OF SECTION

Part 1 General

1.1 SUMMARY

.1 Section Includes:

- .1 Use of mechanical systems during construction.

1.2 USE OF SYSTEMS

.1 Use of new permanent heating ventilating systems for supplying temporary heat ventilation is permitted only under following conditions:.

- .1 Entire system is complete, pressure tested, cleaned, flushed out.
 - .2 Specified water treatment system has been commissioned, water treatment is being continuously monitored.
 - .3 Building has been closed in, areas to be heated/ventilated are clean and will not thereafter be subjected to dust-producing processes.
 - .4 There is no possibility of damage.
 - .5 Supply ventilation systems are protected by 60 % filters, inspected daily, changed every 2 weeks or more frequently as required.
 - .6 Return systems have approved filters over openings, inlets, outlets.
 - .7 Systems will be:
 - .1 Operated as per manufacturer's recommendations and instructions.
 - .2 Operated by Contractor.
 - .3 Monitored continuously by Contractor.
 - .8 Warranties and guarantees are not relaxed.
 - .9 Regular preventive and other manufacturers recommended maintenance routines are performed by Contractor at own expense and under supervision of Departmental Representative.
 - .10 Refurbish entire system before static completion; clean internally and externally, restore to "as- new" condition, replace filters in air systems.
- .2 Filters specified in this Section are over and above those specified in other Sections of this project.
- .3 Exhaust systems are not included in approvals for temporary heating ventilation.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

.1 Not Used.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 Canadian General Standards Board (CGSB)
 - .1 CAN/CGSB-1.181-Latest Edition, Ready-Mixed Organic Zinc-Rich Coating.
- .2 Canada Green Building Council (CaGBC)
 - .1 Green Building Rating System Reference Package For New Construction and Major Renovations (including Addendum 2007).
 - .2 Green Building Rating System Reference Guide For Commercial Interiors.
- .3 Canadian Standards Association (CSA International)
 - .1 CSA B139-Latest Edition, Installation Code for Oil Burning Equipment.
- .4 Green Seal Environmental Standards (GSES)
 - .1 Standard GS-11-2008, 2nd Edition, Environmental Standard for Paints and Coatings.
- .5 National Fire Code of Canada (NFCC 2005)

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Provide manufacturer's printed product literature, specifications and datasheets for piping and equipment and include product characteristics, performance criteria, physical size, finish and limitations.

1.3 QUALITY ASSURANCE

- .1 Sustainability Standards Certification:
 - .1 Low-Emitting Materials: provide listing of sealants used in building, comply with VOC and chemical component limits or restriction requirements.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements:
 - .1 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.
- .3 Packaging Waste Management: remove in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

Part 2 Products

2.1 MATERIAL

- .1 Paint: zinc-rich to CAN/CGSB-1.181.
 - .1 Primers, Paints, Coating: in accordance with manufacturer's recommendations for surface conditions.
 - .2 Primer: maximum VOC limit 250 g/L to Standard GS-11, to SCAQMD Rule 1113.
 - .3 Paints: maximum VOC limit 150 g/L to Standard GS-11, to SCAQMD Rule 1113.
- .2 Sealants: in accordance with Section 07 92 00 - Joint Sealants.
 - .1 Sealants: maximum VOC limit to SCAQMD Rule 1168 to GSES GS-36.
- .3 Sealants: maximum VOC limit to SCAQMD Rule 1168 to GSES GS-36.
- .4 Adhesives: maximum VOC limit to SCAQMD Rule 1168 to GSES GS-36.

Part 3 Execution

3.1 APPLICATION

- .1 Manufacturer's Instructions: comply with manufacturer's written recommendations, including product technical bulletins, handling, storage and installation instructions, and datasheets.

3.2 CONNECTIONS TO EQUIPMENT

- .1 In accordance with manufacturer's instructions unless otherwise indicated.
- .2 Use valves and either unions or flanges for isolation and ease of maintenance and assembly.
- .3 Use double swing joints when equipment mounted on vibration isolation and when piping subject to movement.

3.3 CLEARANCES

- .1 Provide clearance around systems, equipment and components for observation of operation, inspection, servicing, maintenance and as recommended by manufacturer and National Fire Code of Canada CSA B139.
- .2 Provide space for disassembly, removal of equipment and components as recommended by manufacturer, CSA B139, as indicated without interrupting operation of other system, equipment, components.

3.4 DRAINS

- .1 Install piping with grade in direction of flow except as indicated.
- .2 Install drain valve at low points in piping systems, at equipment and at section isolating valves.

- .3 Pipe each drain valve discharge separately to above floor drain.
 - .1 Discharge to be visible.
- .4 Drain valves: NPS 3/4 gate or globe valves unless indicated otherwise, with hose end male thread, cap and chain.

3.5 AIR VENTS

- .1 Install manual air vents to CSA B139 at high points in piping systems.
- .2 Install isolating valve at each automatic air valve.
- .3 Install drain piping to approved location and terminate where discharge is visible.

3.6 DIELECTRIC COUPLINGS

- .1 General: compatible with system, to suit pressure rating of system.
- .2 Locations: where dissimilar metals are joined.
- .3 NPS 2 and under: isolating unions or bronze valves.
- .4 Over NPS 2: isolating flanges.

3.7 PIPEWORK INSTALLATION

- .1 Install pipework to CSA B139.
- .2 Screwed fittings jointed with Teflon tape.
- .3 Protect openings against entry of foreign material.
- .4 Install to isolate equipment and allow removal without interrupting operation of other equipment or systems.
- .5 Assemble piping using fittings manufactured to ANSI standards.
- .6 Saddle type branch fittings may be used on mains if branch line is no larger than half size of main.
 - .1 Hole saw (or drill) and ream main to maintain full inside diameter of branch line prior to welding saddle.
- .7 Install exposed piping, equipment, rectangular cleanouts and similar items parallel or perpendicular to building lines.
- .8 Install concealed pipework to minimize furring space, maximize headroom, conserve space.
- .9 Slope piping, except where indicated, in direction of flow for positive drainage and venting.
- .10 Install, except where indicated, to permit separate thermal insulation of each pipe.
- .11 Group piping wherever possible and as indicated.
- .12 Ream pipes, remove scale and other foreign material before assembly.
- .13 Use eccentric reducers at pipe size changes to ensure positive drainage and venting.
- .14 Provide for thermal expansion as required.

- .15 Valves:
 - .1 Install in accessible locations.
 - .2 Remove interior parts before soldering.
 - .3 Install with stems above horizontal position unless indicated.
 - .4 Valves accessible for maintenance without removing adjacent piping.
 - .5 Install globe valves in bypass around control valves.
 - .6 Use gate, ball, valves at branch take-offs for isolating purposes except where specified.
 - .7 Install plug cocks, ball valves for gas service.
- .16 Check Valves:
 - .1 Install silent check valves on discharge of pumps and as indicated.
 - .2 Install swing check valves in horizontal lines on discharge of pumps and as indicated.

3.8 SLEEVES

- .1 General: install where pipes pass through masonry, concrete structures, fire rated assemblies, and as indicated.
- .2 Material: schedule 40 black steel pipe.
- .3 Construction: use annular fins continuously welded at mid-point at foundation walls and where sleeves extend above finished floors.
- .4 Sizes: 6 mm minimum clearance between sleeve and uninsulated pipe or between sleeve and insulation.
- .5 Installation:
 - .1 Concrete, masonry walls, concrete floors on grade: terminate flush with finished surface.
 - .2 Other floors: terminate 25 mm above finished floor.
 - .3 Before installation, paint exposed exterior surfaces with heavy application of zinc-rich paint to CAN/CGSB-1.181.
- .6 Sealing:
 - .1 Foundation walls and below grade floors: fire retardant, waterproof non-hardening mastic.
 - .2 Elsewhere:
 - .1 Provide space for firestopping.
 - .2 Maintain fire rating integrity.
 - .3 Sleeves installed for future use: fill with lime plaster or other easily removable filler.
 - .4 Ensure no contact between copper pipe or tube and sleeve.

3.9 ESCUTCHEONS

- .1 Install on pipes passing through walls, partitions, floors, and ceilings in finished areas.

- .2 Construction: one piece type with set screws.
 - .1 Chrome or nickel plated brass or type 302 stainless steel..
- .3 Sizes: outside diameter to cover opening or sleeve.
 - .1 Inside diameter to fit around pipe or outside of insulation if so provided.

3.10 PREPARATION FOR FIRE STOPPING

- .1 Install firestopping within annular space between pipes, ducts, insulation and adjacent fire separation in accordance with Section 07 84 00 - Fire Stopping.
- .2 Uninsulated unheated pipes not subject to movement: no special preparation.
- .3 Uninsulated heated pipes subject to movement: wrap with non-combustible smooth material to permit pipe movement without damaging fire stopping material or installation.
- .4 Insulated pipes and ducts: ensure integrity of insulation and vapour barriers.

3.11 FLUSHING OUT OF PIPING SYSTEMS

- .1 Flush system in accordance with Section 23 08 02 - Cleaning and Start-up of Mechanical Piping Systems.
- .2 Before start-up, clean interior of piping systems in accordance with requirements of Section 01 74 11 - Cleaning supplemented as specified in relevant mechanical sections.
- .3 Preparatory to acceptance, clean and refurbish equipment and leave in operating condition, including replacement of filters in piping systems.

3.12 PRESSURE TESTING OF EQUIPMENT AND PIPEWORK

- .1 Advise Departmental Representative and Consultant 48 hours minimum prior to performance of pressure tests.
- .2 PIPework: test as specified in relevant sections of heating, ventilating and air conditioning work.
- .3 Maintain specified test pressure without loss for 4 hours minimum unless specified for longer period of time in relevant mechanical sections.
- .4 Prior to tests, isolate equipment and other parts which are not designed to withstand test pressure or media.
- .5 Conduct tests in presence of Departmental Representative.
- .6 Pay costs for repairs or replacement, retesting, and making good. Departmental Representative to determine whether repair or replacement is appropriate.
- .7 Insulate or conceal work only after approval and certification of tests by Departmental Representative.

3.13 EXISTING SYSTEMS

- .1 Connect into existing piping systems at times approved by Departmental Representative.
- .2 Request written approval by Departmental Representative 10 days minimum, prior to commencement of work.

- .3 Be responsible for damage to existing plant by this work.

3.14 CLEANING

- .1 Clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Remove surplus materials, excess materials, rubbish, tools and equipment.
- .2 Waste Management: separate waste materials for reuse recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 Section Includes:
 - .1 Electrical motors, drives and guards for mechanical equipment and systems.
 - .2 Supplier and installer responsibility indicated in Motor, Control and Equipment Schedule on electrical drawings and related mechanical responsibility is indicated on Mechanical Equipment Schedule on mechanical drawings.
 - .3 Control wiring and conduit is specified in Division 26 except for conduit, wiring and connections below 50 V which are related to control systems specified in Division 22 and 23. Refer to Division 26 for quality of materials and workmanship.

1.2 REFERENCES

- .1 American Society of Heating, Refrigeration and Air-Conditioning Engineers (ASHRAE)
 - .1 ASHRAE 90.1-Latest Edition, Energy Standard for Buildings Except Low-Rise Residential Buildings (IESNA cosponsored; ANSI approved; Continuous Maintenance Standard).
- .2 Electrical Equipment Manufacturers' Association Council (EEMAC)
- .3 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's printed product literature, specifications and datasheet in accordance with Section 01 33 00 - Submittal Procedures. Include product characteristics, performance criteria, and limitations.
 - .1 Submit two copies of Workplace Hazardous Materials Information System (WHMIS) Material Safety Data Sheets (MSDS) in accordance with Section 01 33 00 - Submittal Procedures.
 - .2 Shop Drawings: submit drawings stamped and signed by professional engineer registered or licensed in Province of Manitoba.
- .3 Quality Control: in accordance with Section 01 45 00 - Quality Control.
 - .1 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
 - .2 Instructions: submit manufacturer's installation instructions.
 - .1 Departmental Representative will make available 1 copy of systems supplier's installation instructions.

- .4 Closeout Submittals
 - .1 Provide maintenance data for motors, drives and guards for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.

1.4 QUALITY ASSURANCE

- .1 Regulatory Requirements: work to be performed in compliance with CEPA, CEAA, TDGA, applicable Provincial /Territorial regulations.

1.5 DELIVERY, STORAGE, AND HANDLING

- .1 Packing, shipping, handling and unloading:
 - .1 Deliver, store and handle in accordance with Section 01 61 00 - Common Product Requirements.
 - .2 Deliver, store and handle materials in accordance with manufacturer's written instructions.
- .2 Waste Management and Disposal:
 - .1 Construction/Demolition Waste Management and Disposal: separate waste materials in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

Part 2 Products

2.1 SUSTAINABLE REQUIREMENTS

- .1 Materials and products in accordance with Section 01 47 15 - Sustainable Requirements: Construction.

2.2 GENERAL

- .1 Motors: high efficiency, in accordance with local Hydro company standards and to ASHRAE 90.1.

2.3 MOTORS

- .1 Provide motors for mechanical equipment as specified.
- .2 Motors under 373 W(1/2 HP) : speed as indicated, continuous duty, built-in overload protection, resilient mount, single phase, 120 V, unless otherwise specified or indicated.
- .3 Motors 373 W (1/2 HP) and larger: EEMAC Class B, squirrel cage induction, speed as indicated, continuous duty, drip proof, ball bearing, maximum temperature rise 40 degrees C, 3 phase, 208 V, unless otherwise indicated.

2.4 TEMPORARY MOTORS

- .1 If delivery of specified motor will delay completion or commissioning work, install motor approved by Departmental Representative for temporary use. Work will only be accepted when specified motor is installed.

2.5 BELT DRIVES

- .1 Fit reinforced belts in sheave matched to drive. Multiple belts to be matched sets.
- .2 Use cast iron or steel sheaves secured to shafts with removable keys unless otherwise indicated.
- .3 For motors under 7.5 kW (10 HP) : standard adjustable pitch drive sheaves, having plus or minus 10% range. Use mid-position of range for specified r/min.
- .4 For motors 7.5 kW(10 HP) and over: sheave with split tapered bushing and keyway having fixed pitch unless specifically required for item concerned. Provide sheave of correct size to suit balancing.
- .5 Correct size of sheave determined during commissioning.
- .6 Minimum drive rating: 1.5 times nameplate rating on motor. Keep overhung loads within manufacturer's design requirements on prime mover shafts.
- .7 Motor slide rail adjustment plates to allow for centre line adjustment.
- .8 Supply one set of spare belts for each set installed in accordance with Section 01 78 00 - Closeout Submittals.

2.6 DRIVE GUARDS

- .1 Provide guards for unprotected drives.
- .2 Guards for belt drives;
 - .1 Expanded metal screen welded to steel frame.
 - .2 Minimum 1.2 mm thick sheet metal tops and bottoms.
 - .3 38 mm dia holes on both shaft centres for insertion of tachometer.
 - .4 Removable for servicing.
- .3 Provide means to permit lubrication and use of test instruments with guards in place.
- .4 Install belt guards to allow movement of motors for adjusting belt tension.
 - .1 "U" shaped, minimum 1.6 mm thick galvanized mild steel.
 - .2 Securely fasten in place.
 - .3 Removable for servicing.
- .5 Unprotected fan inlets or outlets:
 - .1 Wire or expanded metal screen, galvanized, 19 mm mesh.
 - .2 Net free area of guard: not less than 80% of fan openings.
 - .3 Securely fasten in place.
 - .4 Removable for servicing.

Part 3 Execution

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.2 INSTALLATION

- .1 Fasten securely in place.
- .2 Make removable for servicing, easily returned into, and positively in position.

3.3 FIELD QUALITY CONTROL

- .1 Site Tests: conduct following tests in accordance with Section 01 45 00 - Quality Control and submit report as described in PART 1 - SUBMITTALS.
- .2 Manufacturer's Field Services:
 - .1 Obtain written report from manufacturer verifying compliance of Work, in handling, installing, applying, protecting and cleaning of product and submit Manufacturer's Field Reports as described in PART 1 - SUBMITTALS.
 - .2 Provide manufacturer's field services consisting of product use recommendations and periodic site visits for inspection of product installation in accordance with manufacturer's instructions.
 - .3 Schedule site visits, to review Work, as directed in PART 1 - QUALITY ASSURANCE.
- .3 Verification requirements in accordance with Section 01 47 17 - Sustainable Requirements: Contractor's Verification, include:
 - .1 Materials and resources.
 - .2 Storage and collection of recyclables.
 - .3 Construction waste management.
 - .4 Resource reuse.
 - .5 Recycled content.
 - .6 Local/regional materials.
 - .7 Certified wood.
 - .8 Low-emitting materials.

3.4 CLEANING

- .1 Proceed in accordance with Section 01 74 11 - Cleaning.
- .2 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 American National Standards Institute/American Society of Mechanical Engineers (ANSI/ASME)
 - .1 ANSI/ASME B31.1-Latest Edition, Power Piping.
 - .2 ANSI/ASME B31.3-Latest Edition, Process Piping.
 - .3 ANSI/ASME Boiler and Pressure Vessel Code-Latest Edition.:
 - .1 BPVC 2007 Section I: Power Boilers.
 - .2 BPVC 2007 Section V: Nondestructive Examination.
 - .3 BPVC 2007 Section IX: Welding and Brazing Qualifications.
- .2 American National Standards Institute/American Water Works Association (ANSI/AWWA)
 - .1 ANSI/AWWA C206-Latest Edition, Field Welding of Steel Water Pipe.
- .3 American Welding Society (AWS)
 - .1 AWS C1.1M/C1.1-2000 Latest Edition, Recommended Practices for Resistance Welding.
 - .2 AWS Z49.1-2005, Safety in Welding, Cutting and Allied Process.
 - .3 AWS W1-2000, Welding Inspection Handbook..
- .4 Canada Green Building Council (CaGBC)
 - .1 Green Building Rating System Reference Package For New Construction and Major Renovations (including Addendum 2007).
 - .2 Green Building Rating System Reference Guide For Commercial Interiors.
- .5 Canadian Standards Association (CSA International)
 - .1 CSA W47.2- Latest Edition, Certification of Companies for Fusion Welding of Aluminum.
 - .2 CSA W48-Latest Edition, Filler Metals and Allied Materials for Metal Arc Welding.
 - .3 CSA B51-03 Latest Edition, Boiler, Pressure Vessel and Pressure Piping Code.
 - .4 CSA-W117.2-Latest Edition, Safety in Welding, Cutting and Allied Processes.
 - .5 CSA W178.1-Latest Edition, Certification of Welding Inspection Organizations.
 - .6 CSA W178.2-Latest Edition, Certification of Welding Inspectors.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.

1.3 QUALITY ASSURANCE

- .1 Qualifications:

- .1 Welders:
 - .1 Welding qualifications in accordance with CSA B51.
 - .2 Use qualified and licensed welders possessing certificate for each procedure performed from authority having jurisdiction.
 - .3 Submit welder's qualifications to Departmental Representative.
 - .4 Each welder to possess identification symbol issued by authority having jurisdiction.
 - .5 Certification of companies for fusion welding of aluminum in accordance with CSA W47.2.
- .2 Inspectors:
 - .1 Inspectors qualified to CSA W178.2.
- .3 Certifications:
 - .1 Registration of welding procedures in accordance with CSA B51.
 - .2 Copy of welding procedures available for inspection.
 - .3 Safety in welding, cutting and allied processes in accordance with CSA-W117.2.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle in accordance with Section 01 61 00 - Common Product Requirements.
- .2 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.
- .3 Packaging Waste Management: remove in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

Part 2 Products

2.1 SUSTAINABLE REQUIREMENTS

- .1 Materials and products in accordance with Section 01 47 15 Sustainable Requirements: Construction.

2.2 ELECTRODES

- .1 Electrodes: in accordance with CSA W48 Series.

Part 3 Execution

3.1 APPLICATION

- .1 Manufacturer's Instructions: comply with manufacturer's written recommendations, including product technical bulletins, handling, storage and installation instructions, and datasheets.

3.2 QUALITY OF WORK

- .1 Welding: in accordance with ANSI/ASME B31.1, B31.3, ANSI/ASME Boiler and Pressure Vessel Code, Sections I and IX and ANSI/AWWA C206, using procedures conforming to AWS B3.0, AWS C1.1, and special procedures specified elsewhere in Division 15 and applicable requirements of provincial authority having jurisdiction.

3.3 INSTALLATION REQUIREMENTS

- .1 Identify each weld with welder's identification symbol.
- .2 Backing rings:
 - .1 Where used, fit to minimize gaps between ring and pipe bore.
 - .2 Do not install at orifice flanges.
- .3 Fittings:
 - .1 NPS 2 and smaller: install welding type sockets.
 - .2 Branch connections: install welding tees or forged branch outlet fittings.

3.4 INSPECTION AND TESTS - GENERAL REQUIREMENTS

- .1 Review weld quality requirements and defect limits of applicable codes and standards with Departmental Representative before work is started.
- .2 Formulate "Inspection and Test Plan" in co-operation with Departmental Representative.
- .3 Do not conceal welds until they have been inspected, tested and approved by inspector.
- .4 Provide for inspector to visually inspect welds during early stages of welding procedures in accordance with Welding Inspection Handbook. Repair or replace defects as required by codes and as specified.

3.5 SPECIALIST EXAMINATIONS AND TESTS

- .1 General:
 - .1 Perform examinations and tests by specialist qualified to CSA W178.1 and CSA W178.2 and approved by Departmental Representative.
 - .2 To ANSI/ASME Boiler and Pressure Vessels Code, Section V, CSA B51 and requirements of authority having jurisdiction.
- .2 Hydrostatically test welds to ANSI/ASME B31.1.
- .3 Visual examinations: include entire circumference of weld externally and wherever possible internally.
- .4 Failure of visual examinations:
 - .1 Upon failure of welds by visual examination, perform additional testing as directed by Departmental Representative ..

3.6 REPAIR OF WELDS WHICH FAILED TESTS

- .1 Re-inspect and re-test repaired or re-worked welds at Contractor's expense.

3.7 CLEANING

- .1 Clean in accordance with Section 01 74 11 - Cleaning.
- .2 Waste Management: separate waste materials in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 American Society of Mechanical Engineers (ASME)
 - .1 ASME B31.1-Latest Edition, Power Piping.
- .2 ASTM International
 - .1 ASTM A125-1996 Latest Edition, Standard Specification for Steel Springs, Helical, Heat-Treated.
 - .2 ASTM A307-Latest Edition , Standard Specification for Carbon Steel Bolts and Studs, 60,000 PSI Tensile Strength.
 - .3 ASTM A563-Latest Edition, Standard Specification for Carbon and Alloy Steel Nuts.
- .3 Canada Green Building Council (CaGBC)
 - .1 Green Building Rating System Reference Package For New Construction and Major Renovations (including Addendum 2007).
 - .2 Green Building Rating System Reference Guide For Commercial Interiors.
- .4 Factory Mutual (FM)
- .5 Manufacturer's Standardization Society of the Valves and Fittings Industry (MSS)
 - .1 MSS SP58-Latest Edition, Pipe Hangers and Supports - Materials, Design and Manufacture.
 - .2 MSS SP69-Latest Edition, Pipe Hangers and Supports - Selection and Application.
 - .3 MSS SP89-Latest Edition, Pipe Hangers and Supports - Fabrication and Installation Practices.
- .6 Underwriter's Laboratories of Canada (ULC)

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Provide manufacturer's printed product literature and data sheets for hangers and supports and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Shop Drawings:
 - .1 Submit drawings stamped and signed by professional engineer registered or licensed in Province of Manitoba, Canada.
 - .2 Submit shop drawings for:
 - .1 Bases, hangers and supports.

- .2 Connections to equipment and structure.
- .3 Structural assemblies.
- .4 Certificates:
 - .1 Submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
- .5 Manufacturers' Instructions:
 - .1 Provide manufacturer's installation instructions.
 - .1 Departmental Representative will make available 1 copy of systems supplier's installation instructions.

1.3 CLOSEOUT SUBMITTALS

- .1 Provide maintenance data for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements:
 - .1 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.
- .3 Packaging Waste Management: remove in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

Part 2 Products

2.1 SYSTEM DESCRIPTION

- .1 Design Requirements:
 - .1 Construct pipe hanger and support to manufacturer's recommendations utilizing manufacturer's regular production components, parts and assemblies.
 - .2 Base maximum load ratings on allowable stresses prescribed by ASME B31.1 or MSS SP58.
 - .3 Ensure that supports, guides, anchors do not transmit excessive quantities of heat to building structure.
 - .4 Design hangers and supports to support systems under conditions of operation, allow free expansion and contraction, prevent excessive stresses from being introduced into pipework or connected equipment.
 - .5 Provide for vertical adjustments after erection and during commissioning. Amount of adjustment in accordance with MSS SP58.

2.2 SUSTAINABLE REQUIREMENTS

- .1 Materials and products in accordance with Section 01 47 15 - Sustainable Requirements: Construction.

2.3 GENERAL

- .1 Fabricate hangers, supports and sway braces in accordance with MSS SP58.

2.4 PIPE HANGERS

- .1 Finishes:
 - .1 Pipe hangers and supports: galvanized after manufacture.
 - .2 Use electro-plating galvanizing process or hot dipped galvanizing process.
 - .3 Ensure steel hangers in contact with copper piping are copper plated epoxy coated.
- .2 Upper attachment structural: suspension from lower flange of I-Beam:
 - .1 Cold piping NPS 2 maximum: malleable iron C-clamp with hardened steel cup point setscrew, locknut carbon steel retaining clip.
 - .1 Rod: 9 mm UL listed.
 - .2 Cold piping NPS 2 1/2 or greater, hot piping: malleable iron beam clamp, eye rod, jaws and extension with carbon steel retaining clip, tie rod, nuts and washers.
- .3 Upper attachment structural: suspension from upper flange of I-Beam:
 - .1 Cold piping NPS 2 maximum: ductile iron top-of-beam C-clamp with hardened steel cup point setscrew, locknut and carbon steel retaining clip.
 - .2 Cold piping NPS 2 1/2 or greater, hot piping: malleable iron top-of-beam jaw-clamp with hooked rod, spring washer, plain washer and nut.
- .4 Upper attachment to concrete:
 - .1 Ceiling: carbon steel welded eye rod, clevis plate, clevis pin and cotters with weldless forged steel eye nut. Ensure eye 6 mm minimum greater than rod diameter.
 - .2 Concrete inserts: wedge shaped body with knockout protector plate.
- .5 Shop and field-fabricated assemblies:
 - .1 Trapeze hanger assemblies:
 - .2 Steel brackets:
- .6 Hanger rods: threaded rod material to MSS SP58:
 - .1 Ensure that hanger rods are subject to tensile loading only.
 - .2 Provide linkages where lateral or axial movement of pipework is anticipated.
- .7 Pipe attachments: material to MSS SP58:
 - .1 Attachments for steel piping: carbon steel galvanized.
 - .2 Attachments for copper piping: copper plated black steel.

- .3 Use insulation shields for hot pipework.
- .4 Oversize pipe hangers and supports.
- .8 Adjustable clevis: material to MSS SP69 clevis bolt with nipple spacer and vertical adjustment nuts above and below clevis.
 - .1 Ensure "U" has hole in bottom for rivetting to insulation shields.
- .9 Yoke style pipe roll: carbon steel yoke, rod and nuts with cast iron roll, to MSS SP69.
- .10 U-bolts: carbon steel to MSS SP69 with 2 nuts at each end to ASTM A563.
 - .1 Finishes for steel pipework: black.
 - .2 Finishes for copper, glass, brass or aluminum pipework: black epoxy coated with formed portion plastic coated.

2.5 RISER CLAMPS

- .1 Steel or cast iron pipe: galvanized carbon steel to MSS SP58, type 42.
- .2 Copper pipe: carbon steel copper plated to MSS SP58, type 42.
- .3 Bolts: to ASTM A307.
- .4 Nuts: to ASTM A563.

2.6 INSULATION PROTECTION SHIELDS

- .1 Insulated cold piping:
 - .1 64 kg/m³ density insulation plus insulation protection shield to: MSS SP69, galvanized sheet carbon steel. Length designed for maximum 3 m span.
- .2 Insulated hot piping:
 - .1 Curved plate 300 mm long, with edges turned up, welded-in centre plate for pipe sizes NPS 12 and over, carbon steel to comply with MSS SP69.

2.7 CONSTANT SUPPORT SPRING HANGERS

- .1 Springs: alloy steel to ASTM A125, shot peened, magnetic particle inspected, with +/-5% spring rate tolerance, tested for free height, spring rate, loaded height and provided with Certified Mill Test Report (CMTR).
- .2 Load adjustability: 10% minimum adjustability each side of calibrated load. Adjustment without special tools. Adjustments not to affect travel capabilities.
- .3 Provide upper and lower factory set travel stops.
- .4 Provide load adjustment scale for field adjustments.
- .5 Total travel to be actual travel + 20%. Difference between total travel and actual travel 25 mm minimum.
- .6 Individually calibrated scales on each side of support calibrated prior to shipment, complete with calibration record.

2.8 EQUIPMENT SUPPORTS

- .1 Fabricate equipment supports not provided by equipment manufacturer from structural grade steel meeting requirements of Section 05 12 23 - Structural Steel for Buildings. Submit calculations with shop drawings.

2.9 EQUIPMENT ANCHOR BOLTS AND TEMPLATES

- .1 Provide templates to ensure accurate location of anchor bolts.

2.10 PLATFORMS AND CATWALKS

- .1 To Section 05 50 00 - Metal Fabrications.

2.11 HOUSE-KEEPING PADS

- .1 Provide 100 mm high concrete housekeeping pads for base-mounted equipment; size pads 50 mm larger than equipment; chamfer pad edges.
- .2 Concrete: to Section 03 30 00 - Cast-in-Place Concrete.

2.12 OTHER EQUIPMENT SUPPORTS

- .1 Fabricate equipment supports from structural grade steel meeting requirements of Section 05 12 23 - Structural Steel for Buildings .
- .2 Submit structural calculations with shop drawings.

Part 3 Execution

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.2 INSTALLATION

- .1 Install in accordance with:
 - .1 Manufacturer's instructions and recommendations.
- .2 Vibration Control Devices:
 - .1 Install on piping systems at pumps, boilers, chillers, cooling towers, and as indicated.
- .3 Clamps on riser piping:
 - .1 Support independent of connected horizontal pipework using riser clamps and riser clamp lugs welded to riser.
 - .2 Bolt-tightening torques to industry standards.
 - .3 Steel pipes: install below coupling or shear lugs welded to pipe.
 - .4 Cast iron pipes: install below joint.

- .4 Clevis plates:
 - .1 Attach to concrete with 4 minimum concrete inserts, one at each corner.
- .5 Provide supplementary structural steelwork where structural bearings do not exist or where concrete inserts are not in correct locations.
- .6 Use approved constant support type hangers where:
 - .1 Vertical movement of pipework is 13 mm or more,
 - .2 Transfer of load to adjacent hangers or connected equipment is not permitted.
- .7 Use variable support spring hangers where:
 - .1 Transfer of load to adjacent piping or to connected equipment is not critical.
 - .2 Variation in supporting effect does not exceed 25 % of total load.

3.3 HANGER SPACING

- .1 Plumbing piping: to Canadian Plumbing and authority having jurisdiction.
- .2 Fire protection: to applicable fire code.
- .3 Gas and fuel oil piping: up to NPS 1/2: every 1.8 m.
- .4 Copper piping: up to NPS 1/2: every 1.5 m.
- .5 Flexible joint roll groove pipe: in accordance with table below for steel, but not less than one hanger at joints. Table listings for straight runs without concentrated loads and where full linear movement is not required.
- .6 Within 300 mm of each elbow.

Maximum Pipe Size : NPS	Maximum Spacing Steel	Maximum Spacing Copper
up to 1-1/4	2.4 m	1.8 m
1-1/2	3.0 m	2.4 m
2	3.0 m	2.4 m
2-1/2	3.7 m	3.0 m
3	3.7 m	3.0 m
3-1/2	3.7 m	3.3 m
4	3.7 m	3.6 m
5	4.3 m	
6	4.3 m	
8	4.3 m	
10	4.9 m	
12	4.9 m	

- .7 Pipework greater than NPS 12: to MSS SP69.

3.4 HANGER INSTALLATION

- .1 Install hanger so that rod is vertical under operating conditions.
- .2 Adjust hangers to equalize load.
- .3 Support from structural members. Where structural bearing does not exist or inserts are not in suitable locations, provide supplementary structural steel members.

3.5 HORIZONTAL MOVEMENT

- .1 Angularity of rod hanger resulting from horizontal movement of pipework from cold to hot position not to exceed 4 degrees from vertical.
- .2 Where horizontal pipe movement is less than 13 mm, offset pipe hanger and support so that rod hanger is vertical in the hot position.

3.6 FINAL ADJUSTMENT

- .1 Adjust hangers and supports:
 - .1 Ensure that rod is vertical under operating conditions.
 - .2 Equalize loads.
- .2 Adjustable clevis:
 - .1 Tighten hanger load nut securely to ensure proper hanger performance.
 - .2 Tighten upper nut after adjustment.
- .3 C-clamps:
 - .1 Follow manufacturer's recommended written instructions and torque values when tightening C-clamps to bottom flange of beam.
- .4 Beam clamps:
 - .1 Hammer jaw firmly against underside of beam.

3.7 FIELD QUALITY CONTROL

- .1 Site Tests: conduct following tests in accordance with Section 01 45 00 - Quality Control and submit report as described in PART 1 - ACTION AND INFORMATIONAL SUBMITTALS.
- .2 Manufacturer's Field Services:
 - .1 Obtain written report from manufacturer verifying compliance of Work, in handling, installing, applying, protecting and cleaning of product and submit Manufacturer's Field Reports as described in PART 1 - ACTION AND INFORMATIONAL SUBMITTALS.
 - .2 Provide manufacturer's field services consisting of product use recommendations and periodic site visits for inspection of product installation in accordance with manufacturer's instructions.
 - .3 Schedule site visits, to review Work, as directed in PART 1 - QUALITY ASSURANCE.

3.8 CLEANING

- .1 Clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Remove surplus materials, excess materials, rubbish, tools and equipment.
- .2 Waste Management: separate waste materials in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

Expansion and Redevelopment of the Emerson Port of Entry
Emerson, MB

Section 23 05 29
HANGERS AND SUPPORTS FOR HVAC PIPING
AND EQUIPMENT

PWGSC Project No. R.068431.001

Page 8 of 8

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 Section Includes:
 - .1 Heat tracing cables for pipes and tanks including controls and installation.
- .2 Sustainable requirements for construction and verification.

1.2 REFERENCES

- .1 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Product Data:
 - .1 Submit manufacturer's printed product literature, specifications and datasheet in accordance with Section 01 33 00 - Submittal Procedures. Include product characteristics, performance criteria, and limitations.
 - .1 Submit two copies of Workplace Hazardous Materials Information System (WHMIS) Material Safety Data Sheets (MSDS) in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Quality assurance submittals: submit following in accordance with Section 01 33 00 - Submittal Procedures.
 - .1 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
- .3 Instructions: submit manufacturer's installation instructions.
 - .1 Departmental Representative will make available 1 copy of systems supplier's installation instructions.

1.4 DELIVERY, STORAGE, AND HANDLING

- .1 Packing, shipping, handling and unloading:
 - .1 Deliver, store and handle in accordance with manufacturer's written instructions and Section 01 61 00 - Common Product Requirements.
- .2 Waste Management and Disposal:
 - .1 Construction/Demolition Waste Management and Disposal: separate waste materials for reuse recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

Part 2 Products

2.1 SUSTAINABLE REQUIREMENTS

- .1 Materials and products in accordance with Section 01 47 15 - Sustainable Requirements: Construction.

2.2 PIPE/TANK TRACING HEATING CABLES

- .1 Type D: self-limiting heating cable with copper ground wire, thermoplastic rubber polyolefin fluoropolymer primary and overall jackets. Heating capacity: 30.2 W/m; for use with 208 V power supply.
- .2 Provide cold lead connection kit, locate as indicated.
- .3 Provide central panel, connectors and sensor connectors.

Part 3 Execution

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.2 INSTALLATION

- .1 Install heating cables in accordance with manufacturer's instructions. Co-ordinate installation with pipe insulation application.
- .2 Install heating cables in accordance with manufacturer's instructions. Distribute and fasten cable evenly on pipe using pipe strap or tape at maximum spacing 0.5 m. Ensure that heating cables do not touch or cross each other. Run only cold leads in conduit and ensure sensing bulb does not touch cable. Ground shield to building ground. Coordinate cable installation with insulation application. Loop additional cable at fittings, valves, and flanges.
- .3 Make power and control connections.

3.3 FIELD QUALITY CONTROL

- .1 Tests:
 - .1 Perform tests in accordance with Section 26 05 00 - Common Work Results for Electrical.
- .2 Use 500 V Megger to test cables for continuity and insulation value and record readings before, during and after installation.
- .3 Where resistance of 50 megohms or less is measured, stop work and advise Departmental Representative.
- .4 Verification requirements in accordance with Section 01 47 17 - Sustainable Requirements: Contractor's Verification, include:
 - .1 Materials and resources.

- .2 Storage and collection of recyclables.
- .3 Construction waste management.
- .4 Resource reuse.
- .5 Recycled content.
- .6 Local/regional materials.
- .7 Low-emitting materials.

3.4 CLEANING

- .1 Proceed in accordance with Section 01 74 11 - Cleaning.
- .2 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 Section Includes:
 - .1 Vibration isolation materials and components, seismic control measures and their installation.

1.2 REFERENCES

- .1 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).
- .2 National Fire Protection Association (NFPA)
 - .1 NFPA 13-Latest Edition, Standard for the Installation of Sprinkler Systems.
- .3 National Building Code of Canada (NBC) – Latest Edition

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
 - .1 Submit manufacturer's printed product literature, specifications and datasheet in accordance with Section 01 33 00 - Submittal Procedures. Include product characteristics, performance criteria, and limitations.
 - .1 Submit two copies of Workplace Hazardous Materials Information System (WHMIS) Material Safety Data Sheets (MSDS) in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Submit shop drawings in accordance with Section 01 33 00 - Submittal Procedures.
 - .1 Shop drawings: submit drawings stamped and signed by professional engineer registered or licensed in Province of Manitoba, Canada.
 - .2 Provide separate shop drawings for each isolated system shop drawings complete with performance and product data.
 - .3 Provide detailed drawings of seismic control measures for equipment and piping.
- .3 Quality assurance submittals: submit following in accordance with Section 01 33 00 - Submittal Procedures.
 - .1 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
 - .2 Instructions: submit manufacturer's installation instructions.
 - .1 Departmental Representative will make available 1 copy of systems supplier's installation instructions.
 - .3 Manufacturer's Field Reports: manufacturer's field reports specified.

1.4 DELIVERY, STORAGE, AND HANDLING

- .1 Packing, shipping, handling and unloading:

- .1 Deliver, store and handle in accordance with Section 01 61 00 - Common Product Requirements.
- .2 Deliver, store and handle materials in accordance with manufacturer's written instructions.
- .2 Waste Management and Disposal:
 - .1 Construction/Demolition Waste Management and Disposal: separate waste materials in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

Part 2 Products

2.1 GENERAL

- .1 Size and shape of bases type and performance of vibration isolation as indicated.

2.2 ELASTOMERIC PADS

- .1 Type EP1 - neoprene waffle or ribbed; 9 mm minimum thick; 50 durometer; maximum loading 350 kPa.
- .2 Type EP2 - rubber waffle or ribbed; 9 mm minimum thick; 30 durometer natural rubber; maximum loading 415 kPa.
- .3 Type EP3 - neoprene-steel-neoprene; 9 mm minimum thick neoprene bonded to 1.71 mm steel plate; 50 durometer neoprene, waffle or ribbed; holes sleeved with isolation washers; maximum loading 350 kPa.
- .4 Type EP4 - rubber-steel-rubber; 9 mm minimum thick rubber bonded to 1.71 mm steel plate; 30 durometer natural rubber, waffle or ribbed; holes sleeved with isolation washers; maximum loading 415 kPa.

2.3 ELASTOMERIC MOUNTS

- .1 Type M1 - colour coded; neoprene in shear; maximum durometer of 60; threaded insert and two bolt-down holes; ribbed top and bottom surfaces.

2.4 SPRINGS

- .1 Design stable springs: ratio of lateral to axial stiffness is equal to or greater than 1.2 times ratio of static deflection to working height. Select for 50% travel beyond rated load. Units complete with levelling devices.
- .2 Ratio of height when loaded to diameter of spring between 0.8 to 1.0.
- .3 Cadmium plate for outdoor installations.
- .4 Colour code springs.

2.5 SPRING MOUNT

- .1 Zinc or cadmium plated hardware; housings coated with rust resistant paint.

- .2 Type M2 - stable open spring: support on bonded 6 mm minimum thick ribbed neoprene or rubber friction and acoustic pad.
- .3 Type M3 - stable open spring: 6 mm minimum thick ribbed neoprene or rubber friction and acoustic pad, bonded under isolator and on isolator top plate; levelling bolt for rigidly mounting to equipment.
- .4 Type M4 - restrained stable open spring: supported on bonded 6 mm minimum thick ribbed neoprene or rubber friction and acoustic pad; built-in resilient limit stops, removable spacer plates.
- .5 Type M5 - enclosed spring mounts with snubbers for isolation up to 950 kg maximum.
- .6 Performance: as indicated.

2.6 HANGERS

- .1 Colour coded springs, rust resistant, painted box type hangers. Arrange to permit hanger box or rod to move through a 30 degrees arc without metal to metal contact.
- .2 Type H1 - neoprene - in-shear, moulded with rod isolation bushing which passes through hanger box.
- .3 Type H2 - stable spring, elastomeric washer, cup with moulded isolation bushing which passes through hanger box.
- .4 Type H3 - stable spring, elastomeric element, cup with moulded isolation bushing which passes through hanger box.
- .5 Type H4 - stable spring, elastomeric element with precompression washer and nut with deflection indicator.
- .6 Performance: as indicated.

2.7 ACOUSTIC BARRIERS FOR ANCHORS AND GUIDES

- .1 Acoustic barriers: between pipe and support, consisting of 25 mm minimum thick heavy duty duck and neoprene isolation material.

Part 3 Execution

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.2 INSTALLATION

- .1 Seismic control measures to meet requirements of NBC.
- .2 Install vibration isolation equipment in accordance with manufacturers instructions and adjust mountings to level equipment.

- .3 Ensure piping, ducting and electrical connections to isolated equipment do not reduce system flexibility and that piping, conduit and ducting passage through walls and floors do not transmit vibrations.
- .4 Unless indicated otherwise, support piping connected to isolated equipment with spring mounts or spring hangers with 25 mm minimum static deflection as follows:
 - .1 Up to NPS4: first 3 points of support. NPS5 to NPS8: first 4 points of support. NPS10 and Over: first 6 points of support.
 - .2 First point of support: static deflection of twice deflection of isolated equipment, but not more than 50 mm.
- .5 Where isolation is bolted to floor use vibration isolation rubber washers.
- .6 Block and shim level bases so that ductwork and piping connections can be made to rigid system at operating level, before isolator adjustment is made. Ensure that there is no physical contact between isolated equipment and building structure.

3.3 FIELD QUALITY CONTROL

- .1 Manufacturer's Field Services:
 - .1 Arrange with manufacturer's representative to review work of this Section and submit written reports to verify compliance with Contract Documents.
 - .2 Manufacturer's Field Services: consisting of product use recommendations and periodic site visits to review installation, scheduled as follows:
 - .1 After delivery and storage of Products.
 - .2 After preparatory work is complete but before installation commences.
 - .3 Twice during the installation, at 25% and 60% completion stages.
 - .4 Upon completion of installation.
 - .3 Submit manufacturer's reports to Departmental Representative within 3 days of manufacturer representative's review.
 - .4 Make adjustments and corrections in accordance with written report.
- .2 Inspection and Certification:
 - .1 Experienced and competent sound and vibration testing professional engineer to take vibration measurement for HVAC systems after start up and TAB of systems to Section 23 05 93 - Testing, Adjusting and Balancing for HVAC.
 - .2 Take vibration measurements for equipment as indicated listed below.
 - .3 Provide Departmental Representative with notice 24 h in advance of commencement of tests.
 - .4 Establish adequacy of equipment isolation and acceptability of noise levels in occupied areas and where appropriate, remedial recommendations (including sound curves).
 - .5 Submit complete report of test results including sound curves.
- .3 Verification requirements in accordance with Section 01 47 17 - Sustainable Requirements: Contractor's Verification, include:
 - .1 Materials and resources.

- .2 Storage and collection of recyclables.
- .3 Construction waste management.
- .4 Resource reuse.
- .5 Recycled content.
- .6 Local/regional materials.
- .7 Certified wood.
- .8 Low-emitting materials.

3.4 CLEANING

- .1 Proceed in accordance with Section 01 74 11 - Cleaning.
- .2 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 TAB is used throughout this Section to describe the process, methods and requirements of testing, adjusting and balancing for HVAC.
- .2 TAB means to test, adjust and balance to perform in accordance with requirements of Contract Documents and to do other work as specified in this section.

1.2 QUALIFICATIONS OF TAB PERSONNEL

- .1 Submit names of personnel to perform TAB to Departmental Representative within 90 days of award of contract.
- .2 Provide documentation confirming qualifications, successful experience.
- .3 TAB: performed in accordance with the requirements of standard under which TAB Firm's qualifications are approved:
 - .1 Associated Air Balance Council, (AABC) National Standards for Total System Balance, MN-1-Latest Edition.
 - .2 National Environmental Balancing Bureau (NEBB) TABES, Procedural Standards for Testing, Adjusting, Balancing of Environmental Systems-Latest Edition.
 - .3 Sheet Metal and Air Conditioning Contractors' National Association (SMACNA), HVAC TAB HVAC Systems - Testing, Adjusting and Balancing-2002.
- .4 Recommendations and suggested practices contained in the TAB Standard: mandatory.
- .5 Use TAB Standard provisions, including checklists, and report forms to satisfy Contract requirements.
- .6 Use TAB Standard for TAB, including qualifications for TAB Firm and Specialist and calibration of TAB instruments.
- .7 Where instrument manufacturer calibration recommendations are more stringent than those listed in TAB Standard, use manufacturer's recommendations.
- .8 TAB Standard quality assurance provisions such as performance guarantees form part of this contract.
 - .1 For systems or system components not covered in TAB Standard, use TAB procedures developed by TAB Specialist.
 - .2 Where new procedures, and requirements, are applicable to Contract requirements have been published or adopted by body responsible for TAB Standard used (AABC, NEBB, or TABB), requirements and recommendations contained in these procedures and requirements are mandatory.

1.3 PURPOSE OF TAB

- .1 Test to verify proper and safe operation, determine actual point of performance, evaluate qualitative and quantitative performance of equipment, systems and controls at design, average and low loads using actual or simulated loads
- .2 Adjust and regulate equipment and systems to meet specified performance requirements and to achieve specified interaction with other related systems under normal and emergency loads and operating conditions.
- .3 Balance systems and equipment to regulate flow rates to match load requirements over full operating ranges.

1.4 EXCEPTIONS

- .1 TAB of systems and equipment regulated by codes, standards to satisfaction of authority having jurisdiction.

1.5 CO-ORDINATION

- .1 Schedule time required for TAB (including repairs, re-testing) into project construction and completion schedule to ensure completion before acceptance of project.
- .2 Do TAB of each system independently and subsequently, where interlocked with other systems, in unison with those systems.

1.6 PRE-TAB REVIEW

- .1 Review contract documents before project construction is started confirm in writing to Departmental Representative adequacy of provisions for TAB and other aspects of design and installation pertinent to success of TAB.
- .2 Review specified standards and report to Departmental Representative in writing proposed procedures which vary from standard.
- .3 During construction, co-ordinate location and installation of TAB devices, equipment, accessories, measurement ports and fittings.

1.7 START-UP

- .1 Follow start-up procedures as recommended by equipment manufacturer unless specified otherwise.
- .2 Follow special start-up procedures specified elsewhere in Division 23.

1.8 OPERATION OF SYSTEMS DURING TAB

- .1 Operate systems for length of time required for TAB and as required by Departmental Representative for verification of TAB reports.

1.9 START OF TAB

- .1 Notify Departmental Representative 7 days prior to start of TAB.
- .2 Start TAB when building is essentially completed, including:
- .3 Installation of ceilings, doors, windows, other construction affecting TAB.

- .4 Application of weatherstripping, sealing, and caulking.
- .5 Pressure, leakage, other tests specified elsewhere Division 23.
- .6 Provisions for TAB installed and operational.
- .7 Start-up, verification for proper, normal and safe operation of mechanical and associated electrical and control systems affecting TAB including but not limited to:
 - .1 Proper thermal overload protection in place for electrical equipment.
 - .2 Air systems:
 - .1 Filters in place, clean.
 - .2 Duct systems clean.
 - .3 Ducts, air shafts, ceiling plenums are airtight to within specified tolerances.
 - .4 Correct fan rotation.
 - .5 Fire, smoke, volume control dampers installed and open.
 - .6 Coil fins combed, clean.
 - .7 Access doors, installed, closed.
 - .8 Outlets installed, volume control dampers open.
 - .3 Liquid systems:
 - .1 Flushed, filled, vented.
 - .2 Correct pump rotation.
 - .3 Strainers in place, baskets clean.
 - .4 Isolating and balancing valves installed, open.
 - .5 Calibrated balancing valves installed, at factory settings.
 - .6 Chemical treatment systems complete, operational.

1.10 APPLICATION TOLERANCES

- .1 Do TAB to following tolerances of design values:
 - .1 HVAC systems: plus 10 %, minus 5 %.
 - .2 Hydronic systems: plus or minus 10 %.

1.11 ACCURACY TOLERANCES

- .1 Measured values accurate to within plus or minus 2 % of actual values.

1.12 INSTRUMENTS

- .1 Prior to TAB, submit to Departmental Representative list of instruments used together with serial numbers.
- .2 Calibrate in accordance with requirements of most stringent of referenced standard for either applicable system or HVAC system.
- .3 Calibrate within 3 months of TAB. Provide certificate of calibration to Departmental Representative .

1.13 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit, prior to commencement of TAB:
- .2 Proposed methodology and procedures for performing TAB if different from referenced standard.

1.14 PRELIMINARY TAB REPORT

- .1 Submit for checking and approval of Departmental Representative , prior to submission of formal TAB report, sample of rough TAB sheets. Include:
 - .1 Details of instruments used.
 - .2 Details of TAB procedures employed.
 - .3 Calculations procedures.
 - .4 Summaries.

1.15 TAB REPORT

- .1 Format in accordance with referenced standard.
- .2 TAB report to show results in SI units and to include:
 - .1 Project record drawings.
 - .2 System schematics.
- .3 Submit 6 copies of TAB Report to Departmental Representative for verification and approval, in English French both official languages in D-ring binders, complete with index tabs.

1.16 VERIFICATION

- .1 Reported results subject to verification by Departmental Representative.
- .2 Provide personnel and instrumentation to verify up to 30 % of reported results.
- .3 Number and location of verified results as directed by Departmental Representative.
- .4 Pay costs to repeat TAB as required to satisfaction of Departmental Representative.

1.17 SETTINGS

- .1 After TAB is completed to satisfaction of Departmental Representative, replace drive guards, close access doors, lock devices in set positions, ensure sensors are at required settings.
- .2 Permanently mark settings to allow restoration at any time during life of facility. Do not eradicate or cover markings.

1.18 COMPLETION OF TAB

- .1 TAB considered complete when final TAB Report received and approved by Departmental Representative.

1.19 AIR SYSTEMS

- .1 Standard: TAB to most stringent of TAB standards of AABC NEBB SMACNA ASHRAE.
- .2 Do TAB of systems, equipment, components, controls specified Division 23 and following systems, equipment, components, controls:
 - .1 Supply Air Systems.
 - .2 Exhaust Systems.
 - .3 ERV.
 - .4 Split A/C Systems.
 - .5 Fans.
 - .6 Gas Heaters.
 - .7 Plumbing Systems.
- .3 Qualifications: personnel performing TAB current member in good standing of AABC NEBB.
- .4 Quality assurance: perform TAB under direction of supervisor qualified by to standards of AABC NEBB.
- .5 Measurements: to include as appropriate for systems, equipment, components, controls: air velocity, static pressure, flow rate, pressure drop (or loss), temperatures (dry bulb, wet bulb, dewpoint), duct cross-sectional area, RPM, electrical power, voltage, noise, vibration.
- .6 Locations of equipment measurements: to include as appropriate:
 - .1 Inlet and outlet of dampers, filter, coil, humidifier, fan, other equipment causing changes in conditions.
 - .2 At controllers, controlled device.
- .7 Locations of systems measurements to include as appropriate: main ducts, main branch, sub-branch, run-out (or grille, register or diffuser).

1.20 OTHER TAB REQUIREMENTS

- .1 General requirements applicable to work specified this paragraph:
 - .1 Qualifications of TAB personnel: as for air systems specified this section.
 - .2 Quality assurance: as for air systems specified this section.
- .2 Laboratory fume hoods:
 - .1 Standard: Treasury Board of Canada Handbook of Occupational Health and safety, 4th edition Canada Labour Code state applicable Provincial or other standard.
 - .2 TAB procedures: as described in standard.
- .3 Building pressure conditions:
 - .1 Adjust HVAC systems, equipment, controls to ensure specified pressure conditions at all times during winter summer design conditions.

- .4 Zone pressure differences:
 - .1 Adjust HVAC systems, equipment, controls to establish specified air pressure differentials, with systems in every possible combinations of normal operating modes.
- .5 Smoke management systems:
 - .1 Test for proper operation of all smoke and fire dampers, sensors, detectors, installed as component parts of air systems specified Division 23.
 - .2 Emergency evacuation: see post-occupancy TAB activities specified below.
- .6 Measurement of noise vibration from equipment specified in Division 23.
- .7 Measurement of spatial noise, vibration:

1.21 POST-OCCUPANCY TAB

- .1 Measure DBT, WBT (or %RH), air flow patterns, NC levels, in occupied zone of following areas: interview, office.
- .2 Participate in systems checks twice during Warranty Period - #1 approximately 3 months after acceptance and #2 within 1 month of termination of Warranty Period.

Part 2 Products

2.1 NOT USED

- .1 Not used.

Part 3 Execution

3.1 NOT USED

- .1 Not used.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 Definitions:
 - .1 For purposes of this section:
 - .1 "CONCEALED" - insulated mechanical services and equipment in suspended ceilings and non-accessible chases and furred-in spaces.
 - .2 "EXPOSED" - means "not concealed" as previously defined.
 - .3 Insulation systems - insulation material, fasteners, jackets, and other accessories.
 - .2 TIAC Codes:
 - .1 CRD: Code Round Ductwork,
 - .2 CRF: Code Rectangular Finish.
- .2 Reference Standards:
 - .1 American Society of Heating, Refrigeration and Air Conditioning Engineers (ASHRAE)
 - .1 ANSI/ASHRAE/IESNA 90.1-Latest Edition, SI; Energy Standard for Buildings Except Low-Rise Residential Buildings.
 - .2 ASTM International Inc.
 - .1 ASTM B209M-Latest Edition, Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate (Metric).
 - .2 ASTM C335-Latest Edition, Standard Test Method for Steady State Heat Transfer Properties of Pipe Insulation.
 - .3 ASTM C411-Latest Edition, Standard Test Method for Hot-Surface Performance of High-Temperature Thermal Insulation.
 - .4 ASTM C449/C449M-Latest Edition, Standard Specification for Mineral Fiber-Hydraulic-Setting Thermal Insulating and Finishing Cement.
 - .5 ASTM C547-Latest Edition, Standard Specification for Mineral Fiber Pipe Insulation.
 - .6 ASTM C553-Latest Edition, Standard Specification for Mineral Fiber Blanket Thermal Insulation for Commercial and Industrial Applications.
 - .7 ASTM C612-Latest Edition, Standard Specification for Mineral Fiber Block and Board Thermal Insulation.
 - .8 ASTM C795-Latest Edition, Standard Specification for Thermal Insulation for Use in Contact with Austenitic Stainless Steel.
 - .9 ASTM C921-Latest Edition, Standard Practice for Determining the Properties of Jacketing Materials for Thermal Insulation.
 - .3 Canadian General Standards Board (CGSB)
 - .1 CGSB 51-GP-52Ma-Latest Edition, Vapour Barrier, Jacket and Facing Material for Pipe, Duct and Equipment Thermal Insulation.

- .4 Green Seal Environmental Standards (GSES)
 - .1 Standard GS-36-Latest Edition, Commercial Adhesives.
- .5 South Coast Air Quality Management District (SCAQMD), California State
 - .1 SCAQMD Rule 1168-Latest Edition, Adhesive and Sealant Applications.
- .6 Thermal Insulation Association of Canada (TIAC): National Insulation Standards (2005).
- .7 Underwriters Laboratories of Canada (ULC)
 - .1 CAN/ULC-S102-Latest Edition, Method of Test for Surface Burning Characteristics of Building Materials and Assemblies.
 - .2 CAN/ULC-S701-Latest Edition, Standard for Thermal Insulation, Polystyrene, Boards and Pipe Covering.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Provide manufacturer's printed product literature and datasheets for duct insulation, and include product characteristics, performance criteria, physical size, finish and limitations.
 - .1 Description of equipment giving manufacturer's name, type, model, year and capacity.
 - .2 Details of operation, servicing and maintenance.
 - .3 Recommended spare parts list.
- .3 Shop Drawings:
 - .1 Provide drawings stamped and signed by professional engineer registered or licensed in Province of Manitoba, Canada.
- .4 Samples:
 - .1 Submit for approval: complete assembly of each type of insulation system, insulation, coating, and adhesive proposed.
 - .2 Mount sample on 12 mm plywood board.
 - .3 Affix typewritten label beneath sample indicating service.
- .5 Manufacturers' Instructions:
 - .1 Provide manufacture's written duct insulation jointing recommendations. and special handling criteria, installation sequence, cleaning procedures .

1.3 QUALITY ASSURANCE

- .1 Qualifications:
 - .1 Installer: specialist in performing work of this section, and have at least 3 years successful experience in this size and type of project, member of TIAC.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle in accordance with Section 01 61 00 - Common Product Requirements.
- .2 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address and ULC markings.
- .3 Packaging Waste Management: remove in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

Part 2 Products

2.1 FIRE AND SMOKE RATING

- .1 To CAN/ULC-S102:
 - .1 Maximum flame spread rating: 25.
 - .2 Maximum smoke developed rating: 50.

2.2 INSULATION

- .1 Mineral fibre: as specified includes glass fibre, rock wool, slag wool.
- .2 Thermal conductivity ("k" factor) not to exceed specified values at 24 degrees C mean temperature when tested in accordance with ASTM C335.
- .3 TIAC Code C-1: Rigid mineral fibre board to ASTM C612, with without factory applied vapour retarder jacket to CGSB 51-GP-52Ma (as scheduled in PART 3 of this Section).
- .4 TIAC Code C-2: Mineral fibre blanket to ASTM C553 faced with factory applied vapour retarder jacket to CGSB 51-GP-52Ma (as scheduled in PART 3 of this section).
 - .1 Mineral fibre: to ASTM C553.
 - .2 Jacket: to CGSB 51-GP-52Ma.
 - .3 Maximum "k" factor: to ASTM C553.

2.3 JACKETS

- .1 Canvas:
 - .1 220 gm/m² cotton, plain weave, treated with dilute fire retardant lagging adhesive to ASTM C921.
- .2 Lagging adhesive: compatible with insulation.
 - .1 Maximum VOC limit to SCAQMD Rule 1168 GSES GS-36.
- .3 Aluminum:
 - .1 To ASTM B209 with moisture barrier as scheduled in PART 3 of this section.
 - .2 Thickness: 0.50 mm sheet.
 - .3 Finish: Smooth.
 - .4 Jacket banding and mechanical seals: 12 mm wide, 0.5 mm thick stainless steel.
 - .1 Stainless steel:

- .5 Type: 304 316.
- .6 Thickness: 0.25 0.50 mm sheet.
- .7 Finish: Smooth Corrugated Stucco embossed.
- .8 Jacket banding and mechanical seals: 12 19 mm wide, 0.5 mm thick stainless steel.

2.4 ACCESSORIES

- .1 Vapour retarder lap adhesive:
 - .1 Water based, fire retardant type, compatible with insulation.
 - .1 Maximum VOC limit to SCAQMD Rule 1168 GSES GS-36.
- .2 Indoor Vapour Retarder Finish:
 - .1 Vinyl emulsion type acrylic, compatible with insulation.
- .3 Insulating Cement: hydraulic setting on mineral wool, to ASTM C449.
- .4 ULC Listed Canvas Jacket:
 - .1 220 gm/m² cotton, plain weave, treated with dilute fire retardant lagging adhesive to ASTM C921.
- .5 Outdoor Vapour Retarder Mastic:
 - .1 Vinyl emulsion type acrylic, compatible with insulation.
 - .2 Reinforcing fabric: Fibrous glass, untreated 305 g/m².
- .6 Tape: self-adhesive, aluminum, plain, 50 mm wide minimum.
- .7 Contact adhesive: quick-setting
 - .1 Maximum VOC limit to SCAQMD Rule 1168 GSES GS-36.
- .8 Canvas adhesive: washable.
 - .1 Maximum VOC limit to SCAQMD Rule 1168 GSES GS-36.
- .9 Tie wire: 1.5 mm stainless steel.
- .10 Banding: 12 mm wide, 0.5 mm thick stainless steel.
- .11 Facing: 25 mm stainless steel hexagonal wire mesh stitched on both faces of insulation.
- .12 Fasteners: 2 4 mm diameter pins with 35 mm diameter square clips, length to suit thickness of insulation.

Part 3 Execution

3.1 APPLICATION

- .1 Manufacturer's Instructions: comply with manufacturer's written recommendations, including product technical bulletins, handling, storage and installation instructions, and datasheets.

3.2 PRE-INSTALLATION REQUIREMENTS

- .1 Pressure test ductwork systems complete, witness and certify.
- .2 Ensure surfaces are clean, dry, free from foreign material.

3.3 INSTALLATION

- .1 Install in accordance with TIAC National Standards.
- .2 Apply materials in accordance with manufacturers instructions and as indicated.
- .3 Use 2 layers with staggered joints when required nominal thickness exceeds 75 mm.
- .4 Maintain uninterrupted continuity and integrity of vapour retarder jacket and finishes.
 - .1 Ensure hangers, and supports are outside vapour retarder jacket.
- .5 Hangers and supports in accordance with Section 23 05 29 - Hangers and Supports for HVAC Piping and Equipment.
 - .1 Apply high compressive strength insulation where insulation may be compressed by weight of ductwork.
- .6 Fasteners: install at 300 mm on centre in horizontal and vertical directions, minimum 2 rows each side.

3.4 DUCTWORK INSULATION SCHEDULE

- .1 Insulation types and thicknesses: conform to following table:

TIAC Code	Vapour Retarder	Thickness (mm)	
Rectangular cold and dual temperature supply air ducts	C-1	yes	50
Round cold and dual temperature supply air ducts	C-2	yes	50
Rectangular warm air ducts	C-1	no	25
Round warm air ducts	C-1	no	25
Supply, return and exhaust ducts exposed in space being served	none		
Outside air ducts to mixing plenum	C-1	yes	50
Mixing plenums	C-1	yes	25
Exhaust duct between dampers and louvres	C-1	no	25
Rectangular ducts outside	C-1	special	50
Round ducts outside	C-1	special	50
Acoustically lined ducts	none		

- .2 Exposed round ducts 600 mm and larger, smaller sizes where subject to abuse:
 - .1 Use TIAC code C-1 insulation, scored to suit diameter of duct.

.1 Finishes: conform to following table:

TIAC Code		
Rectangular	Round	
Indoor, concealed	none	none
Indoor, exposed within mechanical room	CRF/1	CRD/1
Indoor, exposed elsewhere	CRF/1	CRD/3
Outdoor, exposed to precipitation	CRF/3	CRD/3
Outdoor, elsewhere	CRF/3	CRD/3

3.5 CLEANING

- .1 Clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Remove surplus materials, excess materials, rubbish, tools and equipment.
- .2 Waste Management: separate waste materials in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 Section Includes:
 - .1 Thermal insulation for piping and piping accessories in commercial type applications.

1.2 REFERENCES

- .1 American Society of Heating, Refrigeration and Air Conditioning Engineers (ASHRAE)
 - .1 ASHRAE Standard 90.1 latest edition Energy Standard for Buildings Except Low-Rise Residential Buildings (IESNA co-sponsored; ANSI approved; Continuous Maintenance Standard).
- .2 American Society for Testing and Materials International (ASTM)
 - .1 ASTM B209M- latest edition, Standard Specification for Aluminum and Aluminum Alloy Sheet and Plate Metric.
 - .2 ASTM C335-latest edition, Standard Test Method for Steady State Heat Transfer Properties of Horizontal Pipe Insulation.
 - .3 ASTM C411-latest edition, Standard Test Method for Hot-Surface Performance of High-Temperature Thermal Insulation.
 - .4 ASTM C449/C449M-latest edition , Standard Specification for Mineral Fiber-Hydraulic-Setting Thermal Insulating and Finishing Cement.
 - .5 ASTM C533-latest edition, Calcium Silicate Block and Pipe Thermal Insulation.
 - .6 ASTM C547-latest edition, Mineral Fiber Pipe Insulation.
 - .7 ASTM C795-latest edition, Standard Specification for Thermal Insulation for Use in Contact with Austenitic Stainless Steel.
 - .8 ASTM C921-latest edition, Standard Practice for Determining the Properties of Jacketing Materials for Thermal Insulation.
- .3 Canadian General Standards Board (CGSB)
 - .1 CGSB 51-GP-52Ma-latest edition, Vapour Barrier, Jacket and Facing Material for Pipe, Duct and Equipment Thermal Insulation.
 - .2 CAN/CGSB-51.53-latest edition, Poly (Vinyl Chloride) Jacketing Sheet, for Insulated Pipes, Vessels and Round Ducts
- .4 Department of Justice Canada (Jus)
 - .1 Canadian Environmental Assessment Act (CEAA), 1995, c. 37.
 - .2 Canadian Environmental Protection Act (CEPA), 1999, c. 33.
 - .3 Transportation of Dangerous Goods Act (TDGA), 1992, c. 34.
- .5 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).
- .6 Manufacturer's Trade Associations

- .1 Thermal Insulation Association of Canada (TIAC): National Insulation Standards (Revised 2004).
- .7 Underwriters' Laboratories of Canada (ULC)
 - .1 CAN/ULC-S102-latest edition, Surface Burning Characteristics of Building Materials and Assemblies.
 - .2 CAN/ULC-S701-latest edition, Thermal Insulation, Polystyrene, Boards and Pipe Covering.
 - .3 CAN/ULC-S702-latest edition, Thermal Insulation, Mineral Fibre, for Buildings
 - .4 CAN/ULC-S702.2-latest edition, Thermal Insulation, Mineral Fibre, for Buildings, Part 2: Application Guidelines.

1.3 DEFINITIONS

- .1 For purposes of this section:
 - .1 "CONCEALED" - insulated mechanical services in suspended ceilings and non-accessible chases and furred-in spaces.
 - .2 "EXPOSED" - will mean "not concealed" as specified.
- .2 TIAC ss:
 - .1 CRF: Code Rectangular Finish.
 - .2 CPF: Code Piping Finish.

1.4 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's printed product literature, specifications and datasheet in accordance with Section 01 33 00 - Submittal Procedures. Include product characteristics, performance criteria, and limitations.
 - .1 Submit two copies of Workplace Hazardous Materials Information System (WHMIS) Material Safety Data Sheets (MSDS) in accordance with Section 01 33 00 - Submittal Procedures.
- .3 Shop Drawings:
 - .1 Submit shop drawings in accordance with Section 01 33 00 - Submittal Procedures.
 - .1 Shop drawings: submit drawings stamped and signed by professional engineer registered or licensed in Province of Manitoba, Canada.
- .4 Samples:
 - .1 Submit samples in accordance with Section 01 33 00 - Submittal Procedures.
 - .2 Submit for approval: complete assembly of each type of insulation system, insulation, coating, and adhesive proposed. Mount sample on 12 mm plywood board. Affix label beneath sample indicating service.
- .5 Quality assurance submittals: submit following in accordance with Section 01 33 00 - Submittal Procedures.

- .1 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
- .2 Instructions: submit manufacturer's installation instructions.
 - .1 Departmental Representative will make available 1 copy of systems supplier's installation instructions.

1.5 QUALITY ASSURANCE

- .1 Qualifications:
- .2 Installer: specialist in performing work of this Section, and have at least 3 years successful experience in this size and type of project, qualified to standards of TIAC.

1.6 DELIVERY, STORAGE AND HANDLING

- .1 Packing, shipping, handling and unloading:
 - .1 Deliver, store and handle in accordance with manufacturer's written instructions and Section 01 61 00 - Common Product Requirements.
 - .2 Deliver, store and handle materials in accordance with manufacturer's written instructions.
 - .3 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.
- .2 Storage and Protection:
 - .1 Protect from weather, construction traffic.
 - .2 Protect against damage.
 - .3 Store at temperatures and conditions required by manufacturer.
- .3 Waste Management and Disposal:
 - .1 Construction/Demolition Waste Management and Disposal: separate waste materials in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
 - .2 Place excess or unused insulation and insulation accessory materials in designated containers.
 - .3 Divert unused metal materials from landfill to metal recycling facility approved by Departmental Representative.
 - .4 Dispose of unused adhesive material at official hazardous material collections site approved by Departmental Representative.

Part 2 Products

2.1 FIRE AND SMOKE RATING

- .1 In accordance with CAN/ULC-S102.
 - .1 Maximum flame spread rating: 25.
 - .2 Maximum smoke developed rating: 50.

2.2 INSULATION

- .1 Mineral fibre specified includes glass fibre, rock wool, slag wool.
- .2 Thermal conductivity ("k" factor) not to exceed specified values at 24 degrees C mean temperature when tested in accordance with ASTM C335.
- .3 TIAC Code A-1: rigid moulded mineral fibre without factory applied vapour retarder jacket.
 - .1 Mineral fibre: to CAN/ULC-S702 ASTM C547.
 - .2 Maximum "k" factor: to CAN/ULC-S702.
- .4 TIAC Code A-3: rigid moulded mineral fibre with factory applied vapour retarder jacket.
 - .1 Mineral fibre: to CAN/ULC-S702.
 - .2 Jacket: to CGSB 51-GP-52Ma.
 - .3 Maximum "k" factor: to CAN/ULC-S702.
- .5 TIAC Code C-2: mineral fibre blanket faced with without factory applied vapour retarder jacket (as scheduled in PART 3 of this section).
 - .1 Mineral fibre: to CAN/ULC-S702 ASTM C547.
 - .2 Jacket: to CGSB 51-GP-52Ma.
 - .3 Maximum "k" factor: to CAN/ULC-S702 ASTM C547.
- .6 TIAC Code A-6: flexible unicellular tubular elastomer.
 - .1 Insulation: with vapour retarder jacket.
 - .2 Jacket: to CGSB 51-GP-52Ma.
 - .3 Certified by manufacturer: free of potential stress corrosion cracking corrodants.
- .7 TIAC Code A-2: rigid moulded calcium silicate in sections and blocks, and with special shapes to suit project requirements.
 - .1 Insulation: to ASTM C533.
 - .2 Design to permit periodic removal and re-installation.

2.3 INSULATION SECUREMENT

- .1 Tape: self-adhesive, aluminum, plain reinforced, 50 mm wide minimum.
- .2 Contact adhesive: quick setting.
- .3 Canvas adhesive: washable.
- .4 Tie wire: 1.5 mm diameter stainless steel.
- .5 Bands: stainless steel, 19mm wide, 0.5 mm thick.

2.4 CEMENT

- .1 Thermal insulating and finishing cement:
 - .1 Hydraulic setting Air drying on mineral wool, to ASTM C449/C449M.

2.5 VAPOUR RETARDER LAP ADHESIVE

- .1 Water based, fire retardant type, compatible with insulation.

2.6 INDOOR VAPOUR RETARDER FINISH

- .1 Vinyl emulsion type acrylic, compatible with insulation.

2.7 OUTDOOR VAPOUR RETARDER FINISH

- .1 Vinyl emulsion type acrylic, compatible with insulation.
- .2 Reinforcing fabric: fibrous glass, untreated 305 g/m².

2.8 JACKETS

- .1 Polyvinyl Chloride (PVC):
 - .1 One-piece moulded type and sheet to CAN/CGSB-51.53 with pre-formed shapes as required.
 - .2 Colours: by Departmental Representative.
 - .3 Minimum service temperatures: -20 degrees C.
 - .4 Maximum service temperature: 65 degrees C.
 - .5 Moisture vapour transmission: 0.02 perm.
 - .6 Thickness: 0.75 mm.
 - .7 Fastenings:
 - .1 Use solvent weld adhesive compatible with insulation to seal laps and joints.
 - .2 Tacks.
 - .3 Pressure sensitive vinyl tape of matching colour.
 - .8 Special requirements:
 - .1 Indoor: 0.5.
 - .2 Outdoor: UV rated material at least 0.5 mm thick.
- .2 ABS Plastic:
 - .1 One-piece moulded type and sheet with pre-formed shapes as required.
 - .2 Colours: by Departmental Representative.
 - .3 Minimum service temperatures: -40 degrees C.
 - .4 Maximum service temperature: 82 degrees C.
 - .5 Moisture vapour transmission: 0.012 perm.
 - .6 Thickness: 0.75 mm.
 - .7 Fastenings:
 - .1 Solvent weld adhesive compatible with insulation to seal laps and joints.
 - .2 Tacks.
 - .3 Pressure sensitive vinyl tape of matching colour.
 - .8 Locations:
 - .1 For outdoor use ONLY.

- .3 Canvas:
 - .1 220 and 120 gm/m² cotton, plain weave, treated with dilute fire retardant lagging adhesive to ASTM C921.
 - .2 Lagging adhesive: compatible with insulation.
- .4 Aluminum:
 - .1 To ASTM B209.
 - .2 Thickness: 0.50 mm sheet.
 - .3 Finish: smooth.
 - .4 Joining: longitudinal and circumferential slip joints with 50 mm laps.
 - .5 Fittings: 0.5 mm thick die-shaped fitting covers with factory-attached protective liner.
 - .6 Metal jacket banding and mechanical seals: stainless steel, 19 mm wide, 0.5mm thick at 300 mm spacing.

2.9 WEATHERPROOF CAULKING FOR JACKETS INSTALLED OUTDOORS

- .1 Caulking to: Section 07 92 00 - Joint Sealants.

Part 3 Execution

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.2 PRE-INSTALLATION REQUIREMENT

- .1 Pressure testing of piping systems and adjacent equipment to be complete, witnessed and certified.
- .2 Surfaces clean, dry, free from foreign material.

3.3 INSTALLATION

- .1 Install in accordance with TIAC National Standards.
- .2 Apply materials in accordance with manufacturers instructions and this specification.
- .3 Use two layers with staggered joints when required nominal wall thickness exceeds 75 mm.
- .4 Maintain uninterrupted continuity and integrity of vapour retarder jacket and finishes.
 - .1 Install hangers, supports outside vapour retarder jacket.
- .5 Supports, Hangers:
 - .1 Apply high compressive strength insulation, suitable for service, at oversized saddles and shoes where insulation saddles have not been provided.

3.4 REMOVABLE, PRE-FABRICATED, INSULATION AND ENCLOSURES

- .1 Application: at expansion joints, valves, primary flow measuring elements flanges and unions at equipment.
- .2 Design: to permit movement of expansion joint to permit periodic removal and replacement without damage to adjacent insulation.
- .3 Insulation:
 - .1 Insulation, fastenings and finishes: same as system.
 - .2 Jacket: high temperature fabric.

3.5 INSTALLATION OF ELASTOMERIC INSULATION

- .1 Insulation to remain dry. Overlaps to manufacturers instructions. Ensure tight joints.
- .2 Provide vapour retarder as recommended by manufacturer.

3.6 PIPING INSULATION SCHEDULES

- .1 Includes valves, valve bonnets, strainers, flanges and fittings unless otherwise specified.
- .2 TIAC Code: A-1.
 - .1 Securements: Tape at 300 mm on centre.
 - .2 Seals: lap seal adhesive, lagging adhesive.
 - .3 Installation: TIAC Code 1501-H.
- .3 TIAC Code: A-3.
 - .1 Securements: Tape at 300 mm on centre.
 - .2 Seals: VR lap seal adhesive, VR lagging adhesive.
 - .3 Installation: TIAC Code: 1501-C.
- .4 TIAC Code: A-6.
 - .1 Insulation securements: Tape.
 - .2 Seals: lap seal adhesive, lagging adhesive.
 - .3 Installation: TIAC Code: 1501-C.
- .5 TIAC Code: C-2 with without vapour retarder jacket.
 - .1 Insulation securements: Tape.
 - .2 Seals: lap seal adhesive, lagging adhesive.
 - .3 Installation: TIAC Code: 1501-C.
- .6 TIAC Code: A-2.
 - .1 Insulation securements: Tape.
 - .2 Seals: lap seal adhesive, lagging adhesive.
 - .3 Installation: TIAC Code: 1501-H.
- .7 Thickness of insulation as listed in following table.
 - .1 Run-outs to individual units and equipment not exceeding 4000 mm long.

- .2 Do not insulate exposed runouts to plumbing fixtures, chrome plated piping, valves, fittings.

Applica-tion	Temp degrees C	TIAC code	Pipe sizes (NPS) and insulation thickness (mm)										
Run out	to 1	1 1/4 to 2	2 1/2 to 4	5 to 6	8	up to 175	A-1	38	50	65	75		
Hot Water Heating	60 - 94	A-1	25	38	38	38	38	38	25	25	38		
Hot Water Heating	up to 59	A-1	25	25	25	25	38	38	25	25	38		
Domestic HWS	A-1	25	25	25	38	38	38	25	25	25	38		
Refrigerated Drinking Water	A-3	25	25	25	25	25	25						
Domestic CWS	A-3	25	25	25	25	25	25	25	25	25	25		
Domestic CWS with vapour retarder	C-2	25	25	25	25	25	25	25	25	25	25		
Refrigerant hot gas liquid suction	4 - 13	A-6	25	25	25	25	25	25					
Refrigerant hot gas liquid suction	below 4	A-6	25	25	38	38	38	38					
RWL and RWP	C-2	25	25	25	25	25	25	25	25	25	25	25	25
Cooling Coil cond. drain	C-2	25	25	25	25	25	25						

.8 Finishes:

- .1 Exposed indoors: canvas jacket.
- .2 Exposed in mechanical rooms: canvas jacket.
- .3 Concealed, indoors: canvas on valves, fittings. No further finish.
- .4 Use vapour retarder jacket on TIAC code A-3 insulation compatible with insulation.
- .5 Outdoors: water-proof aluminum.
- .6 Finish attachments: SS bands, at 150 mm on centre. Seals: wing.
- .7 Installation: to appropriate TIAC code CRF/1 through CPF/4.

3.7 FIELD QUALITY CONTROL

- .1 Verification requirements in accordance with Section 01 47 17 - Sustainable Requirements: Contractor's Verification, include:
 - .1 Materials and resources.
 - .2 Storage and collection of recyclables.
 - .3 Construction waste management.
 - .4 Resource reuse.
 - .5 Recycled content.
 - .6 Local/regional materials.
 - .7 Certified wood.
 - .8 Low-emitting materials.

3.8 CLEANING

- .1 Proceed in accordance with Section 01 74 11 - Cleaning.
- .2 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION

Part 1 General

1.1 GASEOUS FUEL SYSTEMS

- .1 Operation tests:
 - .1 Measure gas pressure at gas meter outlet and at burner manifold.
 - .2 Verify details of temperature and pressure compensation at meter.
 - .3 Verify settings, operation, venting of high and low pressure cut-outs, alarms.
 - .4 Check terminals of vents for gas pressure regulators.

1.2 POTABLE WATER SYSTEMS

- .1 When cleaning is completed and system filled:
 - .1 Verify performance of equipment and systems as specified elsewhere in Division 23.
 - .2 Check for proper operation of water hammer arrestors. Run one outlet for 10 seconds, then shut off water immediately. If water hammer occurs, replace water hammer arrestor or recharge air chambers. Repeat for each outlet and flush valve.
 - .3 Confirm water quality consistent with supply standards, verifying that no residuals remain resulting from flushing and/or cleaning.

1.3 WET AND DRY PIPE SPRINKLER SYSTEM, STANDPIPE AND HOSE SYSTEMS

- .1 Cleaning, testing, start-up, performance verification of equipment, systems, components, and devices is specified elsewhere in Division 23.
- .2 Verification of controls, detection devices, alarm devices is specified Division 26.
- .3 Demonstrate that fire hose will reach to most remote location regardless of partitions, and obstructions.
- .4 Verify operation of interlocks between HVAC systems and fire alarm systems.

1.4 SANITARY AND STORM DRAINAGE SYSTEMS

- .1 Buried systems: perform tests prior to back-filling. Perform hydraulic tests to verify grades and freedom from obstructions.
- .2 Ensure that traps are fully and permanently primed.
- .3 Ensure that fixtures are properly anchored, connected to system.
- .4 Operate flush valves, tank and operate each fixture to verify drainage and no leakage.
- .5 Cleanouts: refer to Section 22 42 01 – Plumbing Specialties and Accessories
- .6 Roof drains:
 - .1 Refer to Section 22 42 01 – Plumbing Specialties and Accessories
 - .2 Remove caps as required.

1.5 REPORTS

- .1 In accordance with Section 01 91 13 - General Commissioning (Cx) Requirements:
Reports, supplemented as specified herein.

1.6 TRAINING

- .1 In accordance with Section 01 91 13 - General Commissioning (Cx) Requirements:
Training of O M Personnel, supplemented as specified herein.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 Section Includes:
 - .1 Materials and installation for piping, valves and fittings for gas fired equipment.
 - .2 Sustainable requirements for construction and verification:

1.2 REFERENCES

- .1 American Society of Mechanical Engineers (ASME)
 - .1 ASME B16.5-latest edition, Pipe Flanges and Flanged Fittings.
 - .2 ASME B16.18-latest edition, Cast Copper Alloy Solder Joint Pressure Fittings.
 - .3 ASME B16.22-latest edition, Wrought Copper and Copper Alloy Solder-Joint Pressure Fittings.
 - .4 ASME B18.2.1-latest edition, Square and Hex Bolts and Screws Inch Series.
- .2 American Society for Testing and Materials International (ASTM)
 - .1 ASTM A47/A47M-99(2004), Standard Specification for Ferritic Malleable Iron Castings.
 - .2 ASTM A53/A53M-latest edition, Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc Coated, Welded and Seamless.
 - .3 ASTM B75M-latest edition, Standard Specification for Seamless Copper Tube Metric.
 - .4 ASTM B837-latest edition, Standard Specification for Seamless Copper Tube for Natural Gas and Liquefied Petroleum (LP) Gas Fuel Distribution Systems.
- .3 Canadian Standards Association (CSA International)
 - .1 CSA W47.1-latest edition, Certification of Companies for Fusion Welding of Steel.
- .4 Canadian Standards Association (CSA)/Canadian Gas Association (CGA)
 - .1 CAN/CSA B149.1HB-latest edition, Natural Gas and Propane Installation Code Handbook.
 - .2 CAN/CSA B149.2-latest edition, Propane Storage and Handling Code.
- .5 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's printed product literature, specifications and datasheet for piping, fittings and equipment.

- .3 Test Reports: submit certified test reports from approved independent testing laboratories indicating compliance with specifications for specified performance characteristics and physical properties.
- .4 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
- .5 Instructions: submit manufacturer's installation instructions.
- .6 Closeout Submittals: submit maintenance and engineering data for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Waste Management and Disposal:
 - .1 Separate waste materials in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
 - .2 Remove from site and dispose of packaging materials at appropriate recycling facilities.
 - .3 Divert unused materials from landfill to recycling facility as approved by Departmental Representative.

Part 2 Products

2.1 PIPE

- .1 Steel pipe: to ASTM A53/A53M, Schedule 40, seamless as follows:
 - .1 NPS 1/2 to 2, screwed.
 - .2 NPS 2 1/2 and over, plain end.
- .2 Copper tube: to ASTM B837.

2.2 JOINTING MATERIAL

- .1 Screwed fittings: pulverized lead paste.
- .2 Welded fittings: to CSA W47.1.
- .3 Flange gaskets: nonmetallic flat.
- .4 Brazing: to ASTM B837.

2.3 FITTINGS

- .1 Steel pipe fittings, screwed, flanged or welded:
 - .1 Malleable iron: screwed, banded, Class 150.
 - .2 Steel pipe flanges and flanged fittings: to ASME B16.5.
 - .3 Welding: butt-welding fittings.
 - .4 Unions: malleable iron, brass to iron, ground seat, to ASTM A47/A47M.
 - .5 Bolts and nuts: to ASME B18.2.1.
 - .6 Nipples: schedule 40, to ASTM A53/A53M.

- .2 Copper pipe fittings, screwed, flanged or soldered:
 - .1 Cast copper fittings: to ASME B16.18.
 - .2 Wrought copper fittings: to ASME B16.22.

2.4 VALVES

- .1 Provincial Code approved, lubricated plug ball type.

Part 3 Execution

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.2 PIPING

- .1 Install in accordance with Section 23 05 05 - Installation of Pipework, applicable Provincial/Territorial Codes, CAN/CSA B149.1, CAN/CSA B149.2,, supplemented as specified.
- .2 Install drip points:
 - .1 At low points in piping system.
 - .2 At connections to equipment.

3.3 VALVES

- .1 Install valves with stems upright or horizontal unless otherwise approved by Departmental Representative.
- .2 Install valves at branch take-offs to isolate pieces of equipment, and as indicated.

3.4 FIELD QUALITY CONTROL

- .1 Site Tests/Inspection:
 - .1 Test system in accordance with CAN/CSA B149.1 CAN/CSA B149.2 and requirements of authorities having jurisdiction.
- .2 Manufacturer's Field Services:
 - .1 Have manufacturer of products supplied under this Section review work involved in handling, installation/application, protection and cleaning of its products, and submit written reports, in acceptable format, to verify compliance of work with Contract.
 - .2 Provide manufacturer's field services, consisting of product use recommendations and periodic site visits for inspection of product installation, in accordance with manufacturer's instructions.
- .3 Obtain reports within 3 days of review and submit immediately to Departmental Representative DCC Representative Consultant.

- .4 Verification requirements in accordance with Section 01 47 17 - Sustainable Requirements: Contractor's Verification, include:
 - .1 Materials and resources.
 - .2 Storage and collection of recyclables.
 - .3 Construction waste management.
 - .4 Resource reuse.
 - .5 Recycled content.
 - .6 Local/regional materials.
 - .7 Certified wood.
 - .8 Low-emitting materials.
- .5 Performance Verification:
 - .1 Refer to Section 23 08 01 - Performance Verification of Mechanical Piping Systems.

3.5 ADJUSTING

- .1 Purging: purge after pressure test in accordance with CAN/CSA B149.1 CAN/CSA B149.2.
- .2 Pre-Start-Up Inspections:
 - .1 Check vents from regulators, control valves, terminate outside building in approved location, protected against blockage, damage.
 - .2 Check gas trains, entire installation is approved by authority having jurisdiction.

3.6 CLEANING

- .1 Cleaning: in accordance with Section CAN/CSA B149.1, CAN/CSA B149.2,, supplemented as specified.
- .2 Perform cleaning operations as specified in accordance with manufacturer's recommendations.
- .3 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 ASME
 - .1 ASME Boiler and Pressure Vessel Code (BPVC), Section VII latest edition.
- .2 ASTM International
 - .1 ASTM A47/A47M-99, Standard Specification for Ferritic Malleable Iron Castings.
 - .2 ASTM A278/A278M-01, Standard Specification for Gray Iron Castings for Pressure-Containing Parts for Temperatures up to 650 degrees F (350 degrees C).
 - .3 ASTM A516/A516M-10, Standard Specification for Pressure Vessel Plates, Carbon Steel, for Moderate - and Lower - Temperature Service.
 - .4 ASTM A536-84, Standard Specification for Ductile Iron Castings.
 - .5 ASTM B62-09, Standard Specification for Composition Bronze or Ounce Metal Castings.
- .3 CSA Group
 - .1 CSA B51-latest edition, Boiler, Pressure Vessel, and Pressure Piping Code.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for expansion tanks, air vents, separators, valves, and strainers and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Shop Drawings:
 - .1 Submit drawings stamped and signed by professional engineer registered or licensed in Province of Manitoba, Canada.
- .4 Submit in accordance with Section 01 78 00 - Closeout Submittals.
- .5 Operation and Maintenance Data: submit operation and maintenance data for hydronic specialties for incorporation into manual.
- .6 Submit 3 copies of operation and maintenance manual.

1.3 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:

- .1 Store materials in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
- .2 Store and protect hydronic specialties from nicks, scratches, and blemishes.
- .3 Replace defective or damaged materials with new.
- .4 Develop Construction Waste Management Plan related to Work of this Section.
- .5 Packaging Waste Management: remove for reuse as specified in Construction Waste Management Plan Waste Reduction Workplan in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

Part 2 Products

2.1 AUTOMATIC AIR VENT

- .1 Standard float vent: brass body and NPS 1/8 connection and rated at working pressure.
- .2 Industrial float vent: cast iron body and NPS 1/2 connection and rated at 860 kPa working pressure.
- .3 Float: solid material suitable for 115 degrees C working temperature.

Part 3 Execution

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for hydronic specialties installation in accordance with manufacturer's written instructions.

3.2 APPLICATION

- .1 Manufacturer's Instructions: comply with manufacturer's written recommendations, including product technical bulletins, handling, storage and installation instructions, and data sheets.

3.3 GENERAL

- .1 Run drain lines and blow off connections to terminate above nearest drain.
- .2 Maintain adequate clearance to permit service and maintenance.
- .3 Should deviations beyond allowable clearances arise, request and follow Departmental Representative's directive.
- .4 Check shop drawings for conformance of tappings for ancillaries and for equipment operating weights.

3.4 STRAINERS

- .1 Install in horizontal or down flow lines.
- .2 Ensure clearance for removal of basket.
- .3 Install ahead of each pump.

- .4 Install ahead of each automatic control valve larger than NPS 1 and radiation and as indicated.

3.5 AIR VENTS

- .1 Install at high points of systems.
- .2 Install gate valve on automatic air vent inlet. Run discharge to nearest drain service sink.

3.6 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .3 Waste Management: separate waste in accordance with Section 01 74 21 - Construction/Demolition Waste Management and.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 ASME
 - .1 ASME B16.22-latest edition, Wrought Copper and Copper Alloy Solder - Joint Pressure Fittings.
 - .2 ASME B16.24-latest edition, Cast Copper Pipe Flanges and Flanged Fittings: Class 150, 300, 600, 900, 1500 and 2500.
 - .3 ASME B16.26-latest edition, Cast Copper Alloy Fittings for Flared Copper Tubes.
 - .4 ASME B31.5-latest edition, Refrigeration Piping and Heat Transfer Components.
- .2 ASTM International
 - .1 ASTM A307-latest edition, Standard Specification for Carbon Steel Bolts and Studs, and Threaded Rod 60,000 PSI Tensile Strength.
 - .2 ASTM B280-latest edition, Standard Specification for Seamless Copper Tube for Air Conditioning and Refrigeration Field Service.
- .3 CSA Group
 - .1 CSA B52-05(R2009), B52 Package, Mechanical Refrigeration Code.
- .4 Environment Canada (EC)
 - .1 EPS 1/RA/1-latest edition, Environmental Code of Practice for the Elimination of Fluorocarbon Emissions from Refrigeration and Air Conditioning Systems.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for refrigerant piping, fittings and equipment and include product characteristics, performance criteria, physical size, finish and limitations.
 - .2 Submit 2 copies of WHMIS MSDS in accordance with Section 01 35 43 - Environmental Procedures. Indicate VOC's for adhesive and solvents during application and curing.
- .3 Test Reports: submit certified test reports from approved independent testing laboratories indicating compliance with specifications for specified performance characteristics and physical properties.
- .4 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.

1.3 CLOSEOUT SUBMITTALS

- .1 Submit in accordance with Section 01 78 00 - Closeout Submittals.

- .2 Operation and Maintenance Data: submit operation and maintenance data for refrigerant piping for incorporation into manual.
- .3 Submit 3 copies of operation and maintenance manual.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect refrigerant piping, fittings and equipment from nicks, scratches, and blemishes.
 - .3 Replace defective or damaged materials with new.
- .4 Develop Construction Waste Management Plan related to Work of this Section.
- .5 Packaging Waste Management: remove as specified in Construction Waste Management Plan in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

Part 2 Products

2.1 TUBING

- .1 Processed for refrigeration installations, deoxidized, dehydrated and sealed.
 - .1 Hard copper: to ASTM B280, type ACR B.
 - .2 Annealed copper: to ASTM B280, with minimum wall thickness as per CSA B52 and ASME B31.5.

2.2 FITTINGS

- .1 Service: design pressure 2070 kPa and temperature 121 degrees C.
- .2 Brazed:
 - .1 Fittings: wrought copper to ASME B16.22.
 - .2 Joints: silver solder, and non-corrosive flux.
- .3 Flanged:
 - .1 Bronze or brass, to ASME B16.24, Class 150 and Class 300.
 - .2 Gaskets: suitable for service.
 - .3 Bolts, nuts and washers: to ASTM A307, heavy series.
- .4 Flared:
 - .1 Bronze or brass, for refrigeration, to ASME B16.26.

2.3 PIPE SLEEVES

- .1 Hard copper or steel, sized to provide 6 mm clearance around between sleeve and uninsulated pipe or between sleeve and insulation.

2.4 VALVES

- .1 22 mm and under: Class 500, 3.5 Mpa, globe or angle non-directional type, diaphragm, packless type, with forged brass body and bonnet, moisture proof seal for below freezing applications, brazed connections.
- .2 Over 22 mm: Class 375, 2.5 Mpa, globe or angle type, diaphragm, packless type, back-seating, cap seal, with cast bronze body and bonnet, moisture proof seal for below freezing applications, brazed connections.

Part 3 Execution

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for refrigerant piping installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental Representative
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied and after receipt of written approval to proceed from Departmental Representative.

3.2 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.3 GENERAL

- .1 Install in accordance with CSA B52, EPS1/RA/1 and ASME B31.5 Section 23 05 05 - Installation of Pipework.

3.4 BRAZING PROCEDURES

- .1 Bleed inert gas into pipe during brazing.
- .2 Remove valve internal parts, solenoid valve coils, sight glass.
- .3 Do not apply heat near expansion valve and bulb.

3.5 PIPING INSTALLATION

- .1 General:
 - .1 Soft annealed copper tubing: bend without crimping or constriction Hard drawn copper tubing: do not bend. Minimize use of fittings.

- .2 Hot gas lines:
 - .1 Pitch at least 1:240 down in direction of flow to prevent oil return to compressor during operation.
 - .2 Provide trap at base of risers greater than 2400 mm high and at each 7600 mm thereafter.
 - .3 Provide inverted deep trap at top of risers.
 - .4 Provide double risers for compressors having capacity modulation.
 - .1 Large riser: install traps as specified.
 - .2 Small riser: size for 5.1 m³/s at minimum load. Connect upstream of traps on large riser.

3.6 PRESSURE AND LEAK TESTING

- .1 Close valves on factory charged equipment and other equipment not designed for test pressures.
- .2 Leak test to CSA B52 before evacuation to 2 MPa and 1 MPa on high and low sides respectively.
- .3 Test procedure: build pressure up to 35 kPa with refrigerant gas on high and low sides. Supplement with nitrogen to required test pressure. Test for leaks with electronic or halide detector. Repair leaks and repeat tests.

3.7 FIELD QUALITY CONTROL

- .1 Site Tests/Inspection:
 - .1 Close service valves on factory charged equipment.
- .2 Ambient temperatures to be at least 13 degrees C for at least 12 hours before and during dehydration.
- .3 Use copper lines of largest practical size to reduce evacuation time.
- .4 Use two-stage vacuum pump with gas ballast on 2nd stage capable of pulling 5 Pa absolute and filled with dehydrated oil.
- .5 Measure system pressure with vacuum gauge. Take readings with valve between vacuum pump and system closed.
- .6 Triple evacuate system components containing gases other than correct refrigerant or having lost holding charge as follows:
 - .1 Twice to 14 Pa absolute and hold for 4 hours.
 - .2 Break vacuum with refrigerant to 14 kPa.
 - .3 Final to 5 Pa absolute and hold for at least 12 hours.
 - .4 Isolate pump from system, record vacuum and time readings until stabilization of vacuum.
 - .5 Submit test results to Departmental Representative
- .7 Charging:
 - .1 Charge system through filter-drier and charging valve on high side. Low side charging not permitted.

- .2 With compressors off, charge only amount necessary for proper operation of system. If system pressures equalize before system is fully charged, close charging valve and start up. With unit operating, add remainder of charge to system.
- .3 Re-purge charging line if refrigerant container is changed during charging process.
- .8 Checks:
 - .1 Make checks and measurements as per manufacturer's operation and maintenance instructions.
 - .2 Record and report measurements to Departmental Representative
- .9 Manufacturer's Field Services:
 - .1 Have manufacturer of products, supplied under this Section, review Work involved in the handling, installation/application, protection and cleaning, of its products and submit written reports, in acceptable format, to verify compliance of Work with Contract.
 - .2 Provide manufacturer's field services consisting of product use recommendations and periodic site visits for inspection of product installation in accordance with manufacturer's instructions.
 - .3 Obtain reports, within 3 days of review, and submit, immediately, to Departmental Representative

3.8 DEMONSTRATION

- .1 Instructions:
 - .1 Post instructions in frame with glass cover in accordance with Section 01 78 00 - Closeout Submittals and CSA B52.

3.9 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .3 Waste Management: separate waste materials in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 Canada Green Building Council (CaGBC)
- .2 Sheet Metal and Air Conditioning Contractors' National Association (SMACNA)
 - .1 SMACNA - HVAC Duct Construction Standards - Metal and Flexible, latest edition.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for air duct accessories and include product characteristics, performance criteria, physical size, finish and limitations.
 - .2 Indicate:
 - .1 Flexible connections.
 - .2 Duct access doors.
 - .3 Turning vanes.
 - .4 Instrument test ports.
- .3 Sustainable Design Submittals:
 - .1 Construction Waste Management:
 - .1 Submit project Waste Management Plan highlighting recycling and salvage requirements.

1.3 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect air duct accessories from nicks, scratches, and blemishes.
 - .3 Replace defective or damaged materials with new.
- .4 Develop Construction Waste Management Plan related to Work of this Section.
- .5 Packaging Waste Management: remove for reuse as specified in Construction Waste Management Plan in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

Part 2 Products

2.1 GENERAL

- .1 Manufacture in accordance with SMACNA - HVAC Duct Construction Standards.

2.2 FLEXIBLE CONNECTIONS

- .1 Frame: galvanized sheet metal frame with fabric clenched by means of double locked seams.
- .2 Material:
 - .1 Fire resistant, self extinguishing, neoprene coated glass fabric, temperature rated at minus 40 degrees C to plus 90 degrees C, density of 1.3 kg/m².

2.3 ACCESS DOORS IN DUCTS

- .1 Non-Insulated Ducts: sandwich construction of same material as duct, one sheet metal thickness heavier, minimum 0.6 mm thick complete with sheet metal angle frame.
- .2 Insulated Ducts: sandwich construction of same material as duct, one sheet metal thickness heavier, minimum 0.6 mm thick complete with sheet metal angle frame and 25 mm thick rigid glass fibre insulation.
- .3 Gaskets: neoprene.
- .4 Hardware:
 - .1 Up to 300 x 300 mm: two sash locks complete with safety chain.
 - .2 301 to 450 mm: four sash locks complete with safety chain.
 - .3 451 to 1000 mm: piano hinge and minimum two sash locks.
 - .4 Doors over 1000 mm: piano hinge and two handles operable from both sides.
 - .5 Hold open devices.

2.4 TURNING VANES

- .1 Factory or shop fabricated single thickness double thickness with without trailing edge, to recommendations of SMACNA and as indicated.

2.5 INSTRUMENT TEST

- .1 1.6 mm thick steel zinc plated after manufacture.
- .2 Cam lock handles with neoprene expansion plug and handle chain.
- .3 28 mm minimum inside diameter. Length to suit insulation thickness.
- .4 Neoprene mounting gasket.

2.6 SPIN-IN COLLARS

- .1 Conical galvanized sheet metal spin-in collars with lockable butterfly damper.
- .2 Sheet metal thickness to co-responding round duct standards.

Part 3 Execution

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for air duct accessories installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental Representative.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied and after receipt of written approval to proceed from Departmental Representative.

3.2 INSTALLATION

- .1 Flexible Connections:
 - .1 Install in following locations:
 - .1 Inlets and outlets to supply air units and fans.
 - .2 Inlets and outlets of exhaust and return air fans.
 - .3 As indicated.
 - .2 Length of connection: 100 mm.
 - .3 Minimum distance between metal parts when system in operation: 75 mm.
 - .4 Install in accordance with recommendations of SMACNA.
 - .5 When fan is running:
 - .1 Ducting on sides of flexible connection to be in alignment.
 - .2 Ensure slack material in flexible connection.
 - .6 Locations:
 - .1 Fire and smoke dampers.
 - .2 Control dampers.
 - .3 Devices requiring maintenance.
 - .4 Required by code.
 - .5 Reheat coils, upstream/downstream.
 - .6 Elsewhere as indicated.
- .2 Instrument Test Ports:
 - .1 General:
 - .1 Install in accordance with recommendations of SMACNA and in accordance with manufacturer's instructions.
 - .2 Locate to permit easy manipulation of instruments.
 - .3 Install insulation port extensions as required.
 - .4 Locations:
 - .1 For traverse readings:
 - .1 Ducted inlets to roof and wall exhausters.

- .2 Inlets and outlets of other fan systems.
 - .3 Main and sub-main ducts.
 - .4 And as indicated.
- .2 For temperature readings:
 - .1 At outside air intakes.
 - .2 In mixed air applications in locations as approved by Departmental Representative.
 - .3 At inlet and outlet of coils.
 - .4 Downstream of junctions of two converging air streams of different temperatures.
 - .5 And as indicated.
- .3 Turning Vanes:
 - .1 Install in accordance with recommendations of SMACNA and as indicated.
- .4 Control Dampers:
 - .1 Install control dampers as provided by 25 30 02.

3.3 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .3 Waste Management: separate waste materials in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 Canada Green Building Council (CaGBC)
- .2 Sheet Metal and Air Conditioning National Association (SMACNA)
 - .1 SMACNA HVAC Duct Construction Standards, Metal and Flexible-2013.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for dampers and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Sustainable Design Submittals:
 - .1 Construction Waste Management:
 - .1 Submit project Waste Management Plan highlighting recycling and salvage requirements.

1.3 CLOSEOUT SUBMITTALS

- .1 Submit in accordance with Section 01 78 00 - Closeout Submittals.
- .2 Operation and Maintenance Data: submit operation and maintenance data for dampers for incorporation into manual.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect dampers from nicks, scratches, and blemishes.
 - .3 Replace defective or damaged materials with new.
- .4 Develop Construction Waste Management Plan related to Work of this Section.
- .5 Packaging Waste Management: remove for reuse as specified in Construction Waste Management Plan in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

Part 2 Products

2.1 GENERAL

- .1 Manufacture to SMACNA standards.

2.2 SPLITTER DAMPERS

- .1 Fabricate from same material as duct but one sheet metal thickness heavier, with appropriate stiffening.
- .2 Double thickness construction.
- .3 Control rod with locking device and position indicator.
- .4 Rod configuration to prevent end from entering duct.
- .5 Pivot: piano hinge.
- .6 Folded leading edge.

2.3 SINGLE BLADE DAMPERS

- .1 Fabricate from same material as duct, but one sheet metal thickness heavier. V-groove stiffened.
- .2 Size and configuration to recommendations of SMACNA, except maximum height as indicated.
- .3 Locking quadrant with shaft extension to accommodate insulation thickness.
- .4 Inside and outside bronze end bearings.
- .5 Channel frame of same material as adjacent duct, complete with angle stop.

2.4 MULTI-BLADED DAMPERS

- .1 Factory manufactured of material compatible with duct.
- .2 Opposed blade: configuration, metal thickness and construction to recommendations of SMACNA.
- .3 Maximum blade height: as indicated.
- .4 Bearings: pin in bronze bushings.
- .5 Linkage: shaft extension with locking quadrant.
- .6 Channel frame of same material as adjacent duct, complete with angle stop.

Part 3 Execution

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for damper installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental Representative.

- .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
- .3 Proceed with installation only after unacceptable conditions have been remedied and after receipt of written approval to proceed from Departmental Representative.

3.2 INSTALLATION

- .1 Install where indicated.
- .2 Install in accordance with recommendations of SMACNA and in accordance with manufacturer's instructions.
- .3 Locate balancing dampers in each branch duct, for supply, return and exhaust systems.
- .4 Runouts to registers and diffusers: install single blade damper located as close as possible to main ducts.
- .5 Dampers: vibration free.
- .6 Ensure damper operators are observable and accessible.
- .7 Corrections and adjustments conducted by Departmental Representative.

3.3 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .3 Waste Management: separate waste in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 Canada Green Building Council (CaGBC)
- .2 National Fire Protection Association (NFPA)
 - .1 NFPA 90A-latest edition, Standard for the Installation of Air Conditioning and Ventilating Systems.
- .3 Underwriters Laboratories of Canada (ULC)
 - .1 CAN/ULC-S112-latest edition, Standard Test Method of Fire Test of Fire Damper Assemblies.
 - .2 CAN/ULC-S112.2-latest edition, Standard Method of Fire Test of Ceiling Fire Stop Flap Assemblies.
 - .3 ULC-S505-1974, Standard for Fusible Links for Fire Protection Service.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for fire and smoke dampers and include product characteristics, performance criteria, physical size, finish and limitations.
 - .2 Indicate the following:
 - .1 Fire dampers.
 - .2 Smoke dampers.
 - .3 Fire stop flaps.
 - .4 Operators.
 - .5 Fusible links.
 - .6 Design details of break-away joints.
- .3 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.

1.3 CLOSEOUT SUBMITTALS

- .1 Submit in accordance with Section 01 78 00 - Closeout Submittals.
- .2 Operation and Maintenance Data: submit operation and maintenance data for fire and smoke dampers for incorporation into manual.

1.4 MAINTENANCE MATERIAL SUBMITTALS

- .1 Extra Materials:
 - .1 Submit maintenance materials in accordance with Section 01 78 00 - Closeout Submittals.

- .2 Provide:
 - .1 6 fusible links of each type.

1.5 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect fire and smoke dampers from nicks, scratches, and blemishes.
 - .3 Replace defective or damaged materials with new.
- .4 Develop Construction Waste Management Plan related to Work of this Section.
- .5 Packaging Waste Management: remove as specified in Construction Waste Management Plan in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

Part 2 Products

2.1 FIRE DAMPERS

- .1 Fire dampers: arrangement Type A, B, C, listed bear label of ULC, UL Warnock Hersey, meet requirements of authorities having jurisdiction provincial fire authority Fire Commissioner of Canada (FCC) CFFM and NFPA 90A. Fire damper assemblies fire tested in accordance with CAN/ULC-S112.
- .2 Mild steel, factory fabricated for fire rating requirement to maintain integrity of fire wall and/or fire separation.
 - .1 Fire dampers: 1 hour fire rated unless otherwise indicated.
 - .2 Fire dampers: automatic operating type and have dynamic rating suitable for maximum air velocity and pressure differential to which it will be subjected.
- .3 Top hinged: offset, round or square; sized to maintain full duct cross section.
- .4 Fusible link actuated, weighted to close and lock in closed position when released or having negator-spring-closing operator for multi-leaf type or roll door type in horizontal position with vertical air flow.
- .5 40 x 40 x 3 mm retaining angle iron frame, on full perimeter of fire damper, on both sides of fire separation being pierced.
- .6 Equip fire dampers with steel sleeve or frame installed disruption ductwork or impair damper operation.
- .7 Equip sleeves or frames with perimeter mounting angles attached on both sides of wall or floor opening. Construct ductwork in fire-rated floor-ceiling or roof-ceiling assembly systems with air ducts that pierce ceiling to conform with ULC.

- .8 Design and construct dampers to not reduce duct or air transfer opening cross-sectional area.
- .9 Dampers shall be installed so that the centerline of the damper depth or thickness is located in the centerline of the wall, partition or floor slab depth or thickness.
- .10 Unless otherwise indicated, the installation details given in SMACNA Install Fire Damp HVAC and in manufacturer's instructions for fire dampers shall be followed.

2.2 SMOKE DAMPERS

- .1 Smoke Dampers: to be ULC or UL listed and labelled.
- .2 Normally closed reverse action smoke vent (S/D-RASV): folding blade type, opening by gravity upon detection of smoke, and/or from remote alarm signalling device actuated by an electro thermal link as indicated. Two flexible stainless steel blade edge seals to provide required constant sealing pressure.
- .3 Normally open smoke/seal (S/D-SSSD): folding blade type, closing when actuated by means of electro thermal link and/or from remote alarm signalling device. Blade edge seals of flexible stainless steel to provide required constant sealing pressure. Provide stainless steel negator springs with locking devices to ensure positive closure for units mounted horizontally in vertical ducts.
- .4 Motorized (S/D-M): folding blade type, normally open with power on. When power is interrupted damper shall close automatically. Both damper and damper operator shall be ULC listed and labelled.
- .5 Electro thermal link (S/D-ETL): dual responsive fusible link which melts when subjected to local heat of 74 degrees C and from external electrical impulse of low power and short duration; ULC or UL listed and labelled.

2.3 COMBINATION FIRE AND SMOKE DAMPERS

- .1 Damper: similar to smoke dampers specified above.
- .2 Combined actuator: electrical control system actuated from smoke sensor or smoke detection system and from fusible link.

2.4 FIRE STOP FLAPS

- .1 Fire smoke flaps: ULC listed and labelled and fire tested in accordance with CAN/ULC-S112.2.
- .2 Construct of minimum 1.5 mm thick sheet steel with 1.6 mm thick non-asbestos ULC listed insulation and corrosion-resistant pins and hinges.
- .3 Flaps held open with fusible link conforming to ULC-S505 and close at 74 degrees C.

Part 3 Execution

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for fire and smoke damper installation in accordance with manufacturer's written instructions.

- .1 Visually inspect substrate in presence of Departmental Representative.
- .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
- .3 Proceed with installation only after unacceptable conditions have been remedied and after receipt of written approval to proceed from Departmental Representative.

3.2 INSTALLATION

- .1 Install in accordance with NFPA 90A and in accordance with conditions of ULC listing.
- .2 Maintain integrity of fire separation.
- .3 After completion and prior to concealment obtain approvals of complete installation from authority having jurisdiction.
- .4 Install access door adjacent to each damper. See Section 23 33 00 - Air Duct Accessories.
- .5 Co-ordinate with installer of fire stopping.
- .6 Ensure access doors/panels, fusible links, damper operators are easily observed and accessible.
- .7 Install break-away joints of approved design on each side of fire separation.

3.3 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .3 Waste Management: separate waste in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 ASTM International
 - .1 ASTM C423-latest edition, Standard Test Method for Sound Absorption and Sound Absorption Coefficients by the Reverberation Room Method.
 - .2 ASTM C916-latest edition, Standard Specification for Adhesives for Duct Thermal Insulation.
 - .3 ASTM C1071-latest edition, Standard specification for Fibrous Glass Duct Lining Insulation (Thermal and Sound Absorbing Material).
 - .4 ASTM C1338-latest edition, Standard Test Method for Determining Fungi Resistance of Insulation Materials and Facings.
 - .5 ASTM G21-latest edition, Standard Practice for Determining Resistance of Synthetic Polymeric Materials to Fungi.
- .2 National Fire Protection Association (NFPA)
 - .1 NFPA 90A-latest edition, Standard for the Installation of Air Conditioning and Ventilating Systems.
 - .2 NFPA 90B-latest edition, Standard for the Installation of Warm Air Heating and Air Conditioning Systems.
- .3 North American Insulation Manufacturers Association (NAIMA)
 - .1 NAIMA AH116-latest edition, Fibrous Glass Duct Construction Standards.
- .4 Sheet Metal and Air Conditioning Contractor's National Association (SMACNA)
 - .1 SMACNA, HVAC Duct Construction Standards, Metal and Flexible-latest edition.
 - .2 SMACNA IAQ Guideline for Occupied Buildings Under Construction-2007.
- .5 Underwriter's Laboratories of Canada (ULC)
 - .1 CAN/ULC-S102-10, Standard Method of Test for Surface Burning Characteristics of Building Materials and Assemblies.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for duct liners and include product characteristics, performance criteria, physical size, finish and limitations.

1.3 CLOSEOUT SUBMITTALS

- .1 Submit in accordance with Section 01 78 00 - Closeout Submittals.

- .2 Operation and Maintenance Data: submit operation and maintenance data for duct liners for incorporation into manual.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect duct liners from nicks, scratches, and blemishes.
 - .3 Replace defective or damaged materials with new.
- .4 Develop Construction Waste Management Plan related to Work of this Section.
- .5 Packaging Waste Management: remove as specified in Construction Waste Management Plan Waste Reduction Workplan in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

Part 2 Products

2.1 DUCT LINER

- .1 General:
 - .1 Mineral Fibre duct liner: air surface coated mat facing.
 - .2 Flame spread rating shall not exceed 25. Smoke development rating shall not exceed 50 when tested in accordance with CAN/ULC-S102 NFPA 90A NFPA 90B.
 - .3 Recycled Content: EcoLogo certified with minimum 35 by weight recycled content .
 - .4 Fungi resistance: to ASTM C1338 ASTM G21.
- .2 Rigid:
 - .1 Use on flat surfaces where indicated.
 - .2 25 mm thick, to ASTM C1071 Type 2, fibrous glass rigid board duct liner.
 - .3 Density: 48 kg/m³ minimum.
 - .4 Thermal resistance to be minimum 0.76 (m². degrees C)/W for 25 mm thickness 1.15 (m².degrees C)/W for 38 mm thickness 1.53 (m².degrees C)/W for 50 mm thickness when tested in accordance with ASTM C177, at 24 degrees C mean temperature.
 - .5 Maximum velocity on faced air side: 20.3 m/s.
 - .6 Minimum NRC of 0.70 at 25 mm thickness based on Type A mounting to ASTM C423.

- .7 Recycled Content: EcoLogo certified containing minimum 45 by weight recycled content .
- .3 Flexible:
 - .1 Use on round or oval surfaces indicated.
 - .2 25 mm thick, to ASTM C1071 Type 1, fibrous glass blanket duct liner.
 - .3 Density: 24 kg/m³ minimum.
 - .4 Thermal resistance to be minimum 0.37 (m².degrees C)/W for 12 mm thickness 0.74 (m².degrees C)/W for 25 mm thickness 1.11 (m².degrees C)/W for 38 mm thickness 1.41 (m².degrees C)/W to 50 mm thickness when tested in accordance with ASTM C177, at 24 degrees C mean temperature.
 - .5 Maximum velocity on coated air side: 30.5 m/s.
 - .6 Minimum NRC of 0.65 at 25 mm thickness based on Type A mounting to ASTM C423.

2.2 ADHESIVE

- .1 Adhesive: to NFPA 90A and NFPA 90B ASTM C916.
- .2 Flame spread rating shall not exceed 25. Smoke development rating shall not exceed 50. Temperature range minus 29 degrees C to plus 93 degrees C.
- .3 Water-based fire retardant type.

2.3 FASTENERS

- .1 Weld pins 2.0 mm diameter, length to suit thickness of insulation. Metal retaining clips, 32 mm square.

2.4 JOINT TAPE

- .1 Poly-Vinyl treated open weave fiberglass membrane 50 mm wide.

2.5 SEALER

- .1 Meet requirements of NFPA 90A NFPA 90B.
- .2 Flame spread rating shall not exceed 25. Smoke development rating shall not exceed 50. Temperature range minus 68 degrees C to plus 93 degrees C.

Part 3 Execution

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for duct liner installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental Representative.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.

- .3 Proceed with installation only after unacceptable conditions have been remedied and after receipt of written approval to proceed from Departmental Representative.

3.2 GENERAL

- .1 Do work in accordance with SMACNA HVAC Duct Construction Standard NAIMA AH116 except as specified otherwise.
- .2 Line inside of ducts where indicated.
- .3 Duct dimensions, as indicated, are clear inside duct lining.

3.3 DUCT LINER

- .1 Install in accordance with manufacturer's recommendations, and as follows:
 - .1 Fasten to interior sheet metal surface with 100% coverage of adhesive to ASTM C916.
 - .1 Exposed leading edges and transverse joints to be factory coated or coated with adhesive during fabrication.
 - .2 In addition to adhesive, install weld pins not less than 2 rows per surface and not more than 425 mm on centres to compress duct liner sufficiently to hold it firmly in place.
 - .1 Spacing of mechanical fasteners in accordance with SMAC HVAC Duct Construction Standard NAIMA AH116.
- .2 In systems, where air velocities exceeds 20.3 m/s, install galvanized sheet metal nosing to leading edges of duct liner.

3.4 JOINTS

- .1 Seal butt joints, exposed edges, weld pin and clip penetrations and damaged areas of liner with joint tape and sealer. Install joint tape in accordance with manufacturer's written recommendations, and as follows:
 - .1 Bed tape in sealer.
 - .2 Apply 2 coats of sealer over tape.
- .2 Replace damaged areas of liner at discretion of Departmental Representative
- .3 Protect leading and trailing edges of duct sections with sheet metal nosing having 15 mm overlap and fastened to duct.

3.5 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .3 Waste Management: separate waste materials in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

- .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 American National Standards Institute/Air Movement and Control Association (ANSI/AMCA)
 - .1 ANSI/AMCA Standard 99-latest edition, Standards Handbook.
 - .2 ANSI/AMCA Standard 210-latest edition/(ANSI/ASHRAE 51-07), Laboratory Methods of Testing Fans for Aerodynamic Performance Rating.
 - .3 ANSI/AMCA Standard 300-latest edition, Reverberant Room Method for Sound Testing of Fans.
 - .4 ANSI/AMCA Standard 301-latest edition, Methods for Calculating Fan Sound Ratings from Laboratory Test Data.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for HVAC fans and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Shop Drawings:
 - .1 Submit drawings stamped and signed by professional engineer registered or licensed in Province of Manitoba, Canada.
 - .2 Provide:
 - .1 Fan performance curves showing point of operation, bhp kW and efficiency.
 - .2 Sound rating data at point of operation.
 - .3 Indicate:
 - .1 Motors, sheaves, bearings, shaft details.
 - .2 Minimum performance achievable.

1.3 MAINTENANCE MATERIAL SUBMITTALS

- .1 Extra Materials:
 - .1 Submit in accordance with Section 01 78 00 - Closeout Submittals.
 - .1 Provide:
 - .1 Matched sets of belts.
 - .2 Furnish list of individual manufacturer's recommended spare parts for equipment, include:
 - .1 Bearings and seals.
 - .2 Addresses of suppliers.

- .3 List of specialized tools necessary for adjusting, repairing or replacing.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect HVAC fans from nicks, scratches, and blemishes.
 - .3 Replace defective or damaged materials with new.
- .4 Develop Construction Waste Management Plan related to Work of this Section
- .5 Packaging Waste Management: remove as specified in Construction Waste Management Plan in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal Section.

Part 2 Products

2.1 SYSTEM DESCRIPTION

- .1 Performance Requirements:
 - .1 Catalogued or published ratings for manufactured items: obtained from tests carried out by manufacturer or those ordered by manufacturer from independent testing agency signifying adherence to codes and standards in force.
 - .2 Capacity: flow rate, total static pressure, bhp W, efficiency, revolutions per minute, power, model, size, sound power data and as indicated on schedule.
 - .3 Fans: statically and dynamically balanced, constructed in conformity with ANSI/AMCA Standard 99.
 - .4 Sound ratings: comply with ANSI/AMCA Standard 301, tested to ANSI/AMCA Standard 300. Supply unit with ANSI/AMCA certified sound rating seal.
 - .5 Performance ratings: based on tests performed in accordance with ANSI/AMCA Standard 210. Supply unit with ANSI/AMCA certified rating seal, except for propeller fans smaller than 300 mm diameter.

2.2 FANS GENERAL

- .1 Motors:
 - .1 In accordance with Section 23 05 13 - Common Motors Requirements for HVAC Equipment supplemented as specified herein.
 - .2 For use with variable speed controllers.
 - .3 Sizes as specified.
 - .4 Two speed with two windings and speeds as indicated

- .5 Two speed with split winding, constant horsepower constant or variable torque and speeds as indicated.
- .2 Accessories and hardware: matched sets of V-belt drives, adjustable slide rail motor bases, belt guards, coupling guards fan inlet outlet safety screens as indicated and as specified in Section 23 05 13 - Common Motor Requirements for HVAC Equipment, inlet outlet dampers and vanes and as indicated.
- .3 Factory primed before assembly in colour standard to manufacturer.
- .4 Scroll casing drains: as indicated.
- .5 Bearing lubrication systems plus extension lubrication tubes where bearings are not easily accessible.
- .6 Vibration isolation: to Section 23 05 48 - Vibration and Seismic Controls for HVAC Piping and Equipment.
- .7 Flexible connections: to Section 23 33 00 - Air Duct Accessories.

2.3 CENTRIFUGAL FANS

- .1 Fan wheels:
 - .1 Welded steel aluminum construction.
 - .2 Maximum operating speed of centrifugal fans not more than 50% of first critical speed.
 - .3 Forward curved blades, as indicated.
- .2 Bearings: heavy duty grease lubricated ball or roller self-aligning type with oil retaining, dust excluding seals and a certified minimum rated life of 100,000 hours.
- .3 Housings:
 - .1 Volute with inlet cones: fabricated steel for wheels 300 mm or greater, for smaller wheels, braced, and with welded supports.
 - .2 For horizontally and vertically split housings provide flanges on each section for bolting together, with gaskets of non-oxidizing non-flammable material.
 - .3 Provide bolted latched airtight access doors with handles.

2.4 CABINET FANS - GENERAL PURPOSE

- .1 Fan characteristics and construction: as centrifugal fans.
- .2 Cabinet hung single or multiple wheel with DWDI centrifugal fans in factory fabricated casing complete with vibration isolators and seismic control measures, motor, V-belt drive and guard inside outside casing.
- .3 Fabricate casing of zinc coated or phosphate treated steel of reinforced and braced for rigidity. Provide removable panels for access to interior. Paint uncoated, steel parts with corrosion resistant paint to MPI #18. Finish inside and out, over prime coat, with rust resistant enamel. Internally line cabinet with 50 mm thick rigid acoustic insulation, pinned and cemented.

2.5 UTILITY SETS

- .1 Characteristics and construction: for centrifugal fans.
- .2 Preassemble single width centrifugal fan with removable weatherproof protective hood with vents, and automatic spring loaded back draft dampers 12 mm mesh birdscreens.
- .3 Provide belt driven sets with adjustable motor bed plate.

2.6 IN-LINE CENTRIFUGAL FANS

- .1 Characteristics and construction: as for centrifugal fan wheels, with axial flow construction and belt drive.
- .2 Provide AMCA arrangements 1 or 9 as indicated with stiffened flanges, smooth rounded inlets, and stationary guide vanes.

2.7 PROPELLER FANS

- .1 Fabricate multibladed propellers of sheet steel aluminum of airfoil shape within bell mouth entrance on integral mounts, with grease lubricated ball bearings, with extended lubrication fittings, suited for operating in any position, belt driven, complete with motor as indicated.
- .2 Provide blade guards, bird screen and automatic back draft dampers on discharge, with gasketed edges.

Part 3 Execution

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for HVAC fans installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental Representative.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied and after receipt of written approval to proceed from Departmental Representative.

3.2 FAN INSTALLATION

- .1 Install fans as indicated, complete with resilient mountings specified in Section 23 05 48 - Vibration and Seismic Controls for HVAC Piping and Equipment, flexible electrical leads and flexible connections in accordance with Section 23 33 00 - Air Duct Accessories.
- .2 Provide sheaves and belts required for final air balance.
- .3 Bearings and extension tubes to be easily accessible.
- .4 Access doors and access panels to be easily accessible.

3.3 ANCHOR BOLTS AND TEMPLATES

- .1 Size anchor bolts to withstand seismic acceleration and velocity forces as specified.

3.4 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .3 Waste Management: separate waste materials in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 Canada Green Building Council (CaGBC)

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for diffusers, registers and grilles and include product characteristics, performance criteria, physical size, finish and limitations.
 - .2 Indicate following:
 - .1 Capacity.
 - .2 Throw and terminal velocity.
 - .3 Noise criteria.
 - .4 Pressure drop.
 - .5 Neck velocity.
- .3 Sustainable Design Submittals:
 - .1 Construction Waste Management:
 - .1 Submit project Waste Management Plan highlighting recycling and salvage requirements.

1.3 MAINTENANCE MATERIAL SUBMITTALS

- .1 Extra Materials:
 - .1 Provide maintenance materials in accordance with Section 01 78 00 - Closeout Submittals.
 - .2 Include:
 - .1 Keys for volume control adjustment.
 - .2 Keys for air flow pattern adjustment.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect diffuser, registers and grilles from nicks, scratches, and blemishes.

- .3 Replace defective or damaged materials with new.
- .4 Develop Construction Waste Management Plan related to Work of this Section and in accordance.
- .5 Packaging Waste Management: remove as specified in Construction Waste Management Plan in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

Part 2 Products

2.1 SYSTEM DESCRIPTION

- .1 Performance Requirements:
 - .1 Catalogued or published ratings for manufactured items: obtained from tests carried out by manufacturer or those ordered by manufacturer from independent testing agency signifying adherence to codes and standards.

2.2 GENERAL

- .1 To meet capacity, pressure drop, terminal velocity, throw, noise level, neck velocity as indicated.
- .2 Frames:
 - .1 Full perimeter gaskets.
 - .2 Plaster frames where set into plaster or gypsum board and as specified.
 - .3 Concealed fasteners.
- .3 Concealed manual volume control damper operators.
- .4 Colour: Refer to Drawing schedules.

2.3 MANUFACTURED UNITS

- .1 Grilles, registers and diffusers of same generic type, products of one manufacturer.

2.4 SUPPLY GRILLES AND REGISTERS

- .1 General: Refer to Drawing schedules.

2.5 RETURN AND EXHAUST GRILLES AND REGISTERS

- .1 General: Refer to Drawing schedules.

2.6 DIFFUSERS

- .1 General: Refer to Drawing schedules.

Part 3 Execution

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for diffuser, register and grille installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied and after receipt of written approval to proceed from Departmental Representative.

3.2 INSTALLATION

- .1 Install in accordance with manufacturers instructions.
- .2 Install with screws in countersunk holes where fastenings are visible.
- .3 Bolt grilles, registers and diffusers, in place.

3.3 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .3 Waste Management: separate waste materials in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 ASTM International
 - .1 ASTM E90-Latest Edition , Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements.
- .2 National Fire Protection Association (NFPA)
 - .1 NFPA 96-Latest Edition , Standard for Ventilation Control and Fire Protection of Commercial Cooking Operations.
- .3 Sheet Metal and Air Conditioning Contractors' National Association (SMACNA)
- .4 Society of Automotive Engineers (SAE)

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for louvers, intakes and vents and include product characteristics, performance criteria, physical size, finish and limitations.
 - .2 Indicate following:
 - .1 Pressure drop.
 - .2 Face area.
 - .3 Free area.
- .3 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
- .4 Test Reports: submit certified data from independent laboratory substantiating acoustic and aerodynamic performance to ASTM E90.

1.3 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials indoors in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect louvers, intakes and vents from nicks, scratches, and blemishes.
 - .3 Replace defective or damaged materials with new.
- .4 Develop Construction Waste Management Plan related to Work of this Section.

- .5 Packaging Waste Management: remove as specified in Construction Waste Management Plan in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

Part 2 Products

2.1 SYSTEM DESCRIPTION

- .1 Performance Requirements:
 - .1 Catalogued or published ratings for manufactured items: obtained from tests carried out by manufacturer or those ordered by manufacturer from independent testing agency signifying adherence to codes and standards.

2.2 GRAVITY ROOF OUTSIDE AIR INTAKES AND RELIEF VENTS

- .1 Factory manufactured aluminum galvanized steel.
 - .1 Complete with integral birdscreen of 2.7 mm diameter aluminum ss wire.
 - .2 Vertical Horizontal backdraft dampers on 4 faces.
 - .3 Maximum throat velocity: 3.3 m/s intake.
 - .4 Maximum loss through unit: 15 Pa exhaust static pressure.
 - .5 Maximum velocity through damper area: 1.5 m/s.
- .2 Birdscreens:
 - .1 Complete with integral birdscreen of 2.7 mm diameter aluminum ss wire. Use 12 mm mesh on exhaust 19 mm mesh on intake.

2.3 GOOSENECK HOODS

- .1 Thickness: to ASHRAE SMACNA.
- .2 Fabrication: to ASHRAE SMACNA.
- .3 Joints: to ASHRAE SMACNA.
- .4 Supports: as indicated.
- .5 Complete with integral birdscreen of 2.7 mm diameter aluminum wire. Use 12 mm mesh on exhaust 19 mm mesh on intake.
- .6 Vertical Horizontal backdraft dampers on 4 faces.

2.4 FIXED LOUVRES - ALUMINUM

- .1 Construction: welded with exposed joints ground flush and smooth.
- .2 Material: extruded aluminum alloy 6063-T5.
- .3 Blade: stormproof pattern with centre watershed in blade, reinforcing bosses and maximum blade length of 1500 mm.
- .4 Frame, head, sill and jamb: 150 mm deep one piece extruded aluminum, minimum 3 mm thick with approved caulking slot, integral to unit.
- .5 Mullions: at 1500 mm maximum centres.

- .6 Fastenings: stainless steel SAE-194-8F with SAE-194-SFB nuts and resilient neoprene washers between aluminum and head of bolt, or between nut, ss washer and aluminum body.
- .7 Screen: 12 mm exhaust 19 mm intake mesh, 2 mm diameter wire aluminum birdscreen on inside face of louvres in formed U-frame.
- .8 Finish: factory applied enamel Colour: to Departmental Representative's approval.

2.5 FIXED LOUVRES

- .1 General: copper in welded steel frame, complete with anchors.
- .2 Blades:
 - .1 24 ounce cold rolled copper set at 45 degrees, Z-shaped with drip lips.
 - .2 Stormproof design for outside air intakes.
 - .3 Maximum length without mullions of same material: 1250 mm.
- .3 Frame: galvanized structural steel, welded construction. Paint welds after construction to Section 09 91 13 - Exterior Painting.
- .4 Screen: 12 mm exhaust 19 mm intake mesh, 2 mm diameter wire aluminum birdscreen on inside face of louvres in formed U-frame.
- .5 Finish: factory applied enamel. Colour: to Departmental Representative's approval.

Part 3 Execution

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for louvres, intakes and vents installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental Representative.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied and after receipt of written approval to proceed from Departmental Representative.

3.2 INSTALLATION

- .1 In accordance with manufacturer's and SMACNA recommendations.
- .2 Reinforce and brace as indicated.
- .3 Anchor securely into opening. Seal with caulking to ensure weather tightness.

3.3 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Leave Work area clean at end of each day.

- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .3 Waste Management: separate waste materials for reuse recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 American National Standard Institute (ANSI)/American Society of Heating, Refrigerating and Air-Conditioning Engineers (ASHRAE)
 - .1 ANSI/ASHRAE 52.2-Latest Edition, Method of Testing General Ventilation Air-Cleaning Devices for Removal Efficiency by Particulate Size (ANSI approved).
- .2 Canadian General Standards Board (CGSB)
 - .1 CAN/CGSB-115.10-Latest Edition, Disposable Air Filters for the Removal of Particulate Matter from Ventilating Systems.
 - .2 CAN/CGSB-115.11-Latest Edition, Filters, Air, High Efficiency, Disposable, Bag Type.
 - .3 CAN/CGSB-115.12-Latest Edition, Filters, Air, Medium Efficiency, Disposable, Bag Type.
 - .4 CAN/CGSB-115.13-Latest Edition, Filter Media, Automatic Roll.
 - .5 CAN/CGSB-115.14-Latest Edition, High Efficiency Cartridge Type Supported Air Filters for the Removal of Particulate Matter from Ventilating Systems.
 - .6 CAN/CGSB-115.15-Latest Edition, High Efficiency Rigid Type Air Filters for Removal of Particulate Matter from Ventilating Systems.
 - .7 CAN/CGSB-115.16-Latest Edition Activated Carbon for Odor Removal from Ventilating Systems.
 - .8 CAN/CGSB-115.18-Latest Edition, Filter, Air, Extended Area Panel Type, Medium Efficiency.
 - .9 CAN/CGSB-115.20-Latest Edition, Polarized Media Air Filter.
- .3 International Organization of Standardization (ISO)
 - .1 ISO 14644-1-Latest Edition, Clean Rooms and Associated Controlled Environments - Part 1: Classification of Air Cleanliness.
- .4 National Fire Protection Association (NFPA)
 - .1 NFPA 96-Latest Edition, Standard for Ventilation Control and Fire Protection of Commercial Cooking Operations.
- .5 Underwriters' Laboratories of Canada (ULC)
 - .1 ULC -S111-07, Standard Method of Fire Tests for Air Filter Units.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for HVAC filters and include product characteristics, performance criteria, physical size, finish and limitations.

- .3 Shop Drawings:
 - .1 Submit drawings stamped and signed by professional engineer registered or licensed in Province of Manitoba, Canada.
- .4 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.

1.3 MAINTENANCE MATERIAL SUBMITTALS

- .1 Extra Materials:
 - .1 Provide maintenance materials in accordance with Section 01 78 00 - Closeout Submittals.
 - .2 Furnish list of individual manufacturer's recommended spare parts for equipment such as frames and filters, addresses of suppliers, list of specialized tools necessary for adjusting, repairing or replacing for inclusion in operating manual.
 - .3 Spare filters: in addition to filters installed immediately prior to acceptance by Departmental Representative, supply 2 complete sets of filters for each.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials indoors in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect HVAC filters from nicks, scratches, and blemishes.
 - .3 Replace defective or damaged materials with new.
- .4 Packaging Waste Management: remove as specified in Construction Waste Management Plan Waste Reduction Workplan in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

Part 2 Products

2.1 GENERAL

- .1 Media: suitable for air at 100% RH and air temperatures between -40 and 50 degrees C.
- .2 Number of units, size and thickness of panels, overall dimensions of filter bank, configuration and capacities: as indicated.
- .3 Pressure drop when clean and dirty, sizes and thickness: as indicated on schedule.

2.2 ACCESSORIES

- .1 Holding frames: construction of galvanized steel 1.6 mm thick, except where specified.
- .2 Seals: to ensure leakproof operation.

- .3 Blank-off plates: as required, to fit all openings and of same material as holding frames.
- .4 Access and servicing: through doors/panels on each side and/or from upstream downstream face of filter bank.

2.3 FIBROUS GLASS PANEL FILTERS

- .1 Disposable fibrous glass media: to CAN/CGSB-115.10 with adhesive.
- .2 Holding frame: 1.2 mm minimum thick galvanized steel with 3 mm diameter hinged wire mesh screen.
- .3 Performance: to MERV 16
- .4 Fire rated: to ULC -S111.
- .5 Nominal thickness: 25 to 50 mm. Refer also to drawing equipment schedules.

Part 3 Execution

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for filter installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental Representative.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied and after receipt of written approval to proceed from Departmental Representative.

3.2 INSTALLATION GENERAL

- .1 Install in accordance with manufacturer's recommendations and with adequate space for access, maintenance and replacement.

3.3 REPLACEMENT MEDIA

- .1 Replace media with new upon acceptance.
- .2 Filter media new and clean, as indicated by pressure gauge, at time of acceptance.

3.4 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .3 Waste Management: separate waste materials in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

- .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 American Society of Heating, Refrigeration and Air-Conditioning Engineers (ASHRAE)
 - .1 ASHRAE 84-Latest Edition, Method of Testing Air-to-Air Heat/Energy Exchangers (ANSI approved).

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for energy recovery equipment and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Shop Drawings:
 - .1 Submit drawings stamped and signed by professional engineer registered or licensed in Province of Manitoba, Canada.
- .4 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
- .5 Test Reports:
 - .1 Catalogued or published ratings: obtained from tests carried out by manufacturer or those ordered from independent testing agency signifying adherence to codes and standards in force.
 - .2 Provide confirmation of testing.
- .6 Manufacturers' Instructions: submit manufacturer's installation instructions.
 - .1 Departmental Representative will make available 3 copies of systems supplier's installation instructions.

1.3 MAINTENANCE MATERIAL SUBMITTALS

- .1 Submit maintenance materials in accordance with Section 01 78 00 - Closeout Submittals.
- .2 Extra Materials:
 - .1 Furnish list of individual manufacturer's recommended spare parts for equipment include:
 - .1 Bearings and seals.
 - .2 Addresses of suppliers.
 - .2 List of specialized tools necessary for adjusting, repairing or replacing.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials indoors in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect energy recovery equipment from nicks, scratches, and blemishes.
 - .3 Replace defective or damaged materials with new.
- .4 Develop Construction Waste Management Plan related to Work of this Section.
- .5 Packaging Waste Management: remove as specified in Construction Waste Management Plan in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

Part 2 Products

2.1 GENERAL

- .1 Comply with ASHRAE 84.

2.2 SENSIBLE HEAT TYPE AIR TO AIR ROTARY HEAT EXCHANGER

- .1 Horizontal air flow unit: complete with drain pan with NPS 1 1/2 drain connection.
- .2 Performance characteristics: as indicated.

2.3 AIR TO AIR FIXED PLATE EXCHANGER

- .1 Casing: 0.8 mm thick galvanized steel.
- .2 Heat transfer surfaces: corrugated aluminum, edge sealed and bonded to casing.
- .3 Condensate drain.
- .4 Removable access panels.
- .5 Performance characteristics: as indicated.
- .6 Electric defrost control (DFC), winter operating conditions to -40 C.
- .7 Capable for economiser mode with air handler system.
- .8 Electric heat coil as indicated on drawing schedule.

Part 3 Execution

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for energy recovery equipment installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental Representative.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied and after receipt of written approval to proceed from Departmental Representative.

3.2 INSTALLATION

- .1 Install in accordance with manufacturers recommendations.
- .2 Support independently of adjacent ductwork with flexible connections.
- .3 Install access doors in accordance with Section 23 33 00 - Air Duct Accessories for access to coils, dampers.

3.3 FIELD QUALITY CONTROL

- .1 Tests:
 - .1 Perform tests in accordance with Section 26 05 00 - Common Work Results for Electrical.

3.4 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .3 Waste Management: separate waste materials in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 American National Standards Institute/Air-Conditioning, Heating and Refrigeration Institute (ANSI/AHRI)
 - .1 ANSI/AHRI 430-Latest Edition, Performance Rating of Central Station Air-Handling Units.
- .2 American National Standards Institute/American Society of Heating, Refrigeration and Air Condition Engineers/Illuminating Engineering Society (ANSI/ASHRAE/IES)
 - .1 ANSI/ASHRAE 52.2-Latest Edition, Method of Testing General Ventilation Air-Cleaning Devices for Removal Efficiency by Particle Size.
 - .2 ANSI/ASHRAE/IES 90.1-Latest Edition, Energy Standard for Buildings Except Low-Rise Residential Buildings.
- .3 Green Seal (GS)
 - .1 GS-11-Latest Edition, Standard for Paints and Coatings.
 - .2 GS-36-Latest Edition, Standard for Adhesives for Commercial Use.
- .4 South Coast Air Quality Management District (SCAQMD)
 - .1 SCAQMD Rule 1113-Latest Edition, Architectural Coatings.
 - .2 SCAQMD Rule 1168-Latest Edition, Adhesives and Sealants.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for insulation, filters, adhesives, and paints and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Shop Drawings:
 - .1 Submit drawings stamped and signed by professional engineer registered or licensed in Province of Manitoba, Canada.
 - .2 Indicate on drawings: fan, fan curves showing point of operation motor drive bearings filters mixing box dampers; include performance data.

1.3 CLOSEOUT SUBMITTALS

- .1 Submit in accordance with Section 01 78 00 - Closeout Submittals.
- .2 Operation and Maintenance Data: submit operation and maintenance data for air handling equipment for incorporation into manual.
- .3 Include following: fan bearings motor damper, air volume, total cooling, sensible cooling, EDB, EWB, OAT.

1.4 MAINTENANCE MATERIAL SUBMITTALS

- .1 Submit in accordance with Section 01 78 00 - Closeout Submittals.
- .2 Provide 12 spare sets of filters.
- .3 Provide list of individual manufacturer's recommended spare parts for equipment such as bearings and seals, and addresses of suppliers, together with list of specialized tools necessary for adjusting, repairing or replacing, for placement into operating manual.
- .4 Spare filters: in addition to filters installed immediately prior to acceptance by Departmental Representative, supply 12 complete sets of filters for each filter unit or filter bank.

1.5 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials indoors in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect air handling equipment from nicks, scratches, and blemishes.
 - .3 Replace defective or damaged materials with new.
- .4 Develop Construction Waste Management Plan related to Work of this Section.
- .5 Packaging Waste Management: remove as specified in Construction Waste Management Plan in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

Part 2 Products

2.1 GENERAL - INDOOR

- .1 Factory assembled components to form units supplying air at designed conditions, as indicated. Example product for AHU-1; Lennox CBX25UH.
- .2 Certify ratings: to ANSI/AHRI 430 with AHRI seal.
- .3 Horizontal, split DX Cooling with electrical heat, having air tight modular components consisting of casing, fan section with motor and drive, filter section, dampers, electric heating coil, cooling coil, mixing box, economiser, transformer and blower relay, tool-less filter access, refrigerant line connections, digital thermostat – DDC compatible.

2.2 CASINGS

- .1 Phosphate treated zinc coated prepainted, reinforced and braced for rigidity, insulated.
 - .1 Removable panels: provide access for maintenance of internal parts.
 - .2 Finish unit inside and out, with rust resistant enamel.

- .3 Two layer painted surface to protect from rust and corrosion.
- .4 Two part cabinet construction with rubber gasket between sections.

2.3 DRAIN PANS

- .1 Construction: Dual position, stainless steel, polymer plastic, rounded corners, antimicrobial.
- .2 Connect drain to hub drain.

2.4 FANS

- .1 Cabinet hung AMCA-rated for sound and performance centrifugal fans with forward curved wheels.
 - .1 Provide internally mounted motor as indicated.
 - .2 Motor: Multiple blower speed as indicated.
- .2 Maximum sound power levels, as indicated.
- .3 Internally mounted motor and fan.

2.5 VIBRATION ISOLATION

- .1 Flexible connections at inlet and outlet of fan: to Section 23 33 00 - Air Duct Accessories.
- .2 Vibration isolators on fan section: in accordance with Section 23 05 48 - Vibration and Seismic Controls for HVAC Piping and Equipment.

2.6 FILTER

- .1 Material to match casing. For flat type filter arrangement:
 - .1 Provide access to filter through hinged door removable panels with suitable hardware.
- .2 Filters: in accordance with Section 23 44 00 - HVAC Air Filtration.
 - .1 Minimum Efficiency Reporting Value (MERV) value 16 filtration media to ANSI/ASHRAE 52.2, to be used on return air section of air handling unit.
 - .2 Immediately prior to occupancy, replace filtration media with new filtration media with Minimum Efficiency Reporting Value (MERV) of 16 in accordance with ANSI/ASHRAE 52.2.

2.7 MIXING BOX – WITH ECONOMISER

- .1 Material to match casing and produce uniformly mixed air temperature within plus or minus 5 degrees C of design across face of outlet.
- .2 Dampers for mixing boxes: Section 23 33 15 - Dampers - Operating.

2.8 COILS

- .1 Capacity: as indicated.

- .2 Ratings: AHRI certified, high efficient.
- .3 Construction:
 - .1 Casings: 1.5 mm thick galvanized sheet steel.
 - .1 Supports of galvanized steel channel double angle frames.
 - .2 Blank-off plates. Insulated sandwich construction.
 - .2 Direct expansion refrigerant coils:
 - .1 Serpentine type, Straight tube type arranged to prevent trapping of oil.
 - .1 Liquid distributors to ensure even distribution of liquid refrigerant to all circuits.
 - .2 Silver solder or braze joints in refrigerant tubing.
 - .3 Evacuate and charge coil with nitrogen and seal before sending to site.
 - .2 Tubes: copper.
 - .3 Fins: copper aluminum plate spiral wound.
 - .4 Headers: copper.
 - .5 Check and thermostatic expansion valve, factory provided.
 - .6 Pressure tests: to Canadian Refrigeration Code. Dehydrated. Sealed with nitrogen charge.

Part 3 Execution

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for air handling equipment installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental Representative.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied.

3.2 INSTALLATION

- .1 Provide appropriate protection apparatus.
- .2 Install units in accordance with manufacturer's instructions and as indicated.
- .3 Ensure adequate clearance for servicing and maintenance.

3.3 FANS

- .1 Install fan sheaves required for final air balance.
- .2 Install flexible connections at fan inlet and fan outlets.
- .3 Install vibration isolators.

3.4 DRIP PANS

- .1 Install deep seal P-traps and trap seal primer on drip lines.
 - .1 Depth of water seal to be 1.5 times static pressure at this point.

3.5 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .3 Waste Management: separate waste materials for reuse recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 American Gas Association (AGA)
- .2 American National Standards Institute/Air-Conditioning, Heating and Refrigeration Institute (ANSI/AHRI)
 - .1 ANSI/AHRI 210/240-Latest Edition, Performance Rating of Unitary Air-Conditioning and Air-Source Heat Pump Equipment.
 - .2 ANSI/AHRI 270-Latest Edition, Sound Rating of Outdoor Unitary Equipment.
- .3 CSA Group
 - .1 CSA B52-Latest Edition, Mechanical Refrigeration Code.
 - .2 CSA C22.1-Latest Edition, Canadian Electrical Code, Part 1 (22nd Edition), Safety Standard for Electrical Installations.
- .4 National Fire Protection Association (NFPA)
 - .1 NFPA 90A-Latest Edition, Standard for the Installation of Air Conditioning and Ventilating Systems.
- .5 Underwriters Laboratories (UL)
 - .1 UL 1995-Latest Edition, Standard for Heating and Cooling Equipment.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for outdoor HVAC equipment and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Shop Drawings:
 - .1 Submit drawings stamped and signed by professional engineer registered or licensed in Province of Manitoba, Canada.
 - .2 Drawings to indicate project layout and dimensions; indicate:
 - .1 Equipment, piping, and connections, together with valves, strainers, control assemblies, thermostatic controls, auxiliaries and hardware, and recommended ancillaries which are mounted, wired and piped ready for final connection to building system, its size and recommended bypass connections.
 - .2 Piping, valves, fitting shipped loose showing final location in assembly.
 - .3 Control equipment shipped loose, showing final location in assembly.

- .4 Dimensions, internal and external construction details, recommended method of installation with proposed structural steel support, mounting curb details, sizes and location of mounting bolt holes; include mass distribution drawings showing point loads.
 - .5 Detailed composite wiring diagrams for control systems showing factory installed wiring and equipment on packaged equipment or required for controlling devices of ancillaries, accessories, controllers.
 - .6 Pump and fan performance curves.
 - .7 Details of vibration isolation.
 - .8 Estimate of sound levels to be expected across individual octave bands in dB referred to A rating.
 - .9 Type of refrigerant used.
- .4 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
 - .5 Test Reports: submit certified test reports from approved independent testing laboratories indicating compliance with specifications for specified performance characteristics and physical properties.
 - .6 Manufacturer's Field Reports:
 - .1 Submit manufacturer's field reports specified.

1.3 CLOSEOUT SUBMITTALS

- .1 Submit in accordance with Section 01 78 00 - Closeout Submittals.
- .2 Operation and Maintenance Data: submit operation and maintenance data for outdoor HVAC equipment for incorporation into manual.
 - .1 Indicate: brief description of unit, indexed, with details of function, operation, control, and service for components.
 - .2 Provide for units, manufacturer's name, type, year, number of units, and capacity.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements, with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials indoors in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect outdoor HVAC equipment from nicks, scratches, and blemishes.
 - .3 Replace defective or damaged materials with new.
- .4 Develop Construction Waste Management Plan related to Work of this Section.

- .5 Packaging Waste Management: remove as specified in Construction Waste Management Plan in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

1.5 WARRANTY

- .1 For Work of this Section 23 74 00 - Packaged Outdoor HVAC Equipment, 12 months warranty period is extended to 24 months.
- .2 Contractor hereby warrants that packaged rooftop HAVC units and refrigeration compressors will function and operate in accordance with CCDC 2 GC 24, but for 24 60 months.

Part 2 Products

2.1 GENERAL

- .1 Roof mounted, self-contained single zone unit with electric heating elements and DX refrigeration and bear label of, FM, UL ULC.
- .2 Units to consist of cabinet and frame, supply fan, heater control, air filter, refrigerant cooling coil, compressor, condenser coil and fans, motorized outside air damper, return damper, motorized gravity exhaust damper.
- .3 Prefabricated 16 gauge roof curb to conform to requirements of National Roofing Contractors Association (NRCA), minimum height 425 mm.
- .4 Conform to ANSI/AHRI 210/240, rating for unit larger than 40 kW nominal.

2.2 UNIT CABINET

- .1 Unit cabinet shall be constructed of phosphated, zinc--coated, prepainted steel. Normal service shall be through removable cabinet panels. The unit shall be constructed on a rust proof unit base that has an externally trapped, integrated sloped drain. Evaporator fan compartment top surface shall be insulated with minimum ½ in. (12.7 mm) thick, flexible fiberglass insulation, coated on the air side and retained by adhesive and mechanical means. The evaporator wall sections will be insulated with a minimum semi rigid foil faced board capable of being wiped clean. Aluminum foil faced fiberglass insulation shall be used in the entire indoor air cavity section. Unit shall have a field supplied condensate trap.
- .2 Economizer; Factory installed Economizer with solid state controls and barometric relief dampers including filter racks. Economizer controls to be capable of providing free cooling using outside air and equipped with low leakage dampers not to exceed 3%leakage, at 250 pa (1.0 IN. W.C.) pressure differential. Spring return motor shuts off outdoor damper on power failure. Manual Outside Air Damper, bird screen, and rain hood.
- .3 Filter Rack Kit - Include 25mm (1 in.) filter, to MERV-13, maximum pressure drop 250 pa (0.08 in. W.C.).
- .4 Louvered Grille; factory installed to provide hail guard and vandalism protection.

- .5 Electric Heaters (see Drawing Schedules); Heater elements shall be open wire type, adequately supported and insulated with ceramic bushings. Electric heater packages must provide single point power connection capability.
- .6 Fan Wheel to be made from steel, be double inlet type with forward curved blades with corrosion resistant finish. Fan wheel shall be dynamically balanced.
- .7 Thermostatic Expansion Valve -A hard shutoff, balance port TXV to maintain constant superheat at the evaporator exit (cooling cycle) for higher overall system efficiency.
- .8 Refrigerant system; provide Liquid filter driers, Puron (R-410A) full refrigerant charge, Refrigerant service connections.
- .9 Compressor Start Kit (single phase units): Shall provide additional starting torque for single—phase compressors.
- .10 Thermostat: To provide for one stage heating and cooling in addition manual or automatic changeover and indoor fan control.
- .11 Crankcase Heater: Shall provide anti-flood back protection for low--load cooling applications.
- .12 Controls and Safeties: Unit controls shall be complete with a self-contained low voltage control circuit. Units shall incorporate high and low pressure switches.
- .13 Operating Characteristics: Unit shall be capable of starting and running at 125 F (51 C) ambient outdoor temperature per maximum load criteria of AHRI Standard 210.
- .14 Compressor with standard controls shall be capable of operation down to 40 F (4 C) ambient outdoor temperature.
- .15 LOSS--OF--CHARGE / LOW—PRESSURE SWITCH (Liquid Line) (psig) cut--out Reset (auto)
- .16 HIGH--PRESSURE SWITCH (psig) Cut--out Reset (Auto)
- .17 Unit shall be provided with 60 second fan time delay after the thermostat is satisfied.
- .18 Electrical Requirements: All unit power wiring shall enter the unit cabinet at a single location. Motors: Compressor motors shall be of the refrigerant cooled type with line break thermal and current overload protection. All fan motors shall have permanently lubricated bearings, and inherent, automatic reset, thermal overload protection. Condenser fan motor shall be totally enclosed. Evaporator fan motor to be ECM Motor.
- .19 Compressor: Fully hermetic compressors with factory--installed vibration isolation. Scroll compressors.
- .20 Coils: Evaporator and condenser coils shall have aluminum plate fins mechanically bonded to seamless copper tubes with all joints brazed. Tube sheet openings shall be belled to prevent tube wear.

Part 3 Execution

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for outdoor HVAC equipment installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental Representative .
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied and after receipt of written approval to proceed from Departmental Representative .

3.2 INSTALLATION

- .1 Install as per manufacturers' instructions on roof curbs provided by manufacturer
- .2 Manufacturer to certify installation, supervise start-up and commission unit.
- .3 Run drain line from cooling coil condensate drain pan to discharge over roof drain.

3.3 FIELD QUALITY CONTROL

- .1 Manufacturer's Field Services:
 - .1 Have manufacturer of products supplied under this Section review work involved in handling, installation/application, protection and cleaning of its products, and submit written reports, in acceptable format, to verify compliance of work with Contract.
 - .2 Provide manufacturer's field services, consisting of product use recommendations and periodic site visits for inspection of product installation, in accordance with manufacturer's instructions.
- .2 Obtain reports within 3 days of review and submit immediately to Departmental Representative .
- .3 Performance Verification:
 - .1 General:
 - .1 In accordance with Section 23 08 02 - Cleaning and Start-up of Mechanical Piping Systems, supplemented as specified herein.
 - .2 Rooftop Air Handling Units:
 - .1 Set zone mixing dampers for full cooling, except that where diversity factor forms part of design set that percentage of zone dampers to full heating.
 - .2 Set outside air and return air dampers for minimum outside air.
 - .3 Set face and bypass dampers so face dampers are fully open and bypass dampers are fully closed.
 - .4 Check for smooth, vibration less correct rotation of supply fan impeller.
 - .5 Measure supply fan capacity.

- .6 Adjust impeller speed as necessary and repeat measurement of fan capacity.
- .7 Measure pressure drop each component of air handling unit.
- .8 Set outside air and return air dampers for the percentage of outside air required by design and repeat measurements of fan capacity.
- .9 OAD: verify for proper stroking, interlock with RAD.
- .10 Measure DBT, WBT of SA, RA, EA.
- .11 Measure air cooled condenser discharge DBT.
- .12 Measure flow rates (minimum and maximum) of SA, RA, EA, relief air.
- .13 Simulate maximum cooling load and measure refrigerant hot gas and suction temperatures and pressures.
- .14 Simulate maximum heating load and:
 - .1 Verify temperature rise across heat coil.
- .15 Measure radiated and discharge sound power levels under maximum heating demand and under maximum cooling demand with compressors running.
- .16 Verify operating control strategies, including:
 - .1 Heat coil operating and high limit.
 - .2 Early morning warm-up cycle.
 - .3 Freeze protection.
 - .4 Economizer cycle operation, temperature of change-over.
 - .5 Alarms.
 - .6 Voltage drop across thermostat wiring.
 - .7 Operation of remote panel including pilot lights, failure modes.
- .17 Set zone mixing dampers for full heating and repeat measurements.
- .18 Measure leakage past zone mixing dampers by taking temperature measurements. Reduce leakage to less than 5%.
- .19 Check capacity of heating unit.
- .20 Measure DX refrigeration system performance.
- .21 Refer to other sections of these specifications for PV procedures for other components.
- .3 Start-Up:
 - .1 General: in accordance with Section 23 08 01 – Performance Verification Mechanical Piping Systems.
- .4 Verify accessibility, serviceability of components including motorized dampers, filters coils, fans, motors, operators, humidifiers, sensors, electrical disconnects.
- .5 Verify accessibility, clean ability, drainage of drain pans for coils.
- .4 Commissioning Reports:
 - .1 In accordance with Section 01 91 13 - General Commissioning (Cx) Requirements: reports supplemented as specified herein. Include:
 - .1 Report forms as specified Section 01 91 13 - General Commissioning (Cx) Requirements: Report Forms and Schematics.

3.4 DEMONSTRATION

- .1 Training: in accordance with Section 01 91 13 - General Commissioning (Cx)
Requirements: Training of O M Personnel, supplemented as specified.

3.5 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .3 Perform cleaning operations in accordance with manufacturer's recommendations.
- .4 Waste Management: separate waste in accordance with Section 01 74 21 - Construction/Demolition Waste Management .
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

END OF SECTION

Part 1 General

1.1 RELATED REQUIREMENTS

- .1 Not applicable.

1.2 REFERENCES

- .1 American National Standards Institute/American Society of Heating, Refrigeration and Air-Conditioning Engineers (ANSI/ASHRAE)
 - .1 ANSI/ASHRAE 52.2, Method of Testing General Ventilation Air-Cleaning Devices for Removal Efficiency by Particulate Size.
 - .2 ANSI/ASHRAE 127-, Method of Testing for Rating Computer and Data Processing Room Unitary Air-Conditioners.
- .2 ASTM International
 - .1 ASTM C547-11, Specification for Mineral Fiber Pipe Insulation.
- .3 CSA International
 - .1 CSA B52, Mechanical Refrigeration Code.
 - .2 CAN/CSA-C656, Performance Standard for Single Package Central Air-Conditioners and Heat Pumps.

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for air conditioning components and accessories and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Shop Drawings:
 - .1 Submit drawings stamped and signed by professional engineer registered or licensed in Province of Manitoba, Canada.
 - .2 Indicate on drawings:
 - .1 Major components and accessories including sound power levels of units.
 - .2 Type of refrigerant used.

1.4 CLOSEOUT SUBMITTALS

- .1 Submit in accordance with Section 01 78 00 - Closeout Submittals.
- .2 Operation and Maintenance Data: submit operation and maintenance data for air conditioning components for incorporation into manual.

1.5 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and with manufacturer's written instructions..
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect air conditioning components from nicks, scratches, and blemishes.
 - .3 Replace defective or damaged materials with new.
- .4 Develop Construction Waste Management related to Work of this Section.
- .5 Packaging Waste Management: remove for reuse as specified in Construction Waste Management Plan in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal..

1.6 WARRANTY

- .1 For computer room air conditioning 12 months warranty period is extended to 60 months.
- .2 Contractor hereby warrants that computer room air conditioning will not spall or show visible evidence of cracking, except for normal hairline shrinkage cracks, in accordance with CCDC 2 General Conditions.

Part 2 Products

2.1 SUMMARY

- .1 These specifications describe requirements for an environmental control system. The system shall be designed to control temperature and relative humidity conditions within the room.
- .2 The manufacturer shall design and furnish all equipment in the quantities and configurations shown on the project drawings.
- .3 Standard 60Hz units are CSA Certified to the harmonized U. S. and Canadian product safety standard CSA C22.2 No 236/UL 1995 for "Heating and Cooling Equipment" and are marked with the CSA c-us logo.

2.2 DESIGN REQUIREMENTS

- .1 The environmental control system shall be a factory assembled unit. On direct expansion models, the refrigeration system shall be self-contained or shall be split, with the compressor located in a remote air-cooled condensing unit.
- .2 The self-contained and split evaporator units shall be designed for above-dropped-ceiling installation and serviceable from the front and bottom of the system. Condensing unit for split system shall be designed for outdoor installation.

- .3 The system shall have a total cooling capacity of 14,100 Btu/hr (4.15kW), and a sensible cooling capacity of 11,500 Btu/hr (3.35kW), based on the entering air condition of 72°F (22°C) dry bulb, and 60°F (15.5°C) wet bulb.
- .4 The unit is to be supplied for operation using a 208 volt, 1 phase, 60 Hz power supply.

2.3 SUBMITTALS

- .1 Submittals shall be provided with the proposal and shall include: Single-Line Diagrams; Dimensional, Electrical and Capacity data; Piping and Electrical Connection Drawings.

2.4 QUALITY ASSURANCE

- .1 The specified system shall be factory-tested before shipment. Testing shall include, but shall not be limited to: Quality Control Checks, "HiPot" Test (two times rated voltage plus 1000 volts, per NRTL agency requirements) and Metering Calibration Tests. The system shall be designed and manufactured according to world class quality standards. The manufacturer shall be ISO 9001 certified.

2.5 CABINET CONSTRUCTION

- .1 The cabinet and chassis shall be constructed of heavy gauge galvanized steel and designed for easy installation and service access from front and bottom of unit only (water cooled units require end access). Mounting brackets shall be factory-attached to the cabinet. Internal cabinet insulation shall meet ASHRAE 62.1 requirements for Mold Growth, Humidity & Erosion, tested per UL 181 and ASTM 1338 standards.

2.6 AIR DISTRIBUTION

- .1 The air distribution system shall be constructed with a quiet, direct-drive fan assembly equipped with double-inlet blower, self-aligning ball bearings and lifetime lubrication. Fan motor shall be 1/5hp (149W), permanent-split capacitor, high efficiency type, equipped with two speeds for air flow modulation for precise dehumidification control. Dehumidification shall utilize the lower fan speed.
- .2 Air delivery shall be minimum 600 CFM (1019 CMH) at high fan speed. For ducted applications air delivery shall be 600 CFM (1019 CMH) at 0.3" (8 mm) external static pressure.
- .3 System shall be suitable for plenum or ducted air distribution.

2.7 MICROPROCESSOR CONTROL

- .1 The control system shall be microprocessor-based, factory-wired into the system and tested prior to shipment. The wall-mounted control enclosure shall include a 2-line by 16-character LCD providing continuous display of operating status and alarm condition. An 8-key membrane keypad for setpoint/ program control, fan speed selection and unit On/Off shall be located below the display. The control display shall be field-wired to the control board using 4-conductor field-supplied thermostat wire.
- .2 Temperature and humidity sensors shall be located in the wall box, which shall be capable of being located up to 300 ft (91.4m) from the evaporator unit.

2.8 MONITORING

- .1 The LCD shall provide On/Off indication, operating mode indication (cooling, heating, humidifying, dehumidifying), fan speed indication and current day, time, temperature and humidity (if applicable) indication. The monitoring system shall be capable of relaying unit operating parameters and alarms to the Liebert® SiteScan® monitoring system.

2.9 CONTORL SETPOINT PARAMENTERS

- .1 Temp. Setpoint 65-85°F (18-29°C)
- .2 Temp. Sensitivity 1-9.9 °F (1-5°C)
- .3 Humidity Setpoint 20-80% RH
- .4 Humidity Sensitivity 1-30% RH

2.10 COMPRESSOR SHORT-CYCLE CONTROL

- .1 The control system shall prevent compressor short-cycling by a 3-minute timer from compressor stop to the next start.

2.11 COMMON ALARM AND REMOTE ON/OFF

- .1 A common alarm relay shall provide a contact closure to a remote alarm device. Two (2) terminals shall also be provided for remote On/Off control. Individual alarms shall be “enabled” or “disabled” from reporting to the common alarm.

2.12 SETBACK CONTROL

- .1 The control shall be user-configurable to use a manual setpoint control or a programmable, time-based setback control. The setback control will be based on a 5 day/2 day programmed weekly schedule with capability of accepting 2 events per program day.

2.13 TEMPERATURE CALIBRATION

- .1 The control shall include the capabilities to calibrate the temperature and humidity sensors and adjust the sensor response delay time from 10 to 90 seconds. The control shall be capable of displaying temperature values in °F or °C.

2.14 SYSTEM AUTO RESTART

- .1 For startup after power failure, the system shall provide automatic restart with a programmable (up to 9.9 minutes in 6-second increments) time delay. Programming can be performed either at the wall-mounted controller or from the central, site-monitoring system.

2.15 UNIT ALARMS

- .1 The control system shall monitor unit operation and activate an audible and visual alarm in the event of the following factory preset alarm conditions:
 - .1 High Temperature
 - .2 Low Temperature

- .3 High Humidity
- .4 Low Humidity
- .5 High Water Alarm - Lockout Unit Operation
- .6 High Head Pressure
- .7 Loss of Power
- .8 Compressor Short Cycle

2.16 CUSTOM ALARMS (2X)

- .1 Humidifier Problem
- .2 Filter Clog
- .3 Water Detected

2.17 AUDIBLE ALARM

- .1 The audible alarm shall annunciate any alarm that is enabled by the operator.

2.18 COMMON ALARM

- .1 A programmable common alarm shall be provided to interface user selected alarms with a remote alarm device. Alarms shall be enabled or disabled from reporting to the common alarm.

2.19 EVAPORATOR UNIT – AC-2A

- .1 The evaporator section shall include evaporator coil, thermostatic expansion valve and filter drier. The evaporator coil shall have 2.4 sq.ft. (0.23 sq.m) face area, 2 rows deep. It shall be constructed of copper tubes and aluminum fins and have a maximum face velocity of 232 ft. per minute (1.2 m/s) at minimum 400 CFM (679 CMH). An externally equalized thermostatic expansion valve shall control refrigerant flow. The evaporator coil shall be factory-charged with R-407C refrigerant and sealed. The coil shall be provided with a condensate drain pan with an internally trapped drain line. The evaporator drain pan shall include a factory-installed float switch to shut down the evaporator upon high water condition.

2.20 OUTDOOR AIR-COOLED PROPELLER FAN CONDENSING UNIT – CU-2A

- .1 Condensing unit components shall include a condenser coil, a direct-drive propeller-type fan, a (scroll) (reciprocating) compressor with vibration-isolating grommets, high pressure switch, Liebert® Lee Temp™ receiver and head pressure control valve, hot gas bypass system and liquid line solenoid valve. The condenser coil shall be constructed of copper tubes and aluminum fins.
- .2 A hot gas bypass system shall be provided to reduce compressor cycling and improve operation under low load conditions.
- .3 All components shall be factory-assembled, charged with R-407C refrigerant, sealed and be capable of being connected to the evaporator section using pre-charged refrigerant line sets. No internal piping, brazing, dehydration or charging shall be required. Condensing

unit shall be designed for 95°F (35°C) ambient and be capable of operation to -30°F (-34.4°C).

- .4 Provide crankcase heater.

2.21 STEAM GENERATING HUMIDIFIER

- .1 The environmental control system shall be equipped with a steam generating humidifier that is controlled by the microprocessor control system. It shall be complete with disposable canister, all supply and drain valves, 1" (25.4mm) air gap on fill line, inlet strainer, steam distributor and electronic controls. The need to change canister shall be annunciated on the microprocessor wall box control panel. The humidifier shall have a capacity of 2.5 lb/hr (1.1 kg/h). An LED light on the humidifier assembly shall indicate cylinder full, overcurrent detection, fill system fault and end of cylinder life conditions.

2.22 ELECTRIC REHEAT

- .1 The electric reheat shall be low-watt density, 304/304 stainless steel, finned-tubular and shall be capable of maintaining room dry bulb temperature conditions when the system is calling for dehumidification. The reheat section shall include a UL-approved safety switch to protect the system from overheating. The capacity of the reheat coils shall be 12,160Btu/hr (3.6kW), with unit input voltage of 208 V, controlled in one stage.

2.23 DISCONNECT SWITCH, NON –LOCKING

- .1 The non-automatic, non-locking, molded case circuit interrupter shall be factory mounted in the high voltage section of the electrical panel. The switch handle shall be accessible from the unit front and mounted on the indoor cooling unit.

2.24 FILTER BOX AND DUCT KIT

- .1 A return air filter box shall be provided with hinged filter access, and 1" (25.4 mm) duct flange. A 1" (25.4 mm) duct flange shall also be provided for air discharge. Filters shall be 1" x 16" x 20" (25.4mm x 406mm x 508mm) MERV 8 per ASHRAE 52.2-2007.

2.25 DUCT COLLAR KIT

- .1 1" (25.4 mm) duct flanges shall be provided for each of the discharge and return air openings. Filters and filter box must be field supplied.

2.26 REFRIGERANT LINE SWEAT ADAPTER KIT

- .1 Provide a sweat adapter kit to permit field brazing of refrigerant line connections for application to air cooled split systems.

2.27 REFRIGERANT CHARGE

- .1 Charge refrigerant system at factory, seal and test.
- .2 Holding charge of refrigerant applied at factory.

Part 3 Execution

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for air conditioning components installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental Representative.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied [and after receipt of written approval to proceed from Departmental Representative.

3.2 GENERAL

- .1 Install air conditioning unit in accordance with manufacturer's installation instructions. Install unit plumb and level, firmly anchored in location indicated, and maintain manufacturer's recommended clearances.

3.3 ELECTRICAL WIRING

- .1 Install and connect electrical devices furnished by manufacturer but not specified to be factory-mounted. Furnish copy of manufacturer's electrical connection diagram submittal to electrical contractor. Install and wire per local and national codes.

3.4 PIPING CONNECTIONS

- .1 Install and connect devices furnished by manufacturer but not specified to be factory-mounted. Furnish copy of manufacturer's piping connection diagram submittal to piping contractor.

3.5 SUPPLY AND DRAIN WATER PIPING

- .1 Connect water supply and drains to air conditioning unit. Unit drain shall be trapped internally and shall not be trapped externally.

3.6 FIELD-SUPPLIED PAN

- .1 A field-supplied pan with drain shall be installed beneath ducted cooling units.

3.7 FIELD QUALITY CONTROL

- .1 Startup air conditioning unit in accordance with manufacturer's startup instructions. Test controls and demonstrate compliance with requirements.

3.8 EQUIPMENT PREPARATION

- .1 Provide services of manufacturer's field engineer to set and adjust equipment for operation as specified.

3.9 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .3 Waste Management: separate waste materials In accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

3.10 PROTECTION

- .1 Protect installed products and components from damage during construction.
- .2 Repair damage to adjacent materials caused by computer room air conditioning installation.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 ASTM International
 - .1 ASTM E84-Latest Edition, Standard Test Method for Surface Burning Characteristics of Building Materials.
 - .2 ASTM C916-1985 Latest Edition, Standard Specification for Adhesives for Duct Thermal Insulation.
 - .3 ASTM C1071-Latest Edition, Standard Specification for Fibrous Glass Duct Lining Insulation (Thermal and Sound Absorbing Material).
- .2 National Fire Protection Association (NFPA)
 - .1 NFPA 90A-Latest Edition, Standard for the Installation of Air Conditioning and Ventilating Systems.
 - .2 NFPA 90B-Latest Edition, Standard for the Installation of Warm Air Heating and Air Conditioning Systems (ANSI).
- .3 Underwriters' Laboratories (UL) Inc.
 - .1 UL 2021-Latest Edition, Fixed and Location-Dedicated Electric Room Heaters.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for unit heaters and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Manufacturer's Instructions: provide to indicate special handling criteria, installation sequence, cleaning procedures.
- .4 Shop Drawings:
 - .1 Submit drawings stamped and signed by professional engineer registered or licensed in Province of Manitoba, Canada.
 - .2 Indicate on drawings:
 - .1 Equipment, capacity and piping connections.
 - .2 Dimensions, internal and external construction details, recommended method of installation with proposed structural steel support, sizes and location of mounting bolt holes.

1.3 CLOSEOUT SUBMITTALS

- .1 Submit in accordance with Section 01 78 00 - Closeout Submittals.
- .2 Operation and Maintenance Data: submit operation and maintenance data for unit heaters for incorporation into manual.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements, with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials indoors in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect unit heaters from nicks, scratches, and blemishes.
 - .3 Replace defective or damaged materials with new.
- .4 Develop Construction Waste Management Plan related to Work of this Section.
- .5 Packaging Waste Management: remove as specified in Construction Waste Management Plan in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

Part 2 Products

2.1 UNIT HEATERS

- .1 Cabinet Unit Heaters: to UL 2021.
- .2 Cabinet: type as indicated, steel with rounded exposed corners and edges, removable panels, and integral air outlet and inlet.
- .3 Finish with factory applied primer coat.
- .4 Special cabinets: as indicated.
- .5 Fans: centrifugal double width wheels, statically and dynamically balanced, direct driven, sleeve bearings, resilient mounted.
- .6 Motor: multi-speed, tapped wound permanent split capacitor type with sleeve bearings, built-in thermal overload protection and resilient rubber isolation mounting.
- .7 Capacity: as indicated.
- .8 Control:
 - .1 On-off 2 speed switch key operated with integral overloads in cabinet wall mounted.
 - .2 Control thermostat: integral room electric, line low voltage, electronic, Energy Star Certified, rating to suit cabinet unit heater, locking cover, set point locking device, concealed adjustment, plastic brushed aluminum stainless steel cover and guard, thermometer in cover.

2.2 HORIZONTAL UNIT HEATERS – GAS FIRED

- .1 Gas-fired, separated combustion horizontal unit heaters
 - .1 Provide (90%+) high-efficiency, separated-combustion, power vented, condensing, gas-fired unit heaters.

- .2 Unit heaters shall be ETL Listed for commercial or industrial installation and installed in accordance with CSA B149 Installation Codes.
- .3 Gas connection shall be external to the cabinet
- .2 Burner:
 - .1 The units shall incorporate a single, one piece burner assembly with a single orifice. The burner shall have a continuous wound close pressed stainless steel ribbon separating the flame from the burner interior. All units shall have a single venturi tube and orifice supplying fuel to a one-piece burner housing. Each heat exchanger cell shall use balanced draft induction to maintain optimum flame control
- .3 Controls:
 - .1 Controls shall include a single-stage gas valve; direct spark multi-try ignition with electronic flame supervision with timed lockout integrally controlled via a printed circuit control board. The control board shall also incorporate diagnostic lights, DIP switches for fan overrun settings, and a relay for fan only operation. All units shall be equipped with a safety limit switch.
 - .2 All controls shall be enclosed in the sealed control compartment to protect them from accidental damage, dust, and atmospheric corrosion.
- .4 Combustion Air and Venting:
 - .1 The unit shall have a factory-installed power venter device to draw combustion air from outside of the building. The outside air shall enter the unit through a factory-installed round inlet air terminal on the rear of the heater. The control compartment shall be sealed and the access door shall be gasketed to prevent dirt, lint, dust, or other contaminants present in the heated space from entering the unit. The control compartment door shall be equipped with a safety interlock switch to prevent operation when the door is open.
 - .2 The combustion air supply pipe and flue exhaust pipe all PVC vent pipe must be approved to ULC S636. All venting and drain parts shall be run in parallel from the heater to a factory supplied concentric adapter assembly, which allows for a single wall or roof penetration, to the vertical air inlet and vent terminal. A 4" PVC clean out cap drilled and tapped for attaching a vent condensate drain is included with the vent/combustion air kit.
 - .3 The combustion air/venting system shall include a vibration isolated power venter motor and wheel assembly and a combustion air pressure switch.
- .5 Primer, Cement, and Applicator Requirements
 - .1 Primer for joints shall conform to ASTM F 656.
 - .2 Cement for joints shall conform to ASTM D 2564.
- .6 Electrical:
 - .1 Operation shall be controlled by an integrated circuit board that includes LED diagnostic indicator lights. Supply voltage connections shall be made in a sealed junction box. 24-volt control connections shall be made on an externally mounted terminal strip with connections (W1, W2, R, and G). All internal

wiring, both line and control voltages, shall be terminated by insulated terminal connectors to minimize shock hazard during service. Each unit shall be equipped for use with 115/1 volt power supply. All units will be equipped with a built-in disconnect switch.

.7 Cabinet:

- .1 The cabinet shall be low profile with a pre-coat or powder coat RAL 1001 paint finish. Finish shall be a minimum 80 gloss on G30 galvanized steel. The cabinet shall be constructed so that screws are not visible from the bottom, front, or sides, except for service panel and accessories. Unit construction shall incorporate a beveled front corner on control side for additional cabinet rigidity. All units shall be manufactured with a tooled drawn supply air orifice on the rear panel to reduce fan inlet noise.
- .2 The unit shall be designed for ceiling suspension featuring 3/8"-16 female threads (hanger kits for 1" pipe) at 4-point locations with no additional adapter kits. The cabinet shall be equipped with painted, roll-formed horizontal louvers. Louvers shall be spring held and adjustable for directing airflow.
- .3 The cabinet shall be equipped with a full safety fan guard. The (open drip proof) (enclosed) motor and fan assembly shall be resiliently mounted to the cabinet to reduce vibration and noise. The unit shall be designed with a full opening service access panel complete with screw closure attachment and lifting handle for removal. Service panel shall be fully gasketed and equipped with a safety interlock switch.
- .4 All components in the gas train, all standard electrical controls, and the power venter shall be within the sealed service compartment.
- .5 Minimum top clearance from combustibles shall be 4". Minimum bottom clearance from combustibles shall be 1". Minimum clearance from combustibles on non-service side shall be 2". Casing: 1.6 mm thick cold rolled steel, gloss enamel finish, with threaded connections for hanger rods.

Fan: direct drive propeller type, factory balanced, with anti-corrosive finish and fan guard.

- .8 Motor: speed as indicated continuous duty, built-in overload protection, and resilient motor explosion proof supports.
- .9 Air outlet: adjustable louvres.
- .10 Capacity: as indicated
- .11 Control room thermostat: electric, low voltage, electronic, Energy Star Certified, locking cover, set point locking device, concealed adjustment, cover and guard.

Part 3 Execution

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for unit heaters installation in accordance with manufacturer's written instructions.

- .1 Visually inspect substrate in presence of Departmental Representative DCC Representative Consultant.
- .2 Inform Departmental Representative DCC Representative Consultant of unacceptable conditions immediately upon discovery.
- .3 Proceed with installation only after unacceptable conditions have been remedied and after receipt of written approval to proceed from Departmental Representative DCC Representative Consultant.

3.2 INSTALLATION

- .1 Install in accordance with manufacturer's instructions.
- .2 Include double swing pipe joints as indicated.
- .3 Check final location with Departmental Representative if different from that indicated prior to installation.
 - .1 Should deviations beyond allowable clearances arise, request and follow Departmental Representative's directive.
- .4 Provide supplementary suspension steel as required.
- .5 Install thermostats in locations indicated.
- .6 Before acceptance, set discharge patterns to suit requirements.

3.3 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .3 Waste Management: separate waste materials for reuse recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

3.4 PROTECTION

- .1 Protect installed products and components from damage during construction.
- .2 Repair damage to adjacent materials caused by unit heaters installation.

END OF SECTION