

Part 1 General

1.1 DEFINITIONS

- .1 For additional acronyms and definitions refer to Section 25 05 01 - EMCS: General Requirements.
- .2 AEL: ratio between total test period less any system downtime accumulated within that period and test period.
- .3 Downtime: results whenever EMCS is unable to fulfill required functions due to malfunction of equipment defined under responsibility of EMCS contractor. Downtime is measured by duration, in time, between time that Contractor is notified of failure and time system is restored to proper operating condition. Downtime not to include following:
 - .1 Outage of main power supply in excess of back-up power sources, provided that:
 - .1 Automatic initiation of back-up was accomplished.
 - .2 Automatic shut-down and re-start of components was as specified.
 - .2 Failure of communications link, provided that:
 - .1 Controller automatically and correctly operated in stand-alone mode.
 - .2 Failure was not due to failure of any specified EMCS equipment.
 - .3 Functional failure resulting from individual sensor inputs or output devices, provided that:
 - .1 System recorded said fault.
 - .2 Equipment defaulted to fail-safe mode.
 - .3 AEL of total of all input sensors and output devices is at least 90 % during test period.

1.2 DESIGN REQUIREMENTS

- .1 Confirm with Departmental Representative that Design Criteria and Design Intents are still applicable.
- .2 Commissioning personnel to be fully aware of and qualified to interpret Design Criteria and Design Intents.

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submittals in accordance with Section 01330 - Submittal Procedures.
- .2 Final Report: submit report to Departmental Representative
 - .1 Include measurements, final settings and certified test results.
 - .2 Bear signature of commissioning technician and supervisor
 - .3 Report format to be approved by Departmental Representative before commissioning is started.
 - .4 Revise "as-built" documentation, commissioning reports to reflect changes, adjustments and modifications to EMCS as set during commissioning and submit

to Departmental Representative in accordance with Section 01 78 00 - Closeout Submittals.

- .5 Recommend additional changes and/or modifications deemed advisable in order to improve performance, environmental conditions or energy consumption.

1.4 CLOSEOUT SUBMITTALS

- .1 Provide documentation, O&M Manuals, and training of O&M personnel for review of Departmental Representative before interim acceptance in accordance with Section 01 78 00 - Closeout Submittals.

1.5 COMMISSIONING

- .1 Do commissioning in accordance with Section 01 91 13 - General Commissioning (Cx) Requirements.
- .2 Carry out commissioning under direction of Departmental Representative.
- .3 Inform, and obtain approval from, Departmental Representative in writing at least 14 days prior to commissioning or each test. Indicate:
 - .1 Location and part of system to be tested or commissioned.
 - .2 Testing/commissioning procedures, anticipated results.
 - .3 Names of testing/commissioning personnel.
- .4 Correct deficiencies, re-test in presence of Departmental Representative satisfactory performance is obtained.
- .5 Acceptance of tests will not relieve Contractor from responsibility for ensuring that complete systems meet every requirement of Contract.
- .6 Load system with project software.
- .7 Perform tests as required.

1.6 COMPLETION OF COMMISSIONING

- .1 Commissioning to be considered as satisfactorily completed when objectives of commissioning have been achieved and reviewed by Departmental Representative.

1.7 ISSUANCE OF FINAL CERTIFICATE OF COMPLETION

- .1 Final Certificate of Completion will not be issued until receipt of written approval indicating successful completion of specified commissioning activities including receipt of commissioning documentation.

Part 2 Products

2.1 EQUIPMENT

- .1 Provide sufficient instrumentation to verify and commission the installed system. Provide two-way radios.
- .2 Instrumentation accuracy tolerances: higher order of magnitude than equipment or system being tested.
- .3 Independent testing laboratory to certify test equipment as accurate to within approved tolerances no more than 2 months prior to tests.
- .4 Locations to be approved, readily accessible and readable.
- .5 Application: to conform to normal industry standards.

Part 3 Execution

3.1 PROCEDURES

- .1 Test each system independently and then in unison with other related systems.
- .2 Commission each system using procedures prescribed by the Departmental Representative.
- .3 Commission integrated systems using procedures prescribed by Departmental Representative.
- .4 Debug system software.
- .5 Optimize operation and performance of systems by fine-tuning PID values and modifying CDLs as required.
- .6 Test full scale emergency evacuation and life safety procedures including operation and integrity of smoke management systems under normal and emergency power conditions as applicable.

3.2 FIELD QUALITY CONTROL

- .1 Pre-Installation Testing.
 - .1 Not applicable
- .2 Completion Testing.
 - .1 General: test after installation of each part of system and after completion of mechanical and electrical hook-ups, to verify correct installation and functioning.
 - .2 Include following activities:
 - .1 Test and calibrate field hardware including stand-alone capability of each controller.
 - .2 Verify each A-to-D convertor.

-
- .3 Test and calibrate each AI using calibrated digital instruments.
 - .4 Test each DI to ensure proper settings and switching contacts.
 - .5 Test each DO to ensure proper operation and lag time.
 - .6 Test each AO to ensure proper operation of controlled devices. Verify tight closure and signals.
 - .7 Test operating software.
 - .8 Test application software and provide samples of logs and commands.
 - .9 Verify each CDL including energy optimization programs.
 - .10 Debug software.
 - .11 Provide point verification list in table format including point identifier, point identifier expansion, point type and address, low and high limits and engineering units. Include space on commissioning technician and Departmental Representative. This document will be used in final startup testing.
- .3 Final Startup Testing: Upon satisfactory completion of tests, perform point-by-point test of entire system under direction of Departmental Representative provide:
- .1 2 technical personnel capable of re-calibrating field hardware and modifying software.
 - .2 Detailed daily schedule showing items to be tested and personnel available.
 - .3 Departmental Representative's acceptance signature to be on executive and applications programs.
 - .4 Commissioning to commence during final startup testing.
 - .5 O&M personnel to assist in commissioning procedures as part of training.
 - .6 Commissioning to be supervised by qualified supervisory personnel and Departmental Representative.
 - .7 Operate systems as long as necessary to commission entire project.
 - .8 Monitor progress and keep detailed records of activities and results.
- .4 Final Operational Testing: to demonstrate that EMCS functions in accordance with contract requirements.
- .1 Prior to beginning of 30 day test demonstrate that operating parameters (setpoints, alarm limits, operating control software, sequences of operation, trends, graphics and CDL's) have been implemented to ensure proper operation and operator notification in event of off-normal operation.
 - .1 Repetitive alarm conditions to be resolved to minimize reporting of nuisance conditions.
 - .2 Test to last at least 30 consecutive 24 hour days.
 - .3 Tests to include:
 - .1 Demonstration of correct operation of monitored and controlled points.
 - .2 Operation and capabilities of sequences, reports, special control algorithms, diagnostics, software.
 - .4 System will be accepted when:

- .1 EMCS equipment operates to meet overall performance requirements. Downtime as defined in this Section must not exceed allowable time calculated for this site.
- .2 Requirements of Contract have been met.
- .5 In event of failure to attain specified AEL during test period, extend test period on day-to-day basis until specified AEL is attained for test period.
- .6 Correct defects when they occur and before resuming tests.
- .5 Departmental Representative to verify reported results.

3.3 ADJUSTING

- .1 Final adjusting: upon completion of commissioning as reviewed by Departmental Representative set and lock devices in final position and permanently mark settings.

3.4 DEMONSTRATION

- .1 Demonstrate to Departmental Representative operation of systems including sequence of operations in regular and emergency modes, under normal and emergency conditions, start-up, shut-down interlocks and lock-outs in accordance with Section 01 79 00 - Demonstration and Training.

END OF SECTION

Part 1 General

1.1 DEFINITIONS

- .1 CDL - Control Description Logic.
- .2 For additional acronyms and definitions refer to Section 25 05 01 - EMCS: General Requirements.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submittals in accordance with Section 01 33 00 - Submittal Procedures, supplemented and modified by requirements of this Section.
- .2 Submit training proposal complete with hour-by-hour schedule including brief overview of content of each segment to Departmental Representative 30 days prior to anticipated date of beginning of training.
 - .1 List name of trainer, and type of visual and audio aids to be used.
 - .2 Show co-ordinated interface with other EMCS mechanical and electrical training programs.
- .3 Submit reports within one week after completion of training program that training has been satisfactorily completed.

1.3 QUALITY ASSURANCE

- .1 Provide competent instructors thoroughly familiar with aspects of EMCS installed in facility.
- .2 Departmental Representative reserves right to approve instructors.

1.4 INSTRUCTIONS

- .1 Provide instruction to designated personnel in adjustment, operation, maintenance and pertinent safety requirements of EMCS installed.
- .2 Training to be project-specific.

1.5 TIME FOR INSTRUCTION

- .1 Number of days of instruction to be as specified in this section (3 day = 24 hours including two 15 minute breaks and excluding lunch time).

1.6 TRAINING MATERIALS

- .1 Provide equipment, visual and audio aids, and materials for classroom training.
- .2 Supply manual for each trainee, describing in detail data included in each training program.

- .1 Review contents of manual in detail to explain aspects of operation and maintenance (O&M).

1.7 TRAINING PROGRAM

- .1 To be in 2 phases over 4 month period.
- .2 Phase 1: 1 day program to begin before 30 day test period at time mutually agreeable to Contractor, Departmental Representative.
 - .1 Train O&M personnel in functional operations and procedures to be employed for system operation.
 - .2 Supplement with on-the-job training during 30 day test period.
 - .3 Include overview of system architecture, communications, operation of computer and peripherals, report generation.
 - .4 Include detailed training on operator interface functions for control of mechanical systems, CDL's for each system, and elementary preventive maintenance.
- .3 Phase 2: 2 day program to begin 2 weeks after acceptance for operators, equipment maintenance personnel and programmers.
 - .1 Provide multiple instructors on pre-arranged schedule. Include at least following:
 - .1 Operator training: provide operating personnel, maintenance personnel and programmers with condensed version of Phase 1 training.
 - .2 Equipment maintenance training: provide personnel with 1/2 day training in maintenance of EMCS equipment, including general equipment layout, trouble shooting and preventive maintenance of EMCS components, maintenance and calibration of sensors and controls.
 - .3 Programmers: provide personnel with ½ day training

1.8 ADDITIONAL TRAINING

- .1 List courses offered by name, duration and approximate cost per person per week. Note courses recommended for training supervisory personnel.

1.9 MONITORING OF TRAINING

- .1 Departmental Representative to monitor training program and may modify schedule and content. Provide a video recording of training sessions for future reference by Owner.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 American National Standards Institute (ANSI)/The Instrumentation, Systems and Automation Society (ISA).
 - .1 ANSI/ISA 5.5-1985, Graphic Symbols for Process Displays.
- .2 American National Standards Institute (ANSI)/ Institute of Electrical and Electronics Engineers (IEEE).
 - .1 ANSI/IEEE 260.1-[1993], American National Standard Letter Symbols Units of Measurement (SI Units, Customary Inch-Pound Units, and Certain Other Units).
- .3 American Society of Heating, Refrigerating and Air-Conditioning Engineers, Inc. (ASHRAE).
 - .1 ASHRAE STD 135-R2004, BACNET - Data Communication Protocol for Building Automation and Control Network.
- .4 Canadian Standards Association (CSA International).
 - .1 CAN/CSA-Z234.1-89(R1995), Canadian Metric Practice Guide.
- .5 Consumer Electronics Association (CEA).
 - .1 CEA-709.1-B-2002, Control Network Protocol Specification.
- .6 Department of Justice Canada (Jus).
 - .1 Canadian Environmental Assessment Act (CEAA), 1995, c. 37.
 - .2 Canadian Environmental Protection Act (CEPA), 1999, c. 33.
- .7 Electrical and Electronic Manufacturers Association (EEMAC).
 - .1 EEMAC 2Y-1-1958, Light Gray Colour for Indoor Switch Gear.
- .8 Health Canada/Workplace Hazardous Materials Information System (WHMIS).
 - .1 Material Safety Data Sheets (MSDS).
- .9 Transport Canada (TC).
 - .1 Transportation of Dangerous Goods Act (TDGA), 1992, c. 34.

1.2 ACRONYMS AND ABBREVIATIONS

- .1 Acronyms used in EMCS:
 - .1 AEL - Average Effectiveness Level.
 - .2 AI - Analog Input.
 - .3 AIT - Agreement on International Trade.
 - .4 AO - Analog Output.
 - .5 BACnet - Building Automation and Control Network.
 - .6 BC(s) - Building Controller(s).
 - .7 BECC - Building Environmental Control Center.

- .8 CAD - Computer Aided Design.
- .9 CDL - Control Description Logic.
- .10 CDS - Control Design Schematic.
- .11 COSV - Change of State or Value.
- .12 CPU - Central Processing Unit.
- .13 DI - Digital Input.
- .14 DO - Digital Output.
- .15 DP - Differential Pressure.
- .16 ECU - Equipment Control Unit.
- .17 EMCS - Energy Monitoring and Control System.
- .18 HVAC - Heating, Ventilation, Air Conditioning.
- .19 IDE - Interface Device Equipment.
- .20 I/O - Input/Output.
- .21 ISA - Industry Standard Architecture.
- .22 LAN - Local Area Network.
- .23 LCU - Local Control Unit.
- .24 MCU - Master Control Unit.
- .25 NAFTA - North American Free Trade Agreement.
- .26 NC - Normally Closed.
- .27 NO - Normally Open.
- .28 OS - Operating System.
- .29 O&M - Operation and Maintenance.
- .30 OWS - Operator Work Station.
- .31 PC - Personal Computer.
- .32 PCI - Peripheral Control Interface.
- .33 PCMCIA - Personal Computer Micro-Card Interface Adapter.
- .34 PID - Proportional, Integral and Derivative.
- .35 RAM - Random Access Memory.
- .36 SP - Static Pressure.
- .37 ROM - Read Only Memory.
- .38 TCU - Terminal Control Unit.
- .39 USB - Universal Serial Bus.
- .40 UPS - Uninterruptible Power Supply.
- .41 VAV - Variable Air Volume.

1.3 DEFINITIONS

- .1 Point: may be logical or physical.
 - .1 Logical points: values calculated by system such as setpoints, totals, counts, derived corrections and may include, but not limited to result of and statements in CDL's.
 - .2 Physical points: inputs or outputs which have hardware wired to controllers which are measuring physical properties, or providing status conditions of contacts or

relays which provide interaction with related equipment (stop, start) and valve or damper actuators.

- .2 Point Name: composed of two parts, point identifier and point expansion.
 - .1 Point identifier: comprised of three descriptors, "area" descriptor, "system" descriptor and "point" descriptor, for which database to provide 25 character fields for each point identifier. "System" is system that point is located on.
 - .1 Area descriptor: building or part of building where point is located.
 - .2 System descriptor: system that point is located on.
 - .3 Point descriptor: physical or logical point description. For point identifier "area", "system" and "point" will be short forms or acronyms. Database must provide 25 character field for each point identifier.
 - .2 Point expansion: comprised of three fields, one for each descriptor. Expanded form of short form or acronym used in "area", "system" and "point" descriptors is placed into appropriate point expansion field. Database must provide 32 character field for each point expansion.
 - .3 Bilingual systems to include additional point identifier expansion fields of equal capacity for each point name for second language.
 - .1 System to support use of numbers and readable characters including blanks, periods or underscores to enhance user readability for each of the above strings.
- .3 Point Object Type: points fall into following object types:
 - .1 AI (analog input).
 - .2 AO (analog output).
 - .3 DI (digital input).
 - .4 DO (digital output).
 - .5 Pulse inputs.
- .4 Symbols and engineering unit abbreviations utilized in displays: to ANSI/ISA S5.5.
 - .1 Printouts: to ANSI/IEEE 260.1.
 - .2 Refer also to Section 25 05 54- EMCS: Identification.

1.4 SYSTEM DESCRIPTION

- .1 Work covered by sections referred to above consists of fully operational EMCS, including, but not limited to, following:
 - .1 Building Controllers.
 - .2 Control devices as listed in I/O point summary tables.
 - .3 OWS(s).
 - .4 Data communications equipment necessary to effect EMCS data transmission system.
 - .5 Field control devices.
 - .6 Software/Hardware complete with full documentation.
 - .7 Complete operating and maintenance manuals.
 - .8 Training of personnel.
 - .9 Acceptance tests, technical support during commissioning, full documentation.

- .10 Wiring interface co-ordination of equipment supplied by others.
- .11 Miscellaneous work as specified in these sections and as indicated.
- .2 Design Requirements:
 - .1 Design and provide conduit and wiring linking elements of system.
 - .2 Supply sufficient programmable controllers of types to meet project requirements. Quantity and points contents as reviewed by Departmental Representative, prior to installation.
 - .3 Location of controllers as reviewed by Departmental Representative prior to installation.
 - .4 Provide utility power to EMCS as indicated.
 - .5 Metric references: in accordance with CAN/CSA Z234.1.
- .3 Language Operating Requirements:
 - .1 Provide English operator selectable access codes.
 - .2 Use non-linguistic symbols for displays on graphic terminals wherever possible. Other information to be in English.
 - .3 Operating system executive: existing. Description; Andover Controls, Infinity CX 9200 with T.a.c. Continuum - Cyberstation O.S.
 - .4 System manager software: include in English system definition point database, additions, deletions or modifications, control loop statements, use of high level programming languages, report generator utility and other OS utilities used for maintaining optimal operating efficiency.
 - .5 Include, in English:
 - .1 Input and output commands and messages from operator-initiated functions and field related changes and alarms as defined in CDL's or assigned limits (i.e. commands relating to day-to-day operating functions and not related to system modifications, additions, or logic re-definements).
 - .2 Graphic "display" functions, point commands to turn systems on or off, manually override automatic control of specified hardware points. Reporting function such as trend log, trend graphics, alarm report logs, energy report logs, maintenance generated logs.

1.5 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Make submittals in accordance with Section 01 33 00 - Submittal Procedures and 25 05 02 - EMCS: Shop Drawings, Product Data and Review Process.
- .2 Submit for review:
 - .1 Equipment list and systems manufacturers within 10 days after award of contract.
 - .2 List existing field control devices to be re-used.
- .3 Quality Control:
 - .1 Provide equipment and material from manufacturer's regular production, CSA certified, manufactured to standard quoted plus additional specified requirements.
 - .2 Where CSA certified equipment is not available submit such equipment to inspection authorities for special inspection and approval before delivery to site.

- .3 Submit proof of compliance to specified standards with shop drawings and product data in accordance with Section 25 05 02 - EMCS: Shop Drawings, Product Data and Review Process. Label or listing of specified organization is acceptable evidence.
- .4 For materials whose compliance with organizational standards/codes/specifications is not regulated by organization using its own listing or label as proof of compliance, furnish certificate stating that material complies with applicable referenced standard or specification.
- .5 Permits and fees: in accordance with general conditions of contract.
- .6 Submit certificate of acceptance from authority having jurisdiction to Departmental Representative.
- .7 Existing devices intended for re-use: submit test report.

1.6 QUALITY ASSURANCE

- .1 Have local office within 100 km of project staffed by trained personnel capable of providing instruction, routine maintenance and emergency service on systems
- .2 Have access to local supplies of essential parts and provide 7 year guarantee of availability of spare parts after obsolescence.
- .3 Ensure qualified supervisory personnel continuously direct and monitor Work and attend site meetings.
- .4 The work specified herein shall be an extension or addition of the existing Andover Controls EMCS. All new installed alternate systems must be compatible with the existing EMCS systems.

1.7 DELIVERY, STORAGE AND HANDLING

- .1 Material Delivery Schedule: provide Departmental Representative with schedule within 4 weeks after award of Contract.
- .2 Waste Management and Disposal:
 - .1 Separate waste materials in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
 - .2 Remove from site and dispose of packaging materials at appropriate recycling facilities.
 - .3 Place materials defined as hazardous or toxic in designated containers.

1.8 EXISTING CONDITIONS - CONTROL COMPONENTS

- .1 Utilize existing control wiring and piping as indicated and where suitable.
- .2 Re-use field control devices that are usable in their original configuration provided that they conform to applicable codes, standards specifications.
 - .1 Do not modify original design of existing devices without written permission from Departmental Representative.
 - .2 Provide for new, properly designed device where re-usability of components is uncertain.

- .3 Inspect and test existing devices intended for re-use within 30 days of award of contract, and prior to installation of new devices.
 - .1 Furnish test report within 40days of award of contract listing each component to be re-used and indicating whether it is in good order or requires repair by Departmental Representative.
 - .2 Failure to produce test report will constitute acceptance of existing devices by contractor.
- .4 Non-functioning items:
 - .1 Provide with report specification sheets or written functional requirements to support findings.
 - .2 Departmental Representative will repair or replace existing items judged defective yet deemed necessary for EMCS.
- .5 Submit written request for permission to disconnect controls and to obtain equipment downtime before proceeding with Work.
- .6 Remove existing controls not re-used or not required. Place in approved storage for disposition as directed.

Part 2 Products

2.1 EQUIPMENT

- .1 Control Network Protocol and Data Communication Protocol (BACNET): to ASHRAE STD 135-2004
- .2 Complete list of equipment and materials to be used on project and forming part of tender documents by adding manufacturer's name, model number and details of materials, and submit for approval.

2.2 ADAPTORS

- .1 Provide adaptors between metric and imperial components.

Part 3 Execution

3.1 MANUFACTURER'S RECOMMENDATIONS

- .1 Installation: to manufacturer's recommendations.

3.2 PAINTING

- .1 Painting: not applicable

END OF SECTION

Part 1 General

1.1 DEFINITIONS

- .1 Acronyms and definitions: refer to Section 25 05 01 - EMCS: General Requirements.

1.2 DESIGN REQUIREMENTS

- .1 Preliminary Design Review: to contain following contractor and systems information.
 - .1 Location of local office.
 - .2 Description and location of installing and servicing technical staff.
 - .3 Location and qualifications of programming design and programming support staff.
 - .4 List of spare parts.
 - .5 Location of spare parts stock.
 - .6 Names of sub-contractors and site-specific key personnel.
 - .7 Sketch of site-specific system architecture.
 - .8 Specification sheets for each item including memory provided, programming language, speed, type of data transmission.
 - .9 Descriptive brochures.

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submittals in accordance with Section 01 33 00 - Submittal Procedures and coordinate with requirements in this Section.
- .2 Submit preliminary design document within 15 working days after contract award, for review by Departmental Representative.
- .3 Shop Drawings to consist of 3 hard copies and 1 soft copy of design documents, shop drawings, product data and software.
- .4 Hard copy to be completely indexed and coordinated package to assure compliance with contract requirements and arranged in same sequence as specification and cross-referenced to specification section and paragraph number.
- .5 Soft copy to be in AutoCAD - latest version and Microsoft Word latest version format, structured using menu format for easy loading and retrieval on OWS.

1.4 PRELIMINARY SHOP DRAWING REVIEW

- .1 Submit preliminary shop drawings within 30 working days of award of contract and include following:
 - .1 Specification sheets for each item. To include manufacturer's descriptive literature, manufacturer's installation recommendations, specifications, drawings, diagrams, performance and characteristic curves, catalogue cuts, manufacturer's name, trade name, catalogue or model number, nameplate data, size, layout, dimensions, capacity, other data to establish compliance.

- .2 Detailed system architecture showing all points associated with each controller and where new EMCS ties into existing EMCS.
- .3 Spare point capacity of each controller by number and type.
- .4 Controller locations.
- .5 Auxiliary control cabinet locations.
- .6 Single line diagrams showing cable routings, conduit sizes, spare conduit capacity between control centre, field controllers and systems being controlled.
- .7 Valves: complete schedule listing including following information: designation, service, manufacturer, model, point ID, design flow rate, design pressure drop, required cv, Valve size, actual cv, spring range, pilot range, required torque, actual torque and close off pressure (required and actual).
- .8 Dampers: sketches showing module assembly.

1.5 DETAILED SHOP DRAWING REVIEW

- .1 Submit detailed shop drawings within 60 working days after award of contract and before start of installation and include following:
 - .1 Corrected and updated versions (hard copy only) of submissions made during preliminary review.
 - .2 Wiring diagrams.
 - .3 Piping diagrams and hook-ups.
 - .4 Interface wiring diagrams showing termination connections and signal levels [for equipment to be supplied by others.
 - .5 Shop drawings for each input/output point, sensors, transmitters, showing information associated with each particular point including:
 - .1 Sensing element type and location.
 - .2 Transmitter type and range.
 - .3 Associated field wiring schematics, schedules and terminations.
 - .4 Complete Point Name Lists.
 - .5 Setpoints, curves or graphs and alarm limits (high and low, 3 types critical, cautionary and maintenance), signal range.
 - .6 Software and programming details associated with each point.
 - .7 Manufacturer's recommended installation instructions and procedures.
 - .8 Input and output signal levels or pressures where new system ties into existing control equipment.
 - .6 Control schematics, narrative description, CDL's fully showing and describing automatic and manual procedure required to achieve proper operation of project, including under complete failure of EMCS.
 - .7 Graphic system schematic displays of all systems with point identifiers and textual description of system and floor plan graphics, as specified.
 - .8 Complete system CDL's including companion English language explanations on same sheet but with different font and italics. CDL's to contain specified energy optimization programs.
 - .9 Listing and example of specified reports.
 - .10 Listing of time of day schedules.

- .11 Mark up to-scale construction drawing to detail control room showing location of equipment and operator work space.
- .12 Type and size of memory with statement of spare memory capacity.
- .13 Full description of software programs provided.
- .14 Sample of "Operating Instructions Manual" to be used for training purposes.
- .15 Outline of proposed start-up and verification procedures. Refer to Section 25 01 11 - EMCS: Start-up, Verification and Commissioning.

1.6 QUALITY ASSURANCE

- .1 Preliminary Design Review Meeting: Convene meeting within 45 working days of award of contract to:
 - .1 Undertake functional review of preliminary design documents, resolve inconsistencies.
 - .2 Resolve conflicts between contract document requirements and actual items (e.g.: points list inconsistencies).
 - .3 Review interface requirements of materials supplied by others.
 - .4 Review "Sequence of Operations".
- .2 Contractor's programmer to attend meeting.
- .3 Departmental Representative retains right to revise sequence or subsequent CDL prior to software finalization without cost to Departmental Representative.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 DEFINITIONS

- .1 BECC - Building Environmental Control Centre.
- .2 OWS - Operator Work Station.
- .3 For additional acronyms and definitions refer to Section 25 05 01 - EMCS: General Requirements.

1.2 SUBMITTALS

- .1 Submittals in accordance with Section 01 78 00 - Closeout Procedures, supplemented and modified by requirements of this Section.
- .2 Submit Record Documents As-built drawings and Operation and Maintenance Manual to Departmental Representative in English.
- .3 Provide soft copies and hard copies in hard-back, 50 mm 3 ring, D-ring binders.
 - .1 Binders to be 2/3 maximum full.
 - .2 Provide index to full volume in each binder.
 - .3 Identify contents of each manual on cover and spine.
 - .4 Provide Table of Contents in each manual.
 - .5 Assemble each manual to conform to Table of Contents with tab sheets placed before instructions covering subject.

1.3 AS-BUILTS

- .1 Provide 1 copy of detailed shop drawings generated in Section 25 05 02 - EMCS: Submittals and Review Process and include:
 - .1 Changes to contract documents as well as addenda and contract extras.
 - .2 Changes to interface wiring.
 - .3 Routing of conduit, wiring and control air lines associated with EMCS installation.
 - .4 Locations of obscure devices to be indicated on drawings.
 - .5 Listing of alarm messages.
 - .6 Panel/circuit breaker number for sources of normal/emergency power.
 - .7 Names, addresses, telephone numbers of each sub-contractor having installed equipment, local representative for each item of equipment, each system.
 - .8 Test procedures and reports: provide records of start-up procedures, test procedures, checkout tests and final commissioning reports as specified in Section 25 01 11 - EMCS: Start-up, Verification and Commissioning.
 - .9 Basic system design and full documentation on system configuration.
- .2 Submit for final review by Departmental Representative.

- .3 Provide before acceptance 2 hard and 1 soft copy incorporating changes made during final review.

1.4 O&M MANUALS

- .1 Custom design O&M Manuals (both hard and soft copy) to contain material pertinent to this project only, and to provide full and complete coverage of subjects referred to in this Section.
- .2 Provide 2 complete sets of hard and soft copies prior to system or equipment tests
- .3 Include complete coverage in concise language, readily understood by operating personnel using common terminology of functional and operational requirements of system.
- .4 Functional description to include:
 - .1 Full details of data communications, including data types and formats, data processing and disposition data link components, interfaces and operator tests or self-test of data link integrity.
 - .2 Explicit description of hardware and software functions, interfaces and requirements for components in functions and operating modes.
 - .3 Description of person-machine interactions required to supplement system description, known or established constraints on system operation, operating procedures currently implemented or planned for implementation in automatic mode.
- .5 System operation to include:
 - .1 Complete step-by-step procedures for operation of system including required actions at each OWS.
 - .2 Operation of computer peripherals, input and output formats.
 - .3 Emergency, alarm and failure recovery.
 - .4 Step-by-step instructions for start-up, back-up equipment operation, execution of systems functions and operating modes, including key strokes for each command so that operator need only refer to these pages for keystroke entries required to call up display or to input command.
- .6 Software to include:
 - .1 Documentation of theory, design, interface requirements, functions, including test and verification procedures.
 - .2 Detailed descriptions of program requirements and capabilities.
 - .3 Data necessary to permit modification, relocation, reprogramming and to permit new and existing software modules to respond to changing system functional requirements without disrupting normal operation.
 - .4 Software modules, fully annotated source code listings, error free object code files ready for loading via peripheral device
 - .5 Complete program cross reference plus linking requirements, data exchange requirements, necessary subroutine lists, data file requirements, other information necessary for proper loading, integration, interfacing, and program execution.
 - .6 Software for each Controller and single section referencing Controller common parameters and functions.

- .7 Maintenance: document maintenance procedures including inspection, periodic preventive maintenance, fault diagnosis, repair or replacement of defective components, including calibration, maintenance, repair of sensors, transmitters, transducers, controller and interface firmware's, plus diagnostics and repair/replacement of system hardware.
- .8 System configuration document:
 - .1 Provisions and procedures for planning, implementing and recording hardware and software modifications required during operating lifetime of system.
 - .2 Information to ensure co-ordination of hardware and software changes, data link or message format/content changes, sensor or control changes in event that system modifications are required.
- .9 Programmer control panel documentation: provide where panels are independently interfaced with BECC, including interfacing schematics, signal identification, timing diagrams, fully commented source listing of applicable driver/handler.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 Canadian Standards Association (CSA International).
 - .1 CSA C22.1, the Canadian Electrical Code, Part I (19th Edition), Safety Standard for Electrical Installations.

1.2 DEFINITIONS

- .1 For acronyms and definitions refer to Section 25 05 01 - EMCS: General Requirements.

1.3 SYSTEM DESCRIPTION

- .1 Language Operating Requirements: provide identification for control items in English.

1.4 SUBMITTALS

- .1 Submittals in accordance with Section 01 33 00 - Submittal Procedures supplemented and modified by requirements of this Section.
- .2 Submit to Departmental Representative for approval samples of nameplates, identification tags and list of proposed wording.

Part 2 Products

2.1 NAMEPLATES FOR PANELS

- .1 Identify by Plastic laminate, 3 mm thick, black core, square corners, lettering accurately aligned and engraved into core.
- .2 Sizes: 25 x 67 mm minimum.
- .3 Lettering: minimum 7 mm high.
- .4 Inscriptions: machine engraved to identify function.

2.2 NAMEPLATES FOR FIELD DEVICES

- .1 Identify by plastic encased cards attached by plastic tie.
- .2 Sizes: 50 x 100 mm minimum.
- .3 Lettering: minimum 5 mm high produced from laser printer in black.
- .4 Data to include: point name and point address.
- .5 Companion cabinet: identify interior components using plastic enclosed cards with point name and point address.

2.3 NAMEPLATES FOR ROOM SENSORS

- .1 Identify by stick-on labels using point identifier.
- .2 Location: as directed by Departmental Representative.
- .3 Letter size: to suit, clearly legible.

2.4 WARNING SIGNS

- .1 Equipment including motors, starters under remote automatic control: supply and install orange coloured signs warning of automatic starting under control of EMCS.
- .2 Sign to read: "Caution: This equipment is under automatic remote control of EMCS" as reviewed by Departmental Representative's.

2.5 WIRING

- .1 Supply and install numbered tape markings on wiring at panels, junction boxes, splitters, cabinets and outlet boxes.
- .2 Colour coding: to CSA C22.1. Use colour coded wiring in communications cables, matched throughout system.
- .3 Power wiring: identify circuit breaker panel/circuit breaker number inside each EMCS panel.

2.6 CONDUIT

- .1 Colour code EMCS conduit.
- .2 Pre-paint box covers and conduit fittings.
- .3 Coding: use fluorescent orange paint and confirm colour with Departmental Representative. during "Preliminary Design Review".

Part 3 Execution

3.1 NAMEPLATES AND LABELS

- .1 Ensure that manufacturer's nameplates, CSA labels and identification nameplates are visible and legible at all times.

3.2 EXISTING PANELS

- .1 Correct existing nameplates and legends to reflect changes made during Work.

END OF SECTION

Part 1 General

1.1 DEFINITIONS

- .1 BC(s) - Building Controller(s).
- .2 OWS - Operator Work Station.
- .3 For additional acronyms and definitions refer to Section 25 05 01 - EMCS: General Requirements.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Submit detailed preventative maintenance schedule for system components to Departmental Representative.
- .3 Submit detailed inspection reports to Departmental Representative.
- .4 Submit dated, maintenance task lists to Departmental Representative and include the following sensor and output point detail, as proof of system verification:
 - .1 Point name and location.
 - .2 Device type and range.
 - .3 Measured value.
 - .4 System displayed value.
 - .5 Calibration detail
 - .6 Indication if adjustment required,
 - .7 Other action taken or recommended.
- .5 Submit network analysis report showing results with detailed recommendations to correct problems found.
- .6 Records and logs: in accordance with Section 01 78 00 - Closeout Submittals.
 - .1 Maintain records and logs of each maintenance task on site.
 - .2 Organize cumulative records for each major component and for entire EMCS chronologically.
 - .3 Submit records to Departmental Representative, after inspection indicating that planned and systematic maintenance have been accomplished.
- .7 Revise and submit to Departmental Representative in accordance with Section 01 78 00 - Closeout Submittals "As-built drawings" documentation and commissioning reports to reflect changes, adjustments and modifications to EMCS made during warranty period.

1.3 MAINTENANCE SERVICE DURING WARRANTY PERIOD

- .1 Provide services, materials, and equipment to maintain EMCS for specified warranty period. Provide detailed preventative maintenance schedule for system components as described in Submittal article.

- .2 Emergency Service Calls:
 - .1 Initiate service calls when EMCS is not functioning correctly.
 - .2 Qualified control personnel to be available during warranty period to provide service to "CRITICAL" components whenever required at no extra cost.
 - .3 Furnish Departmental Representative with telephone number where service personnel may be reached at any time.
 - .4 Service personnel to be on site ready to service EMCS within 4 hours after receiving request for service.
 - .5 Perform Work continuously until EMCS restored to reliable operating condition.
- .3 Operation: foregoing and other servicing to provide proper sequencing of equipment and satisfactory operation of EMCS based on original design conditions and as recommended by manufacturer.
- .4 Work requests: record each service call request, when received separately on approved form and include:
 - .1 Serial number identifying component involved.
 - .2 Location, date and time call received.
 - .3 Nature of trouble.
 - .4 Names of personnel assigned.
 - .5 Instructions of work to be done.
 - .6 Amount and nature of materials used.
 - .7 Time and date work started.
 - .8 Time and date of completion.
- .5 Provide system modifications in writing.
 - .1 No system modification, including operating parameters and control settings, to be made without prior written approval of Departmental Representative.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 FIELD QUALITY CONTROL

- .1 Perform as minimum (3) three minor inspections and one major inspection (more often if required by manufacturer) per year. Provide detailed written report to Departmental Representative as described in Submittal article.
- .2 Perform inspections during regular working hours, 0800 to 1630 h, Monday through Friday, excluding statutory holidays.

- .3 Following inspections are minimum requirements and should not be interpreted to mean satisfactory performance:
 - .1 Perform calibrations using test equipment having traceable, certifiable accuracy at minimum 50% greater than accuracy of system displaying or logging value.
 - .2 Check and calibrate each field input/output device in accordance with Canada Labour Code - Part I and CSA Z204.
 - .3 Provide dated, maintenance task lists, as described in Submittal article, as proof of execution of complete system verification.
- .4 Minor inspections to include, but not limited to:
 - .1 Perform visual, operational checks to BC's, peripheral equipment, interface equipment and other panels.
 - .2 Check equipment cooling fans as required.
 - .3 Visually check for mechanical faults, air leaks and proper pressure settings on pneumatic components.
 - .4 Review system performance with Operations Supervisor to discuss suggested or required changes.
- .5 Major inspections to include, but not limited to:
 - .1 Minor inspection.
 - .2 Clean BC, interface and other panels, micro-processor interior and exterior surfaces.
 - .3 Check signal, voltage and system isolation of BC, peripherals, interface and other panels.
 - .4 Verify calibration/accuracy of each input and output device and recalibrate or replace as required.
 - .5 Provide mechanical adjustments, and necessary maintenance on printers.
 - .6 Run system software diagnostics as required.
 - .7 Install software and firmware enhancements to ensure components are operating at most current revision for maximum capability and reliability.
 - .1 Perform network analysis and provide report as described in Submittal article.
- .6 Rectify deficiencies revealed by maintenance inspections and environmental checks.
- .7 Continue system debugging and optimization.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 Canadian Standards Association (CSA International).
 - .1 CSA T529-95 (R2000), Telecommunications Cabling Systems in Commercial Buildings (Adopted ANSI/TIA/EIA-568-A with modifications).
 - .2 CSA T530-99 (R2004), Commercial Building Standard for Telecommunications Pathways and Spaces (Adopted ANSI/TIA/EIA-569-A with modifications).
- .2 Institute of Electrical and Electronics Engineers (IEEE)/Standard for Information technology - Telecommunications and information exchange between systems - Local and metropolitan area networks - Specific requirements.
 - .1 IEEE Std 802.3TM-2002, Part 3: Carrier sense multiple access with collision detection (CSMA/CD) access method and physical layer specifications.
- .3 Telecommunications Industries Association (TIA)/Electronic Industries Alliance (EIA)
 - .1 TIA/EIA-568-[March 2004], Commercial Building Telecommunications Cabling Standards Set, Part 1 General Requirements Part 2 Balanced Twisted-Pair Cabling Components Standard.
 - .2 TIA/EIA-569-A-December 2001, Commercial Building Standard for Telecommunications Pathways and Spaces.
- .4 Treasury Board Information Technology Standard (TBITS).
 - .1 TBITS 6.9-2000, Profile for the Telecommunications Wiring System in Government Owned and Leased Buildings - Technical Specifications.

1.2 DEFINITIONS

- .1 Acronyms and definitions: refer to Section 25 05 01 - EMCS - General Requirements.

1.3 SYSTEM DESCRIPTION

- .1 Data communication network to link Operator Workstations and Master Control Units (MCU) in accordance with CSA T529 TIA/EIA-568 and CSA T530 TIA/EIA-569-A.
 - .1 Provide reliable and secure connectivity of adequate performance between different sections (segments) of network.
 - .2 Allow for future expansion of network, with selection of networking technology and communication protocols.
- .2 Data communication network to include, but not limited to:
 - .1 EMCS-LAN.
 - .2 Network interface cards.
 - .3 Network management hardware and software.
 - .4 Network components necessary for complete network.

1.4 DESIGN REQUIREMENTS

- .1 EMCS Local Area Network (EMCS-LAN).
 - .1 High speed, high performance, local area network over which MCUs and OWSs communicate with each other directly on peer to peer basis in accordance with IEEE 802.3/Ethernet Standard.
 - .2 EMCS-LAN to: BACnet.
 - .3 Each EMCS-LAN to be capable of supporting at least 50 devices.
 - .4 Support of combination of MCUs and OWSs directly connected to EMCS-LAN.
 - .5 High speed data transfer rates for alarm reporting, quick report generation from multiple controllers, upload/download information between network devices. Bit rate to be 10 Megabits per second minimum.
 - .6 Detection and accommodation of single or multiple failures of either OWSs, MCUs or network media. Operational equipment to continue to perform designated functions effectively in event of single or multiple failures.
 - .7 Commonly available, multiple sourced, networking components and protocols to allow system to co-exist with other networking applications including office automation.
 - .8 Refer to the control schematics for system architecture details
- .2 Dynamic Data Access.
 - .1 LAN to provide capabilities for OWSs, either network resident or connected remotely, to access point status and application report data or execute control functions for other devices via LAN.
 - .2 Access to data to be based upon logical identification of building equipment.
- .3 Network Medium.
 - .1 Network medium: twisted cable, shielded twisted cable, compatible with network protocol to be used within buildings.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 General:
 - .1 The new control systems will be connected to the existing OWS and the existing server.
 - .2 A new BACnet Building Controller will support all new EMCS controllers.

Part 2 Products

2.1 OWS HARDWARE

- .1 The OWS is existing.

2.2 OPERATING SYSTEM (OS) OR EXECUTIVE

- .1 OS is existing.

2.3 OWS CONTROL SOFTWARE

- .1 C.T.A.C, ANDOVER.

2.4 OWS FUNCTIONAL ADDITIONS

- .1 All new Building and control systems shall be incorporated into the existing OWS. All existing functionality in the OWS, including display, alarming, trending, reporting, etc shall be incorporated for all new systems in this project
- .2 Utilize the graphics package to generate system schematic diagrams as required in Section 25 90 01 - EMCS: Site Requirements, Applications and System Sequences of Operation, and as directed by Departmental Representative.
- .3 Provide graphics for all systems shown on the control schematics. Provide graphic for floor depicting room sensors and control devices located in their actual location. DCC Representative to provide CAD floor layouts.
- .4 Provide complete directory of system graphics, including other pertinent system information.
- .5 Provide unique sequence of operation graphic or pop-up window for each graphic that is depicted on OWS. Provide access to sequence of operation graphic by link button on each system graphic.

Part 3 Execution

3.1 INSTALLATION REQUIREMENTS

.1 Not applicable

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 American Society of Heating, Refrigeration and Air-Conditioning Engineers, Inc. (ASHRAE).
 - .1 ASHRAE 2003, Applications Handbook, SI Edition.
- .2 Canadian Standards Association (CSA International).
 - .1 C22.2 No.205-M1983(R1999), Signal Equipment.
- .3 Institute of Electrical and Electronics Engineers (IEEE).
 - .1 IEEE C37.90.1-02, Surge Withstand Capabilities (SWC) Tests for Relays and Relay Systems Associated with Electric Power Apparatus.

1.2 DEFINITIONS

- .1 Acronyms and definitions: refer to Section 25 05 01 - EMCS: General Requirements.

1.3 SYSTEM DESCRIPTION

- .1 General: Network of controllers comprising of MCU('s), LCU('s), ECU('s) or TCU('s) to be provided as indicated in System Architecture Diagram to support building systems and associated sequences of operations as detailed in these specifications.
 - .1 Provide sufficient controllers to meet intents and requirements of this section.
 - .2 Controller quantity, and point contents to be approved by Departmental Representative at time of preliminary design review.
- .2 Controllers: stand-alone intelligent Control Units.
 - .1 Incorporate programmable microprocessor, non-volatile program memory, RAM, power supplies, as required to perform specified functions.
 - .2 Incorporate communication interface ports for communication to LANs to exchange information with other Controllers.
 - .3 Capable of interfacing with operator interface device.
 - .4 Execute its logic and control using primary inputs and outputs connected directly to its onboard input/output field terminations or slave devices, and without need to interact with other controller. Secondary input used for reset such as outdoor air temperature may be located in other Controllers.
 - .1 Secondary input used for reset such as outdoor air temperature may be located in other Controllers.

1.4 DESIGN REQUIREMENTS

- .1 To include:
 - .1 Scanning of AI and DI connected inputs for detection of change of value and processing detection of alarm conditions.

- .2 Perform On-Off digital control of connected points, including resulting required states generated through programmable logic output.
- .3 Perform Analog control using programmable logic, (including PID) with adjustable dead bands and deviation alarms.
- .4 Control of systems as described in sequence of operations.
- .5 Execution of optimization routines as listed in this section.
- .2 Total spare capacity for MCUs and LCUs: at least 25 % of each point type distributed throughout the MCUs and LCUs.
- .3 Field Termination and Interface Devices:
 - .1 To: CSA C22.2 No.205.
 - .2 Electronically interface sensors and control devices to processor unit.
 - .3 Include, but not be limited to, following:
 - .1 Programmed firmware or logic circuits to meet functional and technical requirements.
 - .2 Power supplies for operation of logics devices and associated field equipment.
 - .3 Lockable wall cabinet.
 - .4 Required communications equipment and wiring (if remote units).
 - .5 Leave controlled system in "fail-safe" mode in event of loss of communication with, or failure of, processor unit.
 - .6 Input Output interface to accept as minimum AI, AO, DI, DO functions as specified.
 - .7 Wiring terminations: use conveniently located screw type or spade lug terminals.
 - .4 AI interface equipment to:
 - .1 Convert analog signals to digital format with 10 bit analog-to-digital resolution.
 - .2 Provide for following input signal types and ranges:
 - .1 4 - 20mA;
 - .2 0 - 10V DC;
 - .3 100/1000 ohm RTD input;
 - .3 Meet IEEE C37.90.1 surge withstand capability.
 - .4 Where required, dropping resistors to be certified precision devices which complement accuracy of sensor and transmitter range specified.
 - .5 AO interface equipment:
 - .1 Convert digital data from controller processor to acceptable analog output signals using 8 bit digital-to-analog resolution.
 - .2 Provide for following output signal types and ranges:
 - .1 4 - 20 mA.
 - .2 0 - 10 V DC.
 - .3 Meet IEEE C37.90.1 surge withstand capability.
 - .6 DI interface equipment:

- .1 Able to reliably detect contact change of sensed field contact and transmit condition to controller.
- .2 Meet IEEE C37.90.1 surge withstand capability.
- .3 Accept pulsed inputs up to 2 kHz.
- .7 DO interface equipment:
 - .1 Respond to controller processor output, switch respective outputs. Each DO hardware to be capable of switching up to 0.5 amps at 24V AC.
 - .2 Switch up to 5 amps at 220 V AC using optional interface relay.
- .4 Controllers and associated hardware and software: operate in conditions of 0 degrees C to 44 degrees C and 20 % to 90 % non-condensing RH.
- .5 Controllers (MCU, LCU): mount in wall mounted cabinet with hinged, keyed-alike locked door.
 - .1 Provide for conduit entrance from top, bottom or sides of panel.
 - .2 ECUs and TCUs to be mounted in equipment enclosures or separate enclosures.
 - .3 Mounting details as approved by Departmental Representative for ceiling mounting.
 - .4 VAV/reheat terminal controllers shall be mounted on the terminal unit.
- .6 Control Cabinets to provide protection from water dripping from above, while allowing sufficient airflow to prevent internal overheating.
- .7 Provide surge and low voltage protection for interconnecting wiring connections.

1.5 SUBMITTALS

- .1 Make submittals in accordance with Section 01 33 00 - Submittal Procedures and Section 25 05 02 - EMCS: Shop Drawings, Product Data and Review Process.
 - .1 Submit product data sheets for each product item proposed for this project.

1.6 MAINTENANCE PROCEDURES

- .1 Provide manufacturers recommended maintenance procedures for insertion in Section 25 05 03 - EMCS: Project Record Documents.

Part 2 Products

2.1 MASTER CONTROL UNIT (MCU)

- .1 General: primary function of MCU is to provide co-ordination and supervision of subordinate devices in execution of optimization routines such as demand limiting or enthalpy control.
- .2 Include high speed communication LAN Port for Peer to Peer communications with OWS(s) and other MCU level devices.
 - .1 MCU must support BACnet.

- .3 MCU local I/O capacity as follows:
 - .1 MCU I/O points as allocated in I/O Summary Table referenced in MD13800.
 - .2 LCUs may be added to support system functions.
- .4 Central Processing Unit (CPU).
 - .1 Processor to consist of minimum 16 bit microprocessor capable of supporting software to meet specified requirements.
 - .2 CPU idle time to be more than 30 % when system configured to maximum input and output with worst case program use.
 - .3 Minimum addressable memory to be at manufacturer's discretion but to support at least performance and technical specifications to include but not limited to:
 - .1 Non-volatile EEPROM to contain operating system, executive, application, sub-routine, other configurations definition software. Tape media not acceptable.
 - .2 Battery backed (72 hour minimum capacity) RAM (to reduce the need to reload operating data in event of power failure) to contain CDLs, application parameters, operating data or software that is required to be modifiable from operational standpoint such as schedules, setpoints, alarm limits, PID constants and CDL and hence modifiable on-line through operator panel or remote operator's interface. RAM to be downline loadable from OWS.
 - .4 Include uninterruptible clock accurate to plus or minus 5 secs/month, capable of deriving year/month/day/hour/minute/second, with rechargeable batteries for minimum 72 hour operation in event of power failure.
- .5 Local Operator Terminal (OT): Provide OT for each MCU unless otherwise specified in Section 25 90 01 - EMCS: Site Requirements, Applications and System Sequences of Operation.
 - .1 Mount access/display panel in MCU or in suitable enclosure beside MCU as approved by Departmental Representative.
 - .2 Support operator's terminal for local command entry, instantaneous and historical data display, programs, additions and modifications.
 - .3 Display simultaneously minimum of 16 point identifiers to allow operator to view single screen dynamic displays depicting entire mechanical systems. Point identifiers to be in English.
 - .4 Functions to include, but not be limited to, following:
 - .1 Start and stop points.
 - .2 Modify setpoints.
 - .3 Modify PID loop parameters.
 - .4 Override PID control.
 - .5 Change time/date.
 - .6 Add/modify/start/stop weekly scheduling.
 - .7 Add/modify setpoint weekly scheduling.
 - .8 Enter temporary override schedules.
 - .9 Define holiday schedules.

- .10 View analog limits.
- .11 Enter/modify analog warning limits.
- .12 Enter/modify analog alarm limits.
- .13 Enter/modify analog differentials.
- .5 Provide access to real and calculated points in controller to which it is connected or to other controller in network. This capability not to be restricted to subset of predefined "global points" but to provide totally open exchange of data between OT and other controller in network.
- .6 Operator access to OTs: same as OWS user password and password changes to automatically be downloaded to controllers on network.
- .7 Provide prompting to eliminate need for user to remember command format or point names. Prompting to be consistent with user's password clearance and types of points displayed to eliminate possibility of operator error.
- .8 Identity of real or calculated points to be consistent with network devices. Use same point identifier as at OWS's for access of points at OT to eliminate cross-reference or look-up tables.

2.2 LOCAL CONTROL UNIT (LCU)

- .1 Provide multiple control functions for typical built-up and package HVAC systems, hydronic systems and electrical systems.
- .2 Minimum of 16 I/O points of which minimum be 4 AOs, 4 AIs, 4 DIs, 4 DOs.
- .3 Points integral to one Building System to be resident on only one controller.
- .4 Microprocessor capable of supporting necessary software and hardware to meet specified requirements as listed in previous MCU article with following additions:
 - .1 Include minimum 2 interface ports for connection of local computer terminal.
 - .2 Design so that shorts, opens or grounds on input or output will not interfere with other input or output signals.
 - .3 Physically separate line voltage (70V and over) circuits from DC logic circuits to permit maintenance on either circuit with minimum hazards to technician and equipment.
 - .4 Include power supplies for operation of LCU and associated field equipment.
 - .5 In event of loss of communications with, or failure of, MCU, LCU to continue to perform control. Controllers that use defaults or fail to open or close positions not acceptable.
 - .6 Provide conveniently located screw type or spade lug terminals for field wiring.

2.3 SOFTWARE

- .1 General.
 - .1 Include as minimum: operating system executive, communications, application programs, operator interface, and systems sequence of operation - CDL's.
 - .2 Include "firmware" or instructions which are programmed into ROM, EPROM, EEPROM or other non-volatile memory.

- .3 Include initial programming of Controllers, for entire system.
- .2 Program and data storage.
 - .1 Store executive programs and site configuration data in ROM, EEPROM or other non-volatile memory.
 - .2 Maintain CDL and operating data including setpoints, operating constants, alarm limits in battery-backed RAM or EEPROM for display and modification by operator.
- .3 Programming languages.
 - .1 Program Control Description Logic software (CDL) using English like or graphical, high level, general control language.
 - .2 Structure software in modular fashion to permit simple restructuring of program modules if future software additions or modifications are required. GO TO constructs not allowed unless approved by Departmental Representative.
- .4 Operator Terminal interface.
 - .1 Operating and control functions include:
 - .1 Multi-level password access protection to allow user/manager to limit workstation control.
 - .2 Alarm management: processing and messages.
 - .3 Operator commands.
 - .4 Reports.
 - .5 Displays.
 - .6 Point identification.
- .5 Pseudo or calculated points.
 - .1 Software to provide access to value or status in controller or other networked controller in order to define and calculate pseudo point. When current pseudo point value is derived, normal alarm checks must be performed or value used to totalize.
 - .2 Inputs and outputs for process: include data from controllers to permit development of network-wide control strategies. Processes also to permit operator to use results of one process as input to number of other processes (e.g. cascading).
- .6 Control Description Logic (CDL):
 - .1 Capable of generating on-line project-specific CDLs which are software based, programmed into RAM or EEPROM and backed up to OWS. Owner must have access to these algorithms for modification or to be able to create new ones and to integrate these into CDLs on BC(s) from OWS.
 - .2 Write CDL in high level language that allows algorithms and interlocking programs to be written simply and clearly. Use parameters entered into system (e.g. setpoints) to determine operation of algorithm. Operator to be able to alter operating parameters on-line from OWS and BC(s) to tune control loops.
 - .3 Perform changes to CDL on-line.

- .4 Control logic to have access to values or status of points available to controller including global or common values, allowing cascading or inter-locking control.
- .5 Energy optimization routines including enthalpy control, supply temperature reset, to be LCU or MCU resident functions and form part of CDL.
- .6 MCU to be able to perform following pre-tested control algorithms:
 - .1 Two position control.
 - .2 Proportional Integral and Derivative (PID) control.
- .7 Control software to provide ability to define time between successive starts for each piece of equipment to reduce cycling of motors.
- .8 Provide protection against excessive electrical-demand situations during start-up periods by automatically introducing time delays between successive start commands to heavy electrical loads.
- .9 Power Fail Restart: upon detection of power failure system to verify availability of Emergency Power as determined by emergency power transfer switches and analyze controlled equipment to determine its appropriate status under Emergency power conditions and start or stop equipment as defined by I/O Summary. Upon resumption of normal power as determined by emergency power transfer switches, MCU to analyze status of controlled equipment, compare with normal occupancy scheduling, turn equipment on or off as necessary to resume normal operation.
- .7 Event and Alarm management: use management by exception concept for Alarm Reporting. This is system wide requirement. This approach will insure that only principal alarms are reported to OWS. Events which occur as direct result of primary event to be suppressed by system and only events which fail to occur to be reported. Examples of above are, operational temperature alarms limits which are exceeded when main air handler is stopped, or General Fire condition shuts air handlers down, only Fire alarm status shall be reported. Exception is, when air handler which is supposed to stop or start fails to do so under event condition.
- .8 Energy management programs: include specific summarizing reports, with date stamp indicating sensor details which activated and or terminated feature.
 - .1 MCU in coordination with subordinate LCU, TCU, ECU to provide for the following energy management routines:
 - .1 Time of day scheduling.
 - .2 Calendar based scheduling.
 - .3 Holiday scheduling.
 - .4 Temporary schedule overrides.
 - .5 Optimal start stop.
 - .6 Night setback control.
 - .7 Enthalpy (economizer) switchover.
 - .8 Temperature compensated load rolling.
 - .9 Fan speed/flow rate control.
 - .10 Night purge.
 - .2 Programs to be executed automatically without need for operator intervention and be flexible enough to allow customization.

- .3 Apply programs to equipment and systems as specified or requested by the Departmental Representative.
- .9 Function/Event Totalization: features to provide predefined reports which show daily, weekly, and monthly accumulating totals and which include high rate (time stamped) and low rate (time stamped) and accumulation to date for month.
 - .1 MCUs to accumulate and store automatically run-time for binary input and output points.
 - .2 MCU to automatically sample, calculate and store consumption totals on daily, weekly or monthly basis for user-selected analog or binary pulse input-type points.
 - .3 MCU to automatically count events (number of times pump is cycled off and on) daily, weekly or monthly basis.
 - .4 Totalization routine to have sampling resolution of 1 min or less for analog inputs.
 - .5 Totalization to provide calculations and storage of accumulations up to 99,999.9 units (eg. kWh, litres, tonnes, etc.).
 - .6 Store event totalization records with minimum of 9,999,999 events before reset.
 - .7 User to be able to define warning limit and generate user-specified messages when limit reached.

2.4 LEVELS OF ADDRESS

- .1 Upon operator's request, EMCS to present status of any single 'point', 'system' or point group, entire 'area', or entire network on printer or OWS as selected by operator.
 - .1 Display analog values digitally to 1 place of decimals with negative sign as required.
 - .2 Update displayed analog values and status when new values received.
 - .3 Flag points in alarm by blinking, reverse video, different colour, bracketed or other means to differentiate from points not in alarm.
 - .4 Updates to be change-of-value (COV) - driven or if polled not exceeding 2 second intervals.

2.5 POINT NAME SUPPORT

- .1 Controllers (MCU, LCU) to support PWGSC point naming convention as defined in Section 25 05 01 - EMCS: General Requirements.

Part 3 Execution

3.1 LOCATION

- .1 Location of Controllers to be approved by Departmental Representative.

3.2 INSTALLATION

- .1 Install Controllers in secure locking enclosures as directed by Departmental Representative.
- .2 Provide necessary power from local 120 V branch circuit panel for equipment.

- .3 Install tamper locks on breakers of circuit breaker panel.
- .4 Use uninterruptible Power Supply (UPS) and emergency power when equipment must operate in emergency and co-ordinating mode.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 American National Standards Institute (ANSI).
 - .1 ANSI C12.7-1993 (R1999), Requirements for Watthour Meter Sockets.
 - .2 ANSI/IEEE C57.13 - [1993], Standard Requirements for Instrument Transformers.
- .2 American Society for Testing and Materials International, (ASTM).
 - .1 ASTM B148-97 (03), Standard Specification for Aluminum-Bronze Sand Castings.
- .3 National Electrical Manufacturer's Association (NEMA).
 - .1 NEMA 250-03, Enclosures for Electrical Equipment (1000 Volts Maximum).
- .4 Air Movement and Control Association, Inc. (AMCA).
 - .1 AMCA Standard 500-D-98, Laboratory Method of Testing Dampers For Rating.
- .5 Canadian Standards Association (CSA International).
 - .1 CSA-C22.1 - 02, Canadian Electrical Code, Part 1 (19th Edition), Safety Standard for Electrical Installations.

1.2 DEFINITIONS

- .1 Acronyms and Definitions: refer to Section 25 05 01 - EMCS: General Requirements.

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit shop drawings and manufacturer's installation instructions in accordance with Section 25 05 02 - EMCS: Submittals and Review Process.
- .2 Pre-Installation Tests.
 - .1 Submit samples at random from equipment shipped, as requested by Departmental Representative for testing before installation. Replace devices not meeting specified performance and accuracy.
- .3 Manufacturer's Instructions:
 - .1 Submit manufacturer's installation instructions for specified equipment and devices.

1.4 EXISTING CONDITIONS

- .1 Cutting and Patching: in accordance with Section 01 73 00 - Execution Requirements.
- .2 Repair surfaces damaged during execution of Work.

- .3 Turn over to Departmental Representative existing materials removed from Work not identified for re-use.

Part 2 Products

2.1 GENERAL

- .1 Control devices of each category to be of same type and manufacturer.
- .2 External trim materials to be corrosion resistant. Internal parts to be assembled in vibration-proof assembly.
- .3 Operating conditions: 0 - 32 degrees C with 10 - 90% RH (non-condensing) unless otherwise specified.
- .4 Terminations: use standard conduit box with slot screwdriver compression connector block unless otherwise specified.
- .5 Transmitters and sensors to be unaffected by external transmitters including walkie talkies.
- .6 Account for hysteresis, relaxation time, maximum and minimum limits in applications of sensors and controls.
- .7 Outdoor installations: use weatherproof construction in NEMA 4 enclosures.
- .8 Devices installed in user occupied space not exceed Noise Criteria (NC) of 35. Noise generated by any device must not be detectable above space ambient conditions.
- .9 Range: including temperature, humidity, pressure, as indicated in I/O summary in Section 25 90 01 - EMCS: Site Requirements, Applications and System Sequences of Operation.

2.2 TEMPERATURE SENSORS

- .1 General: except for room sensors to be resistance or thermocouple type to following requirements:
 - .1 Thermocouples: limit to temperature range of 200 degrees C and over.
 - .2 RTD's: 100 or 1000 ohm at 0 degrees C (plus or minus 0.2 ohms) platinum element with strain minimizing construction, 3 integral anchored leadwires. Coefficient of resistivity: 0.00385 ohms/ohm degrees C.
 - .3 Sensing element: hermetically sealed.
 - .4 Stem and tip construction: copper or type 304 stainless steel.
 - .5 Time constant response: less than 3 seconds to temperature change of 10 degrees C.
 - .6 Immersion wells: NPS 3/4, stainless steel spring loaded construction, with heat transfer compound compatible with sensor. Insertion length to suit pipe size.
- .2 Room temperature sensors and display wall modules.
 - .1 Temperature sensing and display wall module.

- .1 LCD display to show space temperature and temperature setpoint.
- .2 Buttons for occupant selection of temperature setpoint.
- .3 Jack connection for plugging in contractor supplied zone terminal unit for access to zone bus.
- .4 Integral thermistor sensing element 10,000 ohm at 24 degrees.
- .5 Accuracy 0.2 degrees C over range of 0 to 70 degrees C.
- .6 Stability 0.02 degrees C drift per year.
- .2 Room temperature sensors.
 - .1 Wall mounting, in slotted type covers having brushed aluminum finish, with guard where indicated.
 - .2 Where room sensors are used for monitoring only, sensors shall be mounted behind a blank stainless steel plate.
 - .3 Element 10-50 mm long RTD with ceramic tube or equivalent protection or thermistor, 10,000 ohm, accuracy of plus or minus 0.2 degrees C.
- .3 Duct temperature sensors:
 - .1 General purpose duct type: suitable for insertion into ducts at various orientations, insertion length 460 mm or as indicated.
 - .2 Averaging duct type: incorporates numerous sensors inside assembly which are averaged to provide one reading. Minimum insertion length 6000 mm. Bend probe at field installation time to 100 mm radius at point along probe without degradation of performance.
- .4 Outdoor air temperature sensors:
 - .1 Outside air type: complete with probe length 100 - 150 mm long, non-corroding shield to minimize solar and wind effects, threaded fitting for mating to 13 mm conduit, weatherproof construction in NEMA 4 enclosure.

2.3 TEMPERATURE TRANSMITTERS

- .1 Requirements:
 - .1 Input circuit: to accept 3-lead, 100 or 1000 ohm at 0 degrees C, platinum resistance detector type sensors.
 - .2 Power supply: 24 V DC into load of 575 ohms. Power supply affect less than 0.01 degrees C per volt change.
 - .3 Output signal: 4 - 20 mA into 500 ohm maximum load.
 - .4 Input and output short circuit and open circuit protection.
 - .5 Output variation: less than 0.2% of full scale for supply voltage variation of plus or minus 10%.
 - .6 Combined non-linearity, repeatability, hysteresis effects: not to exceed plus or minus 0.5 % of full scale output.
 - .7 Maximum current to 100 or 1000 ohm RTD sensor: not to exceed 25 mA.
 - .8 Integral zero and span adjustments.
 - .9 Temperature effects: not to exceed plus or minus 1.0% of full scale/ 50 degrees C.

- .10 Long term output drift: not to exceed 0.25 % of full scale/ 6 months.
- .11 Transmitter ranges: select narrowest range to suit application from following:
 - .1 Minus 50degrees C to plus 50 degrees C, plus or minus 0.5 degrees C.
 - .2 0 to 100 degrees C, plus or minus 0.5 degrees C.
 - .3 0 to 50 degrees C, plus or minus 0.25 degrees C.
 - .4 0 to 25 degrees C, plus or minus 0.1 degrees C.
 - .5 10 to 35 degrees C, plus or minus 0.25 degrees C.

2.4 TEMPERATURE SWITCHES

- .1 Requirements:
 - .1 Operate automatically. Reset automatically, except as follows:
 - .1 Low temperature detection: manual reset.
 - .2 High temperature detection: manual reset.
 - .2 Adjustable setpoint and differential.
 - .3 Accuracy: plus or minus 1 degrees C.
 - .4 Snap action rating: 120V, 15 amps or 24V DC as required. Switch to be DPST for hardwire and EMCS connections.
 - .5 Type as follows:
 - .1 Room: for wall mounting on standard electrical box.
 - .2 Duct, general purpose: insertion length 460 mm.
 - .3 Thermowell: stainless steel, with compression fitting for NPS 3/4 thermowell. Immersion length: 100 mm.
 - .4 Low temperature detection: continuous element with 6000 mm insertion length, duct mounting, to detect coldest temperature in any 30 mm length.
 - .5 Strap-on: with helical screw stainless steel clamp.

2.5 SOLID STATE RELAYS

- .1 General:
 - .1 Relays to be socket or rail mounted.
 - .2 Relays to have LED Indicator
 - .3 Input and output Barrier Strips to accept 14 to 28 AWG wire.
 - .4 Operating temperature range to be -20 degrees C to 70 degrees C.
 - .5 Relays to be CSA Certified.
 - .6 Input/output Isolation Voltage to be 4000 VAC at 25 degrees C for 1 second maximum duration.
 - .7 Operational frequency range, 45 to 65 HZ.
- .2 Input:
 - .1 Control voltage, 3 to 32 VDC.
 - .2 Drop out voltage, 1.2 VDC.
 - .3 Maximum input current to match AO (Analog Output) board.

- .3 Output.
 - .1 AC or DC Output Model to suit application.

2.6 CURRENT TRANSDUCERS

- .1 Requirements:
 - .2 Purpose: combined sensor/transducer, to measure line current and produce proportional signal in one of following ranges:
 - .1 4-20 mA DC.
 - .2 0-1 volt DC.
 - .3 0-10 volts DC.
 - .4 0-20 volts DC.
 - .3 Frequency insensitive from 10 - 80 hz.
 - .4 Accuracy to 0.5% full scale.
 - .5 Zero and span adjustments. Field adjustable range to suit motor applications.
 - .6 Adjustable mounting bracket to allow for secure/safe mounting inside MCC.

2.7 CURRENT SENSING RELAYS

- .1 Requirements:
 - .1 Suitable to detect belt loss or motor failure.
 - .2 Trip point adjustment, output status LED.
 - .3 Split core for easy mounting.
 - .4 Induced sensor power.
 - .5 Relay contacts: capable of handling 0.5 amps at 30 VAC / DC. Output to be NO solid state.
 - .6 Suitable for single or 3 phase monitoring. For 3-Phase applications: provide for discrimination between phases.
 - .7 Adjustable latch level.

2.8 GAS DETECTION SENSORS (CO and NO2)

- .1 Requirements:
 - 1. Transmitter certified to CA/CSA C22.2 No. 61010-1
 - 2. Sensor shall be Electrochemical
 - 3. 0-100 ppm (CO) and 0-10 ppm (NO2)
 - 4. Accuracy $\pm 3\%$
 - 5. Outputs: 4-20mA and Relay 5A

6. Audible alarm 65dBA at 1m
7. Supply Voltage 17-27Vac or 24-38 Vdc
8. Transmitters to communicate over a daisy-chain, 2-wire bus with the gas detection Controller. Communication BUS shall be RS-485 MODBUS.

2.9 GAS DETECTION MONITOR AND CONTROLLER

.1 Requirements:

1. Intertek Listed to: UL 61010-1; and CSA C22.2 No. 61010-1-04
2. Capable of operating within relative humidity ranges of 5-99% and temperature ranges of 32°F to 100°F (0°C to 40°C).
3. Using an addressable RS-485 Modbus communication protocol, the controller shall use daisy chain wiring, requiring only 2 pairs of wires to connect up to 96 transmitters on 3 input channels.
4. Continuous alphanumeric display
5. Full array of visual indicators and integrated 65dBA alarm levels
6. Fully programmable relays (can be set as fail-safe or not)
7. R8 relay module with 8 relays, failsafe
8. Audible alarm 65dBA at 1m
9. Programmable time delays
10. Integrated time clock to enable scheduling of system operations
11. Controller shall be complete with datalogger, BACnet/IP output, plastic enclosure

2.10 CONTROL DAMPERS

- .1 Construction: blades, 152 mm wide, 1219 mm long, maximum. Modular maximum size, 1219 mm wide x 1219 mm high. Three or more sections to be operated by jack shafts.
- .2 Materials:
 - .1 Frame: 2.03 mm minimum thickness extruded aluminum. For outdoor air and exhaust air applications, frames to be insulated.
 - .2 Blades: extruded aluminum. For outdoor air/exhaust air applications, blades to be internally insulated.
 - .3 Bearings: maintenance free, synthetic type of material.
 - .4 Linkage and shafts: aluminum, zinc and nickel plated steel.
 - .5 Seals: synthetic type, mechanically locked into blade edges.
 - .1 Frame seals: synthetic type, mechanically locked into frame sides.
- .3 Performance: minimum damper leakage meet or exceed AMCA Standard 500-D ratings.

- .1 Size/Capacity: refer to damper schedule
- .2 Positive seal dampers for outdoor air and exhaust air applications.
- .3 Temperature range: minus 40 degrees C to plus 100 degrees C.
- .4 Arrangements: dampers mixing warm and cold air to be parallel blade, mounted at right angles to each other, with blades opening to mix air stream.
- .5 Jack shafts:
 - .1 25 mm diameter solid shaft, constructed of corrosion resistant metal complete with required number of pillow block bearings to support jack shaft and operate dampers throughout their range.
 - .2 Include corrosion resistant connecting hardware to accommodate connection to damper actuating device.
 - .3 Install using manufacturer's installation guidelines.
 - .4 Use same manufacturer as damper sections.

2.11 ELECTRONIC CONTROL DAMPER ACTUATORS

- .1 Requirements:
 - .1 Direct mount proportional type as indicated.
 - .2 Spring return for "fail-safe" in Normally Open or Normally Closed position as indicated.
 - .3 Operator: size to control dampers against maximum pressure and dynamic closing/opening pressure, whichever is greater.
 - .4 Power requirements: 5 VA maximum at 24 V AC.
 - .5 Operating range: 0 - 10 V DC or 4 - 20 mA DC.
 - .6 For VAV box applications floating control type actuators may be used.
 - .7 Damper actuator to drive damper from full open to full closed in less than 120 seconds.

2.12 CONTROL VALVES

- .1 Body: characterized ball.
 - .1 Flow characteristic, equal percentage, quick opening, as applicable.
 - .2 Flow factor (KV) as required for the flow: CV in imperial units.
 - .3 Normally open and Normally closed, as indicated.
 - .4 Two port, as indicated.
 - .5 Leakage rate ANSI class IV, 0.01% of full open valve capacity.
 - .6 Packing easily replaceable.
 - .7 Stem, stainless steel.
 - .8 Plug and seat, stainless steel.
 - .9 Disc, replaceable, material to suit application.
 - .10 NPS 2 and under:
 - .1 Screwed National Pipe Thread (NPT) tapered female connections.
 - .2 Valves to ANSI Class 250, valves to bear ANSI mark.

.3 Rangeability 50:1 minimum.

2.13 ELECTRONIC / ELECTRIC VALVE ACTUATORS

.1 Requirements:

- .1 Construction: steel, cast iron, aluminum.
- .2 Control signal: 0-10V DC or 4-20 mA DC.
- .3 Positioning time: to suit application. 90 sec maximum.
- .4 Fail to normal position as indicated.
- .5 Scale or dial indication of actual control valve position.
- .6 For interior and perimeter terminal heating and cooling applications floating control actuators are acceptable.
- .7 Minimum shut-off pressure: to suit system pressure.

2.14 PANELS

- .1 Free-standing or wall mounted enamelled steel cabinets with hinged and key-locked front door.
- .2 Multiple panels as required to handle requirements with additional space to accommodate 25% additional capacity as required by Departmental Representative without adding additional cabinets.
- .3 Panels to be lockable with same key.

2.15 WIRING

- .1 In accordance with Section 26 27 10 - Modular Wiring System and 26 27 26 - Wiring Devices.
- .2 For wiring under 70 volts use FT6 rated wiring where wiring is not run in conduit. Other cases use FT4 wiring.
- .3 Wiring must be continuous without joints.
- .4 Sizes:
 - .1 Field wiring to digital device: #18AWG and #20AWG stranded twisted pair, per manufacturer's recommendation.
 - .2 Analog input and output: shielded #18 minimum solid copper and #20 minimum stranded twisted pair, per manufacturer's recommendation.

Part 3 Execution

3.1 INSTALLATION

- .1 Install equipment, components so that manufacturer's and CSA labels are visible and legible after commissioning is complete.

- .2 Install field control devices in accordance with manufacturers recommended methods, procedures and instructions.
- .3 Temperature transmitters, humidity transmitters, current-to-pneumatic transducers, solenoid air valves, controllers, relays: install in NEMA I enclosure or as required for specific applications. Provide for electrolytic isolation in cases when dissimilar metals make contact.
- .4 Support field-mounted panels, transmitters and sensors on pipe stands or channel brackets.
- .5 Fire stopping: provide space for fire stopping in accordance with Section 07 84 00 - Firestopping. Maintain fire rating integrity.
- .6 Electrical:
 - .1 Complete installation in accordance with Section 26 05 00 - Common Work Results - Electrical.
 - .2 Modify existing starters to provide for EMCS as indicated in I/O Summaries and as indicated.
 - .3 Refer to electrical control schematics included as part of control design schematics in Section 25 90 01 - EMCS: Site Requirements Applications and Systems Sequences of Operation. Trace existing control wiring installation and provide updated wiring schematics including additions, deletions to control circuits for review by Departmental Representative before beginning Work.
 - .4 Terminate wires with screw terminal type connectors suitable for wire size, and number of terminations.
 - .5 Install communication wiring in conduit.
 - .1 Provide complete conduit system to link Building Controllers, field panels and OWS(s).
 - .2 Conduit sizes to suit wiring requirements and to allow for future expansion capabilities specified for systems.
 - .3 Maximum conduit fill not to exceed 40%.
 - .4 Design drawings do not show conduit layout.
 - .6 Do not run exposed conduits in normally occupied spaces unless otherwise indicated or unless impossible to do otherwise. Departmental Representative to review before starting Work. Wiring in mechanical rooms, wiring in service rooms and exposed wiring must be in conduit.

3.2 TEMPERATURE AND HUMIDITY SENSORS

- .1 Stabilize to ensure minimum field adjustments or calibrations.
- .2 Readily accessible and adaptable to each type of application to allow for quick easy replacement and servicing without special tools or skills.
- .3 Thermowells: install for piping installations.
 - .1 Locate well in elbow where pipe diameter is less than well insertion length.
 - .2 Thermowell to restrict flow by less than 30%.
 - .3 Use thermal conducting paste inside wells.

3.3 PANELS

- .1 Arrange for conduit and tubing entry from top, bottom or either side.
- .2 Wiring and tubing within panels: locate in trays or individually clipped to back of panel.
- .3 Identify wiring and conduit clearly.

3.4 PRESSURE AND DIFFERENTIAL PRESSURE SWITCHES AND SENSORS

- .1 Install isolation valve and snubber on sensors between sensor and pressure source where code allows.
 - .1 Protect sensing elements on steam and high temperature hot water service with pigtail syphon between valve and sensor.

3.5 IDENTIFICATION

- .1 Identify field devices in accordance with Section 25 05 54 - EMCS: Identification..

3.6 GAS DETECTIONN SYSTEM

- .1 Install in accordance with manufacturer's instructions and current codes.
- .2 Provide complete commissioning service by the manufacturer's authorized representative.

3.7 TESTING AND COMMISSIONING

- .1 Calibrate and test field devices for accuracy and performance in accordance with Section 25 01 11 - EMCS: Start-up, Verification and Commissioning.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 Refer to the control schematics and mechanical drawings

1.2 SEQUENCING

.1 Air Handling Unit AHU-1A (Warehouse)

.1 Run Conditions – Occupied/Unoccupied

System shall run continuously during occupied hours.

The system shall be off during the unoccupied hours. The system may also be returned to the occupied status by selecting the temporary override function on the Operator Workstation.

Alarms shall be provided as follows:

- High Supply Air Temp: If the supply air temperature is 2°C greater than the supply air setpoint.
- Low Supply Air Temp: If the supply air temperature is 2°C less than the supply air setpoint.

.2 Night Cycle Program

The unit shall start and operate when the room temperature drops below the night setpoint (15°C). When the temperature has risen 2°C above the night setpoint the unit shall shut down.

.3 Freeze Protection

The unit shall shut down and generate an alarm upon receiving a low supply air temperature status.

.4 Supply Fan:

The supply fan shall run anytime the unit is commanded to run. The fan shall run for a minimum of 5min (adj.) and be off a minimum of 5min (adj.) unless shutdown on safeties.

Alarms shall be provided as follows:

- Supply Fan Failure: Commanded on, but the status is off.
- Supply Fan in Hand: Commanded off, but the status is on.
- Supply Fan Runtime Exceeded: Status runtime exceeds a user definable limit.

.5 Supply Air Temperature Control

The supply air temperature shall be maintained by modulating the electric heating coil in sequence the mixed air dampers (economizer) and the cooling coil. The supply air temperature setpoint shall be reset by the average of the 4 associated room temperature sensors.

.6 Cooling Coil Control

The cooling coil condenser shall operate when the system is in the cooling mode (outdoor air temperature above 15°C).

.7 Economizer:

The controller shall measure the mixed air temperature and modulate the economizer dampers in sequence to maintain a setpoint 1°C (adj.) less than the supply air temperature setpoint. The outside air dampers shall maintain a minimum adjustable position of 10% (adj.) open whenever the system is in the occupied mode and the ERV is disabled. When the ERV is enabled, the minimum ventilation will be provided by the ERV and the minimum outdoor air damper position shall be 0%.

When outdoor air enthalpy is above the return air enthalpy, the outside air dampers shall close to the minimum position (as noted above).

The economizer shall close whenever:

- Mixed air temperature drops below 4.5°C (adj.)
- OR the low supply air temperature status is on.
- OR on loss of supply fan status.

The outside air and exhaust dampers shall close and the return air damper shall open when the unit is off.

.8 Filter Monitoring:

Monitor the filter pressure drop alarm. Alarms shall be provided as follows:

- Filter Status: An alarm shall be generated if the filter differential pressure exceeds its setpoint.

.2 Energy Recovery Ventilator (ERV-1A) (Warehouse)

.1 Run conditions.

- .1 The ERV shall start/stop based on the associated air handling unit's (AHU-1A) control.

.2 Enabled Mode:

During occupied mode the outdoor air and the exhaust dampers shall open. The supply and exhaust fan shall start. The reheat coil shall modulate to maintain supply air temperature at set point. Supply air temperature set point shall be adjustable from a duct mounted controller. The heating coil shall come complete with air flow sensors and safety interlocks required by the manufacture.

.3 Disabled Mode:

During unoccupied mode the outdoor and exhaust air damper shall be closed and the ERV shall be off.

.3 Data Room Air Conditioning AC-2A

.1 General:

The room is conditioned by a packaged, split system, precision cooling unit.

.2 The AC system shall be integrated into the EMCS via a BACnet communications link.

.3 Temperature and Humidity Control:

If the space requires cooling, the AC unit shall be enabled and the AC unit cooling shall be controlled from the room air temperature controller. Humidity control shall be integral to the unit, adjustable, as provided by the equipment manufacturer.

.4 Monitoring:

All key data points in the AC unit shall be communicated to the EMCS via the BACnet link. The data points shall be available as a graphic, trending, alarming and reporting, as if they were integral to the EMCS. Provide DDC I/Os (inputs and outputs) for Critical Alarm (as programmed in the unit controller), System ENABLE/DISABLE, Supply air temperature (SAT) and Room temperature (SPT).

.4 Truck Bay / Warehouse CO/NO2 Exhaust Ventilation

.1 General

- .1 The system provides ventilation for the area to maintain a safe environment.
- .2 The new exhaust fan EF-1A and existing supply fan SF-5 and existing exhaust fans EF-15 (Room 228), EF-16 (Room 233) and EF-17 (Room 231) shall start and the associated exhaust and outdoor air dampers shall open, when either the CO or the NO2 reading exceed setpoint.
- .3 If the CO/NO2 level does not drop, but rises so the sensor reaches the second alarm set point, the alarm located in the garage will sound and SF-5 shall be energized. The exhaust will continue to run. The motorized damper will remain open.
- .4 The fans shall be hard wired to the CO/NO2 controller.
- .5 A manual reset timer (0 to 30 minutes) shall allow the user to run the fan manually.
- .6 Alarms shall be provided as follows:
 - High CO level: If the CO level is above the alarm setpoint.
 - High NO2 level: If the NO2 level is above the alarm setpoint.
 - Exhaust Fan Failure: Commanded on, but the status is off.
 - Exhaust Fan in Hand: Commanded off, but the status is on.
- .7 Temperature Monitoring:

The space temperature shall be monitored by the EMCS. Refer to mechanical drawings for locations.
- .8 Monitor alarm levels are to activate and the unit is to be installed in accordance with the following parameters:

TOXIC GASES	FIRST ALARM	SECOND ALARM	SENSOR LOCATION	RADIUS OF COVERAGE
	SET POINT (TLV-TWA)	SET POINT (TLV-STEL)		
Carbon Monoxide (CO)	25 PPM	75 PPM	3-5 feet above the floor	50 feet
Diesel (NO ²)	.72 PPM	2 PPM	1 foot below the floor	50 feet

.9 Hand-off Auto Switch for Exhaust Fan EF-1A:

The hand-off auto switch will be able to start or stop the exhaust fan manually. It will also allow for the system to operate in automatic mode if desired. The motorized damper will be interlocked accordingly.

.10 Provide complete commissioning service by the manufacturer's authorized representative.

.5 Exhaust fan EF-1A (Warehouse)

- .1 Fan shall be one speed motor, interlocked with the CO/NO₂ system to operate on call from the CO/NO₂ control system to evacuate noxious vehicle exhaust gas components.
- .2 The Motorized damper shall be interlocked with the exhaust fan to open when the fan starts.

.6 Gas Unit Heater Control (Warehouse)

- .1 A wall mounted DDC BACnet thermostat shall cycle the fan and burners to maintain temperature at set point.
- .2 The BACnet thermostat shall be connected to the EMCS, for control and monitoring access.

.7 Relocated Hydronic Unit Heater Control UH-3 (Warehouse)

- .1 A wall mounted DDC BACnet thermostat shall cycle the fan and modulate the new control valve to maintain temperature at set point.
- .2 The BACnet thermostat shall be connected to the EMCS, for control and monitoring access.

.8 Rooftop Air Handling Units

- .1 The RTUs are supplied with a packaged control system, which includes a wall mounting multi-stage thermostat.
- .2 The packaged thermostat shall be replaced with a DDC BACnet thermostat.
- .3 The BACnet thermostat shall be connected to the EMCS, for control and monitoring access.

- .4 Provide a separate supply air temperature sensor and connect it to the BACnet thermostat for monitoring at the EMCS.
- .5 Provide a separate supply fan status sensor and connect it to the BACnet thermostat for monitoring at the EMCS.
- .9 Energy Recovery Ventilator (ERV-1B) (Tertiary Bus Garage)
 - .1 Run conditions.
 - .1 The ERV shall start/stop based on a time schedule.
 - .2 Enabled Mode:

During occupied mode the outdoor air and the exhaust dampers shall open. The supply and exhaust fan shall start. The preheat coil shall modulate to maintain a minimum preheat discharge temperature (initial setpoint shall be 0° C) to prevent excessive frosting of the ERV.

The reheat coil shall modulate to maintain supply air temperature at set point (initial setpoint shall be 17° C). Supply air temperature set point shall be reset from Outdoor Air temperature and adjustable from the OWS. The heating coils shall come complete with air flow sensors and safety interlocks required by the manufacture.
 - .3 Disabled Mode:

During unoccupied mode the outdoor and exhaust air damper shall be closed and the ERV shall be off.
- .10 Packaged Room Air Conditioning Units AC-1B and AC-2B (Tertiary Bus Garage)
 - .1 General:

The room are conditioned by a packaged, split system, precision cooling unit.
 - .2 The AC system shall be integrated into the EMCS via a BACnet communications link.
 - .3 Temperature and Humidity Control:

If the space requires cooling, the AC unit shall be enabled and the AC unit cooling shall be controlled from the room air temperature controller. Humidity control shall be integral to the unit, adjustable, as provided by the equipment manufacturer.
 - .4 Monitoring:

All key data points in the AC unit shall be communicated to the EMCS via the BACnet link. The data points shall be available as a graphic, trending, alarming and reporting, as if they were integral to the EMCS. Provide DDC I/Os (inputs and outputs) for Critical Alarm (as programmed in the unit controller), System ENABLE/DISABLE, Supply air temperature (SAT) and Room temperature (SPT).
- .11 Tertiary Bus Garage CO/NO2 Exhaust Ventilation
 - .1 General
 - .1 The system provides ventilation for the area to maintain a safe environment.

- .2 The new exhaust fan EF-1B shall start and the associated exhaust and outdoor air dampers shall open, when either the CO or the NO₂ reading exceed setpoint.
- .3 If the CO/NO₂ level does not drop, but rises so the sensor reaches the second alarm set point, the alarm located in the garage will sound and SF-5 shall be energized. The exhaust will continue to run. The motorized damper will remain open.
- .4 The fans shall be hard wired to the CO/NO₂ controller.
- .5 A manual reset timer (0 to 30 minutes) shall allow the user to run the fan manually.
- .6 Alarms shall be provided as follows:
 - High CO level: If the CO level is above the alarm setpoint.
 - High NO₂ level: If the NO₂ level is above the alarm setpoint.
 - Exhaust Fan Failure: Commanded on, but the status is off.
 - Exhaust Fan in Hand: Commanded off, but the status is on.
- .7 Temperature Monitoring:
The space temperature shall be monitored by the EMCS. Refer to mechanical drawings for locations.
- .8 Monitor alarm levels are to activate and the unit is to be installed in accordance with the following parameters:

TOXIC GASES	FIRST ALARM	SECOND ALARM	SENSOR LOCATION	RADIUS OF COVERAGE
	SET POINT (TLV-TWA)	SET POINT (TLV-STEL)		
Carbon Monoxide (CO)	25 PPM	75 PPM	3-5 feet above the floor	50 feet
Diesel (NO ₂)	.72 PPM	2 PPM	1 foot below the floor	50 feet

- .9 Hand-off Auto Switch for Exhaust Fan EF-1B:
The hand-off auto switch will be able to start or stop the exhaust fan manually. It will also allow for the system to operate in automatic mode if desired. The motorized damper will be interlocked accordingly.
- .10 Provide complete commissioning service by the manufacturer's authorized representative.

.12 Exhaust fan EF-1B

- .1 Fan shall be one speed motor, interlocked with the CO/NO₂ system to operate on call from the CO/NO₂ control system to evacuate noxious vehicle exhaust gas components.
- .2 The Motorized damper shall be interlocked with the exhaust fan to open when the fan starts.

.13 Gas Unit Heater Control

- .1 A wall mounted DDC BACnet thermostat shall cycle the fan and burners to maintain temperature at set point.
- .2 The BACnet thermostat shall be connected to the EMCS, for control and monitoring access.

.14 Sump Pit Alarm

- .1 The high level alarm probe (provided by the sump pit manufacturer) shall be connected to generate a critical alarm at the OWS.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION