


DETAIL



1:15

1. THE 4-38x235 TIE BEAM CAN BE LAMINATED ON SITE W/ SPLICES TO SUIT SITE CONDITION DUE TO ACCESS LIMITATION, CONTRACTOR TO PROPOSE SPLICE DETAIL FOR APPROVED PRIOR TO INSTALLATION
2. PROVIDE 3 ROWS OF 82 LG. NAILS @150 O/C STAGG., BETWEEN EACH PLY FOR THE NEW LAMINATED TIE BEAMS

<p>Public Works and Government Services Canada Pacific Region</p> <p>Travaux publics et Services gouvernementaux Canada Région du Pacifique</p>	<p>Drawing title: DETAIL A REVISED (DWG. S4)</p> <p>scale: N.T.S.</p>	<p>designed by: SZ</p> <p>drawn by: CAD</p> <p>reviewed by: -</p>
	<p>date: 2016.11.18</p> <p>revisions: -</p>	<p>approved by: -</p> <p>project no.: R.068835.001</p> <p>dwg. no.: AD-S01</p>
<p>DAWSON CITY YUKON TERRITORY</p> <p>PALACE GRAND THEATRE TEMPORARY WORK & MAJOR UPGRADE</p>		