

## **GENERAL**

The following changes / clarifications in the tender documents are effective immediately.  
This Addendum will form part of the Contract Documents.

### **STRUCTURAL ADDENDUM No. 1**

This Addendum contains 1 page and 1 -8 ½ "x11" sketches

#### **1.0 DWG S4**

- 1.1 **Clarify** the crib foundation base to be minimum 50mm thick gravel layer (20mm size maximum) levelling.
- 1.2 **Clarify** the lag screws to be 22mm diameter for Section 2/S3.
- 1.3 **Revise** Detail A as per attached addendum sketch AD - S01.
- 1.4 **Revise** the lag screw shown on the Section X-X to be through bolts as shown on revised Detail A.
- 1.5 **Clarify** that all steel connectors used in crawl space including steel plates, bolts, lag screws, nails, drift pins, etc. shall be hot-dipped galvanized with zinc coating 600 g/m<sup>2</sup> to CAN/CSA -G164.

#### **2.0 DWG S5**

- 2.1 **Delete** Section 3. The new fuel oil tank will be supported on the exterior concrete pad shown at the east side of the existing mechanical room.

#### **3.0 SPECIFICATION 03 20 00**

- 3.1 **REVISE** the edition of the "1.2 REFERENCES" for CSA Standards to be the edition referred in NBCC2010.

**END OF ADDENDUM S001**