

ADDENDUM



Project:	Campbell River SAR Station	Addendum No.:	A-M01
Project No.:	131-19106-05	Date:	November 22, 2016
Distribution:	Number 10 Architectural Group - Rob Halliday		

GENERAL

This Addendum forms part of the Contract Documents for the above Project and amends the original drawings and Specifications. The following revisions supersede the information contained in the original drawings and Specifications issued to the extent referenced and shall become part thereof. No adjustment to the Contract Price will be considered or allowed due to the Contractor or to any Sub-Contractor or Supplier not being familiar with this Addendum.

1.0 DRAWINGS & SPECIFICATIONS

1.1 Drawing M0.01 – Tank Schedule and Specification Section 21 01 00 Clause 4.2.17

- .1 The heating elements for the Domestic Hot Water Tank T-DHW shall be as follows:
 - .1 2x 4.5kW Non-Simultaneous heating elements. 208V - 3 Phase.

1.2 Drawing M0.01 – Heat Pump (Split Type) Schedule

- .1 Omit the requirement for a double circuited coil.

2.0 CONTRACTOR QUESTIONS

2.1 Does the sanitary sump pump control panel need to be intrinsically safe?

- .1 The sump, pumps, control panel and wiring shall all be suitable for use with sewage.

END OF MECHANICAL ADDENDUM