

NGCC *DES GROSEILLIERS*

F3017-16IN565

Sprinkler Tank

2016-11-17

CCGS DES GROSEILLIERS

List of items

NGCC <i>DES GROSEILLIERS</i>	1
General Information	1
PART 1: SCOPE.....	1
PART 2: HEALTH AND SAFETY RELATED REQUIREMENTS	1
PART 3: GENERAL REQUIREMENTS.....	1
1.0 SCOPE	5
2.0 REFERENCES (Drawings / Standards / Regulations)	5
3.0 TECHNICAL DESCRIPTION	6
4.0 DELIVERABLES	8

CCGS DES GROSEILLIERS

Canadian Coast Guard (CCG) requirements

General Information

LIST OF ACRONYMS

Table 1 - List of Acronyms

CA Contract Authority (PWGSC)

CBW Canadian Bureau of Welding

CCG Canadian Coast Guard

CE Chief Engineer

CLC Canada Labour Code

CSM Contractor Supplied Material

CSA Canadian Standards Association

DFO Department of Fisheries and Oceans

FSM Fleet Safety Manual (CCG)

FSR Field Service Representative

GSM Government Supplied Materials

HC Health Canada

IA Inspection Authority – Technical Inspector CE Chief Engineer

IEEE Institute of Electrical and Electronic Engineers

MSDS Material Safety Data Sheet

PWGSC Public Works and Government Services Canada

SMS Safety Management System

TBS Treasury Board of Canada Secretariat

TCMS Transport Canada Marine Safety

TA Technical Authority (CCG) Jean-François Thibault

WCB Work Safe BC

WHMIS Workplace Hazardous Material Information System

PART 1: SCOPE

1.1 General

- 1.1.1 This document describes Canadian Coast Guard (CCG) requirements applicable to all accompanying Technical Specifications.

PART 2: HEALTH AND SAFETY RELATED REQUIREMENTS

2.1 General

- 2.1.1 The Contractor must appoint a Health & Safety Manager or Supervisor responsible for ensuring compliance with the Health and Safety requirements listed herein. This includes monitoring of all work by Contractor employees and Sub-Contractor employees.
- 2.1.2 During the execution of Work, the Contractor must comply with:
- Applicable Provincial Health and Safety Regulations,
 - Canada Labour Code Part II,
 - Marine Occupational Health and Safety Regulations (MOSH),
 - The Gas Hazard Control Standard (TP3177),
 - Applicable CCG region specific Health and Safety requirements
 - DFO/5672 Welding Health and Safety Technical Program,
 - TBS “Smoking in the Workplace” Policy,
 - The following sections of DFO/5737- CCG Fleet Safety and Security Manual
 - Fall Protection (section 7B2),
 - Confined Space Entry (section 7B3),
 - Hot Work (Section 7B4),
 - Lock-Out - Tag-Out (Section 7B5).
 - Contractor Safety and Security (10.A.7)

CCGS DES GROSEILLIERS
Canadian Coast Guard (CCG) requirements

CCGS DES GROSEILLIERS

Canadian Coast Guard (CCG) requirements

2.2 Hot Work

2.2.1 When executing Hot Work, the Contractor must:

- inform the TA & IA prior to commencing work and upon completion of work,
- supply sufficient and suitable fire extinguishers in support of the Hot Work,
- not use the Ship's fire extinguishers except in the case of emergency. Should the ship's extinguishers be used, the Contractor must ensure they are recharged and certified by a certified facility at no cost to Canada,
- maintain a competent and properly equipped Fire Watch while Hot Work is underway and for one hour following the completion of Hot Work. The Fire Watch must be situated such that all sides of the surfaces undergoing work are visible and accessible,
- ensure that all dust, debris, gas and smoke generated is evacuated from the vessel by the most direct method,
- provide suitable fire retardant coverings to protect wire ways, cables, equipment and structure from welding slag, splatter etc,
- comply with the specific Hot Work requirements listed in section 2.1 herein.

2.2.2 When executing Hot Work, the Contractor must define a surrounding zone that is to be kept sealed off from the rest of the vessel during the work period that involves the generation of welding gases, smoke, and grinding dust etc. All unscheduled work arising during the refit period involving Hot Work must have a similar zone isolated from the remainder of the vessel. The zone must be limited to the space(s) where the Hot Work is conducted, boundary areas where Fire Watches are required, and the access routes between the zone and the exterior of the vessel for workers, welding and cutting equipment and ventilation ductwork.

2.2.3 In areas where occupied accommodations and or workplaces cannot be completely isolated a double sealed door (air lock) arrangement must be erected to minimize ingress of contaminants into the occupied areas. A ventilation extraction point must be located as near as practical to the inside door on the worksite side to reduce the egress into the air lock and subsequently the accommodations and/or workplaces.

2.2.4 All doorways within the affected area that are not required for access to the work or for Fire Watch activities must be sealed off to prevent contaminants from entering. Passageway branches that connect to the zone are to be sealed off as well. The Contractor must clean all surfaces and fabrics within the zone and in surrounding areas, which have become contaminated, upon completion of work.

2.3 Confined Space Entry

2.3.1 In the execution of Confined Space Entry, the Contractor must comply with the requirements listed in section 2.1 herein. The following is a non-exhaustive list of Confined Spaces on CCG Vessels: Bilge Areas; Machinery Compartments; all storage compartments accessed by manhole covers including fuel tanks; water tanks; cofferdams; chain lockers; thruster compartments.

2.4 Monitoring Atmosphere for Confined Space Entry or Hot Work

2.4.1 Prior to Confined Space Entry and Hot Work within a Confined Space, including machinery compartments, the Contractor must:

- have the space gas freed and tested in accordance with TP3177,
- ensure the Permit states the type of work, the time period for which the Permit is valid and also indicates "Safe for Persons" or "Safe for Hot Work" as required,
- post the Permit in a conspicuous location and provide the TA and IA with the signed and dated Marine Chemist's or Contractor qualified persons Certificate,
- renew the Confined Space Entry or Hot Work Permit as required by Regulations.

CCGS DES GROSEILLIERS

Canadian Coast Guard (CCG) requirements

2.5 Work At Heights and Fall Protection

2.5.1 In the execution of Work at Heights, the Contractor must:

- erect staging as required to safely carry-out work and remove it upon completion,
- ensure walkways, gangways, scaffolding, ladders, guard-rails and similar apparatus are maintained in proper and safe condition. Daily inspections are to be conducted and recorded by the Contractor,
- comply with requirements listed in 2.1 herein when conducting work aloft,
- must do so in accordance with the Contractor's standard operating procedures.

2.6 Lock-Out / Tag-Out

2.6.1 The Contractor must comply with requirements listed in 2.1 herein for Lock-Out and Tagout.

2.7 Workplace Hazardous Materials Information System (W.H.M.I.S.)

2.7.1 CCG must provide the Contractor with access to M.S.D.S. for all controlled products located on the vessel. The Contractor must provide M.S.D.S. for all Contractor supplied WHMIS controlled products.

2.8 Smoking

2.8.1 The Contractor must obtain written approval prior to smoking in designated areas.

2.9 Temporary Lighting and Ventillation

2.9.1 The Contractor must ensure temporary lighting and/or ventilation is supplied, installed and maintained in proper and safe condition and removed upon completion.

2.9.2 The Contractor must ensure temporary lighting incorporates shields/guards to protect against breakage.

2.10 Sign-in / Sign-out

2.10.1 When the vessel remains in Care and Custody of the Crown, the Contractor must ensure employees and Sub-Contractors sign-in and sign-out of the Vessel Register located at the Quartermasters Station, or in a convenient location to the gangway, whenever they enter or leave the vessel. Alternatively, the Crown may provide an electronic system whereby passes are issued to those requiring access to the vessel. Individuals violating this requirement may be denied access to the vessel for the duration of the work period upon advice from the TA to the CA.

2.11 Lead Based Paints and Paint Approvals

2.11.1 The Contractor must provide Health Canada product approval for underwater hull surface paints controlled by Health Canada and the Pest Management Regulatory Agency,

2.11.2 The Contractor must identify and take precautionary measures to ensure the application of paints complies with Federal, Provincial and Municipal regulations,

2.11.3 The Contractor must not use lead-based paints.

2.12 Clean and Hazard Free Site

2.11.1 The Contractor must maintain all spaces, compartments, work areas and areas used by Shipyard personnel as transit routes in a clean and sanitary condition and free from debris,

2.11.2 The Contractor must return the vessel to the CCG at least as clean as when work began. This includes both internal and external areas of work, as well as any affected adjacent spaces outside the principle areas of work,

2.11.3 The Contractor must supply own refuse containers to be emptied daily and removed upon completion of work. All rags, debris, and associated refuse are to be removed to refuse container(s) daily,

2.11.4 When working at CCG facilities, the Contractor must clean-up dock areas used by Contractor personnel and/or equipment. This includes but is not limited to the removal of all dirt, grit, debris, staging, containers and equipment as well as the immediate cleanup and proper disposal of leaked oil, solvent or any other hazardous materials,

2.11.5 If work will be conducted in the vicinity, the Contractor must supply and install for the duration of the work period a suitable material approved by the TA and IA at all main entries and over surfaces of the main, upper, flight and navigation officers decks to protect alleyways from dirt,

CCGS DES GROSEILLIERS

Canadian Coast Guard (CCG) requirements

- 2.11.6 The Contractor must ensure safe access to the work area as required by applicable Health and Safety Regulations,
- 2.11.7 The Contractor must prevent rat and vermin harbourage onboard the vessel for the duration of the work period. The Contractor must remove any rats or vermin from the vessel if they do come onboard during the work period.

2.13 Fire Protection

- 2.13.1 The Contractor must ensure the isolation, removal and installation of fire detection and suppression systems or its components is performed by certified technicians familiar with the systems,
- 2.13.2 The Contractor must notify the TA and IA and obtain written approval from the TA prior to disturbing, removing, isolating, deactivating/disabling or locking-out any part of the fire detection or suppression system including heat and smoke sensors. The Contractor must also notify the TA and the IA once the system has been reactivated,
- 2.13.3 The Contractor must ensure protection against fire at all times including when working on the ship's fire detection or suppression system. This may be accomplished as suggested below and requires the written approval from the TA:
- disabling only one portion of the system at a time,
 - by maintaining system function using spares while work is in progress,
 - other means acceptable to the TA.
- 2.13.4 The Contractor must note that failure to take necessary precautions while performing work on fire suppression systems may result in malfunction and discharge of CO₂, Halon or other fire suppression agents. The Contractor must recharge and certify at their cost, containers that are discharged as a result of their work.

2.14 Hydrostatic / Pneumatic Tank Testing

- 2.14.1 The Contractor must verify that all necessary openings are closed prior to hydrostatic or pneumatic testing of tanks. The Contractor must blank all suction and discharge lines, vents and sounding pipes. The Contractor is responsible for supplying, fitting and the subsequent removal of blanks.
- 2.14.2 The Contractor must drain the tanks upon completion of testing and wipe clean and dry the fuel tanks.
- 2.14.3 The Contractor must hydrostatically test tanks as specified with a 2.44m head of water. Where the Contractor wishes to perform a pneumatic test in lieu of the hydrostatic test, written approval must be obtained by the IA and TA.
- 2.14.4 The Contractor must provide the IA and TA with the Contractor's standard operating procedures for conducting pneumatic tank tests.

2.15 Contractor Supplied Potable Water

- 2.15.1 The Contractor must provide water quality test results to the IA to demonstrate the potable water supplied meets the current Health Canada Guidelines for Canadian Drinking Water Quality (http://www.hc-sc.gc.ca/ewh-semt/pubs/water-eau/guidelines_sixth-rec-eng.php).
- 2.15.2 The Contractor must ensure lines are flushed prior to connecting the water supply to the vessel.

CCGS DES GROSEILLIERS

Canadian Coast Guard (CCG) requirements

PART 3: GENERAL REQUIREMENTS

3.1 Electrical Work / Electronics

- 3.1.1 The Contractor must carry-out all electrical and electronic installations, renewals and repairs in accordance with the latest editions of:
- TP127 - "Ship Safety Electrical Standards",
 - IEEE Standard 45 – 2002 "Recommended Practice for Electrical Installations on Shipboard 2002",
 - CGTS-3 - "General Specifications for the Installation of Shipboard Electronic Equipment".
- 3.1.2 The Contractor must replace, at no charge, the entire length of point to point cable if damaged as a result of installation.
- 3.1.3 The Contractor must not use plastic tie-wraps to secure wiring except in panels and junction boxes.

3.2 Paint Application

- 3.2.1 The Contractor must ensure new and/or disturbed steel work is painted in accordance with the specification.
- 3.2.2 The Contractor must power clean all new and disturbed steelwork prior to painting.
- 3.2.3 The Contractor must notify the IA to inspect after the surface preparation and the first coat of paint has cured and prior to application of the second coat.
- 3.2.4 N/A
- 3.2.5 The Contractor must ensure new and/or disturbed steelwork receives application of at least two (2) coats of marine primer immediately upon completion of work, unless specified otherwise.

3.3 Changes to Vessel Stability, Carrying Capacity or Structure

- 3.3.1 The Contractor must discuss with the TA any comments, concerns or observations they may have regarding the effect of work on the vessel's stability or carrying capacity. Additionally, any work item that, in the opinion of the Contractor may pose a vessel structural integrity problem is to be brought to the attention of the TA.
- 3.3.2 The Contractor must advise the IA and TA of the details of any major changes in the distribution of weights on the vessel while the vessel is in dry-dock.

3.4 CCG Employees and others on the Vessel

- 3.4.1 Canadian Coast Guard employees and other personnel such as Manufacturer's Representatives and TCMS Inspectors may carry-out other work, including work items not included in this Statement of Work, on board the vessel during this work period. Every effort will be made by Canada to ensure this work and the associated inspections do not interfere with the Contractor's work. The Contractor is not responsible for coordinating the related inspections or payment of inspection fees for this work.

3.5 Regulatory Inspections

- 3.5.1 The Contractor must ensure all work identified as requiring regulatory inspection is inspected by the applicable authority such as TCMS, Health Canada, Environment Canada etc., and that the required documentation is received to prove the inspections were conducted. The Contractor must not substitute inspection by the TA or IA for required regulatory inspections.
- 3.5.2 The Contractor must provide original Certificates issued by inspectors to the TA and a Copy to the IA.
- 3.5.3 The Contractor must coordinate all regulatory related inspections required for this Statement of Work.
- 3.5.4 The Contractor must provide timely advance notification of scheduled regulatory inspections to the TA and IA so they may attend the inspection.

CCGS DES GROSEILLIERS

Canadian Coast Guard (CCG) requirements

3.6 Welding

- 3.6.1 The Contractor must ensure welding is completed in accordance with DFO/5672 – “Welding Health and Safety Technical Program”.
- 3.6.2 The Contractor must obtain written permission of TA prior to commencing welding.
- 3.6.3 The Contractor must not locally ground welding equipment near bearings or electronic equipment.
- 3.6.4 The Contractor must ensure all steel welding is in accordance with 18-080-000-SG-001 Welding of Ferrous Materials and the Canadian Coast Guard Welding Specifications for Ferrous Materials, Revision 4. (TP6151)
- 3.6.5 The Contractor must comply with CCG specification for ALUMINIUM WELDING (TP9415)
- 3.6.6 The Contractor must ensure that when welding of any item requires the application of fusion welding for stainless steel structures, the Contractor or his Sub-Contractors is certified in accordance with the Canadian Welding Bureau, CSA\ACNOR AWS; Division 1.6 certification – latest revision copies of which must be submitted to the IA/TA prior to the start of welding

3.7 Requirements imposed on Contractor when Equipment must be disturbed

- 3.7.1 The Contractor must coordinate an inspection of the condition of items (i.e.: piping, manholes, parts, equipment etc) to be removed, prior to carrying-out or to gain access to carry-out specified work. The inspection must be conducted jointly by the Contractor, the IA and the TA.
- 3.7.2 The Contractor must repair or replace any item that is damaged in this process. Any piping, manholes, parts, equipment etc. requiring installation after removal, must be refitted using new Contractor supplied materials such as jointing, packing, anti-seize compound, clamps, brackets, fasteners, oils, lubricants, cleaning solvents, preservatives and insulation. Materials must be in accordance with equipment manufacturers’ drawings, manuals or instructions. Where a substitution must be made, the IA and TA must approve in writing the materials used.
- 3.7.3 The Contractor must provide a test plan and test to prove operation of disturbed items after completion of work.

3.8 Test Results

- 3.8.1 The Contractor must ensure tests and trials are performed to the satisfaction of the IA, TA, and TCMS. All tests, measurements, calibrations and readings must be recorded and provided in a report to the IA, TA and TCMS. The reports must be bound and typewritten, double-spaced on 8 1/2" X 11" and indexed by specification number. The reports must also be provided in Adobe pdf format on 3 USB keys.
- 3.8.2 The Contractor must ensure all dimensions are measured and recorded. All measuring devices must be described in the report and the name of the person taking the readings must be recorded.
- 3.8.3 The Contractor must ensure all testing and measurement equipment (mechanical or electronic) are calibrated and that calibration certificates are provided to the IA prior to final inspection or witnessing of tests.

3.9 Contractor Supplied Materials and Tools

- 3.9.1 The Contractor must unless otherwise specified, supply all materials.
- 3.9.2 The Contractor must ensure materials are new.
- 3.9.3 The Contractor must ensure material such as jointing, packing, insulation, small hardware, oils, lubricants, cleaning solvents, preservatives, paints, coatings, etc., are in accordance with the equipment manufacturer’s drawings, manuals or instructions. Where no particular item is specified or where substitution must be made, the IA and TA must approve in writing the materials used. The Contractor must provide certificates of grade and quality for various materials, as requested to the TA and IA.
- 3.9.4 The Contractor must obtain CCG ship specific special tools from the TA and return them to the TA upon completion of work.

CCGS DES GROSEILLIERS

Canadian Coast Guard (CCG) requirements

3.10 Machinery and Overhaul Installation

- 3.10.1 The Contractor must overhaul and install machinery and equipment as per the manufacturer's instructions, drawings and specifications.

3.11 Restricted Areas

- 3.11.1 The Contractor must not enter the following areas except to perform work as required by the specifications: all cabins, offices, workshops, engineer's office, wheelhouse, control room, public washrooms, galley, mess rooms and lounge areas.

3.12 Protecting Equipment/Areas from Damage

- 3.11.1 The Contractor must protect equipment/areas (example: machinery, equipment, fittings stores or items of outfit) from damage by exposure, weather, movement of materials, sand, grit, or shot blasting, welding, grinding, burning, gouging, painting or airborne particles of paint etc.
- 3.11.2 The Contractor must provide the IA and TA the opportunity to inspect any protection installed prior to the work commencing.

3.13 Verification of Information Provided by CCG

- 3.13.1 The Contractor must verify, prior to bid submission, all drawings, pictures, dimensions, descriptions, locations, measurements, engineering values, materials, etc. listed or implied. Information such as engineering drawings, pictures, etc., may have been provided with the accompanying technical specifications.

3.14 Drawing Revisions

- 3.14.1 The Contractor must revise drawings as required to a quality at least equal to those being updated. For example, drawings that have been lettered and dimensioned in a professional manner are not to be updated by hand. Updated hard copy drawings must be provided to the IA and TA in an acceptable format and if electronic format drawings have been provided for updating, these must be returned using the same version of software as originally used.

3.15 Service Conditions

- 3.15.1 The Contractor must provide ice-clearing services if so required for ship movements.
- 3.15.2 The Contractor must provide all enclosures and heating required to carry out work, taking into account the nature of the work, time of year and weather conditions. Examples of work items where heating and enclosures may be required include but are not limited to painting, shaft withdrawal, and tank cleaning.
- 3.15.3 Unless otherwise specified, all components, materials and installations supplied by or carried-out by the Contractor must be adequate to meet the following service conditions:
- In areas that are exposed to the elements:
 - o outside air temperature of minus 40°C to plus +35°C;
 - o wind velocity up to 50 knots;
 - o water temperature of minus 2°C to plus +30°C;
 - shock loading of 2.5g horizontal, 1.5g vertical. All new components, materials and installations within the ship must be adequate to withstand the specified shock loading accelerations.

3.16 Recording of Work in Progress

- 3.16.1 The IA and TA may record work in progress using various means including but not limited to photography and video, digital or film

3.17 Washrooms and Working Hours

- 3.16.1 No washroom on board will be made available for the Contractor
- 3.16.2 Hours of work for CCG personnel working on board the vessel are from 0600 hours to 1930 hours, seven (7) days a week, excluding statutory holidays. Permission to work on the vessel outside these hours must be obtained from the TA.

CCGS DES GROSEILLIERS

Canadian Coast Guard (CCG) requirements

3.18.2 Normes and regulation applicable

- 3.18.1 The following work should be done in accordance with the following construction standards.
- marine Machinery Regulations SOR/90-264
 - ships Electrical Standards (2008) - TP 127 E
 - IAC No. 47 Shipbuilding and Repair Quality Standard;
 - ASTM Standards, Section one Iron and Steel Products, volume 01.07 Ship and Marine Technology;
 - Normes et procédures de mécano-soudage du BCS (ou équivalent);
 - SSPCPA 2 (nov.1982), *Paint Application Specification No.2*;
 - Norme ASTM F708-92, *Standard Practice for Design and Installation of Rigid Pipe Hangers*, 1992 (Reapproved 2008).

CCGS DES GROSEILLIERS
Canadian Coast Guard (CCG) SPECIFICATION

1.0 SCOPE

1.1 MANUFACTURING AND DELIVERY of a pressure vessel with the same dimensions, fittings, accessories, base and specifications as seen in Drawing no A-159153, for use on a sprinkler system, operating at a pressure of 150 lbs / square inch (PSI), and certified to 225 PSI

1.2 Bidders must address any concerns with the Mandatory Requirements and Minimum performance Specifications listed below in written detail to the Contracting Authority before bid closing as outlined in the Request for Quotation.

1.3 MAIN CHARACTERISTICS

The following are the main characteristics of the CCGS "DES GROSEILLIERS":

Vessel name : CCGS "DES GROSEILLIERS"

Type of vessel: Medium icebreaker

Port of registry: Ottawa (Ontario), Canada

Region: Quebec

Home port: Quebec (Québec), Canada

Official number: 802160

Year of construction: 1982

Shipyard: Port Weller Dry Docks, St. Catharines, Ontario, Canada

Length overall: 98.20 m

Length between perpendiculars: 88.04 m

Moulded breadth: 19.80 m

Draft: 7.40 m

Gross tonnage: 6097.80

Net tonnage: 1799.90

Service speed: 12 knots

Maximum speed: 16.5 knots

1.4 The weights and dimensions of the components to be removed and/or installed are as follows:

SPRINKLER TANK TO BE DISMANTLED

Length 120 in.

Diameter 48 in.

Height, Overall 57 in.

Weight 2000 lb.

2.0 REFERENCES (Drawings / Standards / Regulations)

2.1 Drawings

2.1.1 The tank must be manufactured according to the specifications and measurements mentioned on drawing No .: A-159153 (Sprinkler tank - hull # 68) attached.

2.2 Certifications

CCGS DES GROSEILLIERS
Canadian Coast Guard (CCG) SPECIFICATION

- 2.2.1 ASME Section VIII, Division 1 – U Stamp (National Board)
- 2.2.2 CSA-B51 - ASME Section 1, Section IV, Section VIII Div. 1
- 2.2.3 CSA-B51 - ASME Section B31.1, B31.3
- 2.2.4 DESP de la Commission Européenne (Directive Équipement Sous Pression)
- 2.2.5 CWB W47.1 (w59.03), Div. 2

2.3 Regulations

- 2.3.1 Lloyds, RULES AND REGULATIONS FOR THE CLASSIFICATION OF SHIPS, July 2013 - Requirements for Fusion Welding of Pressure Vessels and Piping

2.4 Quality assurance

- 2.4.1 ISO 9001-2000

2.5 Procedures

- 2.5.1 Approved procedures for welding Duplex 2205

3.0 TECHNICAL DESCRIPTION

- 3.1 This specification is about the main works to be performed by the Contractor for the dismantling and the removal from the ship of the existing Sprinkler System tank then the installation of the new Sprinkler System tank. This reservoir must be built in sections fabricated at the contractors installation, and these parts must be assembled and welded together in the motor propulsion room of the vessel.
- 3.2 All dimensions, drawings, and specifications supplied to the Contractor must be verified by the Contractor onboard prior to the beginning of the works by obtaining the necessary information from the different suppliers and manufacturers. Prior to the start of works, the Contractor must compile and verify all compatibility measurements for the old and new equipment and any incompatibility found must be communicated to the Shipowner's representative for appropriate instructions.
- 3.3 Except if otherwise mentioned in this specification, the Contractor must supply the manpower, the technical assistance, the tools, design, drawings, fabrication, installation, testing, certification, the material and all the equipment required for the execution of the works. The Contractor must also supply all the services required for dismantling, reassembling, handling and transportation of all equipment related to the project including disposal of all liquid or solid rubbish. All of these products and services must be accounted for and included in every related items of the tender proposal.
- 3.4 Supply pdf to scale plans showing that the proposed reservoir is compatible avec the current installation. Design drawings and specifications of the pressure vessel must include the maximum design pressure and temperature, the working pressure, the material thickness and specifications (Duplex 2205),

CCGS DES GROSEILLIERS
Canadian Coast Guard (CCG) SPECIFICATION

method of fabrication, welding details and the purpose for which the pressure vessel is to be used.

- 3.5 Before commencing construction of the pressure vessel to be built under these regulations, the manufacturer's drawings and specifications must have been submitted to, and approved by, the Project Officer.
- 3.6 SUMMARY OF SPECIFICATION:
- 3.6.1 Total length, including the extremities: 120 inches
 - 3.6.2 External diameter: 48 inches
 - 3.6.3 Thickness of the cylinder wall: 5/16. Duplex 2205
 - 3.6.4 Thickness of the ends of the tank: 3/8. 2:1 semi-ellip. Duplex 2205
 - 3.6.5 The unit must be registered with Transport Canada and Lloyd's
 - 3.6.6 Subject to the regulations for pressure vessels Lloyd's Class 3
 - 3.6.7 Operation pressure: 150 PSIG
 - 3.6.8 Hydrostatic Test: 225 PSIG
 - 3.6.9 Operating temperature: up to 350°F. (176.7°C)
 - 3.6.10 Capacity: 750 Gallons Imperial
- 3.7 The tank must be ASME Section VIII code stamped and registered
- 3.8 Provide all piping, connections, valves and controls required to connect the existing system. (1) All process piping must meet the requirements of ASME B31.3, Process Piping.
- 3.9 The pressure vessel built under these regulations must conform to them in every detail and must be distinctly stamped as follows denoting that the boiler or pressure vessel has been constructed in accordance with an approved and registered design:
- Registration number (C.R.N.).
 - National Board number
 - Manufacturer and manufacturer's serial number.
 - Plate specification number and tensile strength for shell.
 - Plate specification number and tensile strength for heads.
 - Thickness of shell and heads.
 - Maximum working pressure and temperature.
 - A.S.M.E. Code paragraph number and year built.
 - Initials or symbol of authorized shop inspector.
- 3.9.1 The figures and letters of the stamping must be at least 3/8 inch in size and must be located in accordance with the A.S.M.E. Code requirements unless otherwise approved by the Project Officer. When placed upon a permanently attached brass plate the figures and letters may be not less than 3/8 inch in size; The letters and figures must be legible and stamped fully into the plate of the pressure vessel or stamped on a permanently attached plate.

CCGS DES GROSEILLIERS
Canadian Coast Guard (CCG) SPECIFICATION

- 3.10 The Contractor must make sure that the compartments affected by the works are well ventilated throughout the work period. A special attention must be paid to ensure that fumes and smokes are well evacuated so they do not disturb the crew living onboard. The ventilation must function 24 hours a day.
- 3.10.1 The Contractor must isolate the work area in such a way to eliminate the possibility of any dust from contaminating other areas.
- 3.10.2 The Contractor must cover and protect from dust all equipment, motors, pumps, compressors, air conditioning systems, control panels, etc in the work area.
- 3.10.3 The Contractor must, upon the completion of all welding works, remove all isolation and protective materials used for isolating the area or covering the equipment.
- 3.10.4 The Contractor must be responsible for all removed equipment from the beginning to the end of the works. The Contractor must be responsible for all equipment provided by the Shipowner from the time they are delivered on the works site and all equipment or material to be installed on the ship and this until the end of the works.
- 3.11 Any damage to the ship surface, equipment, furniture and accessories caused by the Contractor or one of his sub-contractor during the works must be repaired at the Contractor's expenses.
- 3.11.1 The Contractor must also be responsible for any damage or drawback detrimental to the ship operation of which the source is under the Contractor's responsibility.
- 3.12 **CLEANING**
- 3.12.1 The Contractor must clean, degrease and drain all surfaces, structures, compartments, or equipment located in the work zone.
- 3.12.2 Cleaning must be done regularly and no accumulation of waste or harmful substance or affecting the safety of the work place will be tolerated onboard.
- 3.12.3 The Contractor must clean the entire work zone to leave it in the same condition as when the works began.
- 4.0 Proof of performance**
- 4.1 Provide dimensional pdf plans demonstrating that the reservoir is compatible for the current installation and specifications.
- 4.2 The Contractor must, at the time of delivery, provide a certificate of acceptability of a regulatory society recognized by Transport Canada, with plans, drawings and fabrication procedures.

CCGS DES GROSEILLIERS
Canadian Coast Guard (CCG) SPECIFICATION

- 4.3 Offers must include delivery, including customs duties and taxes FAB. For this order, delivery will be made at the base of the Canadian Coast Guard in Quebec City, Quebec.
101 Boul Champlain
Quebec City, Qc
G1K7Y7
Canada
- 4.4 Hydrostatic tests must be witnessed by TCMS and the Chief Engineer.