

Channel and Basin Dredging**Petit-de-Grat SCH****Richmond County, NS****Project No. R.077417.001**

Sitework, Demolition and Removals

Page 1

PART 1 - GENERAL

- | | |
|--------------------------------|---|
| 1.1 <u>Description of Work</u> | This Section includes but is not limited to the following: <ul style="list-style-type: none">.1 All normal removals as required to complete the work. All items to be verified by a site visit prior to submission of a tender. All available plans of the existing structure are available for viewing at the Project Manager's office, 2nd floor, 1713 Bedford Row, Halifax, N.S..2 Any derricks, gas lines or buildings to be removed by others unless otherwise indicated. |
| 1.2 <u>Related Work</u> | <ul style="list-style-type: none">.1 Refer to other specification sections for related information..2 Refer to Section 01 33 00 for Shop Drawing/Submission requirements. |
| 1.3 <u>Submissions</u> | <ul style="list-style-type: none">.1 Methodology:<ul style="list-style-type: none">.1 When requested provide methodology for carrying out the work.2 Provide submission in accordance with Section 01 33 00. |
| 1.4 <u>Protection</u> | <ul style="list-style-type: none">.1 Prevent movement, settlement or damage of adjacent structures. Provided bracing and shoring as required. In event of damage, immediately replace such items or make repairs to approval of <i>Departmental Representative</i> and at no additional cost to <i>Departmental Representative</i>..2 Prevent debris from going adrift and becoming a menace to navigation..3 All damage to existing structures, roadways, pipelines, electrical systems not specified for removal to be repaired at the Contractor's cost to the satisfaction of the <i>Departmental Representative</i>. |

Channel and Basin Dredging**Petit-de-Grat SCH****Richmond County, NS****Project No. R.077417.001**

Sitework, Demolition and Removals

Page 2

1.5 Measurement for
Payment

- .1 Sitework, demolition and removals will be measured in accordance with **Section 01 29 00.**

PART 2 - PRODUCTS

Not applicable.

PART 3 - EXECUTION3.1 Preparation

- .1 Inspect site and verify with *Departmental Representative* items designated for removal and items to be preserved.
- .2 Locate and protect utility lines. Preserve in operating condition active utilities traversing site.
- .3 Provide temporary power and lighting as shown on the plan or as required by the *Departmental Representative*.
- .4 Existing fill and vent pipes, oil waste tanks and underground storage tanks to be protected from any damages. All repairs to damages as a result of Contractor's operations to be at his cost and to the satisfaction of the *Departmental Representative*.

3.2 Removal

- .1 Remove items indicated.
- .2 Do not disturb adjacent structures designated to remain in place.
- .3 At end of each day's work, leave work in safe condition so no part is in danger of toppling or falling.

3.3 Disposal of Material

- .1 Disposal of materials not designated for salvage or re-use in work, will be the contractor's responsibility, and must be disposed of off-site.
- .2 The material to be disposed is to be transported and disposed of in an environmentally acceptable manner to the satisfaction of the *Departmental Representative*, and in accordance with any

Channel and Basin Dredging

Petit-de-Grat SCH

Richmond County, NS

Project No. R.077417.001

Sitework, Demolition and Removals

Page 3

local, Municipal, Provincial and Federal restrictions and regulations.

3.4 Restoration

- .1 Upon completion of work, remove debris, trim surfaces and leave work site clean.
- .2 Reinstate areas and existing works outside areas of demolition to conditions that existed prior to commencement of work. Match condition of adjacent, undisturbed areas.