

RETURN BIDS TO:

RETOURNER LES SOUMISSIONS À:

Parks Canada National Contracting Services 702, 5° rue de la Pointe Shawinigan, QC, G9N 1E9

INVITATION TO TENDER APPEL D'OFFRES

AMENDMENT #2 & 3:

Tender To: Parks Canada Agency

We hereby offer to sell to Her Majesty the Queen in right of Canada, in accordance with the terms and conditions set out herein, referred to herein or attached hereto, the goods, services, and construction listed herein and on any attached sheets at the price(s) set out therefor.

Soumission à: l'Agence Parcs Canada


Nous offrons par la présente de vendre à Sa Majesté la Reine du Chef du Canada, aux conditions énoncées ou incluses par référence dans la présente et aux annexes cijointes, les biens, services et construction énumérés ici et sur toute feuille ci-annexée, au(x) prix indiqué(s).

Comments – Commentaires
It is mandatory to complete and
attach to the tender document

Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution

Parks Canada National Contracting Services 702, 5° rue de la Pointe Shawinigan, QC, G9N 1E9



Date

Signature



THE PURPOSE OF THIS AMENDMENT IS:

TO RESPOND TO QUESTIONS POSED BY BIDDERS AND TO EXTEND THE DATE OF CLOSING OF SUBMISSIONS PLEASE TAKE ACCOUNT IN THE EVALUATION OF YOUR SUBMISSION.

Questions and Answers: See page attached hereto.

Opening of tenders:

THE CLOSING DATE DEFERRED TO DECEMBER 09, 2016 - 2:00 PM (ET)

ALL OTHER TERMS AND CONDITIONS REMAIN UNCHANGED

ADDENDUM No. 2

This addendum in an integral of the plans and specifications and should be read in conjunction with them. Items not mentioned in this addendum remain the same as described in the plans and specifications.

1. ANSWERS TO QUESTIONS RECEIVED ON NOVEMBER 23rd 2016 REGARDING THE GEAR BOX:

1. Operating temperature range?

Answer: from - 25 to 30 deg C, the system is used mainly in summer, but Parks Canada can perform tasks during winter.

2. The utilisation rate of the gear box? (Daily hours and the duration length during operating cycle)?

Answer: Operating cycle: 5 minutes to open the door and 5 minutes to close it. An average of 15 cycles per day, from May to October (less than 10 hours per day).

3. What is the rated load torque utilization as well as pull out torque?

Answer: Rated load torque is 4630Nm and the pull out torque for the motor Leeson at its stop point is 11575Nm, see annex D of the technical specification based on the motor provided by Parks Canada.

4. The overhang load on the gear box exit shaft?

Answer: There is no overhang load connected to the shaft.

5. Do you need a double shaft at the reducer exit?

Answer: No.

6. Is it required to have an oil heater? If so, which is the voltage available?

Answer: No, not for this range of activities.

END OF THE ADDENDA

Benoit Tremblay, Eng.

2016-11-18

PAGE 1

ADDENDUM No. 3

This addendum in an integral of the plans and specifications and should be read in conjunction with them. Items not mentioned in this addendum remain the same as described in the plans and specifications.

1. ANSWERS TO QUESTIONS RECEIVED

1. Who will perform the programming of the lubrication systems?

Answer: The programming is done by others, therefore, this is not included in this request for quote.

2. Is it possible to replace the lubrication system P653 by a progressive system with a longer lubricating period but resulting in the same lubricating flow?

Answer: No. The P653 pumps are variable flow pumps and can't be replaced by progressive systems.

END OF THE ADDENDA

Benoit Tremblay, Eng.

2016-11-18