



APPROX. NORTH

NOTES:

1. ALL UNDERGROUND SLEEVES TO BE SLEEVED THROUGH FOUNDATION WALLS. LOCALLY STEP FOOTINGS DOWN AS REQUIRED. COORDINATE PIPE/CONDUIT LOCATIONS AND ELEVATIONS WITH MECHANICAL, ELECTRICAL AND CIVIL DRAWINGS AND CONTRACTORS.
2. IF INTERIOR FOOTINGS ARE REQUIRED TO DROP DUE TO BUILDING SERVICES, PROVIDE A PILASTER AS NOTED IN DETAIL 10/S07 TO ACHIEVE ELEVATION DIFFERENCE.

FOUNDATION LEGEND:

- C#: DENOTES COLUMN. SEE COLUMN SCHEDULE.
- P#: DENOTES PILASTER. SEE DETAILS 15 TO 18/S08 FOR SIZE AND REINFORCING.
- S.F.: DENOTES STEPPED FOOTING. SEE DETAIL 11/S07.
- D.O.: DENOTES DOOR OPENING. SEE DETAIL 7/S07 FOR ADDITIONAL REINFORCING.
- CJ: DENOTES CONSTRUCTION/CONTROL JOINT. SEE DETAIL 6/S07.
- FD: DENOTES FLOOR DRAIN, SEE MECHANICAL DRAWINGS.
- F#: DENOTES FOOTING. SEE FOOTING SCHEDULE.
- F#': DENOTES FOOTINGS THAT ARE OFFSET FROM CENTERLINE OF COLUMN.


FOOTING SCHEDULE		
NUMBER	SIZE	REINFORCING
F1	600 x 600 x 300	3 - 15M BOTTOM E.W.
F2	900 x 900 x 300	4 - 15M BOTTOM E.W.

PLAN - FOUNDATION

SCALE: 1:50



1
S02/S02



2	ISSUED FOR TENDER	11.29 2016
1	100% SUBMISSION	11.23 2016
0	99% SUBMISSION	11.8 2016
revisions		date

project GREEN GABLES-PHASE 1
BARN EXPANSION
AND RENOVATION
QUEENS CO., PEI

drawing STRUCTURAL
FOUNDATION PLAN

designed	SLJM	conçu
date	SEP-2016	
drawn	JLK	dessiné
date	OCT-2016	
approved		approuvé
date		
Tender		Soumission
PWOSC Project Manager	Administrateur de projets TPSGC	
project number	R.081199.001	no. du projet
drawing no.	S02 OF 8	no. du dessin