


LEGEND:

- # ELEVATION NUMBER, FROM PAGE, FOUND ON
- # SECTION NUMBER, FROM PAGE, FOUND ON
- # DETAIL NUMBER, FROM PAGE, FOUND ON



NOTE:
ALL WIRING SERVING DEVICES WITHIN THE GIFT SHOP D107 SHALL BE CONCEALED WITHIN THE WALL CAVITY OR RUN ON TOP OF WOOD BEAMS OUT OF THE LINE OF SIGHT. WHERE CONDUITS MUST BE EXPOSED, THEY MUST BE CENTRED ON THE TIMBER IN AN ORGANIZED FASHION AND RUN PARALLEL, WHERE POSSIBLE, FEED SERVICES FROM THE BASEMENT. DRILLING THROUGH ANY TIMBER FRAMING IS SUBJECT TO REVIEW BY THE STRUCTURAL ENGINEER.

INTERIOR WALL TYPE NO.4
• 8mm SPACE (SEE PLAN DETAILS)
• 38x89 WOOD STUD WALL @ 400mm O.C.
• 16mm GYPSUM BOARD
NOTE: SCREW TOP PLATE OF WALL TO HORIZONTAL TIMBER FRAME ABOVE. DO NOT FASTEN TO COLUMNS.

3/4 HOUR RATED FLOOR ASSEMBLY
• VINYL FLOORING
• 6 mm SUB-FLOORING
• 16 mm PLYWOOD
• FLOOR TRUSSES
• 89mm SOUND ATTENUATION BLANKET
• RESILIENT CHANNELS AT 400mm O.C.
• 1 LAYER OF 16mm FIRECODE C GYPSUM BOARD

SLAB CONSTRUCTION
• CONCRETE SLAB ON GRADE
• VAPOUR BARRIER
• 50mm SAND
• 38mm INSULATION
• 6\"/>

SEE STRUCTURAL FOR FOUNDATION INFORMATION

SECTION
SCALE : 1:20
A
A03/A08



2	ISSUED FOR TENDER	11.29.2016
1	100% SUBMISSION	11.23.2016
0	99% SUBMISSION	11.8.2016
revisions		date

project
GREEN GABLES-PHASE 1 BARN EXPANSION AND RENOVATION
QUEENS CO., PEI

drawing
ARCHITECTURAL BUILDING AND WALL SECTIONS
design

designed KST conq
date NOV-2016
drawn GJU dessin
date NOV-2016
approved
date
Tender Soumission
PWGSC Project Manager Administrateur de projets TPSC
project number no. du projet
R.081199.001
drawing no. no. du dessin
A08 OF 12