

PART 1 GENERAL**1.1 SECTION INCLUDES**

- .1 Text, schedules and procedures for systematic Waste Management Program for construction, deconstruction, demolition, and renovation projects, including:
 - .1 Diversion of Materials.
 - .2 Waste Audit (WA) - Schedule A.
 - .3 Waste Reduction Workplan (WRW) - Schedule B.
 - .4 Demolition Waste Audit (DWA) - Schedule C.
 - .5 Cost/Revenue Analysis Workplan (CRAW) - Schedule D.
 - .6 Materials Source Separation Program (MSSP).
 - .7 Canadian Governmental Responsibility for the Environment Resources - Schedule E.

1.2 DEFINITIONS

- .1 Demolition Waste Audit (DWA): Relates to actual waste generated from project.
- .2 Materials Source Separation Program (MSSP): Consists of series of ongoing activities to separate reusable and recyclable waste material into material categories from other types of waste at point of generation.
- .3 Recyclable: Ability of product or material to be recovered at end of its life cycle and re-manufactured into new product for reuse by others.
- .4 Recycle: Process by which waste and recyclable materials are transformed or collected for purpose of being transferred into new products.
- .5 Recycling: Process of sorting, cleansing, treating and reconstituting solid waste and other discarded materials for purpose of using in altered form. Recycling does not include burning, incinerating, or thermally destroying waste.
- .6 Reuse: Repeated use of product in same form but not necessarily for same purpose. Reuse includes:
 - .1 Salvaging reusable materials from re-modelling projects, before demolition stage, for resale, reuse on current project or for storage for use on future projects.
 - .2 Returning reusable items including pallets or unused products to vendors.
- .7 Salvage: Removal of structural and non-structural materials from deconstruction/disassembly projects for purpose of reuse or recycling.
- .8 Separate Condition: Refers to waste sorted into individual types.

- .9 Source Separation: Acts of keeping different types of waste materials separate beginning from first time they became waste.

1.3 MATERIALS SOURCE SEPARATION PROGRAM (MSSP)

- .1 Prepare MSSP and have ready for use prior to project start-up.
- .2 Implement MSSP for waste generated on project in compliance with approved methods and as reviewed by authorities having jurisdiction.
- .3 Provide on-site facilities for collection, handling, and storage of anticipated quantities of reusable and recyclable materials.
- .4 Provide containers to deposit reusable and recyclable materials.
- .5 Locate containers in locations, to facilitate deposit of materials without hindering daily operations.
- .6 Locate separated materials in areas which minimize material damage.
- .7 Collect, handle, store on-site, and transport off-site, salvaged materials in separate condition.
 - .1 Transport to recycling facility.

1.4 STORAGE, HANDLING AND PROTECTION

- .1 Unless specified otherwise, materials for removal become Contractor's property.
- .2 Protect, stockpile, store and catalogue salvaged items.
- .3 Separate non-salvageable materials from salvaged items. Transport and deliver non-salvageable items to approved local facility.
- .4 Protect structural components not removed for demolition from movement or damage.
- .5 Support affected structures. If safety of building is endangered, cease operations and immediately notify Department having jurisdiction.
- .6 Protect surface drainage, mechanical and electrical from damage and blockage.
- .7 Separate and store materials produced during dismantling of structures in designated areas.
- .8 Prevent contamination of materials to be salvaged and recycled and handle materials in accordance with requirements for acceptance by designated facilities.
 - .1 On-site source separation is recommended.

CONSTRUCTION/DEMOLITION WASTE MANAGEMENT AND DISPOSAL**1.5 DISPOSAL OF WASTES**

- .1 Do not bury rubbish or waste materials.
- .2 Do not dispose of any waste into waterways, storm, or sanitary sewers.
- .3 Remove materials from deconstruction as deconstruction/disassembly Work progresses.
- .4 Prepare project summary to verify destination and quantities on a material-by-material basis as identified in pre-demolition material audit.

1.6 USE OF SITE AND FACILITIES

- .1 Execute work with least possible interference or disturbance to normal use of premises.
- .2 Provide security measures approved by Departmental Representative.

1.7 SCHEDULING

- .1 Coordinate Work with other activities at site to ensure timely and orderly progress of Work.

PART 2 PRODUCTS (NOT APPLICABLE)**PART 3 EXECUTION****3.1 APPLICATION**

- .1 Handle waste materials not reused, salvaged, or recycled in accordance with appropriate regulations and codes.

3.2 CLEANING

- .1 Remove tools and waste materials on completion of Work, and leave work area in clean and orderly condition.
- .2 Clean-up work area as work progresses.
- .3 Source separate materials to be reused/recycled into specified sort areas.

3.3 DIVERSION OF MATERIALS

- .1 Where required, separate materials from general waste stream and stockpile in separate piles or containers, as reviewed by Departmental Representative and consistent with applicable fire and safety regulations.
 - .1 Mark containers or stockpile areas.

- .2 Provide instruction on disposal practices.
- .2 On-site sale or distribution of salvaged materials to third parties is not permitted.

END OF SECTION