

PART 1 - GENERAL

1.1 DESCRIPTION

- .1 This section specifies requirements for demolishing and removing wholly or in part various items designated to be removed or partially removed.
- .2 Demolition and removal will consist of, but not necessarily be limited to, the following:
 - .1 Mobilization and demobilization.
 - .2 Removal of existing floats which is to be turned over to the Dipper Harbour Authority. Removal and disposal of exiting H piles float guides as indicated on the drawings.
 - .3 Remove existing gangway and clearly block off the entrance during construction. Reinstall once floats are complete installed.
 - .4 Reinstallation of the existing aluminum gangway to its original location once new floats are completely installed and approved by the Departmental Representative.

1.2 GENERAL REQUIREMENTS

- .1 A Notice to Shipping is to be issued prior to commencement and upon completion of work.
- .2 During construction, any vessels or barges utilized must be marked in accordance with the provisions of the Canada Shipping Act Collision Regulations.
- .3 Upon completion of the project, a written Notice to Mariners must be issued.

1.3 PROTECTION

- .1 Protect existing objects designated to remain. In event of damage, immediately replace or make repairs to approval of and at no additional cost to Canada.
- .2 Remove all floating debris from water on a routine and timely basis.

1.4 MEASUREMENT FOR PAYMENT

- .1 Removal/Disposal and Reinstallation when required for construction operations will be paid in a lump sum and will include:
Demolition and removal will consist of, but not necessarily be limited to, the following:
 - .1 Temporary Removal and Reinstallation or disposal, for construction operations will be paid as a lump sum and will include:
 - .1 Remove existing floats, H guide piles and associated hardware, and turn over to the Dipper Harbour Authority.
 - .2 Remove and dispose of existing fenders and bridles that are in the way of new pipe pile and guide pile installation. Any ladders that are

in the way of new installation are to be removed and reinstalled in close approximate, to the Departmental Representative's approval.

Note: Contractor will note that an electrical cable runs along the top portion of the wharf, next to the wheelguard. Contractor will take precautions not to damage the cable during the installation of the Guide Pile Connections and the installation of new Concrete Filled Steel Pipe Piles.

- .3 Loading, transportation and installation of floats currently stored on site.
- .4 Clearly block the entrance to the gangway landing during construction. Once the construction is complete and approved, Contractor is to remove the blocked Access to the gangway landing.
- .2 Removal of all other items required for the progress of the work will not be measured separately for payment, it will be considered incidental to this contract.
- .3 Mobilization and Demobilization of all equipment necessary to make work progress for the entire contract will be incidental to this contract.

PART 2 - PRODUCTS

NOT APPLICABLE

PART 3 - EXECUTION

3.1 EXECUTION

- .1 Inspect site and verify with Departmental Representative objects designated for removal.
- .2 Locate and protect utility lines. Preserve in operating condition active utilities traversing site.

3.2 REMOVAL

- .1 Remove in their entirety all materials and objects specified for removal.
- .2 Do not disturb adjacent work designated to remain in place.

3.3 DISPOSAL OF MATERIAL

- .1 All demolished materials, except materials designated to be reused, will become property of contractor and will be removed from site and disposed of to satisfaction of Departmental Representative and in accordance with environmental guidelines. It is the sole responsibility of the contractor to dispose of all demolished materials at an approved disposal site. Ensure that disposal site is approved and willing to accommodate any materials disposed of from work site.

PWGSC
Float and Guide Pile
Installation
Dipper Harbour
Saint John County, N.B.
Project No. R.076365.001

SITework DEMOLITION
AND REMOVAL

Section 02 41 16
Page 3

- .2 Contractor shall obtain and pay for all necessary permits and disposal fees for use of an approved waste disposal site.

3.4 RESTORATION

- .1 Upon completion of work, remove debris, trim surfaces and leave work site in clean condition.
- .2 Reinstate areas and existing works outside areas of demolition to conditions that existed prior to commencement of work.