

PART 1 - GENERAL

1.1 DESCRIPTION

- .1 This section specifies the general requirements for the transportation and installation of floats supplied by the Crown, located on site. Installation of floats are to be as shown on the drawings under this contract.

1.2 RELATED WORK

- .1 Section 05 50 00 - Miscellaneous Metals
- .2 Section 31 62 26 - Steel Pipe Piles

1.3 MEASUREMENT FOR PAYMENT

- .1 Payment for transportation and installations of floats will be paid in a lump sum under this contract. This will include the furnishing, all equipment necessary for the complete float installation, to the locations shown on the plans. It includes all floats that are stored on site.

1.4 DELIVERY AND HANDLING

- .1 Protect floats from damage due to excessive bending stresses, impact, or other causes during handling.
- .2 Protect public and construction personnel, adjacent structures and work of other sections from hazards attributable to handling and moving of new floats.

PART 2 - PRODUCTS

2.1 MATERIALS

- .1 Not applicable.

PART 3 - EXECUTION

3.1 INSTALLATION OF FLOATS

- .1 Method of pickup and placing of floats in water is to be submitted as per section. 01 33 00, for the Departmental Representative's review.
- .2 Any damage during launching is to be repaired and paid by the Contractor, at no

PWGSC	FLOAT INSTALLATION	Section 35 51 24
Float and Guide Pile		Page 2
Installation		
Dipper Harbour		
Saint John County, N.B.		
Project No. R.076365.001		

Additional cost to the Crown.

3.2 FLOAT ANCHORAGE

- .1 Floats are to be installed as indicated on the plan.