

**3.1.2.11 Port and starboard sea bay strainer box vent pipes.** Contractor shall remove, renew and replace both port and starboard sea bay strainer box vent pipes. The port side pipe consists of approximately 28 inches of 2 inch pipe with one 90 degree turn and is flanged at both ends. The Starboard side pipe consists of 22 inches of 2 inch pipe with one 90 degree turn and is flanged at both ends. This pipe is to be renewed with schedule 80 pipe and both pipes shall be hot dipped galvanized. All welds shall have 100percent NDT. The contractor shall also pressure test this pipe to 100 PSI. Testing to be witness by the chief Engineer or his representative. The contractor shall also renew the gaskets with same gasket materials is fitted.

**Location-** Frame 61

