



**RETURN BIDS TO:**  
**RETOURNER LES SOUMISSIONS À:**  
**Bid Receiving Public Works and Government**  
**Services Canada/Réception des soumissions**  
**Travaux publics et Services gouvernementaux**  
**Canada**  
**Room 100,**  
**167 Lombard Ave.**  
**Winnipeg**  
**Manitoba**  
**R3B 0T6**  
**Bid Fax: (204) 983-0338**

## REQUEST FOR PROPOSAL DEMANDE DE PROPOSITION

**Proposal To: Public Works and Government**  
**Services Canada**

We hereby offer to sell to Her Majesty the Queen in right of Canada, in accordance with the terms and conditions set out herein, referred to herein or attached hereto, the goods, services, and construction listed herein and on any attached sheets at the price(s) set out therefor.

**Proposition aux: Travaux Publics et Services**  
**Gouvernementaux Canada**

Nous offrons par la présente de vendre à Sa Majesté la Reine du chef du Canada, aux conditions énoncées ou incluses par référence dans la présente et aux annexes ci-jointes, les biens, services et construction énumérés ici sur toute feuille ci-annexée, au(x) prix indiqué(s).

**Comments - Commentaires**

**Vendor/Firm Name and Address**

**Raison sociale et adresse du**  
**fournisseur/de l'entrepreneur**

**Issuing Office - Bureau de distribution**

Public Works and Government Services Canada - Western  
Region  
Room 100,  
167 Lombard Ave.  
Winnipeg  
Manitoba  
R3B 0T6

|  |   |
|--|---|
| <b>Title - Sujet</b><br>Engineering Services Road Repair   |   |
| <b>Solicitation No. - N° de l'invitation</b><br>EV385-172185/A   | <b>Date</b><br>2017-01-06   |
| <b>Client Reference No. - N° de référence du client</b><br>CSC EV385-172185  |   |
| <b>GETS Reference No. - N° de référence de SEAG</b><br>PW-\$PWZ-202-10107  |   |
| <b>File No. - N° de dossier</b><br>PWZ-6-39267 (202)   | <b>CCC No./N° CCC - FMS No./N° VME</b>                                    |
| <b>Solicitation Closes - L'invitation prend fin</b><br><b>at - à 02:00 PM</b><br><b>on - le 2017-02-17</b>   | <b>Time Zone</b><br><b>Fuseau horaire</b><br>Central Standard Time<br>CST |
| <b>F.O.B. - F.A.B.</b><br><b>Plant-Usine:</b> <input type="checkbox"/> <b>Destination:</b> <input type="checkbox"/> <b>Other-Autre:</b> <input type="checkbox"/>                                   |   |
| <b>Address Enquiries to: - Adresser toutes questions à:</b><br>Thompson, Valerie   | <b>Buyer Id - Id de l'acheteur</b><br>pwz202                              |
| <b>Telephone No. - N° de téléphone</b><br>(204) 509-0349 ( )   | <b>FAX No. - N° de FAX</b><br>(204) 983-7796                              |
| <b>Destination - of Goods, Services, and Construction:</b><br><b>Destination - des biens, services et construction:</b><br>CSC<br>Avenue Central<br>Saskatoon<br>Saskatchewan<br>S7K 3X5<br>Canada |   |

**Instructions: See Herein**

**Instructions: Voir aux présentes**

|  |  |
|--|--|
| <b>Delivery Required - Livraison exigée</b><br>See Herein  | <b>Delivery Offered - Livraison proposée</b> |
| <b>Vendor/Firm Name and Address</b><br><b>Raison sociale et adresse du fournisseur/de l'entrepreneur</b>   |  |
| <b>Telephone No. - N° de téléphone</b><br><b>Facsimile No. - N° de télécopieur</b>   |  |
| <b>Name and title of person authorized to sign on behalf of Vendor/Firm</b><br><b>(type or print)</b><br><b>Nom et titre de la personne autorisée à signer au nom du fournisseur/</b><br><b>de l'entrepreneur (taper ou écrire en caractères d'imprimerie)</b> |  |
| <b>Signature</b>   | <b>Date</b>                                  |

## REQUEST FOR PROPOSAL (RFP)

### TABLE OF CONTENTS

The following is intended to clarify the general structure of the whole document.

#### Front Page

#### Supplementary Instructions to Proponents (SI)

- SI1 Introduction
- SI2 Proposal Documents
- SI3 Questions or request for clarifications
- SI4 Canada's Trade Agreements
- SI5 CERTIFICATIONS**
- SI6 Workers Compensation
- SI7 Web Sites

#### Terms, Conditions and Clauses

##### Agreement

##### Supplementary Conditions (SC)

- SC1 Supplementary Conditions

##### Agreement Particulars

#### Team Identification Format (Appendix A)

#### Declaration/Certifications Form (Appendix B)

#### Price Proposal Form (Appendix C)

#### General Procedures & Standards (Appendix D)

#### Submission Requirements and Evaluation (SRE)

#### Terms of Reference

##### Description of Project (PD)

##### Description of Services - Required Services (RS)

##### Project Administration (PA)

##### Appendix A – Site Plan

---

## SUPPLEMENTARY INSTRUCTIONS TO PROPONENTS (SI)

### SI1 INTRODUCTION

1. Public Works and Government Services Canada (PWGSC) intends to retain an individual consulting firm or joint venture to provide the professional services for the project as set out in this Request for Proposal (RFP).
2. This is a single phase selection process. The nature of the requirement and the anticipated limited number of response by the industry leads PWGSC to believe that this approach will not unduly force a large number of firms to expend an overall unreasonable amount of effort in response to PWGSC.
3. Proponents responding to this RFP are requested to submit a full and complete proposal. The proposal will cover not only the qualifications, experience and organization of the proposed Consultant Team, but also the detailed approach to the work, and the pricing and terms offered. A combination of the technical and price of services submissions will constitute the proposal.

### SI2 PROPOSAL DOCUMENTS

1. All instructions, general terms, conditions and clauses identified in the RFP by number, date and title, are hereby incorporated by reference into and form part of this solicitation and any resultant contract.

All instructions, general terms, conditions and clauses identified in the RFP by number, date and title, are set out in the Standard Acquisition Clauses and Conditions Manual (<https://buyandsell.gc.ca/policy-and-guidelines/standard-acquisition-clauses-and-conditions-manual>) issued by Public Works and Government Services Canada.

2. The following are the proposal documents:
  - (a) Supplementary Instructions to Proponents (SI); R1410T (2016-04-04), General instructions (GI) – Architectural and/or Engineering services – Request for Proposal; Submission Requirements and Evaluation (SRE);
  - (b) the general terms, conditions and clauses, as amended, identified in the Agreement clause;
  - (c) Terms of Reference;
  - (d) the document entitled "General Procedures and Standards";
  - (e) any amendment to the solicitation document issued prior to the date set for receipt of proposals; and
  - (f) the proposal, Declaration/Certifications Form and Price Proposal Form.

3. Submission of a proposal constitutes acknowledgment that the Proponent has read and agrees to be bound by these documents.

### SI3 QUESTIONS OR REQUEST FOR CLARIFICATION

Questions or requests for clarification during the solicitation period must be submitted in writing to the Contracting Authority named on the RFP - Page 1 as early as possible. Enquiries should be received no later than 10 working days prior to the closing date identified on the front page of the Request for Proposal. Enquiries received after that date may not be answered prior to the closing date of the solicitation.

### SI4 CANADA'S TRADE AGREEMENTS

- This procurement is subject to the provisions of the North American Free Trade Agreement (NAFTA), the World Trade Organization - Agreement on Government Procurement (WTO-AGP), Canada-Colombia Free Trade Agreement, Canada-Peru Free Trade Agreement (CPFTA), and Canada-Panama Free Trade Agreement.

### SI5 CERTIFICATIONS

#### 1. Integrity Provisions – Declaration of Convicted Offences

In accordance with the Ineligibility and Suspension Policy (<http://www.tpsgc-pwgsc.gc.ca/ci-if/politique-policy-eng.html>), the Proponent must **provide with its bid, as applicable**, to be given further consideration in the procurement process, the required documentation as per R1410T (2016-04-04), General instructions 1 (GI1), Integrity Provisions – Proposal, **section 3b**.

#### 2. Federal Contractors Program for Employment Equity - Proposal Certification

By submitting a proposal, the Proponent certifies that the Proponent, and any of the Proponent's members if the Proponent is a Joint Venture, is not named on the Federal Contractors Program (FCP) for employment equity "FCP Limited Eligibility to Bid" list ([http://www.labour.gc.ca/eng/standards\\_equity/eq/emp/fcp/list/inelig.shtml](http://www.labour.gc.ca/eng/standards_equity/eq/emp/fcp/list/inelig.shtml)) available from Employment and Social Development Canada (ESDC) - Labour's website.

Canada will have the right to declare a proposal non-responsive if the Proponent, or any member of the Proponent if the Proponent is a Joint Venture, appears on the "FCP Limited Eligibility to Bid" list at the time of contract award.

### SI6 - WORKERS COMPENSATION

1. The recommended Proponent shall provide to the Contracting Authority, prior to Contract award:
  - a) a Workers Compensation Board letter of good standing, also listing covered Directors, Principals, Proprietor(s) or Partners who will be or who are anticipated to be present on the work site(s).

- 
2. The recommended Proponent shall deliver all of the above documents to the Contracting Authority on or before the date stated (usually 3-5 days after notification) by the Contracting Authority. Failure to comply with the request may result in the proposal being declared non-compliant.

## **SI7 - WEBSITES**

The connection to some of the Web sites in the RFP is established by the use of hyperlinks. The following is a list of the addresses of the Web sites:

Employment Equity Act  
<http://laws-lois.justice.gc.ca/eng/acts/E-5.401/index.html>

Federal Contractors Program (FCP)  
[http://www.labour.gc.ca/eng/standards\\_equity/eq/emp/fcp/index.shtml](http://www.labour.gc.ca/eng/standards_equity/eq/emp/fcp/index.shtml)

Certificate of Commitment to Implement Employment Equity form LAB 1168  
<http://www.servicecanada.gc.ca/cgi-bin/search/eforms/index.cgi?app=profile&form=lab1168&dept=sc&lang=e>

Ineligibility and Suspension Policy  
<http://www.tpsgc-pwgsc.gc.ca/ci-if/politique-policy-eng.html>

Code of Conduct for Procurement  
<http://www.tpsgc-pwgsc.gc.ca/app-acq/cndt-cndct/contexte-context-eng.html>

Lobbying Act  
<http://laws-lois.justice.gc.ca/eng/acts/L-12.4/?noCookie>

Buy and Sell  
<https://buyandsell.gc.ca/>

Supplier Registration Information  
<https://srisupplier.contractscanada.gc.ca>

Consultant Performance Evaluation Report Form  
<http://www.tpsgc-pwgsc.gc.ca/app-acq/forms/documents/2913-1.pdf>

Canadian economic sanctions  
<http://www.international.gc.ca/sanctions/index.aspx?lang=eng>

National Joint Council (NJC) Travel Directive  
<http://www.njc-cnm.gc.ca/directive/travel-voyage/index-eng.php>

---

## TERMS, CONDITIONS AND CLAUSES

### AGREEMENT

1. The Consultant understands and agrees that upon acceptance of the offer by Canada, a binding Agreement shall be formed between Canada and the Consultant and the documents forming the Agreement shall be the following:

- (a) the Front Page and this Agreement clause;
- (b) the General Terms, Conditions and Clauses, as amended, identified as:
  - R1210D (2016-04-04), General Condition (GC) 1 - General Provisions – Architectural and/or Engineering Services
  - R1215D (2016-01-28), General Condition (GC) 2 - Administration of the Contract – Architectural and/or Engineering Services
  - R1220D (2015-02-25), General Condition (GC) 3 - Consultant Services
  - R1225D (2015-04-01), General Condition (GC) 4 - Intellectual Property
  - R1230D (2016-01-28), General Condition (GC) 5 - Terms of Payment – Architectural and/or Engineering Services
  - R1235D (2011-05-16), General Condition (GC) 6 - Changes
  - R1240D (2011-05-16), General Condition (GC) 7 - Taking the Services Out of the Consultant's Hands, Suspension or Termination
  - R1245D (2016-01-28), General Condition (GC) 8 - Dispute Resolution – Architectural and/or Engineering Services
  - R1650D (2015-07-03), General Condition (GC) 9 - Indemnification and Insurance

Section GC1.1 of R1210D, Definitions, incorporated by reference above, is amended as follows:

ADD:

“Architectural and Engineering Services”:

means services to provide a range of investigation and recommendation reports, planning, design, preparation, or supervision of the construction, repair, renovation or restoration of a work and includes contract administration services, for real property projects.

“Construction Services”:

means construction, repair, renovation or restoration of any work except a vessel and includes; the supply and erection of a prefabricated structure; dredging; demolition; environmental services related to a real property; or, the hire of equipment to be used in or incidentally to the execution of any construction services referred to above.

“Facility Maintenance Services”:

means services related to activities normally associated with the maintenance of a facility and keeping spaces, structures and infrastructure in proper operating condition in a routine, scheduled, or anticipated fashion to prevent failure and degradation including inspection, testing, servicing, classification as to serviceability, repairs, rebuilding and reclamation, as well as cleaning, waste removal, snow removal, lawn care, replacement of flooring, lighting or plumbing fixtures, painting and other minor works.

Section GC1.12 of R1210D, Not applicable, incorporated by reference above, is deleted in its entirety and replaced with the following:

**R1210D CG1.12 (2016-04-04) Performance evaluation - contract**

1. Consultants shall take note that the performance of the Consultant during and upon completion of the services shall be evaluated by Canada. The evaluation includes all or some of the following criteria:
  - a. Design
  - b. Quality of Results
  - c. Management
  - d. Time
  - e. Cost
2. A weighting factor of 20 points will be assigned to each of the five criteria as follows:
  - a. Unacceptable: 0 to 5 points
  - b. Not satisfactory: 6 to 10 points
  - c. Satisfactory: 11 to 16 points
  - d. Superior: 17 to 20 points
3. The consequences resulting from the performance evaluation are as follows:
  - a. For an overall rating of 85% or higher, a congratulation letter is sent to the Consultant.
  - b. For an overall rating of between 51% and 84%, a standard, meets expectations, letter is sent to the Consultant.
  - c. For an overall rating of between 30% and 50%, a warning letter is sent to the Consultant indicating that if, within the next two (2) years, they receive 50% or less on another evaluation, the firm may be suspended from any new PWGSC solicitations for construction services, architectural and engineering services or facility maintenance services, of real property projects, for a period of one year.
  - d. For an overall rating of less than 30%, a suspension letter is sent to the Consultant indicating that the firm is suspended from any new PWGSC solicitations for construction services, architectural and engineering services or facility maintenance services, of real property projects, for a period of one year.
  - e. For a rating of 5 points or less on any one criterion, a suspension letter is sent to the Consultant indicating that the firm is suspended from any new PWGSC solicitations for construction services, architectural and engineering services or facility maintenance services, of real property projects, for a period of one year.

The form PWGSC-TPSGC 2913-1, Select - Consultant Performance Evaluation Report (CPERF), is used to record the performance.

Supplementary Conditions

Agreement Particulars

- (c) Terms of Reference;
  - (d) the document entitled "General Procedures and Standards";
  - (e) any amendment to the solicitation document incorporated in the Agreement before the date of the Agreement;
  - (g) the proposal, the Declaration/Certifications Form and the Price Proposal Form.
2. The documents identified above by title, number and date are hereby incorporated by reference into and form part of this Agreement, as though expressly set out herein, subject to any other express terms and conditions herein contained.
- The documents identified above by title, number and date are set out in the Standard Acquisition Clauses and Conditions (SACC) Manual, issued by Public Works and Government Services Canada (PWGSC). The SACC Manual is available on the PWGSC Web site:  
<https://buyandsell.gc.ca/policy-and-guidelines/standard-acquisition-clauses-and-conditions-manual>
3. If there is a discrepancy between the wording of any documents that appear on the following list, the wording of the document that first appears on the list has priority over the wording of any document that subsequently appears on the list.
- (a) any amendment or variation in the Agreement that is made in accordance with the terms and conditions of the Agreement;
  - (b) any amendment to the solicitation document incorporated in the Agreement before the date of the Agreement;
  - (c) this Agreement clause;
  - (d) Supplementary Conditions;
  - (e) General Terms, Conditions and Clauses;
  - (f) Agreement Particulars;
  - (g) Terms of Reference;
  - (h) the document entitled "General Procedures and Standards";
  - (i) the proposal.

## **SUPPLEMENTARY CONDITIONS (SC)**

### **SC1 SUPPLEMENTARY CONDITIONS**

*Use the following in Agreements which have no supplementary conditions.*

There are no supplementary conditions which apply to the Agreement.

## **AGREEMENT PARTICULARS**

The Agreement Particulars will be issued at time of award of contract and will identify the fee to be paid to the Consultant for the services determined in the Price Proposal Form.



---

## APPENDIX A - TEAM IDENTIFICATION FORMAT

For details on this format, please see SRE in the Request for Proposal.

The prime consultant and other members of the Consultant Team shall be, or eligible to be, licensed, certified or otherwise authorized to provide the necessary professional services to the full extent that may be required by provincial or territorial law.

### I. Prime Consultant (Proponent – Civil Engineering Firm):

Firm or Joint Venture Name: .....

.....

.....

Key Individuals and provincial professional licensing status and/or professional accreditation:

.....

.....

.....

.....

.....

### II. Key Sub Consultants / Specialists:

#### A. Structural Engineering

Firm Name: .....

.....

.....

Key Individuals and provincial professional licensing status and/or professional accreditation:

.....

.....

.....

.....

.....

---

## B. Geotechnical Engineering

Firm Name: .....  
.....  
.....

Key Individuals and provincial professional licensing status and/or professional accreditation:

.....  
.....  
.....  
.....

## C. Pavement Design and Engineering

Firm Name: .....  
.....  
.....

Key Individuals and provincial professional licensing status and/or professional accreditation:

.....  
.....  
.....  
.....  
.....

## D. Hydraulic Engineering

Firm Name: .....  
.....  
.....

Key Individuals and provincial professional licensing status and/or professional accreditation:

.....  
.....  
.....  
.....  
.....

Solicitation No. - N° de l'invitation  
EV385-172185/A

Amd. No. - N° de la modif.

Buyer ID - Id de l'acheteur  
pwz202

Client Ref. No. - N° de réf. du client  
CSC – EV385-172185

File No. - N° du dossier  
PWZ-6-39230

CCC No./N° CCC - FMS No./N° VME

---

## E. Cost Estimating Specialist

Firm Name: .....  
.....  
.....

Key Individuals and provincial professional licensing status and/or professional accreditation:

.....  
.....  
.....  
.....

## F. Commissioning Specialist

Firm Name: .....  
.....  
.....

Key Individuals and provincial professional licensing status and/or professional accreditation:

.....  
.....  
.....  
.....

Solicitation No. - N° de l'invitation  
EV385-172185/A

Amd. No. - N° de la modif.

Buyer ID - Id de l'acheteur  
pwz202

Client Ref. No. - N° de réf. du client  
CSC – EV385-172185

File No. - N° du dossier  
PWZ-6-39230

CCC No./N° CCC - FMS No./N° VME

---

## APPENDIX B - DECLARATION/CERTIFICATIONS FORM

**Project Title:** A&E Services Road Repair, Resurfacing and Paving, Saskatoon, SK

**Name of Proponent:** \_\_\_\_\_

**Street Address:**

**Mailing Address:** *(insert if different)*

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**Telephone Number:** (    ) \_\_\_\_\_

**Fax Number:** (    ) \_\_\_\_\_

**E-Mail:** \_\_\_\_\_

**Procurement Business Number:** \_\_\_\_\_

|  |   |
|--|---|
| <b>Type of Organization:</b><br><br>____ Sole Proprietorship<br><br>____ Partnership<br><br>____ Corporation<br><br>____ Joint Venture | <b>Size of Organization:</b><br><br>Number of Employees _____<br><br>Graduate / Professional Engineers _____<br><br>Other Professionals _____<br><br>Technical Support _____<br><br>Other _____ |
|--|---|

---

## APPENDIX B - DECLARATION/CERTIFICATIONS FORM (CONT'D)

### Former Public Servant (FPS) - Certification

Contracts awarded to former public servants (FPS) in receipt of a pension or of a lump sum payment must bear the closest public scrutiny, and reflect fairness in the spending of public funds. In order to comply with Treasury Board policies and directives on contracts awarded to FPS, proponents must provide the information required below before contract award. If the answer to the questions and, as applicable the information required have not been received by the time the evaluation of proposals is completed, Canada will inform the Proponent of a time frame within which to provide the information. Failure to comply with Canada's request and meet the requirement within the prescribed time frame will render the proposal non-responsive.

### Definitions

For the purposes of this clause,

"former public servant" is any former member of a department as defined in the *Financial Administration Act*, R.S., 1985, c. F-11, a former member of the Canadian Armed Forces or a former member of the Royal Canadian Mounted Police. A former public servant may be:

- (a) an individual;
- (b) an individual who has incorporated;
- (c) a partnership made of former public servants; or
- (d) a sole proprietorship or entity where the affected individual has a controlling or major interest in the entity.

"lump sum payment period" means the period measured in weeks of salary, for which payment has been made to facilitate the transition to retirement or to other employment as a result of the implementation of various programs to reduce the size of the Public Service. The lump sum payment period does not include the period of severance pay, which is measured in a like manner.

"pension" means a pension or annual allowance paid under the *Public Service Superannuation Act* (PSSA), R.S., 1985, c.P-36, and any increases paid pursuant to the *Supplementary Retirement Benefits Act*, R.S., 1985, c.S-24 as it affects the PSSA. It does not include pensions payable pursuant to the *Canadian Forces Superannuation Act*, R.S., 1985, c.C-17, the *Defence Services Pension Continuation Act*, 1970, c.D-3, the *Royal Canadian Mounted Police Pension Continuation Act*, 1970, c.R-10, and the *Royal Canadian Mounted Police Superannuation Act*, R.S., 1985, c.R-11, the *Members of Parliament Retiring Allowances Act*, R.S., 1985, c.M-5, and that portion of pension payable to the *Canada Pension Plan Act*, R.S., 1985, c.C-8.

---

## APPENDIX B - DECLARATION/CERTIFICATIONS FORM (CONT'D)

### Former Public Servant in Receipt of a Pension

As per the above definitions, is the Proponent a FPS in receipt of a pension?

YES ( ) NO ( )

If so, the Proponent must provide the following information, for all FPS in receipt of a pension, as applicable:

- a) name of former public servant;
- b) date of termination of employment or retirement from the Public Service.

By providing this information, proponents agree that the successful Proponent's status, with respect to being a former public servant in receipt of a pension, will be reported on departmental websites as part of the published proactive disclosure reports in accordance with Contracting Policy Notice: 2012-2 and the Guidelines on the Proactive Disclosure of Contracts.

### Work Force Adjustment Directive

Is the Proponent a FPS who received a lump sum payment pursuant to the terms of a work force reduction program? YES ( ) NO ( )

If so, the Proponent must provide the following information:

- a) name of former public servant;
- b) conditions of the lump sum payment incentive;
- c) date of termination of employment;
- d) amount of lump sum payment;
- e) rate of pay on which lump sum payment is based;
- f) period of lump sum payment including start date, end date and number of weeks;
- g) number and amount (professional fees) of other contracts subject to the restrictions of a work force adjustment program.

For all contracts awarded during the lump sum payment period, the total amount of fees that may be paid to a FPS who received a lump sum payment is \$5,000, including Applicable Taxes.

---

## APPENDIX B - DECLARATION/CERTIFICATIONS FORM (CONT'D)

### Name of Proponent:

#### DECLARATION:

I, the undersigned, being a principal of the proponent, hereby certify that the information given on this form and in the attached proposal is accurate to the best of my knowledge. If any proposal is submitted by a partnership or joint venture, then the following is required from each component entity.

.....  
name signature

.....  
title

I have authority to bind the Corporation / Partnership / Sole Proprietorship / Joint Venture

.....  
name signature

.....  
title

I have authority to bind the Corporation / Partnership / Sole Proprietorship / Joint Venture

.....  
name signature

.....  
title

I have authority to bind the Corporation / Partnership / Sole Proprietorship / Joint Venture

During proposal evaluation period, PWGSC contact will be with the following person:

\_\_\_\_\_.

Telephone Number: (    ) \_\_\_\_\_ Fax Number: (    ) \_\_\_\_\_

E-mail: \_\_\_\_\_

This Appendix "B" should be completed and submitted with the proposal, but may be submitted afterwards as follows: if Appendix "B" is not completed and submitted with the proposal, the Contracting Authority will inform the Proponent of a time frame within which to provide the information. Failure to comply with the request of the Contracting Authority and to provide the certifications within the time frame provided will render the proposal non-responsive.

Solicitation No. - N° de l'invitation  
EV385-172185/A

Amd. No. - N° de la modif.

Buyer ID - Id de l'acheteur  
pwz202

Client Ref. No. - N° de réf. du client  
CSC – EV385-172185

File No. - N° du dossier  
PWZ-6-39230

CCC No./N° CCC - FMS No./N° VME

---

## APPENDIX C - PRICE PROPOSAL FORM

INSTRUCTIONS: Complete this Price Proposal Form and submit in a **separate sealed envelope** with the Name of Proponent, Name of Project, PWGSC Solicitation Number, and the words "PRICE PROPOSAL FORM" typed on the outside of the envelope. Price Proposals are not to include Applicable Taxes.

PROPOSERS SHALL NOT ALTER THIS FORM

**Project Title:** A&E Services Road Repair, Resurfacing and Paving, Saskatoon, SK

**Name of Proponent:**

---

**The following will form part of the evaluation process:**

---

### REQUIRED SERVICES

**Fixed Fee** (R1230D (2016-01-28), GC 5 - Terms of Payment – Architectural and/or Engineering Services)

| SERVICES                                       | FIXED FEE      |
|--|----------------|
| RS 1 Estimating Service                        | \$.....        |
| RS 2 Pre-design Service                        | \$.....        |
| RS 3 Design Development Service                | \$.....        |
| RS 4 Construction Document Service             | \$.....        |
| RS 5 Tender Services                           | \$.....        |
| RS 6 Construction Support service              | \$.....        |
| RS 7 Resident Construction Service             | \$.....        |
| RS 8 Commissioning Services                    | \$.....        |
| RS 9 Post Construction Services                | <u>\$.....</u> |
| <b>MAXIMUM FIXED FEE FOR REQUIRED SERVICES</b> | <b>\$.....</b> |

**TOTAL COST OF SERVICES FOR PROPOSAL EVALUATION PURPOSES**



Solicitation No. - N° de l'invitation  
EV385-172185/A

Amd. No. - N° de la modif.

Buyer ID - Id de l'acheteur  
pwz202

Client Ref. No. - N° de réf. du client  
CSC – EV385-172185

File No. - N° du dossier  
PWZ-6-39230

CCC No./N° CCC - FMS No./N° VME

---

## APPENDIX C - PRICE PROPOSAL FORM (CONT'D)

---

### The following will NOT form part of the evaluation process

---

Canada may accept or reject any of the following fees, disbursements and/or hourly rates. Canada reserves the right to negotiate on these fees, disbursements and/or hourly rates.

### THE FOLLOWING HOURLY RATES MAY BE USED FOR FUTURE CONTRACT AMENDMENTS

#### Principals

Name

\$ per hour

|       |       |
|-------|-------|
| ..... | ..... |
| ..... | ..... |
| ..... | ..... |
| ..... | ..... |
| ..... | ..... |
| ..... | ..... |
| ..... | ..... |
| ..... | ..... |
| ..... | ..... |
| ..... | ..... |
| ..... | ..... |
| ..... | ..... |
| ..... | ..... |
| ..... | ..... |
| ..... | ..... |
| ..... | ..... |

Solicitation No. - N° de l'invitation  
EV385-172185/A

Amd. No. - N° de la modif.

Buyer ID - Id de l'acheteur  
pwz202

Client Ref. No. - N° de réf. du client  
CSC – EV385-172185

File No. - N° du dossier  
PWZ-6-39230

CCC No./N° CCC - FMS No./N° VME

**APPENDIX C - PRICE PROPOSAL FORM (CONT'D)**

**Staff**

| Name / Position | \$ per hour |
|-----------------|-------------|
| .....           | .....       |
| .....           | .....       |
| .....           | .....       |
| .....           | .....       |
| .....           | .....       |
| .....           | .....       |
| .....           | .....       |
| .....           | .....       |
| .....           | .....       |
| .....           | .....       |
| .....           | .....       |
| .....           | .....       |
| .....           | .....       |
| .....           | .....       |
| .....           | .....       |
| .....           | .....       |
| .....           | .....       |
| .....           | .....       |
| .....           | .....       |
| .....           | .....       |
| .....           | .....       |
| .....           | .....       |

**END OF PRICE PROPOSAL FORM**



Public Works and  
Government Services  
Canada

Travaux publics et  
Services gouvernementaux  
Canada

Canada



# GENERAL PROCEDURES & STANDARDS

## For Professional & Design Services

MMXI Edition

[www.pwpsc-tpsgc.gc.ca](http://www.pwpsc-tpsgc.gc.ca)



## Table of Contents:

|          |   |          |
|----------|---|----------|
| <b>I</b> | <b>INTRODUCTION .....</b>   | <b>5</b> |
| 1.1      | GENERAL PROCEDURES AND STANDARDS .....                                      | 5        |
| 1.1.1    | <i>General</i> .....  | 5        |
| 1.1.2    | <i>Harmonization with the Terms of Reference (TOR)</i> .....                | 5        |
| 1.2      | PROJECT DELIVERY .....  | 5        |
| 1.2.1    | <i>General Requirements</i> .....   | 5        |
| 1.2.2    | <i>Service Delivery for all Projects</i> .....                              | 6        |
| 1.2.3    | <i>Service Delivery (Buildings)</i> .....                                   | 6        |
| 1.2.4    | <i>Service Delivery (Engineering)</i> .....                                 | 6        |
| 1.3      | PROCUREMENT OF GOODS AND SERVICES .....                                     | 6        |
| 1.3.1    | <i>Public Procurement</i> .....   | 6        |
| 1.3.2    | <i>Integrity and Guiding Principles</i> .....                               | 7        |
| <b>2</b> | <b>REQUIRED SERVICES STANDARDS .....</b>                                    | <b>8</b> |
| 2.1      | GENERAL .....   | 8        |
| 2.2      | COST MANAGEMENT .....   | 8        |
| 2.2.1    | <i>General</i> .....  | 8        |
| 2.2.2    | <i>Treasury Board (TB) Submissions</i> .....                                | 8        |
| 2.2.3    | <i>Classes of Estimates</i> .....   | 9        |
| 2.2.4    | <i>Class 'D' (Indicative) Estimate</i> .....                                | 9        |
| 2.2.5    | <i>Class 'C' Estimate</i> .....   | 9        |
| 2.2.6    | <i>Class 'B' (Substantive) Estimate</i> .....                               | 9        |
| 2.2.7    | <i>Class 'A' (Pre-Tender) Estimate</i> .....                                | 9        |
| 2.3      | SCHEDULE MANAGEMENT .....   | 10       |
| 2.3.1    | <i>Scheduler</i> .....  | 10       |
| 2.3.2    | <i>Project Schedule</i> .....   | 10       |
| 2.3.3    | <i>Milestones</i> .....   | 10       |
| 2.3.4    | <i>Activities</i> .....   | 10       |
| 2.3.5    | <i>Schedule Review and Approval</i> .....                                   | 11       |
| 2.3.6    | <i>Schedule Monitoring and Control</i> .....                                | 11       |
| 2.4      | RISK MANAGEMENT .....   | 12       |
| 2.4.1    | <i>Context</i> .....  | 12       |
| 2.5      | WASTE MANAGEMENT .....  | 12       |
| 2.5.1    | <i>Protocol</i> .....   | 12       |
| 2.5.2    | <i>Consultant Responsibilities</i> .....                                    | 12       |
| 2.6      | TECHNICAL REPORTS .....   | 12       |
| 2.6.1    | <i>Purpose</i> .....  | 12       |
| 2.6.2    | <i>Standards for PWGSC Technical Reports</i> .....                          | 12       |
| 2.6.3    | <i>Pre-Design Report Content</i> .....                                      | 13       |
| 2.6.4    | <i>Schematic Design Report Content</i> .....                                | 14       |
| 2.6.5    | <i>Design Development Report Content</i> .....                              | 16       |
| 2.7      | CODES, ACTS, STANDARDS, REGULATIONS .....                                   | 19       |
| 2.7.1    | <i>General</i> .....  | 19       |
| 2.7.2    | <i>PWGSC documents available from PWGSC Project Manager:</i> .....          | 19       |
| 2.7.3    | <i>Codes and Regulations:</i> .....   | 19       |
| 2.7.4    | <i>Standards and Guidelines Produced by the Government of Canada:</i> ..... | 20       |



|         |   |    |
|---------|---|----|
| 2.7.5   | <i>Health Canada Standards and Guidelines:</i>      | 20 |
| 2.7.6   | <i>Standards and Guidelines:</i>                    | 21 |
| 2.7.7   | <i>Standards and Guidelines for Transportation:</i> | 23 |
| 2.8     | COMMISSIONING PROCESS                               | 23 |
| 2.8.1   | <i>General</i>                                      | 23 |
| 2.8.2   | <i>Commissioning Plan</i>                           | 24 |
| 2.8.3   | <i>Component Verification</i>                       | 24 |
| 2.8.4   | <i>System &amp; Integrated System Testing</i>       | 24 |
| 2.8.5   | <i>Test Requirements</i>                            | 25 |
| 2.8.6   | <i>Commissioning (Evaluation) Report</i>            | 25 |
| 2.8.7   | <i>Overview of Roles and Responsibilities</i>       | 25 |
| 2.8.8   | <i>Major Tasks and Responsibilities</i>             | 26 |
| 2.9     | CONSTRUCTION DOCUMENTS                              | 27 |
| 2.9.1   | <i>Purpose</i>                                      | 27 |
| 2.9.2   | <i>Principles for PWGSC Contract Documents</i>      | 27 |
| 2.9.3   | <i>Quality Assurance</i>                            | 27 |
| 2.9.4   | <i>Addenda</i>                                      | 27 |
| 2.9.5   | <i>Submissions</i>                                  | 28 |
| 2.9.6   | <i>PWGSC Role</i>                                   | 28 |
| 2.10    | SPECIFICATIONS                                      | 28 |
| 2.10.1  | <i>General</i>                                      | 28 |
| 2.10.2  | <i>National Master Specification (NMS)</i>          | 28 |
| 2.10.3  | <i>Specification Organization</i>                   | 28 |
| 2.10.4  | <i>Terminology</i>                                  | 29 |
| 2.10.5  | <i>Dimensions</i>                                   | 29 |
| 2.10.6  | <i>Standards</i>                                    | 29 |
| 2.10.7  | <i>Specifying Materials</i>                         | 29 |
| 2.10.8  | <i>Acceptable Products and Materials</i>            | 29 |
| 2.10.9  | <i>Alternate Products and Materials</i>             | 30 |
| 2.10.10 | <i>Separate and Alternate Prices</i>                | 30 |
| 2.10.11 | <i>Sole Sourcing</i>                                | 30 |
| 2.10.12 | <i>Unit Prices</i>                                  | 30 |
| 2.10.13 | <i>Cash Allowances</i>                              | 30 |
| 2.10.14 | <i>Warranties</i>                                   | 30 |
| 2.10.15 | <i>Scope of Work</i>                                | 30 |
| 2.10.16 | <i>Summary and Section Includes</i>                 | 30 |
| 2.10.17 | <i>Related Sections</i>                             | 30 |
| 2.10.18 | <i>Index</i>  | 30 |
| 2.10.19 | <i>Health and Safety</i>                            | 31 |
| 2.10.20 | <i>Experience and Qualifications</i>                | 31 |
| 2.10.21 | <i>Prequalification</i>                             | 31 |
| 2.10.22 | <i>Contracting Issues</i>                           | 31 |
| 2.11    | DRAWINGS  | 31 |
| 2.11.1  | <i>General</i>                                      | 31 |
| 2.11.2  | <i>Title Blocks</i>                                 | 31 |
| 2.11.3  | <i>Dimensions</i>                                   | 31 |
| 2.11.4  | <i>Trade Names</i>                                  | 31 |
| 2.11.5  | <i>Specification Notes</i>                          | 32 |
| 2.11.6  | <i>Terminology</i>                                  | 32 |
| 2.11.7  | <i>Information to be included</i>                   | 32 |



|            |   |           |
|------------|---|-----------|
| 2.11.8     | Drawing Numbers.....  | 32        |
| 2.11.9     | Prints .....  | 32        |
| 2.11.10    | Binding .....   | 33        |
| 2.11.11    | Legends.....  | 33        |
| 2.11.12    | Schedules .....   | 33        |
| 2.11.13    | North Points.....   | 33        |
| 2.11.14    | Drawing Symbols.....  | 33        |
| <b>3</b>   | <b>PROJECT ADMINISTRATION .....</b>                               | <b>34</b> |
| 3.1        | GENERAL REQUIREMENTS FOR ALL PROJECTS .....                       | 34        |
| 3.2        | LANGUAGE .....  | 34        |
| 3.3        | MEDIA .....   | 34        |
| 3.4        | PROJECT MANAGEMENT .....  | 34        |
| 3.4.1      | General.....  | 34        |
| 3.4.2      | National Project Management System.....                           | 34        |
| 3.4.3      | Design Stage.....   | 34        |
| 3.4.4      | Implementation Stage .....  | 35        |
| 3.4.5      | Closeout Stage.....   | 35        |
| 3.4.6      | Engineering Projects .....  | 35        |
| 3.5        | LINES OF COMMUNICATION.....                                       | 36        |
| 3.6        | MEETINGS .....  | 36        |
| 3.7        | CONSULTANT RESPONSIBILITIES .....                                 | 36        |
| 3.8        | PWGSC RESPONSIBILITIES .....                                      | 37        |
| 3.9        | USER DEPARTMENT RESPONSIBILITIES.....                             | 38        |
| 3.10       | REVIEW AND APPROVAL BY PROVINCIAL AND MUNICIPAL AUTHORITIES ..... | 38        |
| 3.11       | BUILDING PERMITS AND OCCUPANCY PERMITS .....                      | 38        |
| 3.12       | TECHNICAL AND FUNCTIONAL REVIEWS .....                            | 38        |
| APPENDIX A | CHECKLISTS .....  | 40        |
| APPENDIX B | SPECIFICATION TOC STANDARDS .....                                 | 49        |
| APPENDIX C | ADDENDUM FORMAT STANDARD .....                                    | 50        |
| APPENDIX D | DIGITAL TENDER DOCUMENTS STANDARDS .....                          | 51        |
| APPENDIX E | PDF CREATION STANDARDS.....                                       | 59        |
| APPENDIX F | DEFINITIONS .....   | 62        |



## **I INTRODUCTION**

### **I.1 GENERAL PROCEDURES AND STANDARDS**

#### **I.1.1 GENERAL**

- .1 These PWGSC *General Procedures and Standards* (P&S) have been developed to:
  - .1 Facilitate the development of a rational, well-documented design process; and
  - .2 Ensure compliance with federal government standards, PWGSC Policies and Treasury Board directives.

#### **I.1.2 HARMONIZATION WITH THE TERMS OF REFERENCE (TOR)**

- .1 The P&S document must be used in conjunction with the TOR, as the two documents are complimentary.
- .2 The TOR describes project-specific requirements, services and deliverables while the GP&S document outlines with minimum standards and procedures common to all projects.
- .3 In the case of a conflict between the two documents, the requirements of the TOR override this document.

### **I.2 PROJECT DELIVERY**

#### **I.2.1 GENERAL REQUIREMENTS**

- .1 The project delivery requirements outlined in this section are applicable to the design and construction of all PWGSC projects in Western Region, unless otherwise indicated in the TOR.
- .2 Under the direction of the Consultant, the Consultant team shall provide fully integrated and coordinated professional and design services for the delivery of a project, in accordance with the requirements in the TOR and as contained herein.
- .3 The Consultant must:
  - .1 Obtain written authorization from the Departmental Representative before proceeding from one phase of work to the next phase of a project;
  - .2 Coordinate all services with the Departmental Representative;
  - .3 Deliver each project utilizing best practices in support of User Department needs, respecting the approved financial budget, schedule, scope, quality energy budget;
  - .4 Establish a cohesive functional partnership and open communication between all members of the project delivery team throughout all phases of the project life;
  - .5 Ensure that the Consultant team has an in-depth understanding and collective 'buy-in' of the project requirements, scope, budget and scheduling objectives, working constructively to build a collaborative and cooperative team approach with knowledgeable and timely input and contribution by all project team members, including representatives from PWGSC and the User Department;
  - .6 Conduct rigorous quality assurance reviews during the design and construction phases, including the application of value engineering principles during the design of all complex systems;
  - .7 Provide a written response to all PWGSC comments included in Quality Assurance reviews conducted throughout the design of the project;
  - .8 If any alterations are required during the development of the design, analyse the impact on all project components and resubmit for approval before proceeding further;
  - .9 Establish and maintain a change control procedure for scope changes;



- .10 Ensure that an experienced Project Architect or Project Engineer is assigned to each project, who shall be responsible for the production, coordination and delivery of all design and construction documents for all project disciplines;
- .11 Prepare a continuous risk identification and management program employing effective methodologies to ensure construction safety as well as claims avoidance;
- .12 Provide continuous and comprehensive documentation of the project at all stages of the project implementation;
- .13 Ensure continuity of key personnel and maintain a dedicated working team for the life of the project;

### **I.2.2 SERVICE DELIVERY FOR ALL PROJECTS**

- .1 For all projects, the Consultant shall:
  - .1 Deliver the project to be within;
    - .1 The established construction budget,
    - .2 The key milestones, according to the established project schedule.
  - .2 Ensure that each Consultant team member:
    - .1 Understands the project requirements, for seamless delivery of the required services;
    - .2 Functions as a cohesive partnership with open communication between all members of the project delivery team throughout all phases of the project life;
    - .3 Function as an integrated and focused team with an in-depth understanding and collective 'buy-in' of the project requirements, scope, budget and scheduling objectives.
- .3 Provide;
  - .1 Full co-ordination of services with other consultants engaged by PWGSC,
  - .2 A continuous risk management program to address the risks associated specifically with this project, including construction safety and claims avoidance issues.
- .4 Deliver the work in a professional manner during all phases of the project, employing best practices for budget, schedule, quality, and scope management;
- .5 Maintain continuity of key personnel and maintain a dedicated working team for the life of the project.

### **I.2.3 SERVICE DELIVERY (BUILDINGS)**

- .1 For Building projects, where an Architectural firm is the Prime Consultants, the Consultant team shall, as a minimum, adhere to the standards of services outlined in the "Canadian Handbook of Practice for Architects - Volume 2 Management" (latest edition) distributed by the Royal Architectural Institute of Canada (RAIC).

### **I.2.4 SERVICE DELIVERY (ENGINEERING)**

- .1 For Engineering projects, where an Engineering firm is the Prime Consultants, the Consultant team shall adhere to the standards of services established by the Professional Engineering Association in the Province or Territories where the project is located.

## **I.3 PROCUREMENT OF GOODS AND SERVICES**

### **I.3.1 PUBLIC PROCUREMENT**

- .1 Public procurement by Canada is legislated and guided by a number of international and national trade agreements, and acts, as well as policies, directives, and guidelines provided by the Treasury Board Secretariat (TBS) and PWGSC.





- .2 There is one over-arching principle for all PWGSC procurement activities: Integrity. Subordinate to this are guiding principles, which provide the framework for PWGSC procurement process.
- .3 For further information refer to the following web link;
  - .1 <http://www.tpsgc-pwgsc.gc.ca/app-acq/cndt-cndct/contexte-context-eng.html>

### **I.3.2 INTEGRITY AND GUIDING PRINCIPLES**

- .1 PWGSC procurement processes will be open, fair and honest.
- .2 Client Service:
  - .1 PWGSC will make every reasonable effort to satisfy the operational requirements of its clients, while obtaining the best value in each procurement process.
- .3 National Objectives:
  - .1 PWGSC procurement activities will advance established government policies, within the limits imposed by international trade obligations.
- .4 Competition:
  - .1 PWGSC procurement will be competitive, with specific exceptions.
- .5 Equal Treatment:
  - .1 PWGSC must ensure that all potential bidders of a particular requirement are subject to the same conditions.
- .6 Accountability:
  - .1 PWGSC is accountable for the integrity of the contracting process.



## **2 REQUIRED SERVICES STANDARDS**

### **2.1 GENERAL**

- .1 Where Services are called for in the project specific TOR, the standards outlined in the following articles apply.

### **2.2 COST MANAGEMENT**

#### **2.2.1 GENERAL**

- .1 The following provides a general indication of the information needed by the Consultant's cost estimator to prepare specific classifications of estimates.
- .2 These are the minimum requirements only and should be supplemented where additional information exists or is warranted.
- .3 Construction cost estimates are to be prepared and submitted to PWGSC at various stages during the design process.
- .4 In addition to the Consultants' estimate, PWGSC may have independent estimates performed to compare with the Consultant estimate.

#### **2.2.2 TREASURY BOARD (TB) SUBMISSIONS**

- .1 Projects that are subject to TB approval are normally submitted twice.
  - .1 The first submission is for Preliminary Project Approval (PPA) at Pre-Design or Schematic Design stage of a project and must include an Indicative Estimate for the cost of the work.
  - .2 The second submission is for Effective Project Approval (EPA) at the completion of Design Development or Pre-Tender stage of a project and must include a Substantive Estimate for the cost of the work.
- .2 The Treasury Board estimate definitions are:
  - .1 Indicative Estimate;
    - .1 A low quality, order of magnitude estimate that is not sufficiently accurate to warrant TB approval as a Cost Objective.
  - .2 Substantive Estimate;
    - .1 An estimate which is of sufficiently high quality and reliability as to warrant TB approval as a Cost Objective for the project phase under consideration.
    - .2 It is based on detailed systems and component design, taking into account all project objectives and deliverables.
- .3 TB Terminology:
  - .1 Constant dollar estimate;
    - .1 This is an estimate expressed in terms of the dollars of a particular base fiscal year.
      - .1 It includes no provision for inflation.
      - .2 Cash flows over a number of fiscal years may also be expressed in constant dollars of the base year including no allowance for inflation in the calculation of costs.
  - .2 Budget-year (BY) dollar estimate:
    - .1 Budget year dollars is also be referred to as Nominal dollars or Current dollars.
      - .1 This is an estimate based on costs arising in each FY of the project schedule.
      - .2 It is escalated to account for inflation and other economic factors affecting the period covered by the estimate.
    - .2 The costs and benefits across all periods should initially be tabulated in budget year dollars for three following reasons:



- .1 First; this is the form in which financial data are usually available,
- .2 Second; adjustments, such as tax adjustments, are accurately and easily made in budget year dollars,
- .3 Finally; working in budget-year dollar enables the analyst to construct a realistic picture over time, taking into account changes in relative prices.

### **2.2.3 CLASSES OF ESTIMATES**

- .1 PWGSC applies a detailed, four level, classification using the terms Class A, B, C and D.
- .2 Apply these estimate classifications at the project stages as defined in the TOR.
- .3 For projects required to be submitted to TB for approval:
  - .1 An Indicative Estimate shall be at least a class 'D'; and
  - .2 A Substantive Estimate shall be at least a class 'B'.

### **2.2.4 CLASS 'D' (INDICATIVE) ESTIMATE**

- .1 Based upon a comprehensive statement of requirements and an outline of potential solutions, this estimate is to provide an indication of the final project cost, and allow for ranking of all the options being considered.
- .2 Submit Class 'D' cost estimates in elemental analysis format, in accordance with the latest edition issued by the Canadian Institute of Quantity Surveyors, with cost per m<sup>2</sup> for current industry statistical data for the appropriate building type and location.
- .3 Include a summary in the cost estimate, plus full back up, showing items of work, quantities, unit prices, allowances and assumptions.
- .4 The level of accuracy of a class D cost estimate shall be such that no more than a 20% design contingency allowance is required.

### **2.2.5 CLASS 'C' ESTIMATE**

- .1 Based on a comprehensive list of requirements and assumptions, including a full description of the preferred Schematic Design option, construction experience, design experience and market conditions, this estimate must be sufficient for making the correct investment decision.
- .2 Submit Class 'C' cost estimates in elemental analysis format, in accordance with the latest edition issued by the Canadian Institute of Quantity Surveyors, with cost per m<sup>2</sup> for current industry statistical data for the appropriate building type and location.
- .3 Include a summary in the cost estimate, plus full back up, showing items of work, quantities, unit prices, allowances and assumptions.
- .4 The level of accuracy of a class C cost estimate shall be such that no more than a 15% design contingency allowance is required.

### **2.2.6 CLASS 'B' (SUBSTANTIVE) ESTIMATE**

- .1 Based on design development drawings and outline specifications, which include the preliminary design of all major systems and subsystems, as well as the results of all site/installation investigations, this estimate must provide for the establishment of realistic cost objectives and be sufficient to obtain effective project approval.
- .2 Submit Class 'B' cost estimates in both elemental analysis format and trade divisional format, in accordance with the latest edition issued by the Canadian Institute of Quantity Surveyors.
- .3 Include a summary in the cost estimate, plus full back up, showing items of work, quantities, unit prices, allowances and assumptions.
- .4 The level of accuracy of a class 'B' cost estimate shall be such that no more than a 10% design contingency allowance is required.

### **2.2.7 CLASS 'A' (PRE-TENDER) ESTIMATE**



- .1 Based on completed construction drawings and specifications prepared prior to calling competitive tenders, this estimate must be sufficient to allow a detailed reconciliation and/or negotiation with any contractor's tender.
- .2 Submit Class 'A' cost estimates in both elemental analysis format and trade divisional format, in accordance with the latest edition issued by the Canadian Institute of Quantity Surveyors.
- .3 Include a summary in the cost estimate, plus full back up, showing items of work, quantities, unit prices, allowances and assumptions.
- .4 The level of accuracy of a class 'A' cost estimate shall be such that no more than a 5% design contingency allowance is required.

## **2.3 SCHEDULE MANAGEMENT**

### **2.3.1 SCHEDULER**

- .1 The Scheduler shall provide a Project Planning and Control Schedule for the project, for the purpose of Planning, Scheduling, Progress Monitoring (Time Management), during all the design phases up to the construction procurement phase.
- .2 A qualified Scheduler, with experience commensurate with the complexity of the project, is required to develop and monitor the project schedule during the design process.
- .3 The Scheduler shall adhere to good industry practices for schedule development and maintenance, as recognized by the Project Management Institute (PMI).
- .4 PWGSC presently utilizes the Primavera Suite software and Microsoft Project for its current Control Systems and any software used by the consultant should be fully integrated with either of these programs, using one of the many commercially available software packages.

### **2.3.2 PROJECT SCHEDULE**

- .1 A Detailed Project Schedule is a schedule developed in reasonable detail to ensure adequate Time Management planning and control of the project.
- .2 Project Schedules are used as a guide for the planning, design and implementation phases of the project, as well as to communicate to the project team when activities are to happen, based on network techniques using Critical Path Method (CPM).
- .3 When building a Project Schedule, the Consultant must consider:
  - .1 The level of detail required for control and reporting;
  - .2 The reporting cycle shall be monthly, unless otherwise identified in the Terms of Reference;
  - .3 What is required for reporting in the Project Teams Communications Plan; and
  - .4 The nomenclature and coding structure for naming of scheduled activities, which must be submitted to the Project Manager for acceptance.

### **2.3.3 MILESTONES**

- .1 The Major Milestones are standard Deliverables and Control Points within NPMS and are required in all schedule development.
- .2 These Milestones will be used in Time Management Reporting within PWGSC as well as used for monitoring project progress using Variance Analysis.
- .3 Milestones may also be external constraints such as the completion of an activity, exterior to the project, affecting the project.

### **2.3.4 ACTIVITIES**

- .1 All activities will need to be developed based on:
  - .1 Project Objectives;
  - .2 Project Scope;



- .3 Milestones;
- .4 Meetings with the project team; and
- .5 The scheduler's full understanding of the project and its processes.
- .2 Subdivide the elements down into smaller more manageable pieces that organize and define the total scope of work in levels that can be scheduled, monitored and controlled.
  - .1 This process will develop the Activity List for the project.
- .3 Each activity will describe the work to be performed using a verb and noun combination (i.e. Review Design Development Report).
- .4 These elements will become activities, interdependently linked in the Project Schedule.

### **2.3.5 SCHEDULE REVIEW AND APPROVAL**

- .1 Once the scheduler has identified and properly coded all the activities to the acceptance of the Project Manager, the activities are then sorted into a logical order and appropriate duration are applied to complete the schedule.
- .2 The scheduler, together with the Project Team, can then analyze the schedule to see if the milestone dates meet the project timelines and then adjust the schedule accordingly by modifying durations or changing logic.
- .3 When the schedule has been satisfactorily prepared, the scheduler can present the detailed schedule back to the Project Team for acceptance and application as the project baseline.
- .4 There may be several iterations before the schedule meets with the Project Teams agreement and the critical project timelines.
- .5 The final agreed version must be copied and saved as the baseline to monitor variances during the design process.

### **2.3.6 SCHEDULE MONITORING AND CONTROL**

- .1 Once Baseline, the schedule can be better monitored, controlled and reports can be produced.
- .2 Monitoring is performed by, comparing the baseline activities completed and milestone dates to the actual and forecast dates to identify the variance and record any potential delays, outstanding issues and concerns and provide options for dealing with any serious planning and scheduling issues.
- .3 There will be several schedules generated from the analysis of the baseline schedule as outlined in the Required Services Sections of the TOR.
- .4 Each updated schedule reflects the progress of each activity to date, any logic changes, both historic and planned, projections of progress and completion indicating the actual start and finish dates of all activities being monitored.
- .5 The Scheduler is to provide continuous monitoring and control, timely identification and early warning of all unforeseen or critical issues that affect or potentially affect the project in accordance with the TOR.
- .6 If unforeseen or critical issues arise, the Scheduler will advise the Project Manager and submit proposed alternative solutions in the form of an Exception Report.
  - .1 An Exception Report will include sufficient description and detail to clearly identify:
    - .1 Scope Change: Identifying the nature, reason and total impact of all identified and potential project scope changes affecting the project;
    - .2 Delays and accelerations: Identifying the nature, the reason and the total impact of all identified and potential duration variations;
    - .3 Options Enabling a Return to the project baseline: Identifying the nature and potential effects of all identified options proposed to return the project within baselined duration.



- .7 At each submission or deliverable stage, provide an updated schedule and exception report.

## **2.4 RISK MANAGEMENT**

### **2.4.1 CONTEXT**

- .1 The Departmental Representative prepares the Risk Management Plan.
- .2 The Departmental Representative may ask for assistance from the Consultant Team for identification of risk items and factors arising from the technical requirements of the project.

## **2.5 WASTE MANAGEMENT**

### **2.5.1 PROTOCOL**

- .1 The Construction, Renovation, and Demolition (CRD) Non-hazardous Solid Waste Management Protocol to which PWGSC is bound, provides direction on the undertaking of non-hazardous solid waste management actions on projects.
  - .1 The protocol is designed to meet the federal requirements, provincial/territorial policies and the objectives of the PWGSC Sustainable Development Strategy (SDS).
- .2 The contractor must implement a solid waste management program.
- .3 Contractors must be instructed to plan for extra project time when implementing CRD waste diversion initiatives.
  - .1 Added labour costs can be recuperated and waste management costs savings can be achieved through reduced tipping fees, avoided haulage costs, and the sale of reusable and recyclable materials.

### **2.5.2 CONSULTANT RESPONSIBILITIES**

- .1 Research and investigate hazardous waste disposal strategies in context of the project and make recommendations.
- .2 Include in the contract documents, a requirement for the contractor to develop a waste reduction and management plan during the construction of this project.
- .3 Identify, on the site plan where large (garbage) bins shall be stored, as well as easy disposal truck access/exit to/from same, to assist the Contractor in reducing waste or re-cycling of materials on and off site.

## **2.6 TECHNICAL REPORTS**

### **2.6.1 PURPOSE**

- .1 This section provides direction and standards for the preparation of reports delivered to PWGSC during all the various stages of project delivery and for specific services such as investigations, studies, analysis, strategies, audits, surveys, programs, plans, etc.
- .2 Technical Reports are official government documents, which are typically used to support an application for approval or to obtain authorization or acceptance and as such they must:
  - .1 Be complete, clear and professional in appearance and organization, with proper reference to related parts and contents in the report;
  - .2 Clearly outline the intent, objectives, process, results and recommendations;
  - .3 Present the flow of information and conclusions in a logical, easy to follow sequence;
  - .4 Be in written narrative, graphic, model (traditional and / or computer generated), and photographic format, which can be web enabled;
  - .5 Ensure that all pages are numbered in sequence; and
  - .6 Be printed double-sided, if hard copies are produced.

### **2.6.2 STANDARDS FOR PWGSC TECHNICAL REPORTS**

- .1 Standard practice for the organization of technical reports requires:



- .1 A cover page, clearly indicating the nature of the report, the date, the PWGSC reference number and who prepared the report;
- .2 A Table of Contents;
- .3 An Executive Summary;
- .4 The body of the report is to be structured such that the reader can easily review the document and locate, respond to and /or reference related information contained elsewhere in the report;
- .5 Appendices used for lengthy segments of the report, supplementary and supporting information and / or for separate related documents.
- .2 The report content must:
  - .1 Ensure that the executive summary is a true condensed version of the report following the identical structure, including only key points and results / recommendations requiring review and / or approval;
  - .2 Use a proper numbering system (preferably legal numbering), for ease of reference and cross-reference;
    - .1 The use of 'bullets' is to be avoided.
  - .3 Use proper grammar, including using complete sentences, in order to ensure clarity, avoid ambiguity and facilitate easy translation into French, if required;
    - .1 The use of undefined technical terms, industry jargon and cryptic phrases are to be avoided.
  - .4 Be written as efficiently as possible, with only essential information included in the body of the report and supporting information in an appendix if needed.

### 2.6.3 PRE-DESIGN REPORT CONTENT

- .1 Administrative aspects to be included (but not limited to) are:
  - .1 Quality management process for the consultant team;
  - .2 Confirmation that all necessary pre-design documentation required for this project is available and confirmation that the information is still current and up-to-date.
- .2 Regulatory Analysis aspects to be included (but not limited to) are:
  - .1 Preliminary summary of regulatory and statutory requirements, authorities having jurisdiction, and codes, regulations, and standards.
- .3 Program Analysis aspects to be included (but not limited to) are a review and analysis of:
  - .1 Functional program, User Department reports and studies, Space data sheets, Work stations, offices, common areas and commercial space requirements, Laboratories, Data Room requirements, etc.
- .4 Site Analysis aspects to be included (but not limited to) are a review and analysis of:
  - .1 Site features and restrictions (i.e. landscape features, topographical feature, climatic influences, setback requirements, easements, existing buildings, and / or structures.);
  - .2 Subsurface, geotechnical analysis of soils;
  - .3 Municipal infrastructure, subsurface and above grade services, including capacities and limitations (i.e. storm water drainage, fire protection, domestic water, power, telecommunications,);
  - .4 Historical/archaeological features, previous uses;
  - .5 Environmental features including sustainable design opportunities.
- .5 Building Analysis aspects to be included (but not limited to) are a review and analysis of:
  - .1 Substructure, including foundations and basement(s), parking;
  - .2 Shell, including superstructure, interior structural systems, exterior enclosure, roofing;
  - .3 Interiors, including interior construction, stairs, interior finishes;





- .4 Services, including conveying (elevators, escalators), plumbing, HVAC, fire protection, electrical, telecommunications, building automation;
- .5 Equipment and furnishings;
- .6 Special construction and demolition, materials abatement.
- .6 Budget, Schedule, and Risk Analysis aspects to be included (but not limited to) are:
  - .1 Updated Class 'D' estimate and revised schedule;
  - .2 Analysis of risk implications and preliminary mitigation strategies.
- .7 Sustainable Development Strategies
  - .1 Proposed policy for the project to minimize environmental impacts consistent with the project objectives and economic constraints, including:
    - .1 Recommendations on Sustainable Development Design standards to be applied to the project;
    - .2 Achievable levels for LEED® or Green Globes certification;
    - .3 Preliminary sustainability targets for water and energy use, waste reduction etc.
  - .2 Environmental impacts and application of the Canadian Environmental Assessment (CEA) Act.

#### **2.6.4 SCHEMATIC DESIGN REPORT CONTENT**

- .1 Standard practice for the organization of technical reports requires:
  - .1 Executive Summary;
  - .2 Regulatory Analysis;
    - .1 Preliminary building code analysis,
    - .2 Preliminary zoning analysis,
    - .3 Fire and life safety strategy, and
    - .4 Preliminary standards analysis.
  - .3 Program Analysis;
    - .1 Updated Functional Program requirements,
    - .2 Preliminary horizontal and vertical zoning diagrams,
    - .3 Spatial relationship diagrams,
    - .4 Facilities services strategy,
    - .5 Basic area calculations and analyses.
  - .4 Site Analysis;
    - .1 Drawings, renderings and supporting 3D visualization illustrating the building and site,
    - .2 Site features and restrictions (i.e. landscape features, topographical features, climatic influences, setback requirements, easements, existing buildings and/or structures etc.),
    - .3 Subsurface features,
    - .4 Municipal infrastructure, subsurface and above grade services, including capacities and limitations (i.e. storm water drainage, fire protection, domestic water, power, telecommunications etc.),
    - .5 Historical site features,
    - .6 Archaeological features,
    - .7 Environmental features including sustainable design strategies (i.e. storm water management, landscaping etc.).
- .2 Building Analysis and Design Options;
  - .1 Architectural,





- .1 Prepare a site plan indicating relationships, landscape concept, building outlines, main accesses, roadways, vehicular and pedestrian traffic patterns,
- .2 Provide building plans, showing relative disposition of main accommodation areas, circulation patterns, floors, horizontal and vertical space relationships, mechanical / electrical shafts,
- .3 Include elevations, sections and typical wall details for the building envelope,
- .4 Provide perspectives and / or 3D visualization diagrams, and
- .5 Calculate the gross building area and provide a net area summary of all accommodation areas required.
- .2 Civil,
  - .1 Describe the overall impact on the site systems infrastructure,
  - .2 Verify of all site services information,
  - .3 Provide a site plan showing the existing building, proposed site services, building service connections, site drainage, roads, parking and sidewalks, and
  - .4 Include a preliminary analysis of the impact on existing systems, where contributing to existing sewer lines.
- .3 Structural / Seismic,
  - .1 Describe the potential impact on the existing building structure and include any required structural modifications and /or upgrades,
  - .2 Provide a general description of structures, including systems considered and benefits/disadvantages,
  - .3 Include design loads for all load cases, and
  - .4 Prepare concept drawings of structural systems proposed, including typical floor plans, foundations, lateral systems and explanatory sketches.
- .4 Mechanical Engineering,
  - .1 Provide narratives describing the following,
    - .1 Overview,
    - .2 Code & Standards Considerations & Concerns,
    - .3 Potential Energy Conservation Measures,
    - .4 Description of three distinct mechanical options including,
      - .1 Narratives of each option,
      - .2 Discussion of advantages and disadvantages of each,
      - .3 System schematics sufficient to describe each option,
      - .4 Preliminary energy analysis for each,
      - .5 Discussion of recommendations.
- .5 Electrical Engineering,
  - .1 Provide an electrical design synopsis, describing the electrical work in sufficient detail for assessment and acceptance by the Departmental Representative,
    - .1 Include feasibility and economic studies of proposed systems complete with cost figures and loads, and in accordance with Sustainable Development requirements.
  - .2 Prepare a site plan showing the location of electrical and telecommunication service entrances.
  - .3 Prepare floor plans indicating locations and size of,
    - .1 Major electrical equipment and distribution centres,
    - .2 Telecommunications rooms, closets and major conduits,



- .4 Provide Normal and Emergency power distribution details, including a diagram showing the distribution up to distribution centres on each floor,
- .5 Indicate typical lighting concepts for the interior and exterior environments,
- .6 Indicate typical ceiling (or floor) distribution systems for lighting, power and telecommunications, and
- .7 Provide concept descriptions of Fire alarm and Security systems.
- .3 Commissioning;
  - .1 Provide preliminary commissioning plan.
- .4 Cost Management;
- .5 Schedule Management;
- .6 Furniture / Equipment;
  - .1 Prepare a Furniture Recommendation Report based on the Functional Program and on parameters developed in conjunction with the Departmental Representative and the Client / User. Report to include an examination of the following;
    - .1 Procurement process and requirements,
    - .2 Furniture type and layout,
    - .3 Panel screen height,
    - .4 Power requirements,
    - .5 Finishes.
  - .2 Recommendations are to take into consideration current inventory of furniture and reflect the client's vision, functional requirements, proposed planning alternatives, space allocation and project budget.
  - .3 Prepare a Class 'C' cost estimate for refurbishment of existing furniture and / or the purchase of new furniture and equipment.
  - .4 Document scheduling requirements for refurbishment of existing furniture and / or the procurement of new furniture and equipment.
- .7 Budget;
  - .1 Class 'C' Estimates for each option.
- .8 Schedule;
  - .1 Milestone project schedule including allowances for reviews and approvals for each stage of the project life cycle.
- .9 Risk Analysis;
  - .1 Report on any deviations that may affect cost or schedule and recommend corrective measures.
- .10 Sustainable Development Strategies;
  - .1 Indicate how each option can meet the sustainability targets, and
  - .2 Provide energy simulations of the proposed design options, including estimated annual energy cost as predicted by using current energy cost for the appropriate area.
- .11 Response to PWGSC Quality Assurance Report ; and
- .12 Project Log tracking all approved major decisions including those affecting changes to project scope, budget and schedule.

#### **2.6.5 DESIGN DEVELOPMENT REPORT CONTENT**

- .1 Executive Summary
- .2 Regulatory Analysis
  - .1 Preliminary building code analysis;



- .2 Preliminary zoning analysis;
- .3 Fire and life safety strategy;
- .4 Preliminary standards analysis
- .3 Program Analysis
  - .1 Updated Functional Program requirements
  - .2 Preliminary horizontal and vertical zoning diagrams;
  - .3 Facilities services strategy;
  - .4 Basic area calculations and analyses;
- .4 Site Analysis
  - .1 Drawings, renderings and supporting 3D visualization illustrating the building and site,
  - .2 Site features and restrictions (i.e. landscape features, topographical features, climatic influences, setback requirements, easements, existing buildings and/or structures etc.);
  - .3 Subsurface features;
  - .4 Municipal infrastructure, subsurface and above grade services, including capacities and limitations (i.e. storm water drainage, fire protection, domestic water, power, telecommunications etc.);
  - .5 Historical site features;
  - .6 Archaeological features;
  - .7 Environmental features including sustainable design strategies (i.e. storm water management, landscaping etc.);
- .5 Building Analysis and Design Options
  - .1 Architectural
    - .1 Prepare a site plan showing the building and Infrastructure items including the following:
      - .1 Pedestrian, vehicular, security, delivery service access,
    - .2 Provide floor plans of each level (including the roof) showing all accommodation required, including all necessary circulation areas, stairs, elevators, and ancillary spaces anticipated for service use. Indicate building grids, modules, and key dimensions.
    - .3 Provide reflected ceiling plans of ceilings with special features.
    - .4 Show elevations of all exterior building facades indicating all doors and windows, accurately sized and projected from the floor plans and sections.
      - .1 Clearly indicate levels for grade, all floors, ceilings, roof and penthouse levels.
    - .5 Develop cross-sections through the building to show floor levels, room heights, inner corridor elevations, etc.
    - .6 Identify primary architectural materials proposed for the exterior and interior of the building, including choice of finishes.
    - .7 Provide plans and preliminary details for millwork, built-in furniture and lab casework.
    - .8 Provide detail sections of walls with special design features requiring illustration and explanation at this stage, such as firewalls, acoustical barriers, security partitions, isolation or separation of laboratory spaces, etc.
    - .9 Special construction and demolition, including heritage conservation and rehabilitation requirements, hazardous materials abatement,
    - .10 Provide sections and details for any spaces requiring acoustic security.
      - .1 Include STC ratings for doors, transfer ducts and other assemblies
  - .2 Civil



- .1 Further refine site plans showing site services and building service connections referenced to proposed building outlines, site access roads and sidewalks, including existing and proposed grades and drainage improvements.
- .2 Indicate locations of manholes (complete with invert elevations), valves, and fire hydrant locations.
- .3 Identify proposed pipe sizes and slopes, where applicable, and include pipe invert elevations at building foundation.
- .4 Identify, by means of Design Summary Sheets, pipe capacity and estimated flows for storm and sanitary sewers. Where contributing to an existing sewer, include analysis of impact on existing systems.
- .5 Provide Hydraulic Analysis of any relevant alterations to existing water distribution system in the vicinity of the proposed building to confirm anticipated maximum available fire flow. Calculate and compare site flows to building site fire flow.
- .6 Provide typical trench and related details, including profiles of below grade services.
- .3 Structural
  - .1 Provide drawings indicating modifications to existing structure and new structural systems, structural materials, cladding details, fireproofing methods and other significant or unusual details.
  - .2 Indicate all design loads, e.g. dead and live loads on all plans with atypical loads marked. Live loads to include localized seismic, wind and snow.
  - .3 Provide brief design calculations including outputs from computerized analysis.
- .4 Mechanical
  - .1 Provide narratives describing the following
    - .1 Overview
    - .2 Code & Standards Analysis
    - .3 Site Services & Utilities
    - .4 Fire Protection Systems
    - .5 Plumbing Systems
    - .6 Heating Systems
    - .7 Cooling Systems
    - .8 Ventilation Systems
    - .9 Exhaust Systems
    - .10 Insulation
    - .11 Humidification Systems
    - .12 Acoustic and sound control measures
    - .13 Controls
    - .14 Energy Conservation Measures & Energy Analysis & Report
  - .2 Provide system schematics for heating water, chilled water, ventilation and plumbing systems.
  - .3 Provide catalogue cut sheets of representative equipment for each type of component to be used on the project.
  - .4 Provide preliminary layout drawings showing locations of all major components.
  - .5 Provide brief design calculations including outputs from computerized analysis.
- .5 Electrical
  - .1 Update the electrical design synopsis for the selected option. Provide data on the total connected load, the maximum demand and diversity factors, and the sizing of the emergency load.



- .2 Elaborate on proposed emergency power scheme and provide preliminary installation details for any emergency generator installation.
  - .3 Indicate metering locations on distribution diagram.
  - .4 Provide typical lighting, power and telecommunication system details for all workspaces.
  - .5 Include lighting design and control schemes for typical lighting arrangements.
  - .6 Elaborate on exterior lighting scheme. Provide typical fixture concepts.
  - .7 Provide a fire alarm riser diagram.
  - .8 Indicate security system major conduit requirements on floor plans.
  - .9 Provide typical security system details (conduit and boxes) that will be included on construction drawings.
  - .10 Provide brief design calculations including outputs from computerized analysis.
- .6 Sustainable Development Strategies:
- .1 Indicate how each option can meet the sustainability targets
  - .2 Provide energy simulations of the proposed design options, including estimated annual energy cost as predicted by using current energy cost for the appropriate area,
- .7 Response to PWGSC Quality Assurance Report

## **2.7 CODES, ACTS, STANDARDS, REGULATIONS**

### **2.7.1 GENERAL**

- .1 The Codes, Acts, Standards and Guidelines listed in the following articles, may apply to this project. The Consultant must identify and analyse the applicable documents in the Code Analysis.
- .2 In all cases the most stringent Code, standard and guideline shall apply.

### **2.7.2 PWGSC DOCUMENTS AVAILABLE FROM PWGSC PROJECT MANAGER:**

- .1 PWGSC Fit-Up Standards: Technical Reference Manual;
- .2 Public Works and Government Services MD Standards – Departmental Representative to provide on request;
  - .1 MD 15000; Environmental Standards for Office Accommodation,
  - .2 MD 15116-2006; Computer Room Air conditioning Systems,
  - .3 MD-15126; Laboratory HVAC (currently in draft form),
  - .4 MD 15128; Laboratory Fume Hoods: Guidelines for owners, design professionals and maintenance personnel – 2008,
  - .5 MD 15129; Guidelines for Perchloric Acid fumehoods and their exhaust systems – 2006,
  - .6 MD 15161; Control of Legionella in Mechanical Systems - 2006,
  - .7 MD 250005; Energy Monitoring and Control Systems Design Guidelines - 2009,
- .3 PWGSC Best Practice; Prescribing indoor humidity levels for Federal Buildings - 2006,
- .4 Public Works and Government Services Commissioning Standards and Guidelines,
- .5 PWGSC Commissioning Manual CP-I version 2006.

### **2.7.3 CODES AND REGULATIONS:**

- .1 The NRC National Building Code of Canada 2010;
- .2 The NRC National Fire Code of Canada, 2010;
- .3 The NRC National Plumbing Code of Canada 2010;
- .4 The NRC Model National Energy Code for Buildings 2011;
- .5 CSA C22.1-09, Canadian Electrical Code Part I Safety Standard for Electrical Installations and CE Code Handbook. Amendments for Provinces;



- .6 Canadian Code for Preferred Packaging;
- .7 National Electrical Manufacturers Association (NEMA);
- .8 Electrical and Electronic Manufacturers' Association of Canada (EEMAC);
- .9 American National Standards Institute/Institute of Electrical and Electronics Engineers (ANSI/IEEE) - ANSI/IEEE C62.41-1991, Surge Voltages in Low-Voltage AC Power Circuits;
- .10 American Society for Testing and Materials (ASTM);
- .11 ASTM F 1137-00(2006), Specification for Phosphate/Oil and Phosphate/Organic Corrosion Protective Coatings for Fasteners;
- .12 The Canada Labour Code;
- .13 <http://laws.justice.gc.ca/en/L-2/>
- .14 The Canada Occupational Health and Safety Regulations;
- .15 <http://laws.justice.gc.ca/eng/SOR-86-304/index.html>
- .16 All other Territorial and Municipal Acts, Codes, By-laws and regulations appropriate to the area of concern.

#### **2.7.4 STANDARDS AND GUIDELINES PRODUCED BY THE GOVERNMENT OF CANADA:**

- .1 Standards and Directives of the Treasury Board (TB):
  - .1 <http://www.tbs-sct.gc.ca/pol/index-eng.aspx?tree=standard>
  - .2 <http://www.tbs-sct.gc.ca/pol/index-eng.aspx?tree=directive>
  - .3 And including;
    - .1 Accessibility Standard for Real Property,
      - .1 <http://www.tbs-sct.gc.ca/pol/doc-eng.aspx?id=12044>
    - .2 Fire Protection Standard.
      - .1 <http://www.tbs-sct.gc.ca/pol/doc-eng.aspx?id=17316>
- .2 Labour Canada's, Fire Commissioner of Canada Standards;
  - .1 [http://www.hrsdc.gc.ca/eng/labour/fire\\_protection/policies\\_standards/commissioner/index.shtml](http://www.hrsdc.gc.ca/eng/labour/fire_protection/policies_standards/commissioner/index.shtml).
  - .2 And including,
    - .1 FC-301 Standard for Construction Operations, June 1982,
    - .2 FC-302 Standard for Welding and Cutting, June 1982,
    - .3 FC-311 Standard for Record Storage, May 1979.
    - .4 FC-403 Fire Protection Standard for sprinkler Systems, November 1994
- .3 The Standards and Guidelines for the Conservation of Historic Places in Canada
  - .1 [www.historicplaces.ca](http://www.historicplaces.ca);
- .4 Labour Canada's, Technical Documents;
  - .1 [http://www.hrsdc.gc.ca/eng/labour/fire\\_protection/policies\\_standards/guidelines/index.shtml](http://www.hrsdc.gc.ca/eng/labour/fire_protection/policies_standards/guidelines/index.shtml)
  - .2 And Including,
    - .1 Fire Protection for Information Technology Facilities and Equipment.
- .5 Canadian Food Inspection Agency's Containment Standard for Facilities Handling Plant Pests.
- .6 Public Health Agency of Canada's Laboratory Biosafety Guidelines, 3<sup>rd</sup> Edition,
- .7 Canadian Council of Animal Care's Guidelines on: Laboratory Animal Facilities – Characteristics, Design and Development.

#### **2.7.5 HEALTH CANADA STANDARDS AND GUIDELINES:**

- .1 Guidelines for Canadian Drinking Water Quality – Sixth Edition – 1996;
- .2 Guidelines for Canadian Drinking Water Quality – Summary Table – Dec 2010;



- .3 Guidance for Providing Safe Drinking Water in Areas Of Federal Jurisdiction – Version I – 2005;
- .4 The Canadian Council of Ministers of the Environment (CCME) ;
- .5 Environmental Code of Practice for Aboveground and Underground Storage Tank Systems Containing Petroleum and Allied Petroleum Products (CCME, 2003);
- .6 Canada – Wide Strategy for the Management of municipal Waste Water Effluent;
- .7 The Canadian Environmental Protection Act (CEPA, 1999);
- .8 The Storage Tank Systems for Petroleum Products and Allied Petroleum Products Regulations, published in Canada Gazette Part II on June 12, 2008 (Registration SOR/2008-197).

#### **2.7.6 STANDARDS AND GUIDELINES:**

- .1 Air Conditioning and Refrigeration Institute (ARI);
- .2 American Conference of Governmental Industrial Hygienists (ACGIH, Industrial Ventilation Handbook);
- .3 Air Diffusion Council (ADC);
- .4 Air Movement and Control Association (AMCA);
- .5 American Association of State Highway and Transportation Officials (AASHTO) Standards
- .6 American National Standards Institute (ANSI);
- .7 ANSI/AIHA Z9.5, Laboratory Ventilation;
- .8 .1 ANSI/NEMA C82.1-04, Electric Lamp Ballasts-Line Frequency Fluorescent Lamp Ballast;
- .9 .2 ANSI/NEMA C82.4-02, Ballasts for High-Intensity-Discharge and Low-Pressure Sodium Lamps;
- .10 ANSI/TIA/EIA-606- Administration Standard for the Telecommunications Infrastructure of Commercial Buildings;
- .11 ANSI Z358.1, Emergency Eyewash and Shower Equipment;
- .12 American Society of Heating, Refrigerating, and Air Conditioning Engineers (ASHRAE), including but not limited to;
  - .1 ASHRAE Laboratory Design Guide,
  - .2 ASHRAE Standards and Guidelines,
  - .3 ASHRAE Applications Handbook – 2007,
  - .4 ASHRAE HVAC Systems and Equipment Handbook – 2008,
  - .5 ASHRAE Fundamentals Handbook – 2009,
  - .6 ASHRAE Refrigeration Handbook – 2010,
  - .7 ASHRAE 52.2 Method of Testing General Ventilation Air-Cleaning Devices for Removal Efficiency by Particle Size – 2007,
  - .8 ANSI/ASHRAE 55, Thermal Environmental Conditions for Human Occupancy – 2004,
  - .9 ANSI/ASHRAE 62.1, Ventilation for Acceptable Indoor Air Quality – 2010,
  - .10 ASHRAE 90.1, Energy Efficient Design of New Buildings – 2010,
  - .11 ASHRAE 105: Standard Method of Measuring and Expressing Building Energy Performance,
  - .12 ASHRAE 110, Method of Testing Performance of Laboratory Fume Hoods,
  - .13 ASHRAE 111; Practices for Measurement, Testing, Adjusting and Balancing of Building HVAC&R Systems,
  - .14 ASHRAE 114; Energy Management Control Systems Instrumentation, and
  - .15 ASHRAE 135; BACnet: A Data Communication Protocol for Building Automation and Control Networks.
- .13 Asphalt Institute Standards for Hot Mix;





- .14 American Society of Mechanical Engineers (ASME);
- .15 American Society for Testing and Materials (ASTM);
- .16 American Water Works Association (AWWA) Standards;
- .17 American Welding Society (AWS);
- .18 Associated Air Balance Council (AABC);
- .19 Canadian Standards Association;
- .20 CSA A23.3-04 (2010) Design of Concrete Structures;
- .21 CSA B51-09 Boiler, pressure vessel and pressure piping Code;
- .22 CSA B52-05 Mechanical Refrigeration Code;
- .23 CSA B64-01 Backflow Preventers and Vacuum Breakers;
- .24 CSA B139-09 Installation Code for Oil Burning Equipment;
- .25 CSA B149.1-10 Natural Gas and Propane Installation Code;
- .26 CSA B651-04 Accessible Design for the Built Environment;
- .27 CSA C22.2 No. 41-07 Grounding and Bonding Equipment;
- .28 CSA S16-09 Design of Steel Structures;
- .29 CSA Z204-1994 Guideline for Managing Indoor Air Quality in Office Buildings;
- .30 CSA Z320-11 Building Commissioning Standard & Check Sheets;
- .31 CSA Z316.5-94, Fume Hoods and Associated Exhaust Systems;
- .32 CAN/CSA-23.1-04 and CAN/CSA-A23.2-04 Concrete materials and methods of concrete construction; and Methods of test and standard practice for concrete CAN/CSA-C22.2 No. 214-94 "Communications Cables";
- .33 CAN/CSA-C22.3 No.3-[98(R2007)], Electrical Co-ordination;
- .34 CAN/CSA-B651-04(R2010), Accessible Design for the Built Environment;
- .35 CAN3 C235-[83(R2010)], Preferred Voltage Levels for AC Systems, 0 to 50,000 V;
- .36 CAN/CSA-T528-93, "Design Guidelines for Administration of Telecommunications Infrastructure in Commercial Buildings", Canadian Standards Association;
- .37 CAN/ULC – S524-06 Standard for the Installation of Fire Alarm Systems;
- .38 CAN/ULC – S537-04 Fire Alarm System Verification Report;
- .39 CAN/ULC – S102-07 Standard Method of Test for Surface Burning Characteristics of Building Materials and Assemblies;
- .40 CAN/ULC – S102.2-07 Method of Test for Surface Burning Characteristics of Flooring, Floor Coverings, and Miscellaneous Materials and Assemblies  
CAN/ULC S112-M90 (R2001) Standard Methods of Fire Test of Fire-Damper Assemblies;
- .41 CAN/ULC S115-05 Standard Method of Fire Tests of Fire stop Systems;
- .42 International Mechanical Code – Latest Version;
- .43 Institute of Boiler and Radiation, Hydronic Institute (IBR);
- .44 Manufacturers Standardization Society of Valve and Fitting Industry (MSS);
- .45 National Fire Protection Association (NFPA), including;
  - .1 NFPA 10; Standard for Portable Fire Extinguishers – 2010,
  - .2 NFPA 13; Standard for Installation of Sprinkler Systems – 2010,
  - .3 NFPA 14; Standard for Installation of Standpipe and Hose Systems – 2010,
  - .4 NFPA 24: Standard for the Installation of Private Fire Service Mains and Their Appurtenances-2010,
  - .5 NFPA 30; Flammable and Combustible Liquids Code,
  - .6 NFPA 45; Standard on Fire Protection for Laboratories Using Chemicals,
  - .7 NFPA 1142: Standard on Water Supplies for Suburban and Rural Fire Fighting-2007.





- .46 SEFA I.2, Scientific Equipment & Furniture Association;
- .47 Sheet Metal and Air Conditioning Contractors National Association (SMACNA);
- .48 Transportation Association of Canada (TAC) Guide for Canadian Roads;
- .49 Manual of Uniform Traffic Control Devices (MUTCD);
- .50 Telecommunications Industry Association (TIA);
  - .1 Commercial Building Telecommunications Cabling Standard TIA/EIA-568,
    - .1 Part 1: General Requirements, TIA/EIA-568-B.1,
    - .2 Part 2: Balanced Twisted Pair Cabling Components, TIA/EIA-568-B.2,
    - .3 Addendum 1 - Transmission Performance Specification for 4-pair 100 Ohm Category 6 Cabling, TIA/EIA-568-B.2-1,
    - .4 Optical Fibre Cabling Components Standards, TIA/EIA-568-B.3.
  - .2 ANSI/TIA/EIA-569-A Commercial Building Standards for Telecommunications pathways and spaces,
  - .3 Pathways and Spaces, ANSI/TIA/EIA-569-B,
  - .4 Telecommunications Infrastructure Standard for Data centers TIA-942,
  - .5 J-STD-607-A Commercial Building Grounding and - Bonding Requirements for Telecommunications.
- .51 Underwriters' Laboratories of Canada (ULC);
- .52 ULC/CSA Approval is required for all electrical and mechanical equipment.

#### **2.7.7 STANDARDS AND GUIDELINES FOR TRANSPORTATION**

- .1 Canadian Highway Bridge Design Code
- .2 Transportation Association of Canada - Manuals, Guides and Handbooks.

### **2.8 COMMISSIONING PROCESS**

#### **2.8.1 GENERAL**

- .1 This section summarizes the PWGSC commissioning process, the requirements and associated roles and responsibilities as they relate to the various phases in the delivery of a project.
- .2 It is to be used as a guide in further developing the commissioning plan, specification and related documents for a project.
- .3 Commissioning is not a replacement for good design and construction practices.
  - .1 It requires coordinated efforts on the part of all parties involved in the Project.
- .4 The Commissioning overlaps the design phase through construction and into the operation phase.
- .5 The PWGSC Commissioning Manual CP.1 4<sup>th</sup> edition, November 2006, is available for free download at the following site:
  - .1 <http://www.tpsgc-pwgsc.gc.ca/biens-property/sngp-npms/bi-rp/tech/miseenservice-commissioning/manuel-manual-eng.html>
- .6 The PWGSC Commission Manual CP.2 – Commissioning Glossary is available for free download at the following site:
  - .1 <http://www.tpsgc-pwgsc.gc.ca/biens-property/sngp-npms/bi-rp/tech/miseenservice-commissioning/manuel-manual-b-eng.html>
- .7 “Commissioning” is a quality assurance process, in which the functional requirements of the Owner/occupant and the operational requirements of facility management are proven to function as intended.



- .8 The “commissioning process” is a planned program of quality management and information transfer that extends through all phases of a project’s development and delivery, up to and including the warranty period.
- .9 The process consists of a series of checks and balances to ensure that the work is designed, installed and proven to operate as intended.
- .10 Commissioning has two main components, functional and operational.
  - .1 The functional component deals with:
    - .1 Security, Health (indoor air quality) and occupant safety;
    - .2 Comfort (temperature, relative humidity, ventilation, air flow patterns, air purity and well being);
    - .3 Cost-effectiveness of design; and
    - .4 Systems and equipment supporting Owner’s functional requirements.
  - .2 The operational component deals with:
    - .1 Operation and Maintenance (O&M) issues; e.g., design review with a particular concern for the operation and maintenance of the systems today and in the future, when repairs are required;
    - .2 Performance evaluation of systems and equipment;
    - .3 Accessibility to O&M Documentation; and
    - .4 Review of the training plan against the current needs now and in the future.

## 2.8.2 COMMISSIONING PLAN

- .1 The Commissioning Plan will typically be developed by the Contractor through his own Commissioning Agent.
- .2 The Commissioning Plan is the project-specific document and which describes the process for verifying that all built works meet the Investor's requirements within the limits of the working documents.
- .3 It is essential that the Consultant provide specifications that detail requirements for all submittals and testing in each Specification Section in order for the Contractor to properly prepare a complete Commissioning Plan.
- .4 The Commissioning Plan will be reviewed and accepted by the Departmental Representative prior to commencement of construction.
- .5 The Commissioning Plan may require periodic update throughout design.

## 2.8.3 COMPONENT VERIFICATION

- .1 Component verification sheets (CV) sheets are developed by the Consultant and incorporated in the contract documents to ensure the facility is an operating entity and meets the requirements as described in the Agreement.
- .2 The CV sheets are intended to monitor and track the supply and shop drawing requirements associated with each component. The *Consultant* must verify that the components being installed in the built works are acceptable to their design and the approved shop drawings.
- .3 The commissioning process requires the documentation of all the components installed as part of a system that will have performance verification testing conducted.
- .4 Sample CV sheets for various types of components are to be provided by the Consultant in Div 01.

## 2.8.4 SYSTEM & INTEGRATED SYSTEM TESTING

- .1 The “performance verification tests” (PVTs) are developed by the Design-Builder to ensure the facility is an operating entity and meets the requirements as described in the Agreement.



- .2 The PVTs are intended to demonstrate the functional performance of the systems & integrated system during the various modes of operation, against the design intent. Each test must be uniquely identified and reflected in the contractor's commissioning schedule.
- .3 Once the contract has been awarded the Design-Builder must monitor the sub-contractor's process to help ensure the timely completion of these tests. The Design-Builder must witness each test. The Design-Builder must provide final certification of the test results. After an acceptable review of the test document, the PWGSC Commissioning Specialist will recommend to the Departmental Representative the acceptance or rejection of the test results.
- .4 Sample PVT sheets for various types of system are to be provided by the Consultant in Div 01.

### 2.8.5 TEST REQUIREMENTS

- .1 Each CV or PVT shall be uniquely named, numbered and categorized by discipline.
- .2 Tests shall define:
  - .1 Test Purpose;
  - .2 System design narrative;
  - .3 Test Prerequisites;
  - .4 Testing Procedures;
  - .5 Test Comments; and
  - .6 Test Sign-off Block.
- .3 System Performance Verifications Tests
  - .1 These tests have prerequisites that are to be completed and approved prior to conducting the tests, which, may include but are not limited to:
    - .1 CV and PVT sheets developed and accepted,
    - .2 Contractor proving start-up and tests,
    - .3 Manufacturers start-ups,
    - .4 Consultant has certified testing, adjusting & balancing (TAB) results, per TAB specification.
      - .1 TAB work must be completed and approved prior to the control system Pts.
    - .5 Associated control device calibrations and physical point verifications are completed and approved.
      - .1 Note, control system end to end checks to be completed and approved prior to the control system PVTs.
    - .6 Other specified deliverables, i.e. factory test reports, O&M submissions, etc.
    - .7 System performance tests associated with the integrated systems under test,
    - .8 Integrated System Performance Verifications,
    - .9 Fire alarm verifications.

### 2.8.6 COMMISSIONING (EVALUATION) REPORT

- .1 The Commissioning (Evaluation) Report must provide:
  - .1 An executive summary,
  - .2 Completed CV and PVT sheets,
  - .3 A complete assessment of the project,
  - .4 Lessons learned from this project and any necessary recommendations,
  - .5 Variances between the actual and planned levels of performance,
  - .6 An evaluation of the validation and acceptance process and of the commissioning phase.

### 2.8.7 OVERVIEW OF ROLES AND RESPONSIBILITIES



- .1 The following provides a general overview of the roles, responsibilities and implementation of the commissioning process. The commissioning process is a logical sequence of verifications from component verifications through to system & integrated system, performance verification testing.
- .2 At completion of the commissioning process all results are documented and audited for acceptance.

## **2.8.8 MAJOR TASKS AND RESPONSIBILITIES**

- .1 Schematic Design and Design Development Phase:
  - .1 Consultant;
    - .1 Develop commissioning strategy,
    - .2 Develop preliminary commissioning plan.
  - .2 Construction Documentation Phase:
    - .1 Consultant;
      - .1 Complete the final commissioning plan,
      - .2 Specify the Commissioning requirements in Div 01 and provide sample Commissioning CV and PCT sheets in Div 01 for Bidders purposes,
      - .3 Develop project specific CV and PVT sheets.
  - .3 Construction Phase:
    - .1 Consultant;
      - .1 Monitor and report on contract commissioning activities,
      - .2 Finalize development of job specific CV and PVT sheets,
      - .3 Review and certify component verification sheets as they are completed by the Contractor, and
      - .4 Review commissioning schedule
    - .2 Contractor;
      - .1 Comply with the requirements in the Specifications,
      - .2 Complete the component verification,
      - .3 Conduct the equipment system start-up and proving, and
      - .4 Develop the commissioning schedule, reflecting the PVTs.
  - .4 Commissioning Phase
    - .1 Consultant
      - .1 Witness all system and integrated systems tests,
      - .2 Review and certify commissioning test results,
      - .3 Track and compile all commissioning documentation submitted by the contractor and confirm that all commissioning tasks are completed,
      - .4 Incorporate all commissioning documentation into a preliminary commissioning report and recommend interim acceptance.
      - .5 Identify “deferred” commissioning tests due to seasonal constraints, etc.
    - .2 Contractor
      - .1 Comply with the requirements in the specifications,
      - .2 Conduct the system testing, and
      - .3 Conduct the integrated system testing.
  - .5 Operating Phase
    - .1 Consultant
      - .1 Provide advice and recommendations for fine tuning, if required,
      - .2 Witness “deferred” commissioning tests,



- .3 Review and certify “deferred” systems test results,
- .4 Incorporate deferred system test results and all other commissioning documentation into a final commissioning report with an executive summary recommending final acceptance.
- .2 Contractor
  - .1 Address warranty issues,
- .6 Evaluation Phase
  - .1 Consultant
    - .1 Provide advice and recommendations during the final evaluation.

## **2.9 CONSTRUCTION DOCUMENTS**

### **2.9.1 PURPOSE**

- .1 This section provides direction in the preparation of construction contract documents (namely specifications, drawings and addenda) for PWGSC.
- .2 Drawings, specifications and addenda must be complete and clear, in order that a contractor can prepare a bid without guesswork. Standard practice for the preparation of construction contract documents requires that:
  - .1 Drawings are the graphic means of showing work to be done, as they depict shape, dimension, location, quantity of materials and relationship between building components.
  - .2 Specifications are written descriptions of materials and construction processes in relation to quality, colour, pattern, performance and characteristics of materials, installation and quality of work requirements.
  - .3 Addenda are changes to the construction contract documents or tendering procedures, issued during the tendering process.

### **2.9.2 PRINCIPLES FOR PWGSC CONTRACT DOCUMENTS**

- .1 PWGSC’s contract documents are based on common public procurement principles.
- .2 PWGSC does not use Canadian Construction Document Committee (CCDC) documents.
- .3 The construction contract and the terms and conditions are prepared and issued by PWGSC, along with all other related bidding and contractual documents.
  - .1 For more detailed information, the clauses are available on the following web site:
  - .2 <http://ccua-sacc.tpsgc-pwgsc.gc.ca/pub/acho-eng.jsp>
  - .3 Any questions should be directed through the PWGSC Project Manager.

### **2.9.3 QUALITY ASSURANCE**

- .1 Consultants are required to undertake their own quality control process and must review, correct and coordinate (between disciplines) their documents before issuing them to PWGSC.

### **2.9.4 ADDENDA**

- .1 Format
  - .1 Prepare addenda using the format shown in Appendix ‘C’.
  - .2 No signature type information is to appear.
  - .3 Every page of the addendum (including attachments) must be numbered consecutively.
  - .4 All pages must have the PWGSC project number and the appropriate addendum number.
  - .5 Sketches shall appear in the PWGSC format, stamped and signed.
  - .6 No Consultant information (name, address, phone #, consultant project # etc.) may appear in the addendum or its attachments (except on sketches).
- .2 Content



- .1 Each item should refer to an existing paragraph of the specification or note/detail on the drawings. The clarification style is not acceptable.

## **2.9.5 SUBMISSIONS**

- .1 For each construction document submission, the Consultant shall provide:
  - .1 A completed and signed Checklist for the Submission of Construction Documents (See Appendix 'B')
  - .2 Original specification; printed one side on 216 mm x 280 mm white bond paper.
  - .3 Index, as per Appendix 'C'
  - .4 Reproducible original drawings; sealed and signed by the design authority.
  - .5 Addenda (if required), as per Appendix 'D;' (to be issued by PWGSC)
- .2 Tender information:
  - .1 Include a description of all units and estimated quantities to be included in unit price table.
  - .2 Include a list of significant trades including costs.
    - .1 PWGSC will then determine which trades, if any, will be tendered through the Bid Depository.
- .3 Government Electronic Tendering System (MERX):
  - .1 Consultants shall provide an electronic true copy of the final documents (specifications and drawings) on one or multiple CD-ROM in Portable Document Format (PDF) without password protection and printing restrictions.
  - .2 The electronic copy of drawings and specifications is for bidding purposes only and do not require to be signed and sealed.

## **2.9.6 PWGSC ROLE**

- .1 PWGSC shall provide:
  - .1 General and Special Instructions to Bidders
  - .2 Bid and Acceptance Form
  - .3 Standard Construction Contract Documents

## **2.10 SPECIFICATIONS**

### **2.10.1 GENERAL**

- .1 In preparing project specifications, the Consultant must use the current edition of the National Master Specification (NMS) in accordance with the "NMS User's Guide".

### **2.10.2 NATIONAL MASTER SPECIFICATION (NMS)**

- .1 In preparing project specifications, the Consultant must use the current edition of the National Master Specification (NMS) in accordance with the "NMS User's Guide".
- .2 The NMS is a master construction specification available in both official languages, which is divided into 48 Divisions (Masterformat 2004) and is used for a wide range of construction and/or renovation projects.
- .3 The Consultant retains overriding responsibility for content and shall edit, amend and supplement the NMS as deemed necessary to produce an appropriate project specification, free of conflict and ambiguity.

### **2.10.3 SPECIFICATION ORGANIZATION**

- .1 Narrow scope sections describing single units of work are preferred for more complex work; however, broad scope sections may be more suitable for less complex work.
- .2 Use either the NMS 1/3 - 2/3 page format or the Construction Specifications Canada full-page format.



- .3 For specifications not included in the NMS, but required for the project, follow the number and title recommendations of Masterformat 2004
- .4 Number each page and start each Section on a new page
- .5 Bind specifications
- .6 Include Division I, edited to PWGSC requirements.
- .7 Note: Consultant's name is not to be indicated in the specifications..

#### **2.10.4 TERMINOLOGY**

- .1 Use the term "Departmental Representative" instead of Engineer, PWGSC, Owner, Consultant or Architect.
- .2 "Departmental Representative" means the person designated in the Contract, or by written notice to the Contractor, to act as the Departmental Representative for the purposes of the Contract, and includes a person, designated and authorized in writing by the Departmental Representative to the Contractor.
- .3 Notations such as: "verify on site", "as instructed", "to match existing", "example", "equal to" or "equivalent to", "to be determined on site by "Departmental Representative", should not be indicated in the specifications as this promotes inaccurate and inflated bids.
- .4 Specifications must permit bidders to calculate all quantities and bid accurately.
  - .1 If quantities are impossible to identify (i.e. cracks to be repaired) give an estimated quantity for bid purposes (unit prices).
- .5 Ensure that the terminology used throughout the specifications is consistent and does not contradict the applicable standard construction contract documents.

#### **2.10.5 DIMENSIONS**

- .1 Dimensions are to be in metric only (no dual dimensioning).

#### **2.10.6 STANDARDS**

- .1 As references in the NMS may not be up to date, it is the responsibility of the consultant to ensure that the project specification uses the latest applicable edition of all references quoted.
- .2 Canadian standards should be used wherever possible.

#### **2.10.7 SPECIFYING MATERIALS**

- .1 The practice of specifying actual brand names, model numbers, etc., is against departmental policy except for special circumstances.
- .2 The method of specifying materials shall be by using industry recognized standards.
- .3 If the above method cannot be used and where no standards exist, specify by a non-restrictive, non-trade name "prescription" or "performance" specifications.
- .4 In exceptional or justifiable circumstances, or if no standards exist and when a suitable non-restrictive, non-trade name "prescription" or "performance" specification cannot be developed; specify by trade name
- .5 Include all known materials acceptable for the purpose intended, and in the case of equipment, identify by type and model number.

#### **2.10.8 ACCEPTABLE PRODUCTS AND MATERIALS**

- .1 The term "Acceptable Manufacturers" must not be used, as this restricts competition and does not ensure the actual material or product will be acceptable.
  - .1 A list of words and phrases that should be avoided is included in the NMS User's Guide.
- .2 Listing of acceptable products or materials is to be an exception, due to a unique specification or for the purpose of assisting bidders in identifying lesser known potential products or materials.





- .3 For exceptions, provide justifiable reasons for listing products and materials and submit to the *Departmental Representative* for acceptance.
- .4 When authorized to list acceptable products or materials, list all, with a minimum of three (3), trade names of products and materials acceptable for the intended purpose.

#### **2.10.9 ALTERNATE PRODUCTS AND MATERIALS**

- .1 Alternates must be approved by addendum issued by the *Departmental Representative* in accordance with Instructions to bidders.
- .2 Review applications for approval of alternate products and materials and provide recommendations to the *Departmental Representative*.
- .3 Compare products/materials to specifications. Do not compare product-to-product or material-to-material.

#### **2.10.10 SEPARATE AND ALTERNATE PRICES**

- .1 Do not include Separate or Alternate Pricing .

#### **2.10.11 SOLE SOURCING**

- .1 Sole sourcing for materials and work may be used for proprietary systems (i.e. fire alarm systems, EMCS systems).
- .2 Substantiation and/or justification will be required.
- .3 Prior to including sole source materials and/or work, the Consultant must contact the *Departmental Representative* to obtain the approval for the sole sourcing.

#### **2.10.12 UNIT PRICES**

- .1 Unit prices are used where the quantity can only be estimated (e.g. earth work) and the approval of the Project Manager must be sought in advance of their use.

#### **2.10.13 CASH ALLOWANCES**

- .1 Construction contract documents should be complete and contain all of the requirements for the contractual work.
- .2 Cash allowances are to be used only under exceptional circumstances (i.e. utility companies, municipalities), where no other method of specifying is appropriate.
- .3 Obtain approval from the Project Manager in advance to include cash allowances and then use "Section 01 21 00 - Allowances" of the NMS to specify the criteria.

#### **2.10.14 WARRANTIES**

- .1 It is the practice of PWGSC to have a 12-month warranty and to avoid extending warranties for more than 24 months.
- .2 When it is deemed necessary to extend a warranty beyond the 12 month period provided for in the General Conditions of the contract, obtain approval from the Project Manager.
- .3 Delete all references to manufacturers' guarantees.

#### **2.10.15 SCOPE OF WORK**

- .1 No paragraphs noted as "Scope of Work" are to be included.

#### **2.10.16 SUMMARY AND SECTION INCLUDES**

- .1 In Part - I All Sections; do not use (delete):
  - .1 "Summary" and
  - .2 "Section Includes."

#### **2.10.17 RELATED SECTIONS**

- .1 In Part I All Sections; do not use (delete)

#### **2.10.18 INDEX**





- .1 List all the plans and specification sections with correct number of pages, section names and correct drawing titles in the format shown in Appendix C.

#### **2.10.19 HEALTH AND SAFETY**

- .1 Confirm with the Project Manager to determine if there are any instructions to meet regional requirements.

#### **2.10.20 EXPERIENCE AND QUALIFICATIONS**

- .1 Remove experience and qualification requirements from specification sections.

#### **2.10.21 PREQUALIFICATION**

- .1 Do not include in the specification any mandatory contractor and/or subcontractor prequalification requirements that could become a contract award condition.
- .2 If a prequalification process is required, contact the Project Manager.
- .3 There should be no references to certificates, transcripts or license numbers of a trade or subcontractor being included with the bid.

#### **2.10.22 CONTRACTING ISSUES**

- .1 Specifications describe the workmanship and quality of the work.
  - .1 Contracting issues should not appear in the specifications.
- .2 Division 00 of the NMS is not used for PWGSC projects.
- .3 Remove all references within the specifications, to the following:
  - .1 General Instructions to Bidders
  - .2 General Conditions
  - .3 CCDC documents
  - .4 Health and Safety requirements
  - .5 Priority of documents
  - .6 Security clauses
  - .7 Terms of payment or holdback
  - .8 Tendering process
  - .9 Bonding requirements
  - .10 Insurance requirements
  - .11 Alternative and separate pricing
  - .12 Site visit (Mandatory or Optional)
  - .13 Release of Lien and deficiency holdbacks

### **2.11 DRAWINGS**

#### **2.11.1 GENERAL**

- .1 Drawings shall be in accordance with PWGSC Western CADD Standards and CSA B78.3.
- .2 Refer to:
  - .1 <http://www.tpsgc-pwgsc.gc.ca/cdao-cadd/ouest-western/tdm-toc-eng.html>
  - .2 The above link is subject to change
  - .3 The Consultant shall check with the Project Manager to ensure that the link is current.
- .3 Download and use the Toolkit which includes drawing border templates, layer utility and drawing standards checker.

#### **2.11.2 TITLE BLOCKS**

- .1 Use PWGSC title block for drawings and sketches (including addenda).

#### **2.11.3 DIMENSIONS**

- .1 Dimensions are to be in metric only (no dual dimensioning).

#### **2.11.4 TRADE NAMES**



- .1 Trade names on drawings are not acceptable.
- .2 Refer to SECTION 2.3, SPECIFICATIONS; 2.3.6 Specifying Materials for specifying materials by trade name.

#### 2.11.5 SPECIFICATION NOTES

- .1 No specification type notes are to appear on any drawing.

#### 2.11.6 TERMINOLOGY

- .1 Use the term "Departmental Representative" instead of Engineer, PWGSC, Owner, Consultant or Architect.
- .2 "Departmental Representative" means the person designated in the Contract, or by written notice to the Contractor, to act as the Departmental Representative for the purposes of the Contract, and includes a person, designated and authorized in writing by the Departmental Representative to the Contractor.
- .3 Notations such as: "verify on site", "as instructed", "to match existing", "example", "equal to" or "equivalent to", "to be determined on site by "Departmental Representative", may not be indicated on the drawings or in the specifications as this promotes inaccurate and inflated bids.
- .4 Specifications & drawings must permit bidders to calculate all quantities and bid accurately.
- .5 If quantities are impossible to identify (i.e. cracks to be repaired) give an estimated quantity for bid purposes (unit prices).
- .6 Ensure that the terminology used throughout the drawings & specifications is consistent and does not contradict the applicable standard construction contract documents.

#### 2.11.7 INFORMATION TO BE INCLUDED

- .1 Drawings must show the quantity and configuration of the project, the dimensions and details of how it is constructed.
- .2 There should be no references to future work and no any information that will be changed by future addenda.
- .3 The scope of work should be clearly detailed and elements not in contract should be eliminated or kept to an absolute minimum.

#### 2.11.8 DRAWING NUMBERS

- .1 Number drawings in sets according to the type of drawing and the discipline involved as follows:
  - .1 The requirements of SECTION 2 PWGSC NATIONAL CADD STANDARD will supersede these requirements, where warranted.
- .2 During the Design Phase of the project each submission and review must be noted on the Notes block of the drawing title, but at the time of construction document preparation, all revision notes should be removed.

| Discipline      | Drawing        |
|-----------------|----------------|
| Demolition      | D1, D2, etc.   |
| Architectural   | A1, A2, etc.   |
| Civil           | C1, C2, etc.   |
| Landscaping     | L1, L2, etc.   |
| Mechanical      | M1, M2, etc.   |
| Electrical      | E1, E2, etc.   |
| Structural      | S1, S2, etc.   |
| Interior Design | ID1, ID2, etc. |

#### 2.11.9 PRINTS



- .1 Print with black lines on white paper.
- .2 Blue prints are acceptable for document submissions at stages outlined in the TOR.
- .3 Confirm with Departmental Representative the size of prints to be provided for review purposes.

#### **2.11.10 BINDING**

- .1 Staple or otherwise bind prints into sets.
- .2 Where presentations exceed 20 sheets, the drawings for each discipline may be bound separately for convenience and ease of handling.

#### **2.11.11 LEGENDS**

- .1 Provide a legend of symbols, abbreviations, references, etc., on the front sheet of each set of drawings or, in large sets of drawings, immediately after the title sheet and index sheets.

#### **2.11.12 SCHEDULES**

- .1 Where schedules occupy entire sheets, locate them next to the plan sheets or at the back of each set of drawings for convenient reference.
  - .1 See CGSB 33-GP-7 Architectural Drawing Practices for schedule arrangements.

#### **2.11.13 NORTH POINTS**

- .1 On all plans include a north point.
- .2 Orient all plans in the same direction for easy cross-referencing.
- .3 Wherever possible, lay out plans so that the north point is at the top of the sheet.

#### **2.11.14 DRAWING SYMBOLS**

- .1 Follow generally accepted drawing conventions, understandable by the construction trades, and in accordance with PWGSC publications.



## **3 PROJECT ADMINISTRATION**

### **3.1 GENERAL REQUIREMENTS FOR ALL PROJECTS**

- .1 The administration requirements outlined in this section are applicable to all PWGSC projects in Western Region, unless otherwise indicated in the TOR.
- .2 “Project Team” refers to key representatives involved in this project.
- .3 All team members must maintain a professional, cordial and collaborative relationship.

### **3.2 LANGUAGE**

- .1 Construction documents must be prepared in English.

### **3.3 MEDIA**

- .1 The Consultant shall not respond to any media inquiry.
- .2 Direct all media requests to the Departmental Representative.

### **3.4 PROJECT MANAGEMENT**

#### **3.4.1 GENERAL**

- .1 Public Works and Government Services Canada administers the project on behalf of Canada and exercises continuing control over the project during all phases of development.
- .2 This project is to be organized, managed and implemented in a collaborative manner.
- .3 The PWGSC project management team, the Consultant, the Contractor and the User Department teams are to work cooperatively at every stage of the design and construction process in order to assure the creation of a successful and meaningful work of architecture.
- .4 Under the leadership of the PWGSC Departmental Representative, all team members are responsible for establishing and maintaining a professional and cordial relationship.

#### **3.4.2 NATIONAL PROJECT MANAGEMENT SYSTEM**

- .1 PWGSC uses the National Project Management System (NPMS) for management of its building projects in order to align with the Federal Government approvals processes. Refer to the PWGSC NPMS web site for more details.
- .2 <http://www.tpsgc-pwgsc.gc.ca/biens-property/sngp-npms/index-eng.html>
- .3 This GP&S document speaks to services that are normally provided by the professional during the Project Delivery Phase of the NPMS.

#### **3.4.3 DESIGN STAGE**

- .1 Pre-design Process
  - .1 The purpose of this phase is to analyze all project requirements including codes, regulations, programming, sustainability, cost, time management and risk to demonstrate a full understanding of the project
  - .2 The approved deliverable will become the formal project work plan and will be utilized throughout the project to guide the delivery.
- .2 Schematic Design Process
  - .1 The purpose of this phase is to explore three distinctly different design options and to analyze them against the project requirements.
  - .2 The Schematic Design will be in sufficient detail to illustrate and communicate the project characteristics.
    - .1 Provide a detailed review and analysis of the project requirements including all updates and amendments to ensure all requirements are fully integrated into the Schematic Design.



- .2 Out of this process the Schematic Design will be accepted and authorization to proceed to Design Development will be based on the accepted Schematic Design.
- .3 The *Departmental Representative*, in concert with others shall choose one option to be further developed.
  - .1 Although the *Consultant* is required to identify a preferred option, the *Departmental Representative* may select another option.
  - .2 The approved deliverable will become the formal project work plan and will be utilized throughout the project to guide the delivery.

#### 3.4.4 IMPLEMENTATION STAGE

- .1 Design Development Process
  - .1 The purpose of this phase is to further develop the design option selected for refinement at the Schematic Design stage.
  - .2 The Design Development documents consist of drawings and other documents to describe the scope, quality and cost of the project in sufficient detail to facilitate design approval, confirmation of code compliance, detailed planning of construction and project approval.
  - .3 This design will be used as the basis for preparation of construction documents.
  - .4 The approved deliverable will become the formal project work plan and will be utilized throughout the project to guide the delivery.
- .2 Commissioning Process
  - .1 “Commissioning” is a quality assurance process, in which the functional requirements of the Owner/occupant and the operational requirements of facility management are tested, verified and proven to function as intended.
  - .2 Commissioning deliverables occur at various phases throughout the project as detailed in section 2.8.
  - .3 Commissioning shall be in accordance with the PWGSC Commissioning Manual CP.1 (2003).
- .3 Construction Document Process
  - .1 The purpose of this phase is to translate design development documents into construction drawings and specifications, for use by the contractor to determine a cost for the work and to construct the building.
- .4 Contract Procurement Process
  - .1 The purpose of this phase is to obtain and evaluate bids/proposals from qualified contractors to construct the project, as per the Construction Contract Documents and to award the construction contract according to government regulations.
- .5 Construction Contract Administration Process
  - .1 The purpose of this phase is to implement the project in compliance with the Construction Contract Documents and to direct and monitor all necessary or requested changes to the scope of work during construction, commissioning and closeout.

#### 3.4.5 CLOSEOUT STAGE

- .1 Post Construction Process
  - .1 The purpose of this phase is to ensure the orderly completion and recording of all aspects of the work during the construction and liaise with the Public Works And Government Services Canada and other agencies as appropriate to close out the project.

#### 3.4.6 ENGINEERING PROJECTS



- .1 Refer to the project specific TOR where the stages for an Engineering Project differs slightly.

### **3.5 LINES OF COMMUNICATION**

- .1 In general, communications will be through the Departmental Representative, unless directed otherwise.
  - .1 This includes formal contact between the Consultant, the Contractor, the PWGSC Project Team and the User Department.
- .2 Direct communication between members of the PWGSC Project Team on routine matters may be required for resolution of technical issues.
  - .1 However, this shall not alter project scope, budget or schedules, unless confirmed in writing by the Departmental Representative.
- .3 During construction tender call, PWGSC will conduct all correspondence with bidders and award the contract.

### **3.6 MEETINGS**

- .1 The Departmental Representative will arrange meetings throughout the project, with representatives from:
  - .1 The User Department;
  - .2 PWGSC
  - .3 The Consultant team; and
  - .4 The Contractor (during the construction phase)
- .2 Standing agenda items shall include:
  - .1 Project Schedule,
  - .2 Cost,
  - .3 Risk,
  - .4 Quality,
  - .5 Health and safety

### **3.7 CONSULTANT RESPONSIBILITIES**

- .1 The “Consultant Team” includes the Consultant’s staff, sub-consultants and specialists.
  - .1 This team must maintain its expertise for the duration of the project.
  - .2 The team must include qualified registered architectural and engineering professionals, with extensive relevant experience, capable of providing all required services.
  - .3 Team members may be qualified to provide services in more than one discipline.
  - .4 The Consultant may expand the team to include additional disciplines.
- .2 The Consultant is responsible for:
  - .1 Obtaining Departmental Representative acceptance for each project phase before proceeding to the next phase.
  - .2 Accurately communicating design, budget, and scheduling issues to staff, sub-consultants and specialists.
  - .3 Co-ordinating input for the Departmental Representative’s Risk Management Plan
  - .4 Co-ordinating the quality assurance process and ensuring that submissions of sub-consultants are complete and signed-off by reviewers;
  - .5 During the design phases:
    - .1 Attend meetings,
    - .2 Record the issues and decisions,
    - .3 Prepare and distribute minutes within two working days of the meeting,



- .4 Ensure all meetings are green i.e. using electronic documents or double-sided hard copies and
- .5 Ensure sub-consultants attend required meetings.
- .6 During the construction phase:
  - .1 Attend meetings and provide site inspection services
  - .2 Ensure sub-consultants provide site inspection services and attend required meetings.
- .3 The Consultant is responsible for:
  - .1 Coordinating and directing the work of all team activities, sub-consultants and specialists
  - .2 Preparing a design that meets project requirements.
  - .3 Obtaining approvals on behalf of the Departmental Representative from the User and other levels of government such as provincial and municipal governments
    - .1 The Consultant shall adjust the documentation to meet the requirements of these authorities.

### 3.8 PWGSC RESPONSIBILITIES

- .1 Administration
  - .1 PWGSC administers the project and exercises continuing control over the project during all phases of development.
  - .2 The following administrative requirements apply during all phases of the project delivery.
- .2 Reviews
  - .1 PWGSC will review the work at various stages and reserves the right to reject unsatisfactory work at any stage.
  - .2 If later reviews show that earlier acceptances must be withdrawn, the Consultant shall re-design and re-submit at no extra cost.
- .3 Acceptance
  - .1 PWGSC acceptance of submissions from the Consultant simply indicates that, based on a general review, the material complies with governmental objectives and practices, and meets overall project objectives
  - .2 Acceptance does not relieve the Consultant of professional responsibility for the work and for compliance with the contract.
- .4 PWGSC Project Management
  - .1 The Project Manager assigned to the project is the Departmental Representative.
  - .2 The Departmental Representative is directly responsible for:
    - .1 The progress and administration of the project, on behalf of PWGSC
    - .2 Day-to-day project management and is the Consultant's single point of contact for project direction.
    - .3 Providing authorizations to the Consultant on various tasks throughout the project.
  - .3 Unless directed otherwise by the Departmental Representative, the Consultant obtains all Federal approvals necessary for the work.
- .5 PWGSC Professional & Technical Resources Team
  - .1 Provides professional advice and quality assurance reviews of consultant deliverables by Architectural and Engineering professional disciplines.
  - .2 Offers expert technical advice on related project issues, such as functional programming, options analysis, risk management, cost planning, scheduling, contract interpretation, specifications, terms of reference, commissioning, claims management, project delivery approach and project compliance.



- .3 Participates regularly in design phases and may attend (during construction), contractor meetings and conduct field reviews on behalf of the Departmental Representative.
- .4 Provides a Design Manager for the project, who will coordinate the services of the Professional & Technical Resources Team through the Departmental Representative;
  - .1 The Design Manager is the assembler and coordinator of the Resources Team of Architects, Engineers, Interior Designers, Project Planners, Cost Planners and Commissioning Specialists, all with specific areas of expertise.
- .6 PWGSC Commissioning Specialist represents the Departmental Representative's interests in the commissioning process for buildings by:
  - .1 Providing technical advice on O&M matters, operational criteria and quality assurance on the commissioning process throughout the project life cycle;
  - .2 Coordinating and overseeing internal PWGSC commissioning activities during all project phases to ensure that O&M concerns are addressed;
  - .3 Working closely with the Consultant, the Consultant's Commissioning Manager, the Contractor, and the Departmental Representative for Commissioning activities and,
  - .4 Reviews all documentation and reported results relative to commissioning throughout the project delivery.

### **3.9 USER DEPARTMENT RESPONSIBILITIES**

- .1 The User Department Project Leader
  - .1 Is accountable for the expenditure of public funds and delivery of the project in accordance with terms accepted by the Treasury Board
  - .2 Reports to senior User Department executive management
  - .3 Will play several critical roles for the successful implementation of the project, as follows:
    - .1 Coordinate the quality, timing and completeness of information and decisions relating to issues related to the functional performance of the facility;

### **3.10 REVIEW AND APPROVAL BY PROVINCIAL AND MUNICIPAL AUTHORITIES**

- .1 The federal government generally defers to provincial and municipal authorities for specific regulations, standards and inspections but in areas of conflict, the more stringent authority prevails.
- .2 Municipal authority review
  - .1 The purpose of this review is information and awareness;
  - .2 Submissions will be reviewed at the completion of specific phases as outlined in the Required Services Section of the TOR.

### **3.11 BUILDING PERMITS AND OCCUPANCY PERMITS**

- .1 The Consultant will support the Contractor in applying for building permits by providing the required documentation.
  - .1 These documents will be submitted at phases as requested by the municipal authorities.
  - .2 The Consultant will negotiate and resolve building permit related issues.
- .2 The Consultant shall support the Contractor in its application for an occupancy permit and coordinate the resolution of all outstanding issues relating to the permit.
- .3 The Contractor shall pay for the permits on behalf of PWGSC.

### **3.12 TECHNICAL AND FUNCTIONAL REVIEWS**

- .1 This includes both COE reviews and User Department reviews.





- .1 The Purpose of these reviews is technical and functional quality assurance;
- .2 Submissions will be reviewed at the completion of specific phases as outlined in the Required Services Section of the TOR.
- .2 HRSDC Reviews of building projects
  - .1 The purpose of these reviews is for fire protection, health and life safety;
  - .2 Submissions will be reviewed at the completion of specific phases as outlined in the Required Services Section of the TOR.



## APPENDIX A CHECKLISTS

### A.1 CHECKLIST FOR THE SUBMISSION OF CONSTRUCTION DOCUMENTS

#### A1.1 TITLE BLOCK

|                           |                      |                         |
|---------------------------|----------------------|-------------------------|
| <b>Project Title:</b>     |                      | <b>Date:</b>            |
|                           |                      |                         |
| <b>Project Location:</b>  |                      | <b>Project Number:</b>  |
|                           |                      |                         |
| <b>Consultant's Name:</b> |                      | <b>Contract Number:</b> |
|                           |                      |                         |
| <b>PWGSC PM:</b>          | <b>Review Stage:</b> |                         |
|                           |                      |                         |

#### A1.2 STANDARDS & GUIDELINES

| ITEM  | Checked by: | Progress Submission | Pre-Tender or Tender Ready Submission | Comments: |
|---|-------------|---------------------|---------------------------------------|-----------|
| <b>I. General</b><br>The design meets the requirements of;  |             |                     |                                       |           |
| .1 National Building Code - 2005  |             |                     |                                       |           |
| .2 National Fire Code - 2005  |             |                     |                                       |           |
| .3 National Plumbing Code - 2005  |             |                     |                                       |           |
| .4 Canada Labour Code   |             |                     |                                       |           |
| .5 NFPA 10 - Standard for Portable Fire Extinguishers - 2002  |             |                     |                                       |           |
| .6 NFPA 13 - Standard for the Installation of Sprinkler Systems - 2007  |             |                     |                                       |           |
| .7 NFPA 14 – Standard for the Installation of Standpipe and Hose Systems - 2003   |             |                     |                                       |           |
| <b>2. Treasury Board</b><br>The design meets the requirements of;   |             |                     |                                       |           |
| .1 Chapter 3-6: Fire Protection Standard for Correctional Institutions. <a href="http://www.tbs-sct.gc.ca/pol/doc-eng.aspx?id=13580">http://www.tbs-sct.gc.ca/pol/doc-eng.aspx?id=13580</a> |             |                     |                                       |           |
| .2 Chapter 3-2: Fire Protection Standard for Design & Construction. <a href="http://www.tbs-sct.gc.ca/pol/doc-eng.aspx?id=13581">http://www.tbs-sct.gc.ca/pol/doc-eng.aspx?id=13581</a>     |             |                     |                                       |           |
| .3 Fire Protection Standard for Electronic Data Processing  |             |                     |                                       |           |



|  |  |  |  |  |
|--|--|--|--|--|
| Equipment. <a href="http://www.tbs-sct.gc.ca/pol/doc-eng.aspx?id=13582">http://www.tbs-sct.gc.ca/pol/doc-eng.aspx?id=13582</a>   |  |  |  |  |
| <b>3. HRSDC Fire Protection Engineer Standards</b><br><br>The design meets the requirements of;  |  |  |  |  |
| .1 Federal Fire Protection Standards.<br><a href="http://www.hrsdc.gc.ca/eng/labour/fire_protection/policies_standards/index.shtml">http://www.hrsdc.gc.ca/eng/labour/fire_protection/policies_standards/index.shtml</a>   |  |  |  |  |
| .2 FC-403 Standard for Sprinkler Systems.<br><a href="http://www.hrsdc.gc.ca/eng/labour/fire_protection/policies_standards/commissioner/403/page00.shtml">http://www.hrsdc.gc.ca/eng/labour/fire_protection/policies_standards/commissioner/403/page00.shtml</a> |  |  |  |  |
| .3 FC-311-M Standard for Record Storage.<br><a href="http://www.hrsdc.gc.ca/eng/labour/fire_protection/policies_standards/commissioner/311/page00.shtml">http://www.hrsdc.gc.ca/eng/labour/fire_protection/policies_standards/commissioner/311/page00.shtml</a>  |  |  |  |  |
| <b>4. Labour Canada Standards</b><br><br>The design meets the requirements of;   |  |  |  |  |
| .1 Canada Labour Code.<br><a href="http://laws.justice.gc.ca/en/L-2/">http://laws.justice.gc.ca/en/L-2/</a>  |  |  |  |  |
| .2 Canada Occupational Health and Safety Regulations.<br><a href="http://laws.justice.gc.ca/eng/SOR-86-304/index.html">http://laws.justice.gc.ca/eng/SOR-86-304/index.html</a>   |  |  |  |  |
| .3 Movable Storage Units Standard.<br><a href="http://www.hrsdc.gc.ca/eng/labour/fire_protection/policies_standards/guidelines/mobile.shtml">http://www.hrsdc.gc.ca/eng/labour/fire_protection/policies_standards/guidelines/mobile.shtml</a>                    |  |  |  |  |
| <b>5. ASHRAE Standards</b><br><br>The design meets the requirements of;  |  |  |  |  |
| .1 ANSI/ASHRAE 55 – 2004 Thermal Environmental Conditions for Human Occupancy  |  |  |  |  |
| .2 ASHRAE 62.1 – 2007 – Ventilation for Acceptable Indoor Air Quality  |  |  |  |  |
| .3 ASHRAE Applications Handbook  |  |  |  |  |
| .4 ASHRAE Fundamentals Handbook  |  |  |  |  |



|                                       |  |  |  |  |  |
|---------------------------------------|--|--|--|--|--|
| <b>6. PWGSC MD Standards</b>          |  |  |  |  |  |
| The design meets the requirements of; |  |  |  |  |  |
| .1                                    | MD 15116 – Computer Room Air Conditioning Systems - 2006                   |  |  |  |  |
| .2                                    | MD 15128 – Minimum Guidelines for Laboratory Fume Hoods – March 2004       |  |  |  |  |
| .3                                    | MD 15129 – Perchloric Acid Fume Hoods - 2006                               |  |  |  |  |
| .4                                    | MD 15161 – Guidelines for the control of Legionella in mechanical systems  |  |  |  |  |
| .5                                    | MD 250005 – Energy Monitoring and Control Systems Design Guidelines - 2009 |  |  |  |  |

### A1.3 SPECIFICATIONS – ALL DISCIPLINES

| ITEM   | Checked by:   | Progress Submission | Pre-Tender or Tender Ready Submission | Comments: |
|--|---|---------------------|---------------------------------------|-----------|
| <b>1. General</b>                            |   |                     |                                       |           |
| The Specifications meet the requirements of; |   |                     |                                       |           |
| .1   | The NMS Users Guide. .  |                     |                                       |           |
| .2   | Masterformat 2004   |                     |                                       |           |
| .3   | The current edition of the NMS database   |                     |                                       |           |
| .4   | Deletion of “Related Sections” and “Section Includes” throughout.                                 |                     |                                       |           |
| .5   | PWGSC GCs for projects tendered through PWGSC   |                     |                                       |           |
| .6   | Consistent use of CCDC or other for privately tendered projects.                                  |                     |                                       |           |
| .7   | Non-proprietary Specifications.   |                     |                                       |           |
| .8   | Being completely edited with removal of all square choice brackets and Spec Notes.                |                     |                                       |           |
| .9   | Including all relevant Sections as evident by the by the scope of work indicated by the drawings. |                     |                                       |           |
| .10  | Not referring to the Tender Submission (Contract B)   |                     |                                       |           |
| .11  | Use of command imperative style of language.  |                     |                                       |           |
| .12  | Formatting in either the NMS  |                     |                                       |           |



|     |   |  |  |  |  |
|-----|---|--|--|--|--|
|     | 1/3 - 2/3 page format or the Construction Specifications Canada full page format.   |  |  |  |  |
| .13 | Each Section starting on a new page and the Project Number, Section Title, Section Number and Page Number show on the header of each page only.                 |  |  |  |  |
| .14 | Specification headers not including date or consultant's name.  |  |  |  |  |
| .15 | Departmental Representative being used throughout instead of Engineer, PWGSC, Owner, Consultant or Architect. (That is; the contractual entity)                 |  |  |  |  |
| .16 | Non use of notations such as: "verify on site", "as instructed", "to match existing", "example", "equal to", "equivalent to" and "to be determined on site by". |  |  |  |  |
| .17 | Dimensions being provided in metric only.   |  |  |  |  |
| .18 | Indicating the latest edition of all references noted in Part 1 of each Section and that un-used reference Standards are deleted.                               |  |  |  |  |
| .19 | No bolding of text.   |  |  |  |  |
| .20 | Use of Western Regions standard payments procedures clause.   |  |  |  |  |

#### AI.4 DRAWINGS GENERAL – ALL DISCIPLINES

| ITEM   | Checked by: | Progress Submission | Pre-Tender or Tender Ready Submission | Comments: |
|--|-------------|---------------------|---------------------------------------|-----------|
| <b>1. General</b><br>The Drawings meet the requirements of;  |             |                     |                                       |           |
| .1 PWGSC Western Region AutoCAD drafting standards.          |             |                     |                                       |           |
| .2 Using the "toolkit" and the "drawing checker".            |             |                     |                                       |           |
| .3 All dimensions in SI. No dual dimensioning has been used. |             |                     |                                       |           |
| .4 Providing a north arrow.                                  |             |                     |                                       |           |
| .5 Providing a legend on all relevant sheets.                |             |                     |                                       |           |
| .6 Indicating grid lines on all                              |             |                     |                                       |           |



|     |   |  |  |  |  |
|-----|---|--|--|--|--|
|     | sheets.   |  |  |  |  |
| .7  | Using standard scales.<br>(1:50, 1:100 etc.)  |  |  |  |  |
| .8  | Cross referencing and<br>detailing is consistent.   |  |  |  |  |
| .9  | No Specifications on<br>drawings.   |  |  |  |  |
| .10 | All notes being written in the<br>command imperative style of<br>speech.                        |  |  |  |  |
| .11 | Not naming the "Contractor"<br>or "sub trades" in the notes.                                    |  |  |  |  |
| .12 | Numbering all rooms on all<br>floor plans.  |  |  |  |  |
| .13 | Using appropriate line<br>weights to differentiate new<br>versus existing versus<br>demolition. |  |  |  |  |
| .14 | Using font sizes and types<br>following PWGSC drafting<br>standards.                            |  |  |  |  |
| .15 | Providing separate drawings<br>for demolition and new work.                                     |  |  |  |  |
| .16 | Drawing acceptance by the<br>FPE of HRSDC.  |  |  |  |  |

#### AI.5 DRAWINGS - DISCIPLINE SPECIFIC

| ITEM   | Checked<br>by: | Progress<br>Submission | Pre-Tender<br>or Tender<br>Ready<br>Submission | Comments: |
|--|----------------|------------------------|--|-----------|
| <b>1. Architectural</b><br>The Drawings meet the<br>requirements of;   |                |                        |  |           |
| .1 Providing a Building Code<br>Analysis.  |                |                        |  |           |
| .2 Indicating fire separations<br>and firewalls and rating.  |                |                        |  |           |
| .3 Providing a complete site<br>plan with all related details.   |                |                        |  |           |
| .4 Providing a fully detailed<br>reflected ceiling plan<br>showing lighting, diffusers,<br>sprinkler heads, etc. |                |                        |  |           |
| .5 Wall sections being<br>coordinated with the<br>structural and other<br>disciplines drawings.                  |                |                        |  |           |
| .6 Building elevations showing<br>all mechanical and electrical<br>ancillaries.                                  |                |                        |  |           |
| .7 Sub surface drainage being<br>shown on the foundation<br>plans and coordinated with<br>all other disciplines. |                |                        |  |           |



|  |  |  |  |  |  |
|--|--|--|--|--|--|
| .8                                     | Accessibility conforming to CAN/CSA 651-04.  |  |  |  |  |
| .9                                     | Coordination of door, finish, hardware schedules in conjunction with fire separations and other disciplines. |  |  |  |  |
| .10                                    | All conflict points identified by BIM have been resolved.  |  |  |  |  |
| <b>2. Structural</b>                   |  |  |  |  |  |
| The Drawings meet the requirements of; |  |  |  |  |  |
| .1                                     | Ensuring that General Notes provide additional information that is NOT covered in Specifications.            |  |  |  |  |
| .2                                     | Remove all information that is or should be covered by the Specifications.                                   |  |  |  |  |
| .3                                     | Note loads used for design.  |  |  |  |  |
| .4                                     | PWGSC policy of using general product descriptions, not proprietary product names followed.                  |  |  |  |  |
| .5                                     | Table of Abbreviations used provided.  |  |  |  |  |
| .6                                     | Section bubbles properly cross referenced.   |  |  |  |  |
| .7                                     | Coordination with all other disciplines.   |  |  |  |  |
| <b>3. Mechanical</b>                   |  |  |  |  |  |
| The Drawings meet the requirements of; |  |  |  |  |  |
| .1                                     | Separate drawings for Plumbing, HVAC, Fire Suppression, etc.   |  |  |  |  |
| .2                                     | Provision for humidification with a clean source of water and no standing water                              |  |  |  |  |
| .3                                     | Provision of separate HVAC zoning for each unique thermal zone.  |  |  |  |  |
| .4                                     | Providing Ventilation to ASHRAE 62.1.  |  |  |  |  |
| .5                                     | Meets all requirements of ASHRAE 62.1, Section 5.  |  |  |  |  |
| .6                                     | All thermostats are wall mounted.  |  |  |  |  |
| .7                                     | The building and systems and equipment meeting all requirements of Section 5 of ASHRAE 62.1.                 |  |  |  |  |
| .8                                     | Conformance to ASHRAE 55 for;  |  |  |  |  |
| .1                                     | Operative  |  |  |  |  |



|     |  |  |  |  |  |
|-----|--|--|--|--|--|
|     | temperature<br>.2 Air motion<br>.3 Radiant<br>Temperature Asymmetry<br>.4 Draft<br>.5 Vertical<br>Temperature Difference<br>.6 Floor Surface<br>Temperature<br>.7 Temperature<br>Variations with Time<br>.8 Cyclic Variations<br>.9 Drifts and Ramps |  |  |  |  |
| .9  | Providing building cross-sections at all key locations showing clearances for the mechanical installation and access for maintenance.  |  |  |  |  |
| .10 | Providing sufficient access to mechanical equipment for maintenance.   |  |  |  |  |
| .11 | Providing mechanical schematics showing design pressure and temperatures as well as all instrumentation and control points labels.   |  |  |  |  |
| .12 | Design complies with all referenced PWGSC MD Standards.  |  |  |  |  |
| .13 | Equipment schedules on the drawings coordinate and agree with the Book Specifications.   |  |  |  |  |
| .14 | Duct attenuation is designed to conform to the STC requirements shown on the architectural drawings.   |  |  |  |  |
| .15 | Coordination with all other disciplines.   |  |  |  |  |
|     | <b>4. Electrical</b><br>The Drawings meet the requirements of;   |  |  |  |  |
| .1  | Separate drawings for Lighting, Power, Fire Alarm System, Communication and Data, Security & CCTV etc.   |  |  |  |  |
| .2  | Verification and acceptance of the Grounding condition for this project.   |  |  |  |  |
| .3  | The Overcurrent and Short Circuit Study and confirming all components are fully coordinated.   |  |  |  |  |
| .4  | The Arch-Flash Study and confirming all components are fully coordinated.  |  |  |  |  |
| .5  | Providing Arch protection  |  |  |  |  |





|   |   |  |  |  |  |
|---|---|--|--|--|--|
|   | warning signs and labeling.   |  |  |  |  |
| .6  | Providing lighting Levels in accordance with the National Building Code and IESNA recommendations.  |  |  |  |  |
| .7  | Not using Armored Cable. Using Armored Cable will be allowed only for jumping from one light fixture to the other in a distance up to 3m.   |  |  |  |  |
| .8  | Providing identification for each circuit including:<br>.1 Name<br>.2 Voltage,<br>.3 Phase,<br>.4 Amps,<br>.5 Circuit-s<br>.6 Fed from Panel, Destination.  |  |  |  |  |
| .9  | The Voltage Drop Calculation for each circuit and conformance to CEC requirements.  |  |  |  |  |
| .10   | Providing phase load and total load for each panel and ensuring proper balance of the Electrical System.  |  |  |  |  |
| .11   | Coordination with all other disciplines.  |  |  |  |  |
| <b>5. Civil</b><br>The Drawings meet the requirements of; |   |  |  |  |  |
| .1  | The design criteria. (e.g. design vehicle for surface structures, design period and other data for WM.WW, SW and other systems including data and calculations showing design requirements and provided capacities) |  |  |  |  |
| .2  | The reference standards. (e.g. minimum service connection pipe or minimum WM size, etc have been used for municipal works, name the local authority whose standards are used.)                                      |  |  |  |  |
| .3  | Indicating existing sub-grade soil properties and strength that has been used for the design is indicated on drawings or in a report.   |  |  |  |  |
| .4  | Indicating Bench Marks used for the Topographic Survey are shown with Northing, Easting and elevation data.   |  |  |  |  |
| .5  | Indicating the Final  |  |  |  |  |



|    |  |  |  |  |  |
|----|--|--|--|--|--|
|    | Geometric layout for existing and new infrastructures and facilities including centerline of all access roads and pipes. The data provided includes Northing and Easting of all points including start and end point and for all other points wherever there is change in direction, and all horizontal curve data |  |  |  |  |
| .6 | Providing typical X-sections for all structures, including type, thickness of various materials for pavement structures, and pipe diameter, material types and thickness and SDR values.   |  |  |  |  |
| .7 | Providing design grades and slopes.  |  |  |  |  |
| .8 | Providing details for all infrastructures and facilities indicating all works and type of materials and all geometrics and dimensions..  |  |  |  |  |
| .9 | Coordination with all other disciplines.   |  |  |  |  |



## APPENDIX B SPECIFICATION TOC STANDARDS

### B.1 GENERAL

#### B1.1 SPECIFICATIONS

- .1 List all Divisions, Sections (by number and title) and number of pages.

#### B1.2 DRAWINGS

- .1 List all Drawings by number and title.

### B.2 SAMPLE OF TABLE OF CONTENTS

| Project No: | Table of Contents | Index        |
|-------------|-------------------|--------------|
| R.xxxxxx    |                   | Page I of xx |

#### SPECIFICATIONS:

- .3  
.4  
No. Pages  
.5 Division 01 – GENERAL REQUIREMENTS  
  
.6 01 11 00 – Summary of Work xx pages  
.7 01 14 00 – Work Restrictions xx pages  
.8 01 29 00 – Payment Procedures xx pages  
  
.9 Division 02 – EXISTING CONDITIONS  
  
.10 ETC.  
  
.11

#### DRAWINGS:

- C-I Civil  
  
L-I Landscaping  
  
A-I Architectural  
  
S-I Structural  
  
M-I Mechanical  
  
E-I Electrical



## APPENDIX C ADDENDUM FORMAT STANDARD

### C.1 SAMPLE OF ADDENDUM FORMAT

#### CI.1 DRAWINGS

- .1 Indicate drawing number and title, then list changes or indicate revision number and date, and re-issue drawing with addendum.

#### CI.2 SPECIFICATIONS

- .1 Indicate section number and title.
- .2 List all changes (i.e. delete, add or change) by article or paragraph

|   |                        |
|---|------------------------|
| <b>Project Title:</b>   | <b>Addendum No:</b>    |
|   |                        |
| <b>Project Location:</b>  | <b>Project Number:</b> |
|   |                        |
| <b>Consultant's Name:</b>   | <b>Date:</b>           |
|   |                        |
| <b>The following changes in the bid documents are effective immediately.<br/>This addendum will form part of the contract documents</b> |                        |
| <b>Drawings</b>   |                        |
| 1 AI Architectural  |                        |
| <b>Specifications</b>   |                        |
| 1 Section 01 00 10 - General Instructions   |                        |
| .1 Delete article (xx) entirely.  |                        |
| .2 Refer to paragraph (xx) and revise "xxx", to read "xxxx"..   |                        |
| 2 Section 23 05 00 - Common Work Results - Mechanical   |                        |
| .1 Add new article (x.xx) as follows:   |                        |



## APPENDIX D DIGITAL TENDER DOCUMENTS STANDARDS

### D.1 CONVENTION STANDARDS FOR TENDER DOCUMENTS


#### D1.1 USER MANUAL

- .1 Refer to the User manual on directory structure and naming convention standards for construction tender documents on CD ROM.
  - .1 Issued by: Real Property Contracting Directorate, PWGSC,
  - .2 Version 1.0, May 2005.

#### D1.2 PREFACE

- .1 The Government of Canada (GoC) has committed to move towards an electronic environment for the majority of the services it offers.
- .2 This covers the advertisement and distribution of contract opportunities, including construction solicitations.
- .3 As a result, it is now necessary to obtain a copy of construction drawings and specifications (in PDF format *without* password protection) on one or multiple CD-ROM to facilitate for the GoC the transfer of the construction drawings and specifications electronically to the Government Electronic Tendering System (GETS).
- .4 There is therefore a need to adopt a common directory structure and file-naming convention to ensure that the information made available to contractors electronically and in hard (printed) copy is in accordance with the sequence adopted in the real property industries, both for design and construction.
- .5 This manual defines the standard to be followed by both consultants and print shops at time of formatting and organizing the information, whether drawings and specifications are created by scanning print documents or saved as PDF files from the native software (AutoCAD, NMS Edit, MS-Word, etc...) in which these were created.
- .6 It is important to note that the procedure described in this manual is not an indication that consultants are relieved from following the established standards for the production of drawings and specifications.
- .7 The sole purpose of this manual is to provide a standard for the organization and naming of the electronic files that will be recorded on CD-ROM.

#### D1.3 DIRECTORY STRUCTURE







#### D1.4 1<sup>ST</sup>, 2<sup>ND</sup> AND 3<sup>RD</sup> TIER SUB-FOLDERS

- .1 Each CD-ROM, whether it is for the original solicitation (tender call) or for an amendment (addendum), must have the applicable elements of the following high-level Directory Structure created:
- .2 The following important points are to be noted about the Directory Structure:
  - .1 The “Project #####” folder is considered the 1<sup>st</sup> Tier of the Directory Structure where ##### represents each digit of the Project Number.
  - .2 The Project Number must always be used to name the 1<sup>st</sup> Tier folder and it is always required.
  - .3 Free text can be added following the Project Number, to include such things as a brief description or the project title;
- .3 The “Bilingual - Bilingue”, “English” and “Français” folders are considered the 2<sup>nd</sup> Tier of the Directory Structure. The folders of the 2<sup>nd</sup> Tier **cannot** be given any other names since GETS uses these names for validation purposes. At least one of the “Bilingual - Bilingue”, “English” and “Français” folders is always required, and these must always have one of the applicable sub-folders of the 3<sup>rd</sup> Tier;
- .4 The “Drawings - Dessins”, “Drawings”, “Specifications”, “Dessins” and “Devis” folders are considered the 3<sup>rd</sup> Tier of the Directory Structure. The folders of the 3<sup>rd</sup> Tier **cannot** be given any other names since GETS also uses these names for validation purposes. There must be always at least one of the applicable 3<sup>rd</sup> Tier folder in each document.
- .5 IMPORTANT NOTE:
  - .1 The applicable elements of the Directory Structure (1<sup>st</sup>, 2<sup>nd</sup> and 3<sup>rd</sup> Tier folders) are always required and cannot be modified.

#### D1.5 4<sup>TH</sup> TIER SUB-FOLDERS FOR DRAWINGS

- .1 The “Drawings – Dessins”, “Drawings” and “Dessins” folders must have 4<sup>th</sup> Tier sub-folders created to reflect the various disciplines of the set of drawings.
- .2 Because the order of appearance of the sub-folders on the screen will also determine the order of printing, it is necessary to start with a number the identification name of the sub-folders in the “Drawings – Dessins”, “Drawings” and “Dessins” folders.
- .3 Note:
  - .1 The first sub-folder must be always reserved for the Title Page and/or the List of Drawings unless the first drawing of the set is an actual numbered discipline drawing.
- .4 Examples of 4<sup>th</sup> Tier sub-folders for drawings:





## DI.6 NAMING CONVENTION - 4<sup>TH</sup> TIER DRAWINGS


- .1 The 4<sup>th</sup> Tier sub-folders for drawings must adhere to the following standard naming convention.
  - .1 For the “Drawings” and “Dessins” folders:
    - 1 ## - Y, Where:
      - 1 ## = A two digit number ranging from 01 to 99 (leading zeros must be included)
      - 2 Y = The title of the folder
    - 2 Example: 03 – Mechanical
  - .2 For the “Drawings - Dessins” folder:
    - 1 ## - Y – Z, Where:
      - 1 ## = A two digit number ranging from 01 to 99 (leading zeros must be included)
      - 2 Y = The English title of the folder
      - 3 Z = The French title of the folder
    - 2 Example: 04 - Electrical – Électricité
- .2 It should be noted that the numbering of the 4<sup>th</sup> Tier sub-folders is for sorting purposes only and is not tied to a specific discipline. For example, “Architectural” could be numbered 05 for a project where there is four other disciplines before “Architectural” in the set of drawings or 01 in another project where it’s the first discipline appearing in the set.
- .3 It is essential to ensure that the order of the drawings on the CD-ROM be exactly the same as in the hard copy set. GETS will sort each drawing for both screen display and printing as per the following rules:
  - .1 The alphanumerical sorting is done on an ascending order;
  - .2 The alphanumerical order of the sub-folders determines the order of appearance on the screen as well as the order of printing (as an example: all the drawing PDF files in the 01 sub-folder will be printed in alphanumerical order before the drawings in the 02 sub-folder etc...);
  - .3 Each drawing PDF file within each sub-folder will also be sorted alphanumerically. This will determine the order of appearance on the screen as well as the order of printing




(i.e. Drawing A001 will be printed before Drawing A002, Drawing M02 before Drawing M03, etc...).

#### D1.7 4<sup>TH</sup> TIER SUB-FOLDERS FOR SPECIFICATIONS

- .1 The “Specifications” and “Devis” folders must have 4<sup>th</sup> Tier sub-folders created to reflect the various elements of the specifications.
- .2 Because the order of appearance of the sub-folders on the screen will also determine the order of printing, it is necessary to start with a number the identification name of the sub-folders in the “Specifications” and “Devis” folders.
- .3 Examples of 4<sup>th</sup> Tier sub-folders for specifications:



or



#### D1.8 NAMING CONVENTION - 4<sup>TH</sup> TIER SPECIFICATIONS

- .1 The 4<sup>th</sup> Tier sub-folders for specifications must adhere to the following standard naming convention.
  - .1 For the “Specifications” and “Devis” folders:
    - 1 ## - Y, Where:
      - 1 ## = A two digit number ranging from 01 to 99 (leading zeros must be included)
      - 2 Y = The title of the folder
    - 2 Example: 02 – Divisions
  - .2 It should be noted that the numbering of the 4<sup>th</sup> Tier sub-folders is for sorting purposes only and is not tied to an element of the specifications.





- .3 It is essential to ensure that the order of the elements of the specifications on the CD-ROM be exactly the same as in the hard copy. GETS will sort each element of the specifications for both screen display and printing as per the following rules:
- .4 The alphanumerical sorting is done on an ascending order;
  - .1 The alphanumerical order of the sub-folders determines the order of appearance on the screen as well as the order of printing (as an example: all the specifications PDF files in the 01 sub-folder will be printed, in alphanumerical order before the PDF files in the 02 sub-folder, etc...);
  - .2 Each specifications PDF file within each sub-folder will also be sorted alphanumerically.
    - 1 This will determine the order of appearance on the screen as well as the order of printing (i.e. Division 01 will be printed before Division 02, 01 - Appendix A before 02 - Appendix B, etc...).

## **DI.9 NAMING CONVENTION FOR PDF FILES**

- .1 Each drawing, specifications division or other document that are part of the tender documents must be converted in PDF format (without password protection) in accordance with the following standard naming convention and each PDF file must be located in the appropriate sub-folder of the Directory Structure.

## **DI.10 DRAWINGS**

- .1 Each drawing must be a separate single page PDF file.
- .2 The naming convention of each drawing must be:
  - .1 X### - Y, Where;
    - 1 X = The letter or letters from the drawing title block ("A" for Architectural or "ID" for Interior Design for example) associated with the discipline,
    - 2 ### = The drawing number from the drawing title block (one to three digits),
    - 3 Y = The drawing name from the drawing title block (for bilingual drawings, the name in both English and French is to appear).
  - .2 Example; A001 - First Floor Details.
- .3 Each drawing that will be located in the appropriate discipline 4<sup>th</sup> Tier sub-folders must be named with the same letter ("A" for Architectural Drawings for example) and be numbered.
- .4 The drawing number used to name the PDF file must match as much as possible the drawing number of the actual drawing (the exception being when leading zeros are required).
- .5 The following important points about drawings are to be noted:
  - .1 The drawing PDF files within each sub-folder are sorted alphanumerically for both displaying and printing. If there are more than 9 drawings in a particular discipline the numbering must use at least two numerical digits (i.e. A01 instead of A1) in order to avoid displaying drawing A10 between A1 and A2.
    - 1 The same rule applies when there are more than 99 drawings per discipline i.e. three digits instead of two must be used for the numbering (for example M003 instead of M03);
  - .2 If drawing PDF files are included in the "*Bilingual - Bilingue*" folder, these cannot be included as well in the "*English*" and/or "*Français*" folders;
  - .3 If drawings not associated with a particular discipline are not numbered (Title Page or List of Drawings for example), these will be sorted alphabetically.
    - 1 While this does not represent a problem if there is only one drawing in the sub-folder, it could disrupt the order when there are two or more drawings. If the alphabetical order of the drawings name does not represent the order on the



hard copy set, the drawings are to be named as per the following standard convention when converted in PDF format to ensure proper display and printing order.

1 ## - Y, Where:

1 ## = A two digit number ranging from 01 to 99 (leading zeros must be included)

2 Y = The name of the drawing


2 Example:

1 01 - Title Page

2 02 - List of Drawings

.4 If numbers are not used in the PDF files name, “List of Drawings” will be displayed before “Title Page” because “L” comes before “T” in the alphabet.

#### DI.11 EXAMPLE OF A 4<sup>TH</sup> TIER DRAWINGS SUBFOLDER’S CONTENT:



#### DI.12 SPECIFICATIONS


- .1 Each Specifications Division must be a separate PDF file and all pages contained in each PDF file must have the same physical size (height, width).
- .2 The Plans and Specifications Index must also be a separate PDF file.
- .3 If there are other documents that are part of the Specifications (e.g. Appendix or other) these are to be separate PDF files as well.

#### DI.13 DOCUMENTS OTHER THAN SPECIFICATIONS DIVISIONS

- .1 Because PDF files within the Specifications sub-folders are sorted alphanumerically (in ascending order) for both on screen display and printing order, all files that appear in folders other than the “Divisions” sub-folder must be named using a number:
  - .1 ## - Y, Where:
    - 1 ## = Two digit number ranging from 01 to 99 with leading zeros required
    - 2 Y = Name of the document
  - .2 Example: 01 - Plans and Specifications Index



#### DI.14 EXAMPLE OF A SUB-FOLDER CONTENT (SUB-FOLDER OTHER THAN “DIVISIONS”):



#### DI.15 SPECIFICATIONS DIVISIONS

- .1 The Specifications Divisions must be named as follows:
  - .1 Division ## - Y, Where:
    - 1 Division ## = The actual word “Division” followed by a space and a two digit number ranging from 01 to 99 (with leading zeros required)
    - 2 Y = Name of the Specifications Division as per CSC/CSI MasterFormat™
  - .2 Example: Division 05 – Metals
- .2 The following important point about specifications is to be noted:
  - .1 The Numbering of the Divisions cannot be altered from CSC/CSI MasterFormat™ even if some Divisions are not used in a given project.
    - 1 For example, Division 05 will always remain Division 05 even if Division 04 is not used for a given project.

#### DI.16 EXAMPLE OF A “DIVISIONS” SUB-FOLDER CONTENT:





## DI.17 CD-ROM LABEL

- .1 Each CD-ROM is to be labelled with the following information:
  - .1 Project Number;
  - .2 Project Title;
  - .3 Documents for Tender;
  - .4 CD X of X.
- .2 Example:
  - .1 Project 123456;
  - .2 Repair Alexandra Bridge;
  - .3 Documents for Tender;
  - .4 CD 1 of 1.



## APPENDIX E PDF CREATION STANDARDS

### E.1 CONVERTING CONSTRUCTION DRAWINGS INTO PDF

#### E1.1 REFERENCE GUIDE

- .1 Refer to the basic reference guide on converting construction drawings into portable document format (PDF), Issued by Real Property Contracting Directorate. PWGSC, Version 1.0, May 2005.

#### E1.2 PREFACE

- .1 Portable Document Format (PDF) is the standard format for documents that are posted on the Government Electronic Tendering System (GETS).
- .2 There is therefore a need to obtain from architectural and engineering consultants an electronic copy of drawings and specifications in PDF for tendering Government of Canada (GoC) construction projects.
- .3 In order to have the highest quality in term of resolution and printing, consultants should to the greatest extent possible have the PDF drawing and specification files derived from the native software in which they were created. Scanning is permissible but only in special circumstances, for example when there is no electronic version of a drawing being included in a construction tender package.
- .4 The purpose of this document is to provide basic information on the conversion of Computer Aided Design and Drafting (CADD) drawings in PDF. Creating a PDF file from a CADD drawing is a relatively simple process once all the necessary configurations and settings are in place.
  - .1 It actually should not take any longer than it would take to create a plot file or to send a drawing to a printer.
  - .2 The information in this guide is not intended to cover all technical aspects of the conversion, which can be done using various methods, but rather to highlight important points about the process and file settings.
  - .3 The conversion of specifications is not covered in this basic reference guide since it does not require any special configuration or setting.
- .5 The information provided in this basic reference guide is not an indication that consultants are relieved from following the established standards for the production of drawings and specifications.
  - .1 The sole purpose of this guide is to provide basic information on the PDF conversion process bearing in mind that additional detailed technical information is available from the various software manufacturers.

#### E1.3 PRINTER DRIVERS

- .1 Adobe Acrobat provides two different printer drivers that are able to convert CADD drawing into PDF format, Acrobat PDF Writer and Acrobat Distiller.
- .2 Before creating a PDF file from a CADD drawing, a choice must be made as to which one will be used.
- .3 Acrobat PDF Writer is a non-PostScript printer driver that works best with documents that don't contain complex graphics.
- .4 Acrobat Distiller is a PostScript printer driver that works best with documents that contain PostScript fills, Encapsulated PostScript (EPS) graphics, or other complex elements.
- .5 It is recommended that Acrobat Distiller be used to create PDF file of architectural and engineering drawings due to their size and complex graphical nature.



#### EI.4 PRINTER CONFIGURATION

- .1 Before converting a CADD drawing to PDF, an Acrobat printer configuration file for the PDF paper size needs to be created.
- .2 This function can be done in the CADD software rather than using a custom paper size defined for the Acrobat distiller feature.
- .3 The recommended method is to add a PostScript Adobe plotter in the CADD software and making the necessary setting in terms of media source and size, scale and orientation.
- .4 The configuration can then be re-used to simplify the conversion process for future files that use the same page size.
- .5 As an alternative, although not recommended, a custom-defined size can be created in Acrobat Distiller in the *properties* menu.

#### EI.5 CREATING PDF FILES

- .1 Once the printer configuration has been done in the CADD software, open Acrobat Distiller and make the necessary settings in the *preferences* and *job options* sub-menu.
  - .1 Ensure that the page size match the sheet size selected in the CADD software to create the file.
  - .2 Particular settings can be saved under different names for future use.
- .2 With the Acrobat Distiller application open, ensure the required sheet size is displayed in the job options window. Then it is simply a matter of bringing the CADD file into the Acrobat Distiller creation box.
- .3 A progress bar will show during the conversion and the newly converted PDF file should open up and be displayed for verification.

#### EI.6 PDF FILES SETTINGS

- .1 Security
  - .1 Adobe Acrobat contains security features that can be used to secure the files by restricting any changes to the files.
  - .2 Since the files will be posted on MERX and will be used for printing copies, the files must not be password protected and must allow printing.

#### EI.7 DRAWING ORIENTATION

- .1 The final PDF drawing files must be displayed on the screen in the same direction that the users are intended to view them. This can be achieved by adjusting the setup of the plotter. If the drawing is not oriented properly after the conversion, it can be rotated manually within Adobe Acrobat.

#### EI.8 FONT TYPE

- .1 In order to avoid any problems during the conversion and to minimize the potential for font display errors, the fonts used for the production of construction drawings must be PostScript or True Type fonts.

#### EI.9 RESOLUTION

- .1 Since the PDF files will be used for printing, it is important that a proper resolution be selected. It is recommended to select 600 dots per inch (dpi).

#### EI.10 SCALE

- .1 When choosing the Plot scale in Adobe, it is important to choose the 1:1 scale to ensure the integrity of the scale from which the drawings were created in the CADD software.

#### EI.11 SCANNING



- .1 Scanning is not recommended and should be done only when the drawing is not available electronically.
- .2 When scanning a drawing, it is important that it be done in real size (scale 1:1) to ensure that the scale remains intact in subsequent printing.
- .3 It is recommended that each scanned drawing be opened and verified to ensure that the resolution, scale and border are of an acceptable quality.

#### **EI.12 FINAL CHECKLIST**

- .1 When the drawing file has gone through the PDF conversion, it is recommended to open it and verify the following:
  - .1 That the sheet size displayed is what was intended to be created (the size is viewable in the lower left corner of the drawing);
  - .2 That the orientation of the sheet is correct;
  - .3 That the line types, line weights and fonts match the CADD drawing.
  - .4 That the PDF file is in black and white;
  - .5 That each drawing is a single PDF file;
  - .6 That the PDF file is not password protected and printable.
- .2 If all the items are verified, the PDF file is useable.

#### **EI.13 ADDITIONAL INFORMATION**

- .1 For more information about the creation of PostScript and EPS files please refer to the User's Guide of the CADD software being used to produce the drawings. For more information about creating PDF file please refer to the Acrobat Distiller User's Guide and/or visit the Adobe Web site at [www.adobe.com](http://www.adobe.com).



## APPENDIX F DEFINITIONS

### F.1 TERMINOLOGY

| TERMS                       | DESCRIPTION  |
|-----------------------------|--|
| As-builts/Record Drawings   | See Record Drawings  |
| Base Building               | Refers to the building shell, as opposed to the tenant fit-up. It includes finished floors, exterior walls, interior core, finished ceilings with lighting, and other building systems for the planned general use of the building. Generally, the work for the base building is separate from the work for tenant-fit-ups             |
| Circulation                 | Space used, primarily by people, to move from one area to another. It includes major as well as secondary aisles.  |
| Client                      | A term that refers to the client, the client department or user department   |
| Co-location                 | Placing items together for better organization   |
| Consultant                  | The word refers both to an individual consultant, or a consultant team. The consultant is generally selected by PWGSC using a Request for Proposal.  |
| Contractor                  | The company, organization or firm who is responsible for the construction of the project   |
| Consolidation               | Reducing the number of co-located items by placing them in a common floor facility to eliminate duplication of space.  |
| Constant dollar estimate    | This is an estimate expressed in terms of the dollars of a particular base fiscal year.  |
| Cost Specialist             | Refers to the cost estimating, planning and control team or an individual performing these functions.  |
| Current dollar estimate     | Refer to: <i>budget year dollars</i>   |
| Budget-year dollars         | This is an estimate based on costs arising in each FY of the project schedule, which is escalated to account for inflation and other economic factors affecting the period covered by the estimate<br><b>Budget year</b> dollars is also be referred to as <b>Nominal</b> dollars or <b>Current</b> dollars                            |
| Departmental Representative | The person designated in the contract, or by written notice to the Consultant or Contractor, to act for PWGSC for the purposes of the contract. It can also be a person designated in writing by the Departmental Representative to act on his/her behalf. In most cases, the PWGSC Project Manager is the Departmental Representative |
| EMV                         | Expected monetary value of risk event (i.e. cost or saving to the project if risk event occurs)  |





|   |  |
|---|--|
| Final Certificate of Completion           | A document issued by the Project Manager after the final inspection by the Project Acceptance Board. The final payment to the Contractor by PWGSC is based on the final certificate of completion  |
| Final Inspection                          | The inspection performed by the Project Acceptance Board after project completion and after correction of deficiencies identified during Interim Inspection  |
| Fit-up for initial occupancy              | The preparation of accommodation for initial occupancy, in accordance with the federal Fit-up Standards. This fit-up may include alternations to the base building and its building systems.   |
| Fit-up of existing space for reuse, Refit | Work required to alter space previously occupied by one organization to meet the requirements of a different organization.   |
| Fit-Up Cost Limits                        | The funding limits for the fit-up of office accommodation. The limits are based on the average cost per useable square meter, for fit-up elements in specific urban centres across Canada, and are updated from time to time. The limits do not include soft costs or items funded by clients or under base building costs.  |
| Fit-Up Items                              | Components that are installed removed or relocated to prepare the space for occupancy. They include partition walls, doors, frames, hardware, counters and cabinetry, modifications to base building systems, etc. as detailed in the Fit-up standards. Some base building components are included in consultant scope of work, such as the flooring and the ceiling finishes or telecommunications spaces and related environmental controls. |
| Focus Group                               | Group sessions held to establish qualitative requirements. They are most effective at the strategic planning level. They are used primarily to translate the Client Department's mission statement into organizational requirements and to assess planning alternatives  |
| Full-time equivalent.                     | It measures of labour utilization in the federal government which approximates the actual number of persons "employed" by the government for carrying out the unit of work   |
| Functional space equation                 | Identifies space requirements (in usable m2) by group along with summary of the total space required for all groups.   |
| Gross Space                               | The total floor space  |
| High risk                                 | A project (or element of a project) may be assessed as high risk if one or more hazards exist in a significant way and, unless mitigated, would result in probable failure to achieve project objectives   |
| Impact                                    | The result of the occurrence of an event on the project either positive or negative (i.e. a schedule delay as a result of late delivery of a piece of equipment may have a high negative impact on a project; increased access to a construction site due to early departure of occupants in an office space may have positive   |



|                                    |  |
|------------------------------------|--|
|                                    | impact on a project).<br>The Impact of individual Risk Events can be qualified as low, medium, high or quantified in terms of time, cost (immediate cost or in-service cost (O&M)) or performance.   |
| Interim Certificate of Completion  | The certificates issued by Project manager following the Interim Inspection. Interim payment to the Contractor by PWGSC is based on the interim certificates. This payment takes place of a regular progress claim.  |
| Interim Inspection                 | The inspection performed by the Project Acceptance Board after substantial completion of the project. A list of deficiencies is prepared, and subject to the Contractor's agreement to correct these, the Project Manager accepts the work and prepares the interim certificates |
| LEED®                              | Leadership in Energy & Environmental Design; an environmental rating system  |
| Low risk                           | A project (or element of a project) should be assessed as low risk if hazards do not exist or have been reduced to the point where routine project management control should be capable of preventing any negative effect on the attainment of project objectives                |
| Medium risk                        | A project (or element of a project) may be assessed as medium risk if some hazards exist but have been mitigated to the point that allocated resources and focused risk management planning should prevent significant negative effect on the attainment of project objectives   |
| National Project Management System | The system used by PWGSC for management of its projects. It replaces the earlier Project Delivery System (PDS).  |
| PI Forms                           | Product Information forms; used in commissioning documentation   |
| Probability                        | The likelihood that an event will occur (i.e. Low, Medium, High)   |
| Project Acceptance Board           | A team assembled by the Project Manager to perform interim and final inspections of the Client Department's improvements.  |
| PV Forms                           | Performance Verification forms; used in commissioning documentation  |
| Record drawings                    | Drawings used to record field deviations, dimensional data, and changes or deviations from the 'Construction Document-Issued for Construction'. They indicate the work as 'actually' installed. They are also called as-builts   |
| Rentable Space                     | Usable space plus space occupied by columns, convectors, elevator lobbies and washrooms. It also includes some common base building areas such as telephone and janitorial closets.  |
| Request for Proposal               | The document used for requesting consultant services. It includes the Terms of Reference as well as other contracting documents  |



|                        |   |
|------------------------|---|
| Risk management        | The art and science of identifying, analysing, and responding to risk factors throughout the life of a project and in the best interests of its objectives  |
| Risk Event             | A discrete occurrence that may affect the project for better or worse (i.e. late delivery of a piece of equipment is a “risk event” that may cause a schedule delay)  |
| Scheduler              | Refers to the Time Scheduler; also referred to as Time Specialist   |
| Space Equation         | A spreadsheet that reflects the Client’s organizational structure, functional requirements, and proposed planning alternatives. It is used to determine the total usable area required to accommodate the following:<br>Open and enclosed workstations/worksettings;<br>Support space;<br>Special purpose space circulation factor;<br>Building loss factor;<br>Total population; and<br>Total space required; and<br>Summary by group  |
| Space Optimization     | Maximizing the utilization of space.  |
| Special Purpose Spaces | Non-standard spaces required to accommodate activities that are essential to departmental programs. This space is often not suitable for conversion to office accommodation because of its special requirements. Examples include: laboratories, health units or clinics, meeting or training complexes which serve outside groups, processing space, departmental libraries, gymnasiums, warehouses, file or storage areas not allowed by the PWGSC Fit-Up Standards, trade shops, mailrooms, computer training rooms, cash offices and similar spaces requiring special service and security features and hearing rooms.                              |
| Support Space          | Space for typical office support functions not included in workstation or circulation space but necessary for office operation. The Fit-Up Standards identify specific sizes and ratios for kitchenette / recycling centre / lunchroom / resource areas, shared equipment spaces, meeting rooms, quiet / touch down rooms, printer stations, reception / mail drop / waiting / display areas and coat / storage closets. Limited allowances for “Other” support spaces including non-dedicated workstations, storage rooms, LAN rooms, breakout rooms, interview rooms, training rooms, reading rooms etc. are also identified in the Fit-Up Standards. |
| Terms of Reference     | A document prepared by PWGSC when requesting Consultant services, which forms part of the RFP and is also included in the Consultant Agreement with PWGSC.  |
| Universal Footprint    | One standard module which can be multiplied to accommodate  |



|                               |   |
|-------------------------------|---|
|                               | all office functions including workstations, support space and special purpose space  |
| Usable space, “Walk-on” Space | The space, in M <sup>2</sup> , that is actually usable by the occupant. Measurement calculations do not include columns and convectors, building service areas and accessory areas. |
| Worksettings                  | Common work areas that support both collaboration and privacy. They include: teaming areas, non-dedicated workstations, privacy nooks, resource areas and multipurpose areas.       |
| Workstations                  | An enclosed or open area dedicated for the use of individual employees.   |

## F.2 ACRONYMS

| ACRONYM | DESCRIPTION   |
|---------|---|
| A&E     | Architecture & Engineering  |
| AHJ     | Authorities Having Jurisdiction   |
| AMP     | Asset Management Report   |
| ASAE    | American Society of Agricultural Engineers                                |
| ASHRAE  | American Society of Heating, Refrigeration and Air Conditioning Engineers |
| ASPE    | American Society of Plumbing Engineers                                    |
| BCC     | Building components and connectivity                                      |
| BCR     | Building Condition Report   |
| BMM     | Building Maintenance Manual   |
| CAD     | Computer aided drawing  |
| CCDC    | Canadian Construction Document Committee                                  |
| CBIP    | Commercial building incentive program                                     |
| COE     | PWGSC Centre of Expertise   |
| EMCS    | Energy Monitoring & Control System  |
| EPA     | Effective Project Approval  |
| FHBRO   | Federal Heritage Building Restoration Office                              |
| FOBS    | Federal Office Building Standards (PWGSC)                                 |
| FTE     | Full-time equivalent  |
| HCP     | Heritage Conservation Program   |
| HRSDC   | Human Resources and Skills Development Canada                             |
| IT/MM   | Information Technology/Multi-media  |
| MMS     | Maintenance management system   |
| NBC     | National Building Code  |
| NCA     | National Capital Area;  |
| NCR     | National Capital Region;  |
| NFBC    | National Farm Building Code   |
| NGMA    | National Greenhouse Manufacturers' Association                            |
| NMS     | The National Master Specification used by PWGSC                           |



|       |   |
|-------|---|
| NPMS  | National Project Management System          |
| OAA   | Ontario Association of Architects           |
| O&M   | Operation and Maintenance                   |
| P&S   | General Procedures and Standards            |
| PA    | Project administration                      |
| PI    | Product Information                         |
| PD    | Project Description                         |
| PM    | Project Manager                             |
| PV    | Performance verification                    |
| PWGSC | Public Works and Government Services Canada |
| RAIC  | Royal Architectural Institute of Canada     |
| RAS   | Requirements and Standards                  |
| RS    | Required Services                           |
| RSR   | Resident site services                      |
| RPCD  | Real Property Contracting Directorate       |
| TOR   | Terms of Reference                          |

## **SUBMISSION REQUIREMENTS AND EVALUATION**

SRE 1 General Information  
SRE 2 Proposal Requirements  
SRE 3 Submission Requirements and Evaluation  
SRE 4 Price of Services  
SRE 5 Total Score  
SRE 6 Submission Requirements - Checklist

### **SUBMISSION REQUIREMENTS AND EVALUATION (SRE)**

#### **SRE 1 GENERAL INFORMATION**

##### **1.1 Reference to the Selection Procedure**

An 'Overview of the Selection Procedure' can be found in R1410T General Instructions to Proponents (GI3).

##### **1.2 Calculation of Total Score**

For this project the Total Score will be established as follows:

|                           |   |                             |
|---------------------------|---|-----------------------------|
| Technical Rating x 90%    | = | Technical Score (Points)    |
| <u>Price Rating x 10%</u> | = | <u>Price Score (Points)</u> |
| Total Score               | = | Max. 100 Points             |

#### **SRE 2 PROPOSAL REQUIREMENTS**

##### **2.1 Requirement for Proposal Format**

The following proposal format information should be implemented when preparing the proposal.

- Submit one (1) bound original plus five (5) bound copies of the proposal
- Paper size should be - 216mm x 279mm (8.5" x 11")
- Minimum font size - 11 point Times or equal
- Minimum margins - 12 mm left, right, top, and bottom
- Double-sided submissions are preferred
- One (1) 'page' means one side of a 216mm x 279mm (8.5" x 11") sheet of paper
- 279mm x 432 mm (11" x 17") fold-out sheets for spreadsheets, organization charts etc. will be counted as two pages.
- The order of the proposals should follow the order established in the Request for Proposal SRE section

---

## 2.2 Specific Requirements for Proposal Format

The maximum number of pages (including text and graphics) to be submitted for the Rated Requirements under SRE 3.2 is thirty (30) pages.

The following are not part of the page limitation mentioned above;

- Covering letter
- Consultant Team Identification (Appendix A)
- Declaration/Certifications Form (Appendix B)
- Integrity Provisions - Required Documentation
- Front page of the RFP
- Front page of revision(s) to the RFP
- Price Proposal Form (Appendix C)

***Consequence of non-compliance: any pages which extend beyond the above page limitation and any other attachments will be extracted from the proposal and will not be forwarded to the PWGSC Evaluation Board members for evaluation.***

## SRE 3 SUBMISSION REQUIREMENTS AND EVALUATION

### 3.1 MANDATORY REQUIREMENTS

Failure to meet the mandatory requirements will render the proposal as non-responsive and no further evaluation will be carried out.

#### 3.1.1 Licensing, Certification or Authorization

The proponent shall be a Civil Engineering Firm, licensed, or eligible to be licensed, certified or otherwise authorized to provide the necessary professional services to the full extent that may be required by provincial or territorial law in the province of Saskatchewan.

#### 3.1.2 Consultant Team Identification

The consultant team to be identified must include the following:

Proponent (prime consultant) - Civil Engineering Firm.

Key Sub-consultants / Specialists - Structural Engineering, Geotechnical Engineering, Pavement Design and Engineering, Hydraulic Engineering, Cost Estimating Specialist, and Commissioning Specialist.

If the proponent proposes to provide multidisciplinary services that might normally be provided by a sub-consultant, this should be indicated here.

Information required - name of firm, key personnel to be assigned to the project. For the prime consultant indicate current license and/or how you intend to meet the provincial or territorial licensing requirements. In the case of a joint venture identify the existing or proposed legal form of the joint venture (refer to R1410T General Instructions to Proponents, GI9 Limitation of Submissions).

An example of an acceptable format (typical) for submission of the team identification information is provided in Appendix A.

### 3.1.3 Declaration/Certifications Form

Proponents must complete, sign and submit the following:

- Appendix B, Declaration/Certifications Form as required.

### 3.1.4 Integrity Provisions - Required documentation

In accordance with the Ineligibility and Suspension Policy (<http://www.tpsgc-pwgsc.gc.ca/ci-if/politique-policy-eng.html>), the Proponent must provide, **as applicable**, to be given further consideration in the procurement process, the required documentation as per R1410T (2016-04-04), General instructions 1 (GI1), Integrity Provisions – Proposal, **section 3a**.

## 3.2 RATED REQUIREMENTS

### 3.2.1 Achievements of Proponent on Projects

Describe the Proponent's accomplishments, achievements and experience as prime consultant on projects.

Select a **maximum** of 2 projects undertaken within the last 6 years. Joint venture submissions are not to exceed the maximum number of projects. Only the first 2 projects listed in sequence will receive consideration and any others will receive none as though not included.

#### Information that should be supplied:

- clearly indicate how this project is comparable/relevant to the requested project.
- brief project description and intent. Narratives should include a discussion of design philosophy / approach to meet the intent, design challenges and resolutions.
- budget control and management - i.e. contract price & final construction cost - explain variation
- project schedule control and management - i.e. initial schedule and revised schedule - explain variation
- client references - name, address, phone and fax of client contact at working level - references may be checked
- names of key personnel responsible for project delivery
- awards received
- sustainable design issues addressed in each project.

The Proponent (as defined in R1410T General Instructions to Proponents, GI2 Definitions) must possess the knowledge on the above projects. Past project experience from entities other than the Proponent will not be considered in the evaluation unless these entities form part of a joint venture Proponent.



Please indicate those projects which were carried out in joint venture and the responsibilities of each of the involved entities in each project.

### **3.2.2 Achievements of Key Sub-consultants and Specialists on Projects**

Describe the accomplishments, achievements and experience either as prime consultant or in a sub-consultant capacity on projects. If the Proponent proposes to provide multi-disciplinary services which might otherwise be performed by a sub-consultant, this should be reflected here.

Select a **maximum** of 2 projects undertaken within the last 6 years per key sub consultant or specialist. Only the first 2 projects listed in sequence (per key sub consultant or specialist) will receive consideration and any others will receive none as though not included.

#### Information that should be supplied:

- clearly indicate how this project is comparable/relevant to the requested project.
- brief project description and intent. Narratives should include a discussion of design philosophy / approach to meet the intent, design challenges and resolutions.
- budget control and management
- project schedule control and management
- client references - name, address, phone and fax of client contact at working level - references may be checked
- names of key personnel responsible for project delivery
- awards received.

### **3.2.3 Achievements of Key Personnel on Projects**

Describe the experience and performance of key personnel to be assigned to this project regardless of their past association with the current proponent firm. This is the opportunity to emphasize the strengths of the individuals on the team, to recognize their past responsibilities, commitments and achievements.

#### Information that should be supplied for each key personnel:

- professional accreditation
- accomplishments/achievements/awards
- relevant experience, expertise, number of years' experience
- role, responsibility and degree of involvement of individual in past projects.

### **3.2.4 Understanding of the Project:**

The proponent should demonstrate understanding of the goals of the project, the functional/technical requirements, the constraints and the issues that will shape the end product.

#### Information that should be supplied:

- The functional and technical requirements

- 
- Broader goals (federal image, sustainable development, sensitivities)
  - The relationship between this commission and any earlier studies completed for PWGSC
  - Significant issues, challenges and constraints
  - Project schedule and cost. Review schedule and cost information and assess risk management elements that may affect the project
  - The Client User's philosophies and values.

### **3.2.5 Scope of Services:**

The proponent should demonstrate capability to perform the services and meet project challenges and to provide a plan of action.

#### Information that should be supplied:

- Scope of Services - detailed list of services
- Work Plan - detailed breakdown of work tasks and deliverables
- Project schedule - proposed major milestone schedule
- Risk management strategy.

### **3.2.6 Management of Services:**

The Proponent should describe how he /she proposes to perform the services and meet the constraints; how the services will be managed to ensure continuing and consistent control as well as production and communication efficiency; how the team will be organized and how it will fit in the existing structure of the firms; to describe how the team will be managed. The proponent is also to identify sub-consultant disciplines and specialists required to complete the consultant team.

If the Proponent proposes to provide multi-disciplinary services which might otherwise be performed by a sub-consultant, this should be reflected here.

#### Information that should be supplied:

- Confirm the makeup of the full project team including the names of the consultant sub-consultants and specialists' personnel and their role on the project.
- Organization chart with position titles and names (Consultant team). Joint Venture business plan, team structure and responsibilities, if applicable
- What back-up will be committed
- Profiles of the key positions (specific assignments and responsibilities)
- Outline of an action plan of the services with implementation strategies and sequence of main activities
- Reporting relationships
- Communication strategies
- Response time: demonstrate how the response time requirements will be met.

### 3.2.7 Design Philosophy / Approach / Methodology

The proponent should elaborate on aspects of the project considered to be a major challenge which will illustrate design philosophy / approach / methodology. This is the opportunity for the Proponent to state the overall design philosophy of the team as well as their approach of resolving design issues and in particular to focus on the unique aspects of the current project.

Information that should be supplied:

- Design Philosophy / Approach / Methodology
- Describe the major challenges and how your team approach will be applied to those particular challenges.

### 3.3 EVALUATION AND RATING

In the first instance, price envelopes will remain sealed and only the technical components of the proposals which are responsive will be reviewed, evaluated and rated by a PWGSC Evaluation Board in accordance with the following to establish Technical Ratings:

| Criterion   | Weight Factor | Rating | Weighted Rating |
|---|---------------|--------|-----------------|
| Achievements of Proponent                         | 2.0           | 0 - 10 | 0 - 20          |
| Achievements of Key Sub-consultants / Specialists | 1.0           | 0 - 10 | 0 - 10          |
| Achievements of Key Personnel on Projects         | 2.0           | 0 - 10 | 0 - 20          |
| Understanding of the Project                      | 2.0           | 0 - 10 | 0 - 20          |
| Scope of Services                                 | 1.0           | 0 - 10 | 0 - 10          |
| Management of Services                            | 1.0           | 0 - 10 | 0 - 10          |
| Design Philosophy / Approach / Methodology        | 1.0           | 0 - 10 | 0 - 10          |
| Technical Rating                                  | 10.0          |        | 0 - 100         |

#### Generic Evaluation Table

PWGSC Evaluation Board members will evaluate the strengths and weaknesses of the Proponent's response to the evaluation criteria and will rate each criterion with even numbers (0, 2, 4, 6, 8 or 10) using the generic evaluation table below:

|         | INADEQUATE | WEAK     | ADEQUATE | FULLY SATISFACTORY | STRONG    |
|---------|------------|----------|----------|--------------------|-----------|
| 0 point | 2 points   | 4 points | 6 points | 8 points           | 10 points |

|   |  |  |  |   |   |
|---|--|--|--|---|---|
| Did not submit information which could be evaluated | Lacks complete or almost complete understanding of the requirements. | Has some understanding of the requirements but lacks adequate understanding in some areas of the requirements. | Demonstrates a good understanding of the requirements.             | Demonstrates a very good understanding of the requirements.                 | Demonstrates an excellent understanding of the requirements.          |
|   | Weaknesses cannot be corrected                                       | Generally doubtful that weaknesses can be corrected  | Weaknesses can be corrected  | No significant weaknesses   | No apparent weaknesses  |
|   | Proponent do not possess qualifications and experience               | Proponent lacks qualifications and experience  | Proponent has an acceptable level of qualifications and experience | Proponent is qualified and experienced                                      | Proponent is highly qualified and experienced                         |
|   | Team proposed is not likely able to meet requirements                | Team does not cover all components or overall experience is weak   | Team covers most components and will likely meet requirements      | Team covers all components - some members have worked successfully together | Strong team - has worked successfully together on comparable projects |
|   | Sample projects not related to this requirement                      | Sample projects generally not related to this requirement  | Sample projects generally related to this requirement              | Sample projects directly related to this requirement                        | Leads in sample projects directly related to this requirement         |
|   | Extremely poor, insufficient to meet performance requirements        | Little capability to meet performance requirements   | Acceptable capability, should ensure adequate results              | Satisfactory capability, should ensure effective results                    | Superior capability, should ensure very effective results             |

To be considered further, proponents **must** achieve a minimum Technical Rating of **sixty (60) points out of the hundred (100) points** available as specified above.

**No further consideration will be given to proponents not achieving the pass mark of sixty (60) points.**

#### **SRE 4 PRICE OF SERVICES**

All price proposal envelopes corresponding to responsive proposals which have achieved the pass mark of sixty (60) points will be opened upon completion of the technical evaluation. An average price is determined by adding all the price proposals together and dividing the total by the number of price proposals being opened.

All price proposals which are greater than twenty-five percent (25%) above the average price will be set aside and receive no further consideration.

The remaining price proposals are rated as follows:

- a) The lowest price proposal receives a Price Rating of 100
- b) The second, third, fourth and fifth lowest prices receive Price Ratings of 80, 60, 40, and 20 respectively. All other price proposals receive a Price Rating of 0.
- c) On the rare occasions where two (or more) price proposals are identical, the matching price proposals receive the same rating and the corresponding number of following ratings are skipped.

The Price Rating is multiplied by the applicable percentage to establish the Price Score.

#### **SRE 5 TOTAL SCORE**

Total Scores will be established in accordance with the following:

| Rating           | Possible Range | % of Total Score | Score (Points) |
|------------------|----------------|------------------|----------------|
| Technical Rating | 0 - 100        | 90               | 0 - 90         |
| Price Rating     | 0 - 100        | 10               | 0 - 10         |
| Total Score      |                | 100              | 0 - 100        |

The Proponent receiving the highest Total Score is the first entity that the Evaluation Board will recommend for the provision of the required services. In the case of a tie, the proponent submitting the lower price for the services will be selected.

#### **SRE 6 SUBMISSION REQUIREMENTS - CHECKLIST**

The following list of documents and forms is provided with the intention of assisting the Proponent in ensuring a complete submission. The Proponent is responsible for meeting all submission requirements.

Please follow detailed instructions in R1410T General Instructions to Proponents, GI16 Submission of Proposal. Proponents may choose to introduce their submissions with a cover letter.

Team Identification - see typical format in Appendix A

Declaration/Certifications Form - completed and signed - form provided in Appendix B

Integrity Provisions - Required documentation – **as applicable** in accordance with the [Ineligibility and Suspension Policy \(http://www.tpsgc-pwgsc.gc.ca/ci-if/politique-policy-eng.html\)](http://www.tpsgc-pwgsc.gc.ca/ci-if/politique-policy-eng.html) and as per R1410T (2016-04-04), General instructions 1 (GI1), Integrity Provisions - Proposal, **section 3a.**

Integrity Provisions - Declaration of Convicted Offences – **with its bid, as applicable** in accordance with the [Ineligibility and Suspension Policy \(http://www.tpsgc-pwgsc.gc.ca/ci-if/politique-policy-eng.html\)](http://www.tpsgc-pwgsc.gc.ca/ci-if/politique-policy-eng.html) and as per R1410T (2016-04-04), General instructions 1 (GI1), Integrity Provisions - Proposal, **section 3b.**

Proposal - one (1) original plus 5 copies

Front page of RFP

Solicitation No. - N° de l'invitation  
EV385-172185/A

Amd. No. - N° de la modif.

Buyer ID - Id de l'acheteur  
pwz202

Client Ref. No. - N° de réf. du client  
CSC – EV385-172185

File No. - N° du dossier  
PWZ-6-39230

CCC No./N° CCC - FMS No./N° VME

---

Front page(s) of any solicitation amendment

In a separate envelope:

Price Proposal Form - one (1) completed and submitted in a separate envelope



# Engineering Services **TERMS OF REFERENCE**

## **CSC-NHQ Regional Psychiatric Centre – Road Repair, Resurfacing and Paving**

**For:  
Correctional Service Canada  
(CSC)  
Regional Psychiatric Centre  
Saskatoon, Saskatchewan**

November 09, 2016



## Table of Contents:

|          |  |           |
|----------|--|-----------|
| <b>1</b> | <b>PROJECT DESCRIPTION</b>             | <b>3</b>  |
| 1.1      | GENERAL                                | 3         |
| 1.2      | BACKGROUND INFORMATION                 | 3         |
| 1.3      | SUMMARY OF DESIGN WORK                 | 5         |
| 1.4      | OBJECTIVES                             | 5         |
| 1.5      | SUMMARY OF SERVICES AND QUALIFICATIONS | 6         |
| 1.6      | SCHEDULE                               | 6         |
| 1.7      | COST                                   | 7         |
| 1.8      | EXISTING DOCUMENTATION                 | 7         |
| 1.9      | CODES, ACTS, STANDARDS, REGULATIONS    | 8         |
| <b>2</b> | <b>REQUIRED SERVICES</b>               | <b>9</b>  |
| 2.1      | GENERAL REQUIREMENTS                   | 9         |
| 2.2      | PROJECT REVIEW AND ACCEPTANCE          | 9         |
| 2.3      | COMMISSIONING SERVICE                  | 10        |
| 2.4      | COST ESTIMATING SERVICE                | 10        |
| 2.5      | PRE-DESIGN SERVICE                     | 10        |
| 2.6      | DESIGN DEVELOPMENT SERVICE             | 14        |
| 2.7      | CONSTRUCTION DOCUMENTS SERVICE         | 16        |
| 2.8      | TENDER SERVICES                        | 18        |
| 2.9      | CONSTRUCTION SUPPORT SERVICE           | 18        |
| 2.10     | RESIDENT CONSTRUCTION SERVICE          | 20        |
| 2.11     | POST CONSTRUCTION SERVICE              | 25        |
| <b>3</b> | <b>PROJECT ADMINISTRATION</b>          | <b>27</b> |
| 3.1      | GENERAL REQUIREMENTS                   | 27        |
| <b>4</b> | <b>APPENDIX A</b>                      | <b>28</b> |
| 4.1      | EXISTING SITE PLAN                     | 28        |





## 1 PROJECT DESCRIPTION

### 1.1 GENERAL

#### 1.1.1 PURPOSE OF TERMS OF REFERENCE (TOR)

- 1 Public Works and Government Services Canada (PWGSC) requires the services of a Civil Engineering Firm experienced in Roads, hydraulic, structural engineering, geotechnical and paving materials design and construction, acting in the capacity of the coordinating engineer of record, together with a multi-disciplinary team of sub-consultants for the provision of service required for this project.

#### 1.1.2 THE PWGSC GENERAL PROCEDURES AND STANDARDS DOCUMENT (GP&S)

- 1 The TOR describes project-specific requirements, services and deliverables while the GP&S document outlines minimum standards and procedures common to all projects.
- 2 The TOR document must be used in conjunction with the GP&S, as the two documents are complementary.
- 3 In the case of a conflict between the two documents, the requirements of the TOR override the GP&S Document.

#### 1.1.3 PROJECT INFORMATION

| Project Information                |   |
|------------------------------------|---|
| Project Title:                     | CSC-NHQ Regional Psychiatric Centre – Road Repair, Resurfacing and Paving           |
| Project Address:                   | Regional Psychiatric Centre<br>2520 Central Avenue North<br>Saskatoon, Saskatchewan |
| PWGSC Project Number:              | R.079994.001  |
| PWGSC Departmental Representative: | Enamul Haque  |

### 1.2 BACKGROUND INFORMATION

#### 1.2.1 USER DEPARTMENT NEED

- 1 CSC needs to repair, resurface and pave existing roads within the perimeter of the Regional Psychiatric Centre at Saskatoon to meet current requirements.

#### 1.2.2 USER DEPARTMENT

- 1 The User Department referred to throughout the TOR is Correctional Service Canada (CSC).
- 2 CSC, as part of the criminal justice system and respecting the rule of law, contributes to public safety by actively encouraging and assisting offenders to become law-abiding citizens, while exercising reasonable, safe, secure and humane control.

#### 1.2.3 EXISTING CONDITIONS

- 1 The Regional Psychiatric Centre (RPC) institution is comprised of 5.75 hectares land area leased from the University of Saskatchewan located within an urban setting surrounded by private homes and businesses. RPC is a federal multilevel institution, for male and female inmates that can accommodate all security designations. It operates both as a penitentiary and as a psychiatric hospital. The institution has a patrol road within the perimeter.
- 2 The access to the fire lane is through the main entrance and then continues in front of the administrative building, all this area is paved. The remainder of the fire route



consist of an unpaved perimeter road which loops around the buildings and runs for the most part between the double secured fence on the south, west, and north sides of the RPC

- .1 The existing perimeter fire road is unable to support loaded fire trucks during all seasons and weather conditions.
- .3 The existing paved roadways have sections in reasonably fair conditions as well as sections in poor condition; exhibiting wear at numerous locations in the form of asphalt cracking and sloughing along the outside edges of the asphalt road surface, as well as several Alligator cracks. Several patches work indicate the occurrence of past repair works. Rutting and pot holes are also observed on the road surfaces in some areas.
- .4 Despite the observed deterioration occurring in some areas, some sections are found to be functional; however, it will continue to deteriorate the condition until a remedial action like repair is undertaken.
- .5 Refer to Appendix A for a site plan showing the road layout.

#### **1.2.4 CONSTRAINTS AND CHALLENGES**

- .1 The Consultant will be required to become familiar with the project site and obtain local information as required.
- .2 The Consultant is required to obtain security clearances for all his/her firm's personnel as well as any sub-consultants to visit the project site for reasons, such as, site reviews, attendance for site design meetings, etc. Security clearance checks may include credit checks.
- .3 All site visits must be arranged through the Departmental Representative.
- .4 The work will be carried out during normal working hours, when the Regional Psychiatric Centre is fully occupied and operational.
- .5 The construction will occur during the full operation of the Regional Psychiatric Centre. Project phasing must be planned to ensure that disruption to the daily operation of the Regional Psychiatric Centre is kept to a minimum.
- .6 Restrict construction to summer months.
- .7 Existing infrastructure affected by the project must be restored to original conditions.
- .8 Environmental conditions must be kept under control during all phases of the work.
- .9 The project scope must be tailored to meet the User Department's budget. Diligent cost estimating and cost control is required.
- .10 Consultant's key personnel must be available to respond to emergencies within 1 day.

#### **1.2.5 PROJECT DELIVERY APPROACH**

- .1 This project will use a traditional design-bid-build approach.
- .2 The Consultant shall prepare one (1) tender package for the entire scope of this project and ensure full co-ordination of the work of all disciplines.



## **1.3 SUMMARY OF DESIGN WORK**

### **1.3.1 SITE WORK**

- .1 Site Condition Assessment:
  - .1 Conduct a visual inspections to identify the road sections and infrastructures to verify the existing condition and the causes of deterioration and suggest future remedial measures/actions;
  - .2 Coordinate with Environmental Department and work with the Planning recommendation;
  - .3 Conduct a geotechnical investigation and Site Survey to determine the soil and ground water conditions at the site, site drainage study and provide geotechnical report with recommendations as input to pavement design of the perimeter road and repair of the existing paved roads.
- .2 Design of Pavement, Culverts for the Institution Road:
  - .1 Pave the Institution Fire Road. This shall comply with the local Fire Code requirements and policies regulating the design of sites with the AHJ;
  - .2 Resurface all existing paved roads and replace damaged curbs, culverts, medians, drains etc.

## **1.4 OBJECTIVES**

### **1.4.1 GENERAL GOALS**

- .1 Achieve an efficient, enduring, sustainable and economically viable road works project that is appropriate for its use and place, through leadership and integration of innovation and technical excellence in the course of the life cycle for the new construction. Meet (at minimum) the following design objectives:
  - .1 Respect the natural environment and the Regional Psychiatric Centre site;
  - .2 Meet or exceed the requirements of the applicable codes, standards and the CSC Technical Criteria;
  - .3 Provide an integrated design and construction process involving:
    - .1 Interdisciplinary collaboration, including all stakeholders as may be identified, design professionals, constructors and authorities having jurisdiction,
    - .2 Agreed upon design principles and decision making protocols.
  - .4 Employ advanced systems and technologies to support contemporary operating requirements with capacity for growth and change.
  - .5 Ensure conformance with appropriate fire protection measures and life safety requirements;
  - .6 Integrate innovative universal design and accessibility to enable inclusiveness and non-discrimination;
  - .7 Ensure solutions are designed to convey a sense of quality, durability and permanence.
    - .1 Use industry proven materials and avoidance of experimental materials; and
  - .8 Is cost effective considering both initial cost and operation & maintenance costs over a life cycle of 25 years.

### **1.4.2 FUNCTIONAL REQUIREMENTS**

- .1 The Consultant will meet with the Departmental Representative and the User Department to review and further develop functional requirements in the Pre-Design phase.



#### **1.4.3 ENVIRONMENTAL/SUSTAINABLE DEVELOPMENT**

- .1 Sustainability
  - .1 Minimize impact on terrain, vegetation and cultural features.
  - .2 Maximize the salvage and re-use of existing materials
  - .3 Reduce the encroachment of non-native species along the roadway.
  - .4 Develop a reasoned approach to clearing or rehabilitating vegetation as appropriate to minimize the need for salt application, improve sight lines.
  - .5 Develop opportunities for improving hydraulic flow (culvert improvement and/or replacement).
- .2 Environmental Assessment
  - .1 Any proposed borrowed sources for embankment material must be approved by CSC.
  - .2 No burying or burning of brush is permitted within the Perimeter.
  - .3 The Consultant is to complete an Environmental Impact Analysis of any proposed design options and identify appropriate mitigation measures with Cost estimates.

#### **1.4.4 PROJECT DELIVERY**

- .1 Deliver the project within the construction budget established during preliminary project approval.
- .2 Deliver the project within the key milestones in this TOR.
- .3 Ensure that each Consultant team member understands the project requirements for seamless delivery of the required services.
- .4 Provide a quality management plan that includes rigorous quality reviews performed in-house by the Consultant Team such that submissions are fully complete and coordinated.
- .5 Ensure minimal disruption to the daily operations of the Institution.

### **1.5 SUMMARY OF SERVICES AND QUALIFICATIONS**

#### **1.5.1 GENERAL SERVICES**

- .1 The coordinating engineer of record will provide a full consulting team including the following consultant services and specialties:
  - .1 Professional Civil Engineering Services;
    - .1 Coordinating Engineer of Record.
  - .2 Professional Engineering Services;
    - .1 Structural Engineering,
    - .2 Geotechnical Engineering,
    - .3 Pavement Design and Engineering,
    - .4 Hydraulic Engineering;
  - .3 Commissioning;
    - .1 Consulting engineers may function as the commissioning agents.
  - .4 Cost Estimating Specialist;
    - .1 Certified by the Canadian Institute of Quantity Surveyors.

### **1.6 SCHEDULE**

#### **1.6.1 GENERAL**

- .1 Deliver the project to be ready for occupancy in accordance with the project milestone listing identified below.



- .2 The schedule is dependent on the Consultant Contract Award date.
- .3 Prepare a Project Schedule in accordance with the milestone list.

#### 1.6.2 ANTICIPATED MILESTONE DATES

| Project Phase   | Milestone Completion Date           | Number of Weeks |
|---|-------------------------------------|-----------------|
| Estimated Consultant Contract Award                               | February 28, 2017                   |                 |
| Pre-Design  |                                     | 2 weeks         |
| PWGSC Quality Assurance Review                                    |                                     | 2 weeks         |
| Design Development  |                                     | 2 weeks         |
| PWGSC Quality Assurance Review                                    |                                     | 2 weeks         |
| 50% Construction Documents  |                                     | 3 weeks         |
| PWGSC Quality Assurance Review                                    |                                     | 2 weeks         |
| 99% Construction Documents  |                                     | 2 weeks         |
| PWGSC Quality Assurance Review                                    |                                     | 2 weeks         |
| Final (100%) Tender Documents                                     |                                     | 1 week          |
| Contract Award  |                                     | 6 weeks         |
| Substantial Completion of Construction                            |                                     | 8 weeks         |
| Final Completion (Commissioning, Final Inspection and Acceptance) |                                     | 2 weeks         |
| Post Construction Deliverables                                    | 1 month past Final Completion date  |                 |
| Post Construction Warranty Evaluation                             | 9 months past Final Completion date |                 |

### 1.7 COST

#### 1.7.1 CONSTRUCTION BUDGET

- .1 The construction estimate does not include project management fees, administration costs, consultant fees, risk allowance, escalation or GST and is in 'Budget-Year (Current)' dollars.

#### 1.7.2 ESTIMATED CONSTRUCTION COST

- .1 The estimated construction cost (excluding GST), is anticipated at this time to be \$1,000,000.

### 1.8 EXISTING DOCUMENTATION

#### 1.8.1 AVAILABLE FOR THE CONSULTANT

- .1 Limited as-built drawings and Operation & Maintenance Manuals will be available at the start of the Pre-Design phase. The Consultant will be responsible for verifying the accuracy of the information incorporated into the design.
- .2 Current as-built drawings in AutoCAD (dwg) format.
  - .1 The drawings will require modifications by the Consultant.
- .3 CSC Technical Criteria for Correctional Institutions, April 2015.
- .4 Federal Correctional Facilities Accommodation Guidelines. December 2015.



### 1.8.2 DISCLAIMER

- .1 Reference information will be available in the language in which it is written.
- .2 The documentation may be unreliable and is offered, “as is” for the information of the Consultant.

## 1.9 CODES, ACTS, STANDARDS, REGULATIONS

### 1.9.1 GENERAL

- .1 A listing of Codes, Acts, Standards and Guidelines potentially applicable to this project are contained in the GP&S Document. In addition the following standards also apply to this project:
  - .1 Commissioning (Cx) to comply with CAN/CSA Standards Z320-11;
  - .2 Accessible Design for the Built Environment – CSA B651-12;
  - .3 The CSC Act;
  - .4 Canadian Environmental Assessment Act, 2012;
  - .5 Transportation Association of Canada (TAC) Geometric Design Guide for Canadian Roads;
  - .6 The current Provincial Department of Infrastructure and Transportation Design Standards;
  - .7 National Bridge Code for Canada.
- .2 The Authorities Having Jurisdiction (AHJ) on this project are:
  - .1 The local AHJs;
  - .2 Treasury Board of Canada Secretariat, accessed through the Departmental Representative;
    - .1 CSC Departmental Fire Protection Coordinator as identified in the TBS Fire Protection Standard.
- .3 The Consultant must identify, analyse and design the project in accordance with the requirements of all AHJs and all applicable Codes, Acts, Standards and Guidelines and Legislation:
  - .1 The applicability of various Codes, Acts, Standards and Guidelines listed in the GP&S document arise out of direct and indirect references in documents which apply to Federal buildings, such as the Canada Labour Code;
  - .2 The consultant team must be fully versed with the legislation and requirements that are unique to Federal Government buildings in Canada;
  - .3 The consultant team must be fully versed with the legislation and requirements that are unique to Federal Government projects tendered through Public Works & Government Services Canada.



## 2 REQUIRED SERVICES

### 2.1 GENERAL REQUIREMENTS

#### 2.1.1 SERVICES

- .1 Commissioning Service.
- .2 Cost Estimating Service.
- .3 Pre-Design Service.
- .4 Design Development Service.
- .5 Construction Document Service.
- .6 Tender Services - to assist the Departmental Representative.
- .7 Construction Support Service.
- .8 Resident Construction Service.
- .9 Post Construction Service.

### 2.2 PROJECT REVIEW AND ACCEPTANCE

#### 2.2.1 GENERAL

1. Comply with all applicable laws and regulatory requirements as required by the General Conditions of the Contract.

#### 2.2.2 PWGSC REVIEWS, ACCEPTANCE AND PRESENTATIONS

- .1 Project delivery team acceptance includes both the PWGSC Architectural & Engineering Centre of Expertise (A&ECoE) reviews and User Department acceptance:
  - .1 The purpose of each review is technical quality and to ascertain for PWGSC that the Consultant has reasonably fulfilled the objectives of this project;
  - .2 PWGSC will not provide solutions, detailed comments and/or coordination for the Consultant;
  - .3 Work that does not meet the objectives of the project will be rejected, rejected work will require further design (including re-design), coordination and documentation at the Consultant's expense;
  - .4 Quality assurance for the project design and documentation remains the responsibility of the Consultant;
  - .5 Submissions will be reviewed at the pre-design phase, design development phase, 50% construction documents phase and 99% construction documents phase;
  - .6 Expected turnaround time is 2 weeks;
  - .7 For each review provide one submission (i.e. electronic copies of documents in pdf format) plus any follow-up submissions.
    - .1 Review submissions to be posted on Buzzsaw.
  - .8 The consultant shall provide a single coordinated written response to the comments;
    - .1 Add comments to the active document provided and returned as an active document once all consulting team comments are included and complete.

#### 2.2.3 PROVINCIAL, TERRITORIAL AND MUNICIPAL AUTHORITIES

- .1 The federal government generally defers to provincial and municipal authorities for specific regulations, standards and inspections but in areas of conflict the more stringent authority prevails.
- .2 Local Authority having Jurisdiction (AHJ) review:





- .1 The purpose of this review is information and awareness;
- .2 Submit documents in formats such as reports, drawings, specifications or other formats as required by the local AHJ;
- .3 Submission will be reviewed for development permit at the design development completion;
- .4 Submission will be reviewed for building permit.
- .5 For each review provide one submission (i.e. electronic copies of documents in pdf format) plus any follow-up submissions.

## **2.3 COMMISSIONING SERVICE**

### **2.3.1 GENERAL**

- .1 The purpose of the Commissioning Service is to ensure that a fully functioning project is delivered to the Client.
- .2 Commissioning (Cx) is an integral part of the Consultants' required services and therefore, required activities and deliverables are listed within each project phase service.
- .3 Provide Commissioning Service on the basis of CSA Z320-11, Canadian Standards Association Building Commissioning Standard.

## **2.4 COST ESTIMATING SERVICE**

### **2.4.1 GENERAL**

- .1 Cost estimates, consultant billing and construction bidding are also required to be broken down by fiscal year (i.e. April 1 - March 31).
- .2 Include a cost breakdown for Commissioning activities in Class A, B and C cost estimates.

## **2.5 PRE-DESIGN SERVICE**

### **2.5.1 GENERAL**

- .1 The Consultant Team will review and analyze all available project information, consult with the Departmental and User Department Representatives, collect additional data and deliver a comprehensive Preliminary Engineering Design Report.
- .2 The Preliminary Engineering Design Report will consolidate the Scope of the Preliminary Engineering activities, provide recommendations, Class C construction cost estimate(s), updated overall project schedule to the completion of 99% tender document stage and will be utilized as the benchmark project control document to monitor progress of the project.

### **2.5.2 SCOPE AND ACTIVITIES**

- .1 The Consultant Team will review and analyze all available existing material related to the project.
- .2 Review and analyse the project requirements identified in the ToR including any amendments.
- .3 Identify and verify all Authorities Having Jurisdiction (AHJ) over the codes, regulations and standards that apply to the project especially the CSC concerns to minimize impact on terrain, waterways, clearing of trees and brush and clean-up of any survey stakes/markers/test pits, etc.
- .4 Identify and analyze all Codes, Acts, Standards and Guidelines that apply to this project.
- .5 Visit the site and consult with Departmental Representative and User Department Representatives.





- .6 Identify all additional information that will be needed to deliver the project
- .7 Prepare and submit a “Geotechnical Field Investigation Plan” outlining proposed locations of drill holes and/or test pits, piezometers, signage/traffic safety plan, method of clean-up, proposed schedule of work and type of equipment .
- .8 Geotechnical Investigation and Recommendations
  - .1 General:
    - .1 The objective of the Geotechnical Investigation is to collect enough information on the in situ material within the study corridor to determine the physical and engineering properties of the various materials encountered and make recommendations;
    - .2 The Consultant must obtain written authorization/approval of the “Geotechnical Field Investigation Plan” from the Departmental Representative before proceeding with Field work and subsequent Laboratory testing of samples collected;
  - .2 Field Work and Laboratory Testing:
    - .1 The Scope of Work listed below is not considered exhaustive and modifications will be considered. All revisions or modifications to the Scope of Work must be justified by the Proponent and approved by PWGSC prior to implementing;
    - .2 Study Area for Geotechnical – to be determined in consultation with CSC and PWGSC after a site visit to the RPC by the Consultant and its geotechnical, roadway design specialists;
    - .3 Test Pitting and sampling is required to determine the physical and engineering properties of the in situ soils. Consultant to propose the extent and type of testing but normally test pits are excavated and sampled every 200 to 300m of a proposed alignment or at any obvious change in soil types. Any potential borrow sources should be tested at this time as well. All test pits shall be logged on site with emphasis on recording soil conditions and depth of groundwater encountered. Disturbed samples representative of in-situ soil gradation shall be taken at each significant change in soil strata or otherwise at one (1) m intervals. Samples shall be packaged and stored so that moisture content determinations of in-situ conditions can be undertaken. Representative Colour Digital pictures of each test pit and the material excavated are to be taken. Upon completion of sampling all test pits are to immediately filled back in, no spoil piles are to be left;
    - .4 Piezometers and Slope Indicators – Consultant to recommend location and type if any are required. Ensure seal of standpipe at surface is secure to prevent surface water from flowing into the hole and unauthorized access is prevented;
    - .5 The Geotechnical Consultant is to record the location of all test holes in UTM – NAD 83 coordinates and the geodetic elevation of the existing ground surface at the top of the test holes. Wooden markers/lath shall be left in the field indicating the location of the test pits and the test pit number. No separate payment will be made for this work, but will be considered incidental to other pay items;
    - .6 Excavators are to be capable of reaching to a 4m depth and equipped to cause minimum damage to the existing terrain;
    - .7 A qualified Geotechnical Technician or Engineer shall be provided to supervise investigation; supervise drilling and/or test pitting and collect



- samples; ensure that detailed logs of drilling and/or pitting and field testing are prepared; and ensure that all test samples are tagged & bagged correctly; pictures taken. Geotechnical Person shall advise PWGSC representative of any potential concerns that may be identified from drilling and/or test pitting which may require additional holes and/or sampling;
- .8 Storage, identification, transport and subsequent Laboratory testing of samples shall be carried out. Laboratory Testing shall consist of visual laboratory identification, determination of moisture content, sieve analysis, and Atterberg Limits. An enough Laboratory testing shall be performed to confirm visual field classification and likely strengthens of the soil type(s)/horizons encountered and potential for corrosion;
- .9 Payment for Laboratory Testing will be for each test performed. Storage and transportation costs considered incidental;
- .3 Geotechnical Reporting and Recommendations:
- .1 Provide a Geotechnical Report detailing the investigation methodology, its findings and recommendations for roadway and culverts;
- .2 Note the Geotechnical Investigation Report will be made available to future construction Contractors to assist them in preparing a tender for work;
- .3 Geotechnical Investigation Report with Recommendations shall as a minimum contain;
- .1 Drill hole and/or test pit logs, laboratory testing results, plan of test hole/pits /piezometers/slope indicators locations,
- .2 A separate section if required to cover analysis and recommendations to improve stability of cut and fill slopes, control groundwater, prevent excessive settlement of embankments, structures within the study area,
- .3 A section discussing the suitability of existing material for roadway construction, excavation methodology, rip ability of rock if any, shrinkage/swelling factors, frost heave potential, recommended Asphaltic Concrete pavement structure including crushed gravels for a road top with a 25 year design life, potential for corrosion of steel culverts and any other issues relating to highway construction.
- .4 Environmental Impact Analysis and Proposed Mitigation Methods:
- .1 The Consultant is to complete an Environmental Impact Analysis of any proposed design options and identify appropriate mitigation measures with Cost estimates.
- .5 Preliminary Engineering Design Report:
- .1 For Road Assessment of other existing roads provide a brief description with a plan showing the roads inspected and highlight/describe any areas where there are issues with;
- .1 Alligator Crack, potholes, pavement failure etc.,
- .2 Soft/unstable roadbed and/or backslopes,
- .3 Insufficient road top width, poor sight lines, side slopes, horizontal curves too tight, inadequate drainage, etc.
- .4 Existing culverts or other drainage structures in poor condition.
- .2 Provide recommendations with Class C cost estimates to address the issues identified.
- .9 Provide an updated overall Project Schedule.



### 2.5.3 DELIVERABLES

- .1 “Geotechnical Field Investigation Plan”:
  - .1 The proposed “Geotechnical Field Investigation Plan” to contain:
    - .1 Drawing showing proposed location of drill holes and/or test pits, piezometers, Slope Indicators, and access trails.
    - .2 Necessary sections to document and present the items listed in the Scope and Activities section,
    - .3 Updated Overall Project schedule.
  - .2 Final “Geotechnical Field Investigation Plan” with a written response to any comments on Draft.
- .2 Geotechnical Report
  - .1 An ACAD Drawing showing the location of all test holes drilled and the placement of the Slope Indicators and Piezometers.
  - .2 A detailed soils log sheets shall be prepared for each test hole and information and data provided shall be descriptive or factual in nature i.e. “auger refusal”, “cohesionless”, “rock”, “moisture content above Plastic Limit”.
    - .1 Each individual soils log sheet shall be provided in a separate electronic ACAD drawing file format or individual DXF format drawing files.
    - .2 Geotechnical Investigations and Recommendations Report.
      - .1 Report content as per the GP&S document.
      - .2 Necessary sections to document and present the items listed in the “Scope and Activities” section above.
      - .3 Report to be provided in electronic PDF format with all pictures in colour. In addition, the Consultant is to provide six (6) print copies of the report. Each individual soils log sheet shall be provided in a spate electronic ACAD drawing file format or individual DXF format drawing files.
- .3 Environmental Impact Analysis and Proposed Mitigation Methods
  - .1 A Draft Environmental Impact Analysis and Proposed Mitigation Methods report that will contain at a minimum:
    - .1 An Executive Summary;
    - .2 Necessary sections to document and present the items listed in the Scope and Activities section;
    - .3 Class C cost estimates for Mitigation methods.
  - .2 Final Environmental Impact Analysis and Proposed Mitigation Methods report with a written response to any comments on Draft.
- .4 Draft and Final Reports are to be provided in PDF electronic format and all pictures in colour. In addition, the Consultant is to provide six (6) print copies of the report.
- .5 Preliminary Engineering Design Report
  - .1 A Draft Preliminary Engineering Report that will contain at a minimum:
    - .1 An Executive Summary;
    - .2 Necessary sections to document and present the items listed in the Scope and Activities section;.
    - .3 Class C cost estimate; and
    - .4 An Updated schedule.
  - .2 Final Preliminary Engineering Report with a written response to comments.
- .6 Draft and Final Reports are to be provided in PDF electronic format and all pictures in colour. In addition, the Consultant is to provide six (6) print copies of the report.



## **2.6 DESIGN DEVELOPMENT SERVICE**

### **2.6.1 GENERAL**

- .1 The object of this phase is to further develop the design option selected for refinement at the completion of the Pre-Design phase.
- .2 The Consultant to prepare Design Development documents, which consist of drawings and other documents to describe the scope, quality, quantities and cost of the project in sufficient detail to facilitate design approval, confirm code compliance and meets User Requirements and to obtain authorization to prepare the construction documents.
- .3 The Consultant must obtain written authorization from the Departmental Representative before proceeding with developing the Construction Documents

### **2.6.2 SCOPE AND ACTIVITIES**

- .1 Ground Surveys and Post Processing:
  - .1 General:
    - .1 The objective for the Topographic Survey is to collect enough ground elevation to accurately describe the lay of the land, drainage and associated features.
  - .2 Surveys:
    - .1 Conduct a digital topographical survey including all utilities using Total Station or GPS units as follows
    - .2 Control is to be produced using the UTM grid system and geodetic mean sea level datum for all survey positioning. Tie in Total Station survey with a minimum of three (3) geodetic monuments and clearly indicate them on survey drawings. Provide ASCII format file containing information in the following order for each survey point: Point number, Northing, Easting, Elevation, and description (as required to identify specific items, abbreviations are acceptable if code table for abbreviations is provided).
    - .3 Indicate and define Grid North UTM, and True North relative angles.
    - .4 All traverses will be closed and balanced. Process horizontal control data using rigorous least squares adjustment program.
    - .5 All surveys shall be carried out with a minimum of 2 people.
    - .6 All signage and safety measures identified in the Consultant's Safety plan to be in place before surveys commence.
- .2 The Consultant shall:
  - .1 Develop the Design for the RPC and provide drawings in sufficient detail to clearly identify the site, all the elements in the design, required environmental mitigation measures and accurate quantities can be established.
  - .2 Prepare a Class "B" Cost Estimate, update the Project schedule and the risk analysis and identify any conflicts and/or items that will need to be addressed with respect to scope, quality, schedule, cost, source of material.
  - .3 Analyse the constructability of the Project and advice on the construction phasing process and duration.
  - .4 Provide outline of the specifications which will apply to the various elements of the design.

### **2.6.3 DELIVERABLES**

- .1 Ground Surveys
  - .1 Deliverables from GPS/Total Station Survey:



- .1 Electronic copy of RAW data file
- .2 Electronic copy of processed RAW file with PWGSC descriptors and the Northing, Easting, and Elevation for each point.
- .3 Electronic or hard copy of survey notes including descriptor code list
- .4 Survey Precision Quality Report
- .2 Deliverable from Total Station Survey:
  - .1 Electronic copy of RAW data file with PWGSC descriptors and the Slope distance, Horizontal and Vertical angles for each point.
  - .2 Electronic copy of processed RAW file with PWGSC descriptors and the Northing, Easting, and Elevation for each point.
  - .3 One hard copy of traverse survey showing backsight and foresight points, height of instrument, height of targets, horizontal and vertical angles, and slope distance.
  - .4 One hard copy of calculations for balancing traverse points.
  - .5 One hard copy of level loop and balancing calculations for control points
  - .6 Electronic copy (ASCII) and hard copy of control points showing Northing, Easting, and Elevation.
  - .7 Electronic or hard copy of survey notes including descriptor code list used.
- .3 Electronic ACAD Drawing file to be produced regardless of the type of survey method employed to collect the required field data.
  - .1 Prepare a 1:1000 scale AutoCAD drawing of all survey points. Each point to have appropriate survey data attached (i.e. northing, easting, elevation, description).
  - .2 Join like features (e.g. edge of pavement, building sides, pavement crown, ditch or swale edge, ditch or swale centre-line, etc.) with lines and Indicating break lines for features.
  - .3 Logically assemble and label like features/object data. Annotate by colour and group by layer in the CAD file. Ensure each data point has its associated Point number annotated. Topographical data points and benchmarks are to be placed on exclusive drawing layers. Provide legend describing each point type Description code.
  - .4 Provide contour lines at maximum 1.0 metre intervals to indicate topographical features on the 1:1000 scale drawings based on the grid elevation data.
  - .5 Surveyed area is to be mapped into a single CAD file only. The CAD file is not to be broken down into separate sub-files joined by match lines. Use 'ground' coordinates to create the file.
  - .6 Provide drawing in UTM Ground Coordinates; indicate BMs and scale factor used to calculate Ground Coordinates.
  - .7 Do not use drawing level 0 (zero).
  - .8 Clearly indicate geodetic monuments and secondary control monuments on the drawing.
  - .9 From the survey files create a "Topographic Survey Plan(s) at 1:1000 scales which displays the following:
    - .1 True North arrow, UTM co-ordinate grid, 1.0m contour lines, manmade features such as culverts, signs, drill holes, highway centreline, edge of pavement, ditch lines, survey monuments, cracks in pavement, edge of



- tree line, utilities, bridges, approach road intersections, etc with appropriate Legend, note date of field surveys.
- .2 Provide six (6) hard copies of the “Topographic Survey Plan(s) as well as an editable electronic file in ACAD format.
- .2 Design Development Report:
  - .1 Consultant is to prepare and submit a Design Development Report, for review and acceptance by the Departmental Representative.
  - .2 Prepare Design Development documents to illustrate the design of the Project in sufficient detail to obtain authorization to commence the preparation of Construction Documents.
  - .3 Drawings to be in accordance with Section 2.11 Drawings of the GP&S Documents
  - .4 The Draft Design Development Report will contain at a minimum
    - .1 An Executive Summary
    - .2 Necessary sections to document and present the items listed in the Scope and Activities section,
    - .3 Engineering Calculations confirming the suitability/adequacy of design elements chosen and long term stability of road cut/fill slopes can be achieved.
  - .5 Final Design Development Report with a written response to comments.
  - .6 Draft and Final Reports are to be provided in PDF electronic format and all pictures in colour. In addition, the Consultant is to provide six (6) print copies of the report.

## **2.7 CONSTRUCTION DOCUMENTS SERVICE**

### **2.7.1 GENERAL**

- .1 The objective of this stage is to translate the Design Development phase into construction drawings and specifications for the purpose of tendering.
- .2 The Consultant must obtain written authorization from the Departmental Representative before proceeding with Construction Documents.
- .3 Prepare one (1) tender package co-ordinated with all disciplines.

### **2.7.2 SCOPE AND ACTIVITIES**

- .1 Create construction documents in accordance with the GP&S document.
- .2 Update the cost estimates:
  - .1 Provide a cost breakdown by unit rate and/or trade for review of bids and comparison with the successful Contractor's cost breakdown.
- .3 Update the project schedule.
- .4 Establish a quality control process for the construction and contract administration stage.
- .5 The Consultant shall:
  - .1 Design according to the budget and schedule;
  - .2 Coordinate the work of various disciplines including scope changes required to remain within budget;
  - .3 In consultation with the Departmental Representative approve construction materials, processes and specifications considering sustainability and commissioning;
  - .4 Update project log tracking approved major decisions;





### 2.7.3 DELIVERABLES

- .1 Include items listed in the “Scope and Activities” section above, the PWGSC GP&S document and items listed below.
- .2 50% complete Construction Documents:
  - .1 Updated class “B” estimate;
  - .2 Updated OPR and BOD documents;
  - .3 Updated project schedule;
  - .4 Construction Drawings;
    - .1 Drawings should reflect 50% completeness with all planned and required drawings / sheets shown.
  - .5 Specifications;
    - .1 Proposed unit price table,
    - .2 Index to specifications (identifying all sections to be used for the project),
    - .3 Draft Division 01 including,
      - .1 Health and Safety Requirements (Section 01 35 29),
      - .2 Commissioning sections.
- .3 99% complete Construction Documents (fully coordinated as if ready for tender):
  - .1 This submission incorporates all revisions required by the review of the previous submission and a written response to the PWGSC 50% review;
  - .2 The Consultant shall submit documents to the Departmental Representative, local municipality, or any other Authority having jurisdiction;
  - .3 Class “A” estimate;
  - .4 Unit price table;
  - .5 An updated project schedule;
  - .6 Construction Drawings;
    - .1 Drawings should reflect 99% completeness as a complete design without any incomplete drawings (as if ready for tendering).
  - .7 Complete Specifications;
    - .1 Specifications should be complete with all sections and thoroughly coordinated with the drawings,
    - .2 Bidders’ price breakdown form (for submission at tender closing);
    - .3 Commissioning specifications.
  - .8 Updated Commissioning Plan.
- .4 Final (100%) Construction Documents ready for tendering:
  - .1 This submission incorporates all revisions required by the review of the previous submission and a written response for the PWGSC 99% QA review;
  - .2 Advise the Departmental Representative of all issues raised by other officials;
  - .3 The submittal shall include;
    - .1 An updated Class ‘A’ cost estimate,
    - .2 Unit price table,
    - .3 An updated project schedule,
    - .4 Construction Drawings & Specifications as per the GP&S document.
    - .5 An updated Commissioning Plan;
  - .4 The Consultant must confirm in writing that;
    - .1 The documents are ready to be issued for tender,



- .2 The checklist in the GP&S Document has been reviewed in concert with the requirements of the Consultant Agreement and
- .3 A full review and coordination of the Contract Documents are complete and in accordance with professional standard of care.

## **2.8 TENDER SERVICES**

### **2.8.1 GENERAL**

- .1 The object of this phase is to support the Departmental Representative with the tender.
- .2 The Contract Authority for this project is the PWGSC Real Property Contracting (RPC) branch.
- .3 Tendering will be using the Public Works and Government Services internet procurement system (<https://buyandsell.gc.ca>).

### **2.8.2 SCOPE AND ACTIVITIES**

- .1 When requested, the Consultant will be required to:
  - .1 Provide the Departmental Representative with information required by bidders to interpret construction documents;
  - .2 Prepare addenda in response to all questions within two (2) business days during the bidding period and submit to the Departmental Representative;
  - .3 Attend pre-tender site visits;
  - .4 If PWGSC decides to re-tender the project, or any specific tender package, provide full services to the Departmental Representative;
  - .5 During Bid Review and Analysis assist the Departmental Representative as required by analyzing and reconciling any differences between pre-tender estimates and submitted bids.

### **2.8.1 DELIVERABLES**

- .1 Addenda.
- .2 Written responses to all questions.
- .3 Bid analysis and/or recommendations.

## **2.9 CONSTRUCTION SUPPORT SERVICE**

### **2.9.1 GENERAL**

- .1 The object of this phase is to support the Departmental Representative with the construction phase and ensure the quality, budget and schedule meet the project requirements.

### **2.9.2 SCOPE AND ACTIVITIES**

- .1 The Consultant shall share all project information with PWGSC:
  - .1 All material specifications, mixes and test results shall be turned over to the Departmental Representative for future maintenance by PWGSC and others.
- .2 General Services:
  - .1 Review shop drawings, test reports and other submissions;
  - .2 Update the project log tracking approved major decisions, including those impacting project scope, budget and schedule;
  - .3 Prepare and issue a communications protocol and a shop drawing review protocol in consultation with the Departmental Representative;
  - .4 Review and comment on Contractor's commissioning submittals including:
    - .1 Contractor's Commissioning Plan;





- .2 Project and Project Commissioning Issues Logs;
  - .3 Cx Report;
  - .4 Cx Schedule reflecting the Performance Verification Tests;
  - .5 Outstanding activities.
- .5 Assist the Contractor and provide required documentation in order to obtain the building permit;
- .3 Construction & Contract Administration:
  - .1 Provide monthly field reviews and as required to fulfill the Consultant's professional obligations to monitor the construction activities throughout the construction period and keep the Departmental Representative informed of work progress;
    - .1 Reject unsatisfactory work,
    - .2 Provide written reports.
  - .2 Provide construction progress reports based on Contractor's submissions and on-site performance;
  - .3 Furnish supplemental instructions to the Contractor with reasonable promptness or in accordance with a schedule for such instructions agreed to by PWGSC and the Contractor;
  - .4 Provide additional drawings to clarify, interpret or supplement the contract documents;
  - .5 Review and comment on various documents such as the Contractor's Progress Claims and updated schedules;
  - .6 Offer timely technical advice on all disputes and claims between PWGSC and the Contractor;
  - .7 Authorize special tests, inspections and minor works that do not impact project cost and schedule;
  - .8 Determine the amounts owing to the Contractor based on work progress and certify payments to the Contractor;
  - .9 Assist the Departmental Representative to prepare the Certificate of Substantial Completion and provide sign-off;
  - .10 Provide a Post-Construction Evaluation report.
- .4 Cost Services:
  - .1 After issue of contract provide details for evaluating the project's cost performance;
  - .2 Assist the construction team with cost management advice, if requested;
  - .3 Evaluate change orders, claims, work completed and cash flow.
- .5 Changes to the Work:
  - .1 Assist the Departmental Representative to prepare Contemplated Change Notices (CCNs) and Change Orders (COs) to be issued by the Departmental Representative.
- .6 Final Commissioning Report documenting all commissioning work, testing, verification and results achieved during the project construction. Include at a minimum the following:
  - .1 Engineer of Record to review, approve and sign off all submittals for performance parameters before and after execution of test.
  - .2 Conduct field reviews, witness and complete reports with Cx forms verifying tests.



- .7 Certify Substantial Completion for Interim Acceptance Report sign off.

### **2.9.3 DELIVERABLES**

- .1 Approved shop drawings, test reports/certificates and other submissions.
- .2 Clarifications, Supplemental Instructions, Contemplated Change Notices and Change Order Recommendations.
- .3 Site Visit/Field Review Reports.
- .4 Reviewed Contractor Progress Claims.
- .5 Comments to Contractor Schedule, Change Orders.
- .6 Completed Certificate of Substantial Completion.
- .7 Cx Deliverables:
  - .1 Final Commissioning Report;
  - .2 Certified Substantial Completion.

## **2.10 RESIDENT CONSTRUCTION SERVICE**

### **2.10.1 GENERAL**

- .1 The purpose of this phase is to represent the Departmental Representative on site during construction and to inspect, co-ordinate, measure for payment and monitor all aspects of the work during construction of the project, and liaise with the Contractor, Public Works and Government Services Canada and other agencies as appropriate to the work.

### **2.10.2 SCOPE AND SERVICES**

- .1 The Consultant will be required to provide resident inspection services for the period of construction and for other times periods as directed by the Departmental Representative.
- .2 Consultant is to provide a survey crew when necessary to make measurements for monthly progress payments and for final payment.
- .3 The Consultant Resident Site representative is responsible for providing resident inspection for all aspects of the Project, maintaining daily records of all construction work placed. He is to ensure constant communication amongst the Departmental Representative, Design Consultant, Contractor, and the Provincial Department of Labour.
- .4 The Consultant Resident Site representative shall:
  - .1 Be directly responsible to the Consultant.
  - .2 Become thoroughly familiar with the Contract documents and be aware of all Provincial and Municipal standards for the health and safety of construction workers
  - .3 Comply with Correctional Services Canada regulations, policies and requirements;
  - .4 Become thoroughly familiar with the requirements of the Consultant's Terms of Reference and Project responsibilities of others, which relate to his/her services.
- .5 Specific Duties and Responsibilities
  - .1 Provide full time resident inspection, co-ordination and monitoring during the construction work and be responsible to the consultant. In addition, the



- Departmental Representative may delegate additional responsibilities subject to Consultant's agreement
- .2 Maintain daily records of all construction work placed and ensure constant communication amongst Departmental Representative, the Contractor, and the appropriate Correctional Services Canada Representative.
  - .3 Co-ordinate and direct an assistant as approved by the Departmental Representative.
  - .4 In case of emergencies, the Consultant Resident Site representative is empowered to stop the work or
  - .5 Give orders to protect the Safety of the workers or Crown property.
  - .6 Inspection and Reporting
    - .1 The Consultant Resident Site representative shall inspect all phases of the work in progress, for the purpose of bringing to the attention of the Contractor, after checking with the Consultant, and Departmental Representative any discrepancies between the work, the contract documents and accepted construction procedures. He shall keep a daily log of such inspections and shall issue a weekly written report to the Consultant, both for distribution, in the form directed. The Resident Site representative shall make any other reports or surveys as may be requested by the Departmental Representative through the Consultant.
  - .7 Interpretation of the Contract Documents
    - .1 Interpretation of the contract documents shall be the responsibility of the Consultant. The Consultant may, however, have the Resident Site representative provide him with information regarding job conditions and may require him to relay day-to-day instructions to the contractor. It shall be the duty of the Resident Site representative to assist the Consultant and further inform the Consultant of any anticipated problems, which may delay the progress of the work. The method of relaying such information shall be determined by the Consultant.
  - .8 Changes in the Work
    - .1 The Resident Site representative shall not authorize or order any change in the work, which will constitute a change in design or in the value of the contract except as delegated by the Departmental Representative. The Consultant may call upon the Resident Site representative to assist in the evaluation of changes in the work, where knowledge of job conditions is required
  - .9 Communications & Liaison
    - .1 The Resident Site Representative shall:
      - .1 Convey the Consultant's instructions regarding the required standards of workmanship to the Contractor(s)
      - .2 For Specifications confer and obtain guidance on these findings with the Consultant. The matter is then to be brought to the attention of the Contractor's Superintendent. Although informal discussions with Sub-trade Superintendents are usually permissible, (but only with the agreement of the Contractor), the Resident Site representative should not deal directly with foreman or tradesmen, or interfere with the progress of the work
      - .3 Communicate formally with the contractor via memorandum form only. When this form is issued, the Resident Site representative must immediately file copies with PWGSC and the Consultant
      - .4 Contact the Consultant immediately when it is apparent that information or action is required of the Consultant, e.g. general instructions, clarifications,



sample of shop drawing approvals, requisitions, contemplated change orders, site instructions, details, drawings, etc

- .5 Accompany PWGSC representatives on inspections and report to the Consultant requirements, comments or instructions of the PWGSC's forces. Note that the Resident Site Representative should encourage such requirements, comments or instructions to be provided to him in writing
- .6 Consider and evaluate any suggestions or modifications to the documents advanced by the Contractor and immediately report these to the Consultant with comments
- .7 Ensure that the Departmental Representative and the Consultant are notified promptly when key pieces and/or components of materials and equipment are delivered, so that these parties can arrange for the appropriate personnel to have an opportunity to inspect same prior to installation.

#### .10 Daily Log

- .1 The Resident Site Representative shall keep a daily log recording:
  - .1 Weather conditions, particularly unusual weather relative to construction activities in progress
  - .2 Major material and equipment deliveries
  - .3 Daily activities and major work done;
  - .4 Start, stop or completion of activities;
  - .5 Presence of inspection and testing firms, tests taken, results, etc;
  - .6 Unusual site conditions experienced;
  - .7 Significant developments, remarks, etc;
  - .8 Communications with the Contractor;
  - .9 Special Visitors on site;
  - .10 Authorities given contractor to undertake certain or hazardous works;
  - .11 Traffic Collisions or reports of damage to private vehicles passing through work area.
  - .12 Environmental incident(s);
  - .13 Reports, instructions Appropriate Authorities Response Actions
    - .1 Note: The log is the personal property of the Resident Site representative. Copies of the logbook, certified as copies, are to be provided to PWGSC and consultant at the end of the project.
  - .14 Representative digital photographs in colour to be taken and logged daily as to date, time of day, location, and type of activity represented in the photo.

#### .11 Weekly Records

- .1 The Resident Site representative shall prepare weekly reports for the Consultant in the form directed:
  - .1 Progress relative to schedule;
  - .2 Major activities commencing or completed during the week; main activities now in progress;
  - .3 Major deliveries of materials and/or equipment;
  - .4 Difficulties which may cause delays in completion;
  - .5 Materials and labour needed immediately
  - .6 Cost estimates of work completed and materials delivered;



- .7 Outstanding information or action required by Consultant or Departmental Representative
  - .8 Work force;
  - .9 Weather;
  - .10 Remarks;
  - .11 Accidents/collisions on site;
  - .12 Environmental incident(s)
  - .13 Life safety hazards caused by the work, the Contractor or its agents.
- .12 Site Records
- .1 The Resident Site representative shall maintain orderly and updated files at the site for the use of the Departmental Representative, Consultant and himself as follows:
    - .1 Contract and Tender Documents;
    - .2 Approved Shop Drawings;
    - .3 Approved Samples;
    - .4 Samples;
    - .5 Site Instructions;
    - .6 Site specify safety plan provided by the Contractor;
    - .7 Contemplated Change Orders;
    - .8 Change Orders;
    - .9 Memoranda;
    - .10 Test and Deficiency Reports;
    - .11 Correspondence and Minutes of Meetings;
    - .12 Names, addresses, telephone numbers of Departmental Representatives, Consultant and all Contractors, sub-trades key personnel associated with the contract; including home telephone numbers in case of emergencies;
    - .13 In addition, the Resident Site representative shall maintain an updated progress schedule.
    - .14 A reproduction of the of the original contract drawings shall be carefully preserved and shall be kept marked up to date with all addenda, change orders, site instructions, details, as-built conditions, etc., issued subsequent to the award of the contract.
- .13 Inspection of the Work
- .1 The Resident Site representative shall make on site observations and spot checks of the work to determine whether the work, materials and equipment conform to the contract documents and supplementary conditions. The Site consultant's representative shall advise the Contractor of any deficiencies or unapproved deviations via memorandum and report immediately to the Consultant and PWGSC Construction Representative any of these on which the Contractor is tardy or refuses to correct.
  - .2 The Resident Site representative shall arrange for the Consultant's Geotechnical Engineer to make the periodic inspections required by the Consultant's contract, and for these inspections to be made timely with respect to the progress of the work.
  - .3 The Resident Site representative shall also report if materials and equipment are being incorporated into the project prior to approval of relative shop drawings or samples.



- .4 The Resident Site representative shall assist in the preparation of all deficiency reports, interim, preliminary, and final, in collaboration with the PWGSC and Consultant's representatives.
- .5 The Resident Site representative shall be responsible for the measurement of all work to be done on a unit-cost basis.
- .14 Site Meetings
  - .1 The Resident Site representative shall attend all job-site meetings
- .15 Inspection and Testing
  - .1 The Resident Site representative must see that the tests and inspections required by the contract documents are conducted, and should observe these tests and report the results in the daily log;
  - .2 The Consultant must be notified if the test results do not meet the specified requirements, or if the Contractor does not have tests undertaken as required.
- .16 Emergencies
  - .1 In case of emergency where safety of persons or property is concerned or work is endangered by the actions of the Contractor or the elements, to safeguard the interests of PWGSC, the Resident Site representative shall give immediate written notice to the Contractor of the possible hazard. He shall further, if necessary, stop the work or give orders for remedial work, and contact the Consultant immediately for further instruction.
- .17 Limitations
  - .1 The Resident representative shall not:
    - .1 Authorize deviations from the contract documents.
    - .2 Conduct tests.
    - .3 Approve shop drawings or samples.
    - .4 Advise the user-client in any matter without obtaining guidance from the Consultant
    - .5 Accept any work or portions of the Project
    - .6 Enter into the area of responsibility of the Contractor's Field Superintendent.
    - .7 Stop the work unless convinced that an emergency exists as noted above.
- .18 Hazardous Construction Operations
  - .1 It is the duty of the Resident Site representative to examine all site conditions and methods to be used by the Contractor undertaking hazardous operations.
  - .2 Give written authority to undertake hazardous operations to the Contractor, when fully satisfied that all necessary precautions and acts have been taken by the Contractor to safeguard the life safety of the workers and travelling Public and Crown property. Written authority shall be countersigned by the Contractor to acknowledge that the latter is aware of the Resident Site representative's instructions and requirements and both parties will retain copies of the authority document signed mutually by them
  - .3 The Resident Site representative shall inspect the areas where hazardous work is under way to ensure that the Contractor is maintaining the agreed safety standards. Any infractions may result in the Resident Site representative stopping the work. All infractions, or work stoppages ordered shall be reported in writing and verbally to the Consultant and PWGSC Construction Supervisor.
- .19 Site Security
  - .1 Site security is the ultimate responsibility of the Contractor, Resident Site Representative to observe/record measures undertaken by the Contractor.



- .2 The Resident Site representative will liaise closely with the Consultant and PWGSC Departmental Representative on all security and/or safety problems that may arise due to the contractor's operations.
- .20 Site Surveys
  - .1 The Consultant is required to acquire all the necessary site survey information necessary to complete the project and to calculate quantities for payment.
  - .2 Additional Services
  - .3 Additional Services, if required, shall be as described elsewhere in the Agreement and shall be determined in the manner set out in the "Calculation of Fees" and "Agreement Particulars" clauses.
- .21 Site Office
  - .1 Site Office and basic furniture shall be provided by the Contractor, Consultant to provide the Resident Site representative with all necessary equipment, vehicle, tools, office supplies including computer, phones, camera, etc to conduct his duties and responsibilities.

### 2.10.3 DELIVERABLES

- .1 Weekly written reports
- .2 Memorandum issued to the Contractor.
- .3 Other reports or surveys as may be requested by the Departmental Representative.
- .4 A copy of the Site Representatives Daily log with digital photos.

## 2.11 POST CONSTRUCTION SERVICE

### 2.11.1 GENERAL

- .1 The purpose of this phase is to support the Departmental Representative in obtaining all final documents required for project close out.

### 2.11.2 SCOPE AND ACTIVITIES

- .1 Project Close-out Services:
  - .1 Revise documentation to reflect all changes, revisions and adjustments after completion of commissioning;
  - .2 Prepare record drawings (AutoCAD format as per GP&S requirements) and specifications based on Contractor's as-builts;
  - .3 Prepare and submit final Certificate of Completion and final records;
  - .4 Review the integrated commissioning manual;
  - .5 Sign-off Final Commissioning Report;
  - .6 Participate in Lessons Learned workshops if requested.
- .2 Warranty Services:
  - .1 Monitor and certify rectification of deficiencies before expiry of warranties;
  - .2 Monitor environmental and life safety system checks to be carried out by Contractor / O&M staff before expiration of warranties;
  - .3 Sign-off on the Final Completion of the construction contract;
  - .4 Participate in warranty inspections with the Departmental Representative and Contractor;
  - .5 Provide warranty deficiency list;
  - .6 Assist with the final PWGSC Commissioning evaluation.





- .3 Commissioning:
  - .1 Coordinate deferred commissioning for those systems that have been functionally tested and/or turned over where retesting and commissioning is required;
  - .2 Resolution of any warranty issues on commissioned systems during the warranty period;
  - .3 Ensure that all completed operating and maintenance manuals, warranties, guarantees and other required submittals are turned over to the Departmental Representative;
  - .4 Provide ongoing consultation with the construction teams in support of their project closeout activities and submittals related to systems and assemblies commissioning specific deliverables in compliance to the Commissioning Plan and Construction Specifications document;
  - .5 Finalize the Commissioning Report;
  - .6 Prepare final Commissioning Manual as per CSA Z320-11.

### 2.11.3 DELIVERABLES

- .1 Warranty Deficiency List.
- .2 Final Certificate.
- .3 As-Builts:
  - .1 One (1) hard copies – full size sets, and 1 electronic PDF copy of each record document on CD or DVD;
  - .2 One (1) copy of each record drawing in AutoCAD - DWG file format.
    - .1 Refer to the GP&S document for AutoCAD drawing requirements and standards.
- .4 Final Commissioning Manual.
- .5 Sign-off on Warranty.





## **3 PROJECT ADMINISTRATION**

### **3.1 GENERAL REQUIREMENTS**

#### **3.1.1 PWGSC PROCEDURES AND STANDARDS**

- .1 The consultant shall comply with the amendments and/or additions in this section in addition to adhering to the requirements contained in the GP&S section 3 (Project Administration).

#### **3.1.2 LANGUAGE**

- .1 No variation.

#### **3.1.3 MEDIA**

- .1 No variation.

#### **3.1.4 PROJECT MANAGEMENT**

- .1 Project commissioning is to comply with the CSA Z320-11 standard.

#### **3.1.5 LINES OF COMMUNICATION**

- .1 No variation.

#### **3.1.6 MEETINGS**

- .1 Design Phase:
  - .1 Monthly meetings with PWGSC and the Consultant team will be held at RPC. Additional meetings (if required) will be held via teleconference.
  - .2 An on-site familiarization meeting will be held at the Regional Psychiatric Centre in Saskatoon.
- .2 Construction Phase:
  - .1 Monthly meetings with PWGSC, the Consultant team and the Contractor will normally be held at the construction site for the duration of the project and as required.
  - .2 The following additional meetings will be held at the project site:
    - .1 One or two meetings for the Substantial Completion Inspection;
    - .2 One meeting just before the end of the Warranty Period.

#### **3.1.7 CONSULTANT RESPONSIBILITIES**

- .1 No variation.

#### **3.1.8 PWGSC RESPONSIBILITIES**

- .1 No variation.

#### **3.1.9 USER DEPARTMENT RESPONSIBILITIES**

- .1 No variation.

#### **3.1.10 REVIEW AND APPROVAL BY PROVINCIAL AND MUNICIPAL AUTHORITIES**

- .1 No variation.

#### **3.1.11 BUILDING PERMITS AND OCCUPANCY PERMITS**

- .1 No variation.

#### **3.1.12 TECHNICAL AND FUNCTIONAL REVIEWS**

- .1 HRSDC reviews are no longer applicable.



## 4 APPENDIX A

### 4.1 EXISTING SITE PLAN

Road Repair, Resurfacing and Paving (Inner Perimeter)

#### SITE PLAN

