



Materiel and Procurement Services
200 Kent Street, Station 9W070
Ottawa, Ontario
K1A 0E6

January 13, 2017

Subject: Invitation to Tender: FP802-160275

Title: Marginal wharf construction.

Work site location: Barre-de-Cocagne, NB

ADDENDUM: No. 5

Further to the above mentioned Invitation to Tender documentation previously posted on the Government Electronic Tendering Site (GETS), BuyandSell.gc.ca, Addendum (#5) is hereby issued.

Department of Fisheries and Oceans

Bid Closing Date: Thursday, January 26, 2017
Time: 14:00 Hours (2:00 pm) Eastern Standard Time (EST)
RFP File No: FP802-160275

**** THE FOLLOWING QUESTIONS WERE SUBMITTED BY POTENTIAL BIDDERS
TO THE CONTRACTING AUTHORITY IN RELATION TO THE SUBJECT ITT****

Q.1 Are a copy of receipt required for disposal of crib work Treated Timber?

A.1 Yes. This will be indicated in this addendum for section "01-74-21: Construction/Demolition Waste Management & Disposal 1.3 Measurement Procedure."

Q.2 Does the containment cell which is currently filled, have to be excavated to handle the new excavated and dredged material? If yes, where can the containment cell material be haul away to?

A.2 No. It will be cleaned out prior to the contract start date.



****PLEASE NOTE THE FOLLOWING CHANGES TO THIS SOLICITATION****

Please Note:

- 1) **Delete:** "FP802-160275 - Construction tender Form.pdf"
Replace with: "FP802-160275 - Construction tender Form - Revision 1.pdf"
- 2) **Delete:** "FP802-160275 - Invitation To Tender Notice.pdf"
Replace with: "FP802-160275 - Invitation To Tender Notice – Revision 1.pdf"

3) **Delete in "FP802-160275 – Specifications.pdf" section 03-30-00, Page 4:**

-2.2 Mixes . 1 . 3 Minimum cement content: 385 kg/ mu of concrete

Replace with:

-2.2 Mixes . 1 . 3 Minimum cement content: 400 kg/m³ of concrete

4) **Add in "FP802-160275 – Specifications.pdf" section 01 74 21: 1.3.1.15:**

The existing containment cell is estimated to be 50 meters long by 25 meters wide will be excavated at a depth of 1m and disposed of at the approved Federal dredge disposal site at Loggies' Pit. This item includes the excavation from on-site containment cell, trucking and spreading of the material at the disposal site. This item also includes the clearing and grubbing of 3 area at the disposal site; Area for the new access road, Area for the disposal of grubbing and Area for the disposal of dredge material as specified on drawing SK-1. This item also includes the construction of the new access road as per specified on the drawing SK-1. Access road to be built using sandstone and to be compacted with suitable equipment.

5) **Delete in "FP802-160275 – Specifications.pdf" section 31 23 10, Page 1, 1.2 Measurement Procedures:**

.1: Excavation above elev. +1.22m: All excavation materials above elevation +1.22m (Dry Material) will be measured for payment by the cubic meter truck measurement (CMTM) for work completed. Price will include stockpiling of dry material on the existing containment cell area as shown on drawings or as directed. Supply and place of silt fence at no additional cost. Do not intermix dry and wet materials.

Replace with:

.1: Excavation above elev. +1.22m: All excavation materials above elevation +1.22m (Dry Material) will be measured for payment by the cubic meter truck



measurement (CMTM) for work completed. Price will include stockpiling of dry material on-site, not in the containment cell. Once the material can be transported, it will become the contractors responsibility and will have to be transported off site at an appropriate location determined by the contractor. Supply and place of silt fence at no additional cost. Do not intermix dry and wet materials.

6) **A new document has been added:** "FP802-160275 - Lump Sum Breakdown.pdf"

All other Terms and Conditions for this requirement remain unchanged.

Tenderers are to acknowledge this Addendum by signing in the space provided below and enclosing a copy of this document with their tender submission.

Regards

Gricha Zurita
Senior Contracting Officer
Telephone: (613) 993-2807
Email: Gricha.Zurita@dfo-mpo.gc.ca

RECEIPT ACKNOWLEDGED

Name of Company _____

Signature _____