



Materiel and Procurement Services
200 Kent Street, Station 9W070
Ottawa, Ontario
K1A 0E6

January 18, 2017

Subject: Invitation to Tender: FP802-160275

Title: Marginal wharf construction.

Work site location: Barre-de-Cocagne, NB

ADDENDUM: No. 6

Further to the above mentioned Invitation to Tender documentation previously posted on the Government Electronic Tendering Site (GETS), BuyandSell.gc.ca, Addendum (#6) is hereby issued.

Department of Fisheries and Oceans

Bid Closing Date: Thursday, January 26, 2017
Time: 14:00 Hours (2:00 pm) Eastern Standard Time (EST)
RFP File No: FP802-160275

**** THE FOLLOWING QUESTIONS WERE SUBMITTED BY POTENTIAL BIDDERS TO THE CONTRACTING AUTHORITY IN RELATION TO THE SUBJECT ITT****

Q.1 Are there start and / or completion dates? Are there any deadlines (blackout dates) or special dates when the work must be completed?

A.1 Work begins after the award date. The work must be completed before December 31, 2017. In addition, there are no date where the work must be stopped or special dates.

Q.2 On the plans, it is required to store the excavation materials on the vacant area west of the wharf. Is it necessary simply to pile the excavated materials or to put them in piles and then dispose of them?



A.2 To add to the recently published addendum 5, any (dry) excavation above elevation +1.22 should be stored on site, however, not over the containment cell, and will become the responsibility of the contractor. Then that material needs to be transported off-site to an appropriate location as determined by the Contractor. Any material (wet) below the 1.22m elevation will be placed in the containment cell that will have been emptied previously under this contract.

Q.3 With regard to cast concrete beams, can you confirm whether the H Beam is embedded in the concrete beam?

A.3 Yes

Q.4 What about the joint between the prefabricated concrete panels and the concrete beam? Do we need to have something special (binder, mortar, etc.)?

A.4 No

Q.5 There appears to be a contradiction in Addendum 5 regarding the excavation of the containment cell. In response to Q.2 “Does the containment cell have to be excavated...” the response states “No. It will be cleaned out prior to the contract start date.” Then on the next page the specification is modified to include this excavation. Further the modification refers to a drawing SK-1 which was not included in the document. Please clarify your intentions, and provide the missing drawing?

A.5 At the time of answering Q2, the containment cell was on track to be cleaned out by others, but that option fell through shortly after. The containment cell will get cleaned out as part of this contract. Drawing SK-1 will be added to the Addendum 6.

Q.6 Most metal items are noted on the drawings as “galvanized” with the exception of the tie rods and connections. The specification Section 05 supports this as well. However, some items are welded directly to the bare steel H-Piles. Is it your intention to have these items galvanized or bare metal?

Specifically:

- **The Bent Steel Plate Corner Detail, D6 dwg M6;**
- **The Steel Strap Panel Support Detail, D3 dwg M6; and**
- **The H-Pile cap plates.**

A.6 No, these items are not to be galvanized.

****PLEASE NOTE THE FOLLOWING CHANGES TO THIS SOLICITATION****

Please Note:

- 1) **A new drawing has been added: “FP802-160275 - Drawings - 3.pdf ”**



All other Terms and Conditions for this requirement remain unchanged.

Tenderers are to acknowledge this Addendum by signing in the space provided below and enclosing a copy of this document with their tender submission.

Regards

Gricha Zurita
Senior Contracting Officer
Telephone: (613) 993-2807
Email: Gricha.Zurita@dfo-mpo.gc.ca

RECEIPT ACKNOWLEDGED

Name of Company _____

Signature _____