



RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
Bid Receiving Public Works and Government
Services Canada/Réception des soumissions Travaux
publics et Services gouvernementaux Canada
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British Columbia
V6Z 0B9
Bid Fax: (604) 775-9381

SOLICITATION AMENDMENT

MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Public Works and Government Services Canada -
Pacific Region
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British C
V6Z 0B9

Title - Sujet Veteran Cemetery Expansion	
Solicitation No. - N° de l'invitation EZ899-172401/A	Amendment No. - N° modif. 003
Client Reference No. - N° de référence du client	Date 2017-01-20
GETS Reference No. - N° de référence de SEAG PW-\$PWY-019-7945	
File No. - N° de dossier PWY-6-39277 (019)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2017-01-30	Time Zone Fuseau horaire Pacific Standard Time PST
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Ngan, Ken (PWY)	Buyer Id - Id de l'acheteur pwy019
Telephone No. - N° de téléphone (604) 658-2755 ()	FAX No. - N° de FAX (604) 775-6633
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction: Veterans Affairs (VAC) - Esquimalt Veteran Cemetery - Victoria, BC	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Solicitation No. - N° de l'invitation
EZ899-172401/A
Client Ref. No. - N° de réf. du client

Amd. No. - N° de la modif.
003
File No. - N° du dossier
pwy-6-39277

Buyer ID - Id de l'acheteur
pwy019
CCC No./N° CCC - FMS No/ N° VME

This Solicitation Amendment 003 is raised to incorporate Addendum #1.

All other terms and conditions remain unchanged.

Please find following Addendum #1.

PUBLIC WORKS & GOVERNMENT SERVICES CANADA

ESQUIMALT VETERANS CEMETERY

1200 Colville Rd., Naden

Project No.: R.080256.003

2017-01-20

ADDENDUM NO. 1

Page 1 of 2

The following changes in the tender documents are effective immediately. This addendum will form part of the contract documents

AMEND/REVISE SPECIFICATIONS AS FOLLOWS:

1. All perimeter fencing is to be aluminum to match existing, per specifications.
2. Delete references to as-built drawings to be provided by the contractor. The contractor is responsible for keeping accurate as-constructed plans and specification records and delivering hardcopy redlines at the completion of the project to the Departmental Representative.
3. Delete Section 01 91 00 Commissioning. This section is not required.
4. Delete reference to a "Waste Audit" on Page 1 of 2 in Section 01 74 19 Waste Management and Disposal. This item is not required.
5. Delete reference to a "Waste Reduction Plan" (WRW) on Page 1 of 2 in in Section 01 74 19 Waste Management and Disposal, and wherever else it appears in the Specifications. This item is not required.
6. Delete reference to "elevator" on page 4 of 8, General Instructions.
7. Add: one additional sign (Signage for Site Traffic - Detail 3, Sheet L3.2) shall be installed at the cemetery gate to alert drivers of golfers when exiting.
8. Remove reference to installation of landscape boulders from plans and specifications. As the number of boulders cannot be determined, any boulders considered suitable for landscape use shall be stockpiled for inspection by the Departmental Representative. Any boulders approved for installation shall be placed as directed, with payment to be made through the Change Order process.
9. Provide pricing for the three trees on golf course property to be removed as shown on the attached sheets. (All three are willows, two are 60 cm DBH and one is 90 cm DBH. All are located in the vicinity of the golf course club house, and accessible from an asphalt path with the capacity to support a 1T truck.) Work to include the removal of all above-ground material but no stump grinding.

PUBLIC WORKS & GOVERNMENT SERVICES CANADA

ESQUIMALT VETERANS CEMETERY

1200 Colville Rd., Naden

Project No.: R.080256.003

2017-01-20

ADDENDUM NO. 1

Page 2 of 2

10. Allow for the placement of 8 logs from tree removals (max 5m length) within the project area to serve as habitat trees. All other tree removed shall be chipped or otherwise removed from the site and disposed of per specifications.
11. All excavated soil is to be removed from the site and disposed of per specifications. Topsoil shall be stockpiled, per specifications, for reuse within the woodland area. Estimated depth of topsoil is 150mm.
12. All surplus tree waste and wood chips are to be removed from site and disposed of per specifications.
13. No hazardous materials are expected to be encountered during excavation.
14. Half of the D.N.D. parking lot indicated on Sheet L3.0 is available for contractor use and staging. Minimize impacts to the other users of this space and their vehicles, include the installation of hoarding if necessary. At project completion, restore the affected area to its preconstruction condition.
15. The washroom facility located within the existing cemetery is available to contractors. If this facility is damaged or not appropriately maintained, the contractor shall be responsible for its repair and cleaning, and thereafter for bringing in portable facilities for his use.
16. Make every effort to minimize impacts on Gorge Vale Golf Course operations and patrons.
17. Coordinate with the columbaria supplier (working under a separate contract) to enable the necessary access and installation of columbaria walls.
18. If sub surface rock removal is considered necessary, the proposed additional work must be submitted and approved through formal change order.
19. Aggregate materials to be used for construction shall meet the specifications provided.
20. Subject trees for removal on golf course property identified in following attached photos.

End of Addendum

Tree Removal

Subject trees for removal

- 1) Willow tree located on the right side of the 10th fairway.
- 2) Willow tree located on the right side of the 11th tee box.
- 3) Willow tree located on the right side of the 11th fairway.

Legend

Untitled Polygon

1) Willow Tree

2) Willow Tree

3) Willow Tree

Google Earth

© 2016 Google

100 m



1) Willow Tree



3) Willow Tree